

Richard Harwood and Ian Lodge

Cambridge IGCSE®

Chemistry

Coursebook

Fourth edition



Completely **Cambridge**
Cambridge resources
for
Cambridge qualifications

Richard Harwood and Ian Lodge

Cambridge IGCSE®

Chemistry

Coursebook

Fourth edition



CAMBRIDGE
UNIVERSITY PRESS

CAMBRIDGE UNIVERSITY PRESS

University Printing House, Cambridge CB2 8BS, United Kingdom

One Liberty Plaza, 20th Floor, New York, NY 10006, USA

477 Williamstown Road, Port Melbourne, VIC 3207, Australia

4843/24, 2nd Floor, Ansari Road, Daryaganj, Delhi – 110002, India

79 Anson Road, #06–04/06, Singapore 079906

Cambridge University Press is part of the University of Cambridge.

It furthers the University's mission by disseminating knowledge in the pursuit of education, learning and research at the highest international levels of excellence.

Information on this title: education.cambridge.org

© Cambridge University Press 2014

This publication is in copyright. Subject to statutory exception and to the provisions of relevant collective licensing agreements, no reproduction of any part may take place without the written permission of Cambridge University Press.

First published 1998

Second edition 2002

Third edition 2010

Fourth edition 2014

20 19 18 17 16 15 14 13 12 11 10

Printed in Dubai by Oriental Press

A catalogue record for this publication is available from the British Library

ISBN 978-1-107-61503-8 Paperback with CD-ROM for Windows® and Mac®

ISBN 978-1-316-11917-4 Cambridge IGCSE Chemistry Coursebook with CD-ROM (Elevate), 2 years

ISBN 978-1-316-63772-2 Paperback with CD-ROM for Windows® and Mac® Paperback + Cambridge Elevate enhanced edition, 2 years

Cambridge University Press has no responsibility for the persistence or accuracy of URLs for external or third-party internet websites referred to in this publication, and does not guarantee that any content on such websites is, or will remain, accurate or appropriate. Information regarding prices, travel timetables, and other factual information given in this work is correct at the time of first printing but Cambridge University Press does not guarantee the accuracy of such information thereafter.

NOTICE TO TEACHERS IN THE UK

It is illegal to reproduce any part of this work in material form (including photocopying and electronic storage) except under the following circumstances:

- (i) where you are abiding by a licence granted to your school or institution by the Copyright Licensing Agency;
- (ii) where no such licence exists, or where you wish to exceed the terms of a licence, and you have gained the written permission of Cambridge University Press;
- (iii) where you are allowed to reproduce without permission under the provisions of Chapter 3 of the Copyright, Designs and Patents Act 1988, which covers, for example, the reproduction of short passages within certain types of educational anthology and reproduction for the purposes of setting examination questions.

All end-of-chapter questions taken from past papers are reproduced by permission of Cambridge International Examinations.

Example answers and all other end-of-chapter questions were written by the author.

® IGCSE is the registered trademark of Cambridge International Examinations.

Cambridge International Examinations bears no responsibility for the example answers to questions taken from its past question papers which are contained in this publication.

Sections of the Cambridge IGCSE Chemistry syllabus included in this resource are reproduced by permission of Cambridge International Examinations.

Contents

Introduction

v

1 Planet Earth

1

- 1.1 Natural cycles and resources
- 1.2 The atmosphere
- 1.3 Seas and rivers
- 1.4 The Earth's crust

2
5
11
14

2 The nature of matter

21

- 2.1 The states of matter
- 2.2 Separating and purifying substances
- 2.3 Atoms and molecules
- 2.4 The structure of the atom
- 2.5 Electron arrangements in atoms

22
27
34
41
47

3 Elements and compounds

55

- 3.1 The Periodic Table – classifying the elements
- 3.2 Trends in groups
- 3.3 Trends across a period
- 3.4 Chemical bonding in elements and compounds
- 3.5 The chemical formulae of elements and compounds
- 3.6 Metals, alloys and crystals

56
60
63
65
75
78

4 Chemical reactions

89

- 4.1 Chemical reactions and equations
- 4.2 Equations for chemical reactions
- 4.3 Types of chemical reaction
- 4.4 A closer look at reactions, particularly redox reactions
- 4.5 Electrolysis
- 4.6 A closer look at electrode reactions

90
91
94
100
102
113

5 Acids, bases and salts

119

- 5.1 What is an acid?
- 5.2 Acid and alkali solutions
- 5.3 Metal oxides and non-metal oxides

120
124
125

- 5.4 Acid reactions in everyday life
- 5.5 Alkalis and bases
- 5.6 Characteristic reactions of acids
- 5.7 Acids and alkalis in chemical analysis
- 5.8 Salts
- 5.9 Preparing soluble salts
- 5.10 Preparing insoluble salts
- 5.11 Strong and weak acids and alkalis

127
129
131
134
136
138
141
143

6 Quantitative chemistry

151

- 6.1 Chemical analysis and formulae
- 6.2 The mole and chemical formulae
- 6.3 The mole and chemical equations
- 6.4 Calculations involving gases
- 6.5 Moles and solution chemistry

152
158
162
166
167

7 How far? How fast?

174

- 7.1 Energy changes in chemical reactions
- 7.2 Rates of reaction
- 7.3 Catalysts
- 7.4 Photochemical reactions
- 7.5 Reversible reactions and chemical equilibria

175
181
187
193
194

8 Patterns and properties of metals

206

- 8.1 The alkali metals
- 8.2 Aluminium
- 8.3 The transition elements
- 8.4 The reactivity of metals
- 8.5 Electrical cells and energy

207
210
212
215
221

9 Industrial inorganic chemistry

226

- 9.1 The extraction of metals by carbon reduction
- 9.2 The extraction of metals by electrolysis
- 9.3 Ammonia and fertilisers
- 9.4 Sulfur and sulfuric acid
- 9.5 The chlor-alkali industry
- 9.6 Limestone
- 9.7 The economics of the chemical industry

227
234
235
238
241
242
245

10 Organic chemistry

- 10.1 The unique properties of carbon
- 10.2 Alkanes
- 10.3 Alkenes
- 10.4 Hydrocarbon structure and isomerism
- 10.5 Chemical reactions of the alkanes
- 10.6 Chemical reactions of the alkenes
- 10.7 Alcohols
- 10.8 The reactions of ethanol
- 10.9 Organic acids and esters

11 Petrochemicals and polymers

- 11.1 Petroleum
- 11.2 Alternative fuels and energy sources
- 11.3 Addition polymerisation
- 11.4 Condensation polymerisation

12 Chemical analysis and investigation

- 12.1 Inorganic analysis
- 12.2 Organic analysis
- 12.3 Experimental design and investigation
- 12.4 Practical examinations

252 Answers to questions 326

Glossary 336

Appendix: The Periodic Table 346

Index 347

Acknowledgements 353

Terms and conditions of use for the CD-ROM 354

CD-ROM

- 275 Study and revision skills
- Self-assessment practice tests
- Practice exam-style papers and marking schemes
- 284 Syllabus contents table
- 287 Syllabus coverage by book chapter
- Glossary
- Notes on Activities for Teachers/Technicians
- 296 Self-assessment checklists
- 297 Activities
- 304 Answers to Coursebook end-of-chapter questions
- 305 Revision checklists
- 310 Animations

Introduction

Chemistry is a laboratory science: its subject material and theories are based on experimental observation. However, its scope reaches out beyond the laboratory into every aspect of our lives – to our understanding of the nature of our planet, the environment we live in, the resources available to us and the factors that affect our health.

This book thoroughly covers the Cambridge International Examinations (IGCSE) Chemistry syllabus and includes features which are aimed at helping you grasp the concepts and detail involved. The areas that cover the **Core** and **Supplement** material of the syllabus are clearly marked (the **Supplement** material having a purple bar like the one here in the margin) so that you can see which topics will be tested on each exam paper that you will take. The topic summaries, questions and end-of-chapter questions are also clearly marked so that you can pick out, study and revise the material relevant to the 'core' and 'extended' papers.

In addition to covering the syllabus, the book also contains additional information. This will not be examined, but is there to help develop your scientific skills and broaden your knowledge. Areas of additional information are marked by the green bar like the one here in the margin.

The first chapter of the book serves to set chemistry in its broader context and as such contains material that 'sets the scene' as well as syllabus material. At various points in this and other chapters there is material that provides and develops some of the context in which chemical ideas are important. These are areas such as:

- ♦ the importance of chemistry to life, and the nature of the universe (Chapter 1)
- ♦ renewable and non-renewable resources (Chapter 1)
- ♦ our need to develop alternative energy sources (Chapter 11).

The introduction to each chapter aims to highlight some of the more novel aspects of chemistry – from unusual alloys and the visualisation of the bonding in molecules to the analytical laboratory on the surface

of Mars. The introductions are found in boxes and as with the additional information, the material within these will not be examined.

Features of the book and the Student CD-ROM

The book is divided into broad **chapters** covering important areas of the syllabus. These chapters are then divided into different **sections** to help you manage your understanding of the ideas involved. At the end of each section there are short **questions** to help you check that you have followed the ideas covered. The **answers** to these short questions are provided at the end of the book to help you with this. Included in the text are a series of **study tips** and **key definitions**. These highlight important areas of learning and useful approaches to a particular topic.

Each chapter finishes with a **summary** of Core and Supplement material to help you particularly with your revision. This is followed by a selection of **end-of-chapter questions** which are there to help you become familiar with the style of question set in each examination.

Answering questions is a great way to get to grips with each of the topics. However, it is not the only way! The **Student CD-ROM** provides information on revision skills and resources available on the internet to help with your study of chemistry. A copy of the syllabus is provided on the CD-ROM, which shows where the different topics are covered in the book – and you can use this interactively as a checklist during revision. 'Mind-mapping' ideas and other revision strategies are discussed on the CD-ROM, and we hope that you can find ideas that will help you study in the most personally effective way.

An important feature which appears both in the book and on the Student CD-ROM is the **glossary**. The terms included in the glossary are highlighted in the text in **dark red bold**. Do use this resource in

addition to the text in order to help you understand the meaning of chemical terms. But more than that, it is important that you can express your ideas clearly in an exam – that is why we have included so many practice questions in the book and in the **practice tests** that appear on the CD-ROM. The information boxes and ‘key definitions’ placed throughout the chapters are there to help you learn how to summarise your knowledge in an effective and clear way. Chemistry, and science in general, can often use certain words in a very precise way, so it is important to read carefully and get used to writing down your answers clearly.

Practical work

We began by saying that chemistry was a practical science and, in this edition, we have included **Activities** throughout the chapters, which we hope will encourage your enjoyment of the practical aspect of the subject. Worksheets for these practicals are included on the Student CD-ROM. In addition, we have aimed to help your preparation for the practical element of the exam in various ways:

- ◆ Chapter 12 of the book gives a summary of the different ways that practical work is assessed and some exemplar questions.
- ◆ There are practice ‘alternative to practical’ papers (Paper 6) on the Student CD-ROM.
- ◆ The separate **Student Workbook** contains exercises involving practice at the key skills of writing up your observations and making deductions from your results. Included there are methods that you can use to assess (by yourself, and with your teacher) how well you are developing your data handling and presentation skills.

Chemistry is an important, exciting and challenging subject that impacts on every aspect of our lives. As we face the challenges of the future, the chemical ‘angle’ on things will figure in our thinking, whatever future course we personally take in our careers. We hope that this book will help you enjoy chemistry, give you some understanding of the ideas involved and help you be successful in the IGCSE course.

Richard Harwood
Ian Lodge

1 Planet Earth

In this chapter, you will find out about:

- A ♦ the water cycle
- S ♦ the carbon cycle
- A ♦ the nitrogen cycle
- ♦ the composition and uses of the gases in the air
- S ♦ the separation of air into its components
- ♦ the sources of air pollution
- ♦ the problems of air pollution, and their solution
- ♦ 'greenhouse gases' and climate change
- ♦ water treatment and sewage treatment
- ♦ the pollution of water
- ♦ metal ores and limestone
- ♦ fossil fuels and the problems they cause
- ♦ alternative sources of energy
- ♦ hydrogen as a fuel
- S ♦ the hydrogen fuel cell.

A brief history of the Earth



Figure 1.1 A satellite image over Africa: one view of the 'blue marble'.

The Earth is a ball of rock orbiting a star along with a group of other planets (Figure 1.1). The star is one of many billions of stars in a galaxy which, in turn, is one of many billion galaxies in a constantly expanding Universe. As such, the Earth is

unremarkable. It is the chemicals which make up the Earth and the ways in which they interact with each other that make life on Earth possible.

At the start, the Earth was a ball of molten rock. The surface solidified to a solid crust as it cooled and contracted, and cracks appeared. Volcanoes shot molten rock and gases from this surface and the first atmosphere (mainly carbon dioxide and water vapour) was formed.

Condensing water vapour fell back to the surface and, over many millions of years, plant life developed in these warm, shallow seas. The plants used carbon dioxide in **photosynthesis** and, crucially, put oxygen into the atmosphere. Once sufficient oxygen was present, animal life began to evolve. Nitrogen entered the atmosphere from bacteria. Because nitrogen is an unreactive gas, it was not removed and it has built up to a large percentage of the atmosphere.

The development of plant and animal life over many millions of years has led to the Earth's present balance of chemicals. The activity of humans is now altering this chemical balance and we are rapidly using up many of the Earth's natural resources.

Study tip

This chapter provides a context for the chemistry that you study. As such, it makes some general comments about the origins of the Earth and the nature of the natural resource cycles that occur. The list at the start of this chapter is similar to those given at the beginning of each chapter. It gives you an idea of the material in the chapter that is contained in the syllabus and that can therefore be examined.

1.1 Natural cycles and resources

There are a number of crucial cycles built into the nature of the resources of our planet.

The water cycle

The Earth is sometimes referred to as the 'blue marble' because of the predominance of water on the surface and the swirling cloud formations seen in satellite images. The Earth is distinctive in the solar system in that its surface temperature is such that all three states of water exist on the surface. There is a distinct **water cycle** taking place on the Earth's surface (Figure 1.2).

- ◆ The energy to drive this cycle comes from the Sun.
- ◆ Water evaporates from the sea and from other areas of water, such as lakes, and enters the atmosphere.

- ◆ As it cools, it changes back into liquid water and forms clouds (tiny water droplets).
- ◆ As the water droplets stick together, rain clouds are formed and the water falls back to the surface as rain, snow or hail.
- ◆ Water then either flows back to the sea or is taken in by plants, which put it back into the atmosphere through their leaves.
- ◆ We use the water by trapping it on its way back to the sea.

The carbon cycle

Carbon is only the twelfth most common element in the Earth, making up less than 1% of the crust. It is, however, very important to us. Without carbon, life would not exist. The way in which carbon moves around in the **carbon cycle** is vital to all life (Figure 1.3).

The source of the carbon in the cycle is carbon dioxide in the atmosphere. Only about 0.04% of the atmosphere is carbon dioxide.

Carbon dioxide leaves the atmosphere in the following ways:

- ◆ Green plants take carbon dioxide and water, combining them together to form glucose and oxygen. This process uses energy from the Sun and is called **photosynthesis**. The word equation for the reaction is:





Figure 1.2 The water cycle.




Figure 1.3 The carbon cycle.

- Carbon dioxide dissolves in water (mainly seawater), where it is used by animals and plants. Plants use it in photosynthesis; animals use it to make their shells.


This is what happens to the carbon once it has been captured from the atmosphere:

- The plants are eaten by animals.
- Animals and plants die and rot away, or they are buried and slowly (over millions of years) are fossilised.
- Tiny sea creatures die and their bodies fall to the bottom of the sea where they slowly (over millions of years) change to limestone.

These are the ways in which carbon dioxide is put back into the atmosphere:

- Animals and plants 'breathe out' carbon dioxide when they respire. The process of **respiration** uses oxygen from the air and releases carbon dioxide:
$$\text{glucose} + \text{oxygen} \rightarrow \text{carbon dioxide} + \text{water}$$
- When plants and animals decay after death, carbon dioxide is produced.

- Wood can be burnt. This **combustion** produces carbon dioxide:



- Fossilised plants and animals form **fossil fuels** (coal, oil and gas); these produce carbon dioxide when they are burnt.
- Limestone produces carbon dioxide when it is heated in industry and when it moves back below the Earth's crust.

The problem we face is balancing the amount of carbon dioxide being added to the atmosphere with the amount being taken out by plants and the oceans (Figure 1.4, overleaf).

The nitrogen cycle

Nitrogen is essential for plant growth and therefore for the life of animals (Figure 1.5, overleaf). There is plenty of nitrogen in the atmosphere (78%) but it is unreactive and so it is difficult to get it into the soil for plants to use.

Plants generally get their nitrogen from nitrates in the soil and animals get theirs from eating plants.




Figure 1.4 Maintaining the levels of oxygen and carbon dioxide in the air.

When plants and animals die and decay, bacteria help the decomposition and nitrogen is returned to the soil.

There are also bacteria that live in the roots of some plants (e.g. beans and clover) that can 'fix' nitrogen

from the atmosphere which the plants can then use. This process is called **nitrogen fixation**.

During thunderstorms, the very high temperature of the lightning provides enough energy to cause atmospheric nitrogen and oxygen to react with water in the atmosphere to form nitric acid. When this falls with rain, it forms nitrates in the soil. Nitrogen is also taken from the air by the chemical industry when fertiliser is made by the Haber process.

Taken together, these processes form the **nitrogen cycle** (Figure 1.5).

These three major cycles – of water, carbon and nitrogen – together with the rock cycle interlink and, between them, provide us with the resources we need.

The Earth's resources

In human terms, **resources** are materials we get from the environment to meet our needs. Some are the basic material resources we and other organisms need to keep alive; others are materials from which we obtain energy, or substances useful for our civilised way of life. Chemistry helps us to understand how the basic resources sustain our life. It also provides the methods of extraction and use of other resources.




Figure 1.5 The nitrogen cycle.

A Material resources can be broadly subdivided into **renewable**, **potentially renewable** and **non-renewable resources**, based on our short human timescale.

- ◆ **Non-renewable resources** are those that exist in a fixed quantity in the Earth's crust – for example, metallic and non-metallic minerals and fossil fuels. They were formed over millions of years and are being used up much faster than they are being formed.
- ◆ **Renewable resources** are those that essentially will never run out (are inexhaustible) – for example, wind, tides and direct solar energy.
- ◆ **Potentially renewable resources** can be renewed, but they will run out if we use them more quickly than they can be renewed. Examples include fresh water and air, fertile soil, and plant and animal biomass.

The biggest environmental concern is the depletion of non-renewable resources. Once they are used up, we will have to manage without them. Metal ores, especially those of iron, aluminium and copper, are becoming scarcer. The ores that still exist are often of low quality, making the process of extraction costly. Fossil fuels are another concern. New deposits of oil are being discovered but the speed at which we are using the oil we have is increasing. A time will come when all the oil, and eventually all the coal, will run out. Phosphate minerals, essential for the manufacture of fertilisers, are also becoming scarcer.

A number of these problems can be reduced by recycling some of the substances we use: recycling metals helps conserve metal ores and recycling plastics helps conserve the petroleum from which they are made. All recycling helps save energy, which comes mainly from fossil fuels.

Fossil fuels are a bigger problem. We will always need energy. A partial solution is to make more use of our renewable resources. Wind power, solar power and water power from rivers, tides and waves can all be used to generate electricity.

An increasing problem is the way in which our potentially renewable resources are being affected by overuse and pollution. The next three sections give more detail on these problems.

Questions

- 1.1 Coal is a fossil fuel produced from plant material underground over very long geological periods of time. What are petroleum and natural gas originally formed from?
- 1.2 How does the Sun keep the carbon cycle working?
- 1.3 Why are metallic and non-metallic minerals and fossil fuels thought of as non-renewable resources?
- 1.4 Write the word equations for:
 - a photosynthesis
 - b the complete combustion of carbon in air
 - c respiration.

S

1.2 The atmosphere

Uses of the gases of the air

Clean air has the following approximate composition: nitrogen 78%, oxygen 21%, argon 0.9% and 'other gases' (including carbon dioxide, water vapour, neon and other **noble gases**) 0.1% (Figure 1.6, overleaf).

Carbon dioxide is an important part of the air but makes up only about 0.04% of it. The carbon dioxide which is used by humans is not usually obtained from the air.

Nitrogen is used in the manufacture of ammonia and fertilisers in the **Haber process**. Liquid nitrogen is used in cryogenics (the storing of embryos and other types of living tissue at very low temperatures). Nitrogen is also sometimes used where an unreactive gas is needed to keep air away from certain products; for example, it is used to fill bags of crisps (chips) to ensure that the crisps do not get crushed or go rancid as a result of contact with oxygen in the air.

The biggest single use of oxygen is in the production of steel from cast iron. It is also used in oxyacetylene torches to produce the high-temperature flames needed to cut and weld metals. In hospitals, oxygen in cylinders is used to help the breathing of sick people.

S

Activity 1.1 Estimating the amount of oxygen in air

This is a demonstration of the reduction in volume when air is passed over heated copper.

A worksheet is included on the CD-ROM.



A




Figure 1.6 The development of the Earth's atmosphere.

Study tip

If you are asked for a use of oxygen, 'breathing' is not considered to be a correct answer because it is air rather than oxygen that we breathe. You need to give a use of pure oxygen.

Argon and other noble gases are used in different types of lighting. Argon is used to 'fill' light bulbs to prevent the tungsten filament burning away (Figure 1.7). It does not react with tungsten even at very high temperatures. The other noble gases are used in advertising signs

because they glow with different colours when electricity flows through them.

Before any of the gases in the air can be used separately, they have to be separated from the air in the atmosphere. The method used is fractional distillation, which works because the gases have different boiling points (Table 1.1).

Study tip

Remember to be careful with temperatures below 0°C (with a negative sign). The boiling point of nitrogen (-196°C) is a lower temperature than -183°C (the boiling point of oxygen).




Figure 1.7 Filament light bulbs contain argon which does not react with the hot tungsten filament.

Gas	Boiling point / °C	Proportion in mixture / %
carbon dioxide (sublimes)	-32	0.04
xenon	-108	— ^(a)
krypton	-153	— ^(a)
oxygen	-183	21
argon	-186	0.9
nitrogen	-196	78
neon	-246	— ^(a)
helium	-249	— ^(a)

^(a)All the other gases in the air make up 0.06% of the total.

Table 1.1 The boiling points of the gases in air.

Most countries produce electricity by burning coal or oil. Both these fuels are contaminated with sulfur, which produces sulfur dioxide when it burns:



Oxides of nitrogen (NO_x) (for example, nitrogen dioxide, NO_2) are also produced when air is heated in furnaces. These gases dissolve in rainwater to produce 'acid rain' (Figure 1.8, overleaf).

There are numerous effects of **acid rain**.


- ◆ Limestone buildings, statues, etc., are worn away.
- ◆ Lakes are acidified, and metal ions (for example, Al^{3+} ions) that are leached (washed) out of the soil damage the gills of fish, which may die.
- ◆ Nutrients are leached out of the soil and from leaves. Trees are deprived of these nutrients. Aluminium ions are freed from clays as aluminium sulfate, which damages tree roots. The tree is unable to draw up enough water through the damaged roots, and it dies.

The wind can carry acid rain clouds away from the industrialised areas, causing the **pollution** to fall on other countries.

One way to remedy the effects of acid rain is to add lime to lakes and the surrounding land to decrease the acidity. The best solution, however, is to prevent

The process of **fractional distillation** involves two stages.

- ◆ First the air must be cooled until it turns into a liquid (liquefies).
- ◆ Then the liquid air is allowed to warm up again. The various gases boil off one at a time at different temperatures.



Pollution of the air

Many gases are accidentally or deliberately released into the air. Some are harmless but many create problems for the environment. The main source of 'problem' gases is the burning of fossil fuels.





Figure 1.8 The formation of acid rain.

the acidic gases from being released in the first place. 'Scrubbers' are fitted to power station furnaces. In these devices, the acidic gases are passed through an alkaline substance such as lime. This removes the acids, making the escaping gases much less harmful. In many countries, though, acidic gases from power stations are still a serious problem.

Petrol (gasoline) and diesel for use in road transport have most of their sulfur removed when they are refined. Sulfur dioxide is not a serious problem with motor vehicles but the other contents of vehicle exhaust fumes (Figure 1.9) can cause problems. Nitrogen dioxide, for example, is still produced. The high temperature inside the engine's cylinders causes the nitrogen and oxygen in the air to react together:



Because of the lack of oxygen in the enclosed space of an engine, the fuel does not usually burn completely and carbon monoxide (CO) is formed.



Figure 1.9 Fumes from a car exhaust.

Another pollution problem arising from motor vehicles is caused by tetraethyl lead in petrol (leaded petrol). Burning this type of petrol releases the toxic metal lead into the environment (Figure 1.9). The use of lead in petrol has decreased significantly over the last 20 years. In 2011, the United Nations announced the successful, worldwide, phasing out of leaded petrol for road vehicles. There are only a handful of countries where it is still available.

The dangers of these pollutants are as follows.

- ◆ **Nitrogen dioxide** causes acid rain and can combine with other gases in very hot weather to cause **photochemical smog**. This contains low-level ozone and is likely to cause breathing problems, especially in people with asthma.
- ◆ **Carbon monoxide** is a highly toxic gas. It combines with the haemoglobin in blood and stops it from carrying oxygen. Even very small amounts of carbon monoxide can cause dizziness and headaches. Larger quantities cause death.
- ◆ **Lead** is a neurotoxic metal and can cause learning difficulties in children, even in small quantities. The body cannot easily get rid of lead, so small amounts can build up to dangerous levels over time.

There are solutions to some of these problems.

Catalytic converters can be attached to the exhaust systems of cars (Figure 1.10). These convert carbon monoxide and nitrogen dioxide into carbon dioxide and nitrogen. Unfortunately, if there is lead in the petrol being used, the **catalyst** becomes poisoned and will no longer work. This means that in countries

exhaust gases: unburnt fuel, carbon monoxide and nitrogen oxides, with carbon dioxide, water and nitrogen



exhaust gases: carbon dioxide, water and nitrogen




Figure 1.10 A catalytic converter changes harmful exhaust gases into safer gases.

where leaded petrol is still being used, catalytic converters cannot be used either.

Study tip

Try to keep these different atmospheric pollution problems clear and distinct in your mind rather than letting them merge together into one (confused?) problem. They each have distinct causes and clear consequences.

Figure 1.11 summarises the effects of the main pollutants of the air.




Figure 1.11 A summary of various atmospheric pollution problems caused by human activity.

Global warming and the 'greenhouse effect'

There are two gases in Figure 1.11, carbon dioxide and methane, which are not in the list of pollutants given so far. These, together with water vapour and oxides of nitrogen, are causing **global warming** due to the '**greenhouse effect**'. The Earth is warmed by the Sun but this heat would quickly escape if it were not for our atmosphere. It is always colder on a clear night because there are no clouds to keep the heat in. Some gases are better at keeping heat in than others; if there is too much of these gases in the atmosphere, the Earth gets warmer and this causes problems (Figure 1.12).




Figure 1.12 The greenhouse effect.

Some of the problems global warming will cause are listed below.

- ◆ Glaciers and polar ice will melt. This will cause a rise in sea level, and low-lying land will be flooded.
- ◆ The surface temperature of the Earth will increase. Deserts will spread and millions of people will have less water.
- ◆ Severe weather events will increase in frequency, and hurricanes and flooding will become more common.
- ◆ In some areas it may become easier to grow food crops but in others it will certainly become more difficult.

Carbon dioxide and methane are the two main problem gases; methane is around 20 times more effective at stopping heat escaping than carbon dioxide is.

Carbon dioxide enters the air through respiration and burning and it is removed by plants during photosynthesis. Burning more fuel and cutting down the forests increase the problem. Burning less fossil fuel and planting more trees would help to solve it.

Methane is produced by animals such as cows: it is a by-product of digesting their food. It emerges from both ends of the cow (but mostly from the mouth). Intriguingly, termites are also significant contributors to the methane in the atmosphere (Figure 1.13a). In addition, it is produced by the decay of food and other dead organic matter. It is produced in large quantities by rice paddy fields (Figure 1.13b) and landfill sites. Treating

organic waste so that the methane could be collected and burnt as fuel would help solve the problem.

The warming of the Arctic region in recent years has heightened our awareness of a further source of methane, known to scientists as 'fire ice' because it can ignite spontaneously. Melting of the Arctic ice and the consequent release of the large amount of the gas stored in the permafrost could have a huge economic and damaging environmental impact.

? Questions

- 1.5 Which gases contribute most significantly to acid rain?
- 1.6 How do the gases responsible for acid rain get into the atmosphere?
- 1.7 What are the problems caused by acid rain?
- 1.8 What is photochemical smog and why is it a problem?
- 1.9 How does carbon monoxide stop the blood from carrying oxygen?
- 1.10 Why are light bulbs filled with argon?
- 1.11 How does methane get into the air?
- 1.12 What is the 'greenhouse effect'?
- 1.13 What does a catalytic converter do to the exhaust gases from a car?
- 1.14 Why is it possible to separate the gases in the air by fractional distillation?



Figure 1.13 **a** A termite mound in Northern Territory, Australia – termites produce methane from digestion in their guts. **b** Terraced rice fields in Bali, Indonesia. Rice is the staple diet of about half the world's population.

1.3 Seas and rivers

There is plenty of water on the Earth but most of it is in seas and oceans and the salts dissolved in it make it unsuitable for many uses. The amount of fresh water (less than 3% of the total) is still sufficient but it is not always in the places where it is needed. Figure 1.14 shows how the Earth's water is distributed.

You will see from the diagram that less than a teaspoon of water out of every 100 dm³ is easily available for human use. This would be enough but it is not equally distributed around the world: rainforests can have more than 11 metres of rainfall in a year and desert areas less than one centimetre. There are places on Earth where it hasn't rained for more than ten years.

Water is essential to life but it can also carry disease. Polluted water kills many millions of people every year. It is important that the water we drink is treated to make it safe, and even more important that sewage (human and animal waste) is treated before being allowed back into rivers used for drinking water.

Water treatment

Water from rivers and lakes, and from underground, can contain dissolved salts, solid particles and bacteria.

The water purification process is designed to remove the last two of these. At its simplest, water treatment involves filtering the water to remove solid particles and adding chlorine to kill any bacteria that could cause disease.

Figure 1.15 (page 13) shows a modern water treatment process. The main difference from the simple treatment is in the use of ozone to remove pesticides and some other dissolved substances which can cause health problems. The water is still not totally pure as it contains some dissolved solids. Some of these, such as calcium salts, can aid health, whereas others, such as nitrate fertilisers, can be harmful.

In some parts of the world, seawater is made drinkable by **desalination** (taking the salt out). This can be done by distillation or by forcing the water through special membranes using high pressures (reverse osmosis). Desalination is particularly important in countries such as Saudi Arabia.

Our water supply is very important. Not only is it used in the home, as shown in Figure 1.16 (page 13), but it is also used in large quantities by industry. Most of the water used by industry is utilised as a solvent for other substances, to cool down reactions or to transfer heat from one part of a factory to another.




Figure 1.14 The availability of water on Earth.

Activity 1.2

Chemicals from seawater

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)


A03.3 Make and record observations, measurements and estimates

A03.4 Interpret and evaluate experimental observations and data


! Wear eye protection throughout.

Take care with hot apparatus and solutions.

The sea is mainly water but there are lots of other things in it too. The most common substance in seawater is sodium chloride, or common salt. Other substances in it include calcium sulfate, magnesium sulfate and tiny amounts of metals such as copper and iron.



This experiment is designed to show that seawater contains a mixture of different salts.



- 1 Place 200 cm³ of seawater in a 250 cm³ beaker.
- 2 Heat and boil the seawater.

- 3 Stop heating when about 60–70 cm³ of liquid remains. Solid will be precipitated during this evaporation process.
- 4 Allow to cool and let any solids settle.
- 5 Pour the clear liquid into a 100 cm³ beaker, leaving the solids behind.
- 6 Add a few drops of dilute hydrochloric acid to the solids left behind and observe what happens.
- 7 Put the 100 cm³ beaker on the tripod and gauze and heat the liquid until another solid appears. This will occur when about 30–40 cm³ of liquid remains.
- 8 Carefully filter the liquid into a conical flask.
- 9 Wash out the 100 cm³ beaker and pour the filtrate into the beaker.
- 10 Boil the liquid again until there is almost none left.
- 11 Let it cool and note what you observe.

The role of the oceans in the carbon cycle: exchanging carbon dioxide between the atmosphere and ocean

- 1 Pour 100 cm³ of seawater into one beaker and 100 cm³ of fresh (tap) water into another.
- 2 Add several drops of Universal Indicator to each so that the colour is clearly visible.
- 3 Next, using a straw, blow gently and consistently into the water samples – first the seawater, then the fresh water. In each case, time how long it takes the indicator to become yellow. Record the results.

? Questions

- A1 What evidence is there that seawater is a mixture of salts?
- A2 What gas is likely to have been given off when hydrochloric acid is added to the solids first collected?
- A3 What does this tell you about the identity of these solids?
- A4 Search the internet to try to find information about the solubilities of sodium chloride and calcium sulfate – two common compounds present in seawater. Use this information to predict the possible identity of the final solid left at the end of your experiment.




Figure 1.15 Purifying water for the domestic and industrial supply.




Figure 1.16 The main uses of water in a UK home. The numbers show how much water is used on average per person for each activity every day.

- ◆ Industry sometimes discharges toxic and harmful substances into rivers.
- ◆ Untreated **sewage** and other animal waste can be released into rivers, especially in areas where there are no sewers. Release of untreated sewage into rivers can lower oxygen levels by chemical reaction and cause the spread of harmful bacteria, increasing the risk of disease.
- ◆ The use of water for cooling by industry can result in warm water being discharged into rivers. Warm water can dissolve less oxygen than cold water, so animals living in the water may be left with insufficient oxygen. All of these, and others, lead to problems in rivers and lakes.

Questions

- 1.15 Why is water filtered before other treatments?
- 1.16 Why is chlorine added to water?
- 1.17 Why is distillation of seawater an expensive way of making drinking water?
- 1.18 What is the main danger of letting untreated sewage into rivers?
- 1.19 Why are nitrates from fertilisers dangerous in the water supply?

Pollution of the water supply

Issues concerning the pollution of water include the following:

- ◆ Nitrate fertilisers can be washed into streams and rivers from farmland. These nitrates are not removed by water treatment and can cause health problems for old people and for young children. They also cause waterways to become overloaded with nutrients, causing plant and algal growth.

1.4 The Earth's crust

The Earth's **crust** is the top layer of solid rock of the planet. As the Earth's crust moves, rock is constantly being taken down into the molten rock beneath the surface. This rock is changed and sometimes decomposed before it rises back to the surface and cools. These processes give rise to different types of rock and we extract some of those near the surface by mining and quarrying for human use. The decomposition also produces gases, mainly carbon dioxide and water vapour, which, together with molten rock, still escape from the Earth's **crust** through volcanoes.

This **rock cycle** is powered by energy produced by radioactive decay and heat from the Earth's **core**. It is a very slow process – the plates of the Earth's crust are moving only a few centimetres each year.

The crust varies in thickness from 5 km below some parts of the ocean to around 50 km in some parts of the land mass. Since the distance from the Earth's surface to its **core** is over 6000 km, the crust is a very thin surface layer. The crust is where the majority of the chemicals that we use come from.

Metal **ores** are rocks that have a relatively high concentration of a mineral containing a certain metal. For more details of ores and methods of obtaining metals from them, see Chapters 8 and 9.

Rocks can be used for building and for the extraction of useful chemicals other than metals. The most useful of these is **limestone**.

The limestone cycle

Limestone is an important resource from which a useful range of compounds can be made. Figure 1.17 shows some of the important uses of limestone and the related compounds quicklime and slaked lime. The reactions involved in producing these compounds can be imitated in the laboratory (Figure 1.18).

A piece of calcium carbonate can be heated strongly for some time to produce **lime** (quicklime, calcium oxide). The piece of lime is allowed to cool and then a few drops of water are added. The solid flakes and expands, crumbling into 'slaked lime'. This reaction is strongly **exothermic**. If more water is added, an alkaline solution (limewater) is obtained. The cycle can be completed by bubbling carbon dioxide into the solution. A white precipitate of calcium carbonate is formed. We can complete what is sometimes referred to as the **limestone cycle** (Figure 1.19).

Activity 1.3

Thermal decomposition of calcium carbonate

This activity illustrates some of the chemistry of limestone (calcium carbonate) and other materials made from it. The experiment demonstrates the 'limestone cycle'.

A worksheet is included on the CD-ROM.




Figure 1.17 Some of the uses of limestone (calcium carbonate).




Figure 1.18 The formation of quicklime and slaked lime in the laboratory.




Figure 1.19 The limestone cycle.

More detail on the importance of limestone and the chemicals derived from it can be found in Section 9.6. This includes the method of making lime industrially.

The problem of fossil fuels

The major **fossil fuels** are **coal**, **petroleum** (or **crude oil**) and **natural gas**. These are important sources of energy but are also very important as sources of raw materials for making plastics, drugs, detergents and

many other useful substances. For more detail of fossil fuels and their uses see Chapter 11.

If these resources were used not as fuels but only as a source of the chemicals we need, there wouldn't be a problem. They are, however, mostly used as fuels and they are a limited, non-renewable resource.

In 2007, it was estimated that the fossil fuel supplies we currently know about would last a further 43 years in the case of petroleum, 167 years for natural gas and 417 years for coal.

As more countries become industrialised, energy use in the world is increasing at an even faster rate than the population. Table 1.2 shows the sources of energy drawn on in the years 2006 and 2011.

The figures show how relatively little energy is obtained from sources other than fossil fuels, with the figure for coal showing a notable increase between 2006 and 2011. Hydroelectric power (6.4%) and nuclear energy (4.9%) do make a contribution, although the figure for nuclear energy has fallen in this time. In 2011, only 1.6% of energy came from solar power, wind power and wave power combined.

Clearly change is necessary (Figure 1.20). The Sun is the greatest provider of energy to the Earth. The amount of solar energy falling on the Earth's surface is immensely vast. In one year it is about twice as much as will ever be obtained from all of the Earth's non-renewable resources combined.

Hydrogen is one possible fuel for the future, either as a substance to burn or for use in fuel cells.

Energy source	Percentage of energy from this source / %	
	for 2006	for 2011
petroleum	36.8	33.1
coal	26.6	30.3
natural gas	22.9	23.7
hydroelectric power	6.3	6.4
nuclear energy	6.0	4.9
renewables (solar, wind, etc.)	1.4	1.6

Table 1.2 The sources of energy used worldwide in 2006 and 2011.




Figure 1.20 Renewable energy resources suitable for development to reduce our dependence on fossil fuels.

Hydrogen as a fuel

Hydrogen gas has attractions as a **fuel**. All it produces on burning is water. When hydrogen burns, it produces more energy per gram than any other fuel (Figure 1.21).

A future 'hydrogen economy' has been talked about, but there are problems of storage and transport. The gas itself is difficult to store and transport because of its low density. The first vehicles to run on hydrogen were the rockets of the US space programme. Hydrogen is not cheap. The main method of obtaining it on a large scale is by the electrolysis of water. However, this is not very economical. It is possible that cheap surplus electricity from nuclear power may make electrolysis more economical. Others have suggested the use of electricity from solar power.

Despite these difficulties, prototype hydrogen-powered cars have been tried. Nissan and Mazda in Japan, and BMW and Daimler-Benz in Germany, are among those who have built and tested cars. The Japanese prototype burns the hydrogen in the engine, while the German-Swiss-British venture uses the hydrogen in a **fuel cell**. Electricity from this cell then powers an electric motor (Figure 1.22). Using a fuel cell operating an electric motor, hydrogen has an efficiency of 60% compared with 35% for a petrol engine. The 'hydrogen economy' may have life in it yet! The advantages and disadvantages are summarised in Table 1.3.




Figure 1.21 The energy produced on burning one gram of various fuels, to produce water and carbon dioxide. Hydrogen produces more energy per gram than any other fuel.

S

A

S

S





Figure 1.22 a How a car runs on a hydrogen fuel cell. The car is powered by electrons released at the negative electrode (anode). Inside the fuel cell, hydrogen ions move to the positive electrode (cathode), where they react with oxygen to form water. b They are regarded as non-renewable because they were formed over very long periods of time and are being used up at a rate far faster than they can be formed. c These hydrogen-powered minicabs are part of a development project at the University of Birmingham in the UK.

Advantages

- ◆ renewable if produced using solar energy
- ◆ lower flammability than gasoline (petrol)
- ◆ virtually emission-free
- ◆ zero emissions of CO_2
- ◆ non-toxic

Disadvantages

- ◆ non-renewable if generated using nuclear energy or energy from fossil fuels
- ◆ large fuel tank required
- ◆ as yet there are very few 'filling stations,' where a car could be topped up with hydrogen
- ◆ engine redesign needed or a fuel cell system
- ◆ currently expensive

Table 1.3 The advantages and disadvantages of hydrogen as a fuel for motor vehicles.

Activity 1.4 Hydrogen power – communicating the benefits

Groups of students are to design a flyer, leaflet or web page to be used as publicity by a car dealership outlining the issues and benefits of hydrogen-powered cars. Use the internet to find information.

A worksheet is included on the CD-ROM.

Activity 1.5 Using solar and hydrogen power


This demonstration connects a small solar panel to a proton exchange membrane (PEM) fuel cell. In this mode, the cell acts as an electrolyser and can decompose distilled water into its elements. The experiment can then be reversed and the gases collected can be used to power the fuel cell to drive a small electric fan.

A worksheet is included on the CD-ROM.

Hydrogen fuel cells

Research has found a much more efficient way of changing chemical energy into electrical energy by

S using a fuel cell. A hydrogen fuel cell can be used to power a car. Such a cell operates continuously, with no need for recharging. The cell supplies energy as long as the reactants are fed in to the electrodes. The overall reaction of the hydrogen–oxygen fuel cell is:



A Land pollution

Cities throughout the world are covered in litter. Some make an effort to control it but it is always there. Most of our waste material is buried and this can lead to problems. Toxic and radioactive waste can make the land unusable and many countries strictly control what can be buried and where. Companies are required, by law, to treat their waste products to make them as harmless as possible.

Domestic waste should be recycled whenever possible. Waste that cannot be treated in this way should be burned to create energy. If it is left in landfill sites, it decays, producing methane gas (by a process known as

anaerobic decay). Methane is much more harmful to the environment than the carbon dioxide produced by burning it, as methane is a more powerful greenhouse gas.

? Questions

- 1.20** What makes an ore different from any other type of rock?
- 1.21** What is the difference between lime and slaked lime?
- 1.22** What useful chemicals can be made from petroleum?
- 1.23** What makes a gas a 'greenhouse gas'?
- 1.24** Currently what is the main source of hydrogen for use as a fuel? What is a disadvantage of this method?
- 1.25** Give an advantage of using hydrogen as a fuel.
- 1.26** What is the essential reaction taking place in a hydrogen fuel cell? Give the word and balanced chemical equations for the reaction.

Summary

You should know:

- S** ◆ that there are important natural cycles that involve the movement of resources within the Earth's ecology
- S** ◆ that there is a third important natural cycle, the carbon cycle, which involves the key processes of photosynthesis and respiration
- ◆ that the air is composed predominantly of nitrogen and oxygen, but that other gases have major roles to play too
- ◆ about the major atmospheric pollution problems that are changing the nature of our world, including global climate change and acid rain
- ◆ that global warming is caused by an increase in the atmosphere of certain 'greenhouse gases' such as carbon dioxide and methane
- S** ◆ how the gases of the air can be separated by the fractional distillation of liquid air, and that the separated gases have their own uses
- ◆ how the availability of clean fresh water is one of the major problems in the world
- ◆ how mineral ores and petroleum provide sources of metals and chemicals for industrial use
- ◆ that limestone, one of these mineral resources, has a range of uses, from the making of cement and concrete to the extraction of iron in the blast furnace
- ◆ that hydrogen is one possible new energy source that is currently under development – it is seen as an environmentally clean fuel because the only product of its combustion is water
- S** ◆ how the hydrogen fuel cell is based on the production of electrical power using the combustion reaction for hydrogen and can be used to power cars.

End-of-chapter questions


- 1 The carbon cycle is of vital importance to life. Explain how it is dependent on energy from the Sun.
- 2 Water is present in the atmosphere, in the seas and in ice and snow.
 - a Describe a chemical test for water. Give the test and the result. [2]
 - b State **one** use of water in industry. [1]
 - c Water is a good solvent. What do you understand by the term *solvent*? [1]
 - d Water vapour in the atmosphere reacts with sulfur dioxide, SO_2 , to produce acid rain.
 - i State **one** source of sulfur dioxide. [1]
 - ii State **two** adverse effects of acid rain. [2]
 - iii Calculate the relative molecular mass of sulfur dioxide. [1]
 - e Water from lakes and rivers can be treated to make the water safer to drink. Describe **two** of the steps in water purification. For each of these steps, give an explanation of its purpose. [4]
 - f Water is formed when hydrogen burns in air. State the percentage of oxygen present in the air. [1]

[Cambridge IGCSE® Chemistry 0620/21, Question 3(a–e & f(i)), June 2011]


- 3 Two important greenhouse gases are methane and carbon dioxide.
 - a Methane is twenty times more effective as a greenhouse gas than carbon dioxide. The methane in the atmosphere comes from both natural and industrial sources.
 - i Describe **two** natural sources of methane. [2]
 - ii Although methane can persist in the atmosphere for up to 15 years, it is eventually removed by oxidation. What are the products of this oxidation? [2]
 - b How do the processes of respiration, combustion and photosynthesis determine the percentage of carbon dioxide in the atmosphere? [4]

[Cambridge IGCSE® Chemistry 0620/31, Question 2, November 2011]

- 4 Fuel cells are used in spacecraft to produce electrical energy.



- a How is oxygen obtained from liquid air? [2]
- b Hydrogen and oxygen react to form water.




- i Give an example of bond breaking in the above reaction. [1]
- ii Give an example of bond forming in the above reaction. [1]
- iii Is the change given in i exothermic or endothermic? [1]

- S**
- c i Give **two** reasons why hydrogen may be considered to be the ideal fuel for the future. [2]
ii Suggest a reason why hydrogen is not widely used at the moment. [1]

[Cambridge IGCSE® Chemistry 0620/32, Question 5, June 2010]

- 5 The diagram shows part of the carbon cycle. This includes some of the processes that determine the percentage of carbon dioxide in the atmosphere.



- a Carbon dioxide is one greenhouse gas. Name another one. [1]
b Explain the term *respiration* and how this process increases the percentage of carbon dioxide in the atmosphere. [3]
c Explain why the combustion of waste crop material should not alter the percentage of carbon dioxide in the atmosphere. [2]
d In 1960 the percentage of carbon dioxide in the atmosphere was 0.032% and in 2008 it was 0.038%. Suggest an explanation for this increase. [2]

[Cambridge IGCSE® Chemistry 0620/31, Question 7, November 2010]

2

The nature of matter

In this chapter, you will find out about:

- ◆ the three states of matter, and changes of state
- ◆ separating and purifying substances
- ◆ filtration
- ◆ use of a separating funnel
- ◆ evaporation and crystallisation
- ◆ distillation
- ◆ paper chromatography
- ◆ criteria of purity
- ◆ elements and compounds
- ◆ atomic theory
- ◆ the kinetic model and changes of state
- ◆ diffusion
- ◆ Brownian motion
- ◆ atomic structure and subatomic particles
- ◆ proton (atomic) number and nucleon (mass) number
- ◆ isotopes
- ◆ relative atomic mass
- ◆ uses of radioactivity
- ◆ the arrangement of electrons in atoms.

Lord of the rings

Saturn is perhaps the most beautiful of the planets of the Solar System. It has fascinated astronomers because of its mysterious rings (Figure 2.1). The Pioneer, Voyager and Cassini–Huygens space-probes sent back a great deal of information on the nature of the rings and the mass of Saturn itself.

Each ring is made up of a stream of icy particles, following each other nose-to-tail around



Figure 2.1 Saturn and its rings silhouetted against the Sun: a photograph taken by the Cassini probe. The rings are made of ice and dust.

the planet. The particles can be of widely varying sizes. The rings resemble a snowstorm, in which tiny snowflakes are mixed with snowballs up to the size of a house. The ice that surrounds one of the most spectacular planets of our solar system is made of water – the same substance (with the same formula) that covers so much of the Earth's surface.

The planet of Saturn is made of gases, mainly hydrogen and helium. Deep in the centre of these lightweight gases is a small rocky core, surrounded by a liquid layer of the gases. The hydrogen is liquid because of the high pressure in the inner regions of the planet nearest the core. The liquid hydrogen behaves with metallic properties. Study of Saturn's physical structure emphasises how substances that we know on Earth can exist in unusual physical states in different environments.

How do changing conditions affect the appearance, properties and behaviour of different substances?

2.1 The states of matter

There are many different kinds of **matter**. The word is used to cover all the substances and materials of which the Universe is composed. Samples of all of these materials have two properties in common: they each occupy space (they have volume) and they have mass.

Chemistry is the study of how matter behaves, and of how one kind of substance can be changed into another. Whichever chemical substance we study, we find it can exist in three different forms (or physical states) depending on the conditions. These three different **states of matter** are known as **solid**, **liquid** and **gas**. Changing temperature and/or pressure can change the state in which a substance exists.

The different physical states have certain general characteristics that are true whatever chemical substance is being considered. These are summarised in Table 2.1.

Key definition

matter – anything that has mass and takes up space. There are three physical states: solid, liquid and gas.

The three physical states show differences in the way they respond to changes in temperature and pressure. All three show an increase in volume (an expansion) when the temperature is increased, and a decrease in volume (a contraction) when the temperature is lowered. The effect is much bigger for a gas than for either a solid or a liquid.

The volume of a gas at a fixed temperature can easily be reduced by increasing the pressure on the gas.

Gases are easy to ‘squash’ – they are easily compressed. Liquids, on the other hand, are only slightly compressible, and the volume of a solid is unaffected by changing the pressure.

Changes in physical state

Large changes in temperature and pressure can cause changes that are more dramatic than expansion or contraction. They can cause a substance to change its physical state. The changes between the three states of matter are shown in Figure 2.2. At atmospheric pressure, these changes can be brought about by raising or lowering the temperature of the substance.

Melting and freezing

The temperature at which a pure substance turns to a liquid is called the **melting point** (m.p.). This always happens at one particular temperature for each pure substance (Figure 2.3). The process is reversed at precisely the same temperature if a liquid is cooled down. It is then called the **freezing point** (f.p.). The melting point and freezing point of any given substance are both the same temperature. For example, the melting and freezing of pure water take place at 0 °C.

Gallium is a metal that has a melting point just above room temperature. Because of this it will melt in a person's hand (Figure 2.4).

Sublimation

A few solids, such as carbon dioxide (‘dry ice’), do not melt when they are heated at normal pressures. Instead, they turn directly into gas. This change of state is called **sublimation**: the solid **sublimes**. Like melting, this also happens at one particular temperature for each pure solid. Iodine is another solid that sublimes. It produces

Physical state	Volume	Density	Shape	Fluidity
solid	has a fixed volume	high	has a definite shape	does not flow
liquid	has a fixed volume	moderate to high	no definite shape – takes the shape of the container	generally flows easily ^(a)
gas	no fixed volume – expands to fill the container	low	no definite shape – takes the shape of the container	flows easily ^(a)

^(a)Liquids and gases are called **fluids**.

Table 2.1 Differences in the properties of the three states of matter.




Figure 2.2 Changes of physical state and the effect of increasing temperature at atmospheric pressure.




Figure 2.3 The relationship between the melting point and boiling point of a substance.

a purple vapour, but then condenses again on a cold surface (Figure 2.5, overleaf).

Evaporation, boiling and condensation

If a liquid is left with its surface exposed to the air, it evaporates. Splashes of water evaporate at room temperature. After rain, puddles dry up! When liquids change into gases in this way, the process is called **evaporation**. Evaporation takes place from the surface of the liquid. The larger the surface area, the faster the liquid evaporates.




Figure 2.4 The metal gallium has a melting point just above room temperature. It will literally melt in the hand.

The warmer the liquid is, the faster it evaporates. Eventually, at a certain temperature, it becomes hot enough for gas to form within the liquid and not just at the surface. Bubbles of gas appear inside the liquid. This process is




Figure 2.5 Iodine sublimes. On warming, it produces a purple vapour which then condenses again on the cool part of the tube.

known as **boiling**. It takes place at a specific temperature, known as the **boiling point** (b.p.) for each pure liquid (Figure 2.3). Water evaporates fairly easily and has a relatively low boiling point – it is quite a **volatile** liquid. Ethanol, with a boiling point of 78°C , is more volatile than water. It has a higher **volatility** than water.

- ◆ A **volatile** liquid is one which evaporates easily and has a relatively low boiling point.
- ◆ Ethanol (b.p. 78°C) is a more volatile liquid than water (b.p. 100°C).

The reverse of evaporation is **condensation**. This is usually brought about by cooling. However, we saw earlier that the gas state is the one most affected by changes in pressure. It is possible, at normal temperatures, to condense a gas into a liquid by increasing the pressure, without cooling.

The boiling point of a liquid can change if the surrounding pressure changes. The value given for the boiling point is usually stated at the pressure of the atmosphere at sea level (**atmospheric pressure** or **standard pressure**). If the surrounding pressure falls,

the boiling point falls. The boiling point of water at standard pressure is 100°C . On a high mountain it is lower than 100°C . If the surrounding pressure is increased, the boiling point rises. In a pressure cooker, the boiling point of water is raised to around 120°C and food cooks more quickly at this higher temperature.

Pure substances

A **pure substance** consists of only one substance. There is nothing else in it: it has no contaminating impurities. A pure substance melts and boils at definite temperatures. Table 2.2 shows the melting points and boiling points of some common substances at atmospheric pressure.

The values for the melting point and boiling point of a pure substance are precise and predictable. This means that we can use them to test the purity of a sample. They can also be used to check the identity of an unknown substance. The melting point can be measured using an electrically heated melting-point apparatus (Figure 2.6). A capillary tube is filled with a small amount of the solid and is placed in the heating block. The melting is viewed through a magnifying lens.

A substance's melting and boiling points in relation to room temperature (taken as 20°C) determine whether it is usually seen as a solid, a liquid or a gas. For example,

Substance	Physical state at room temperature (20°C)	Melting point/ $^{\circ}\text{C}$	Boiling point/ $^{\circ}\text{C}$
oxygen	gas	-219	-183
nitrogen	gas	-210	-196
ethanol (alcohol)	liquid	-117	78
water	liquid	0	100
sulfur	solid	115	444
common salt (sodium chloride)	solid	801	1465
copper	solid	1083	2600
carbon dioxide	gas	$-78^{(a)}$	

^(a)Sublimes.

Table 2.2 The melting and boiling points of some common chemical substances.




Figure 2.6 An electrical melting-point apparatus.

if the m.p. is below 20°C and the b.p. is above 20°C , the substance will be a liquid at room temperature.

Study tip

Remember to practise using melting and boiling point data to decide whether a particular substance is a solid, a liquid or a gas at room temperature. These are quite common questions.

Be careful with temperatures below 0°C ; -100°C is a higher temperature than -150°C .

The effect of impurities

Seawater is impure water. You can show this if you put some seawater in an evaporating dish and boil away the water, because a solid residue of salt is left behind in the dish. Seawater freezes at a temperature well below the freezing point of pure water (0°C) and boils at a temperature above the boiling point of pure water (100°C). Other impure substances show similar differences.

In addition, the impurity can also reduce the 'sharpness' of the melting or boiling point. An impure

substance sometimes melts or boils over a range of temperatures, not at a particular point.

The presence of an impurity in a substance:

- ◆ lowers the melting point, and
- ◆ raises the boiling point of the substance.

Study tip

Remember that pure substances have definite, sharp melting and boiling points. The presence of an impurity means that these changes will be spread over a range of temperatures in each case.

Heating and cooling curves

The melting point of a solid can also be measured using the apparatus shown in Figure 2.7. A powdered solid is put in a narrow melting-point tube so that it can be heated easily. An oil bath is used so that melting points above 100°C can be measured. We can follow the temperature of the sample before and after melting. These results can then be used to produce a heating curve (Figure 2.8, overleaf). Similar apparatus can be used to produce a cooling curve but the thermometer must be placed in a test tube containing the solid being studied.

Figure 2.8 shows how the temperature changes when a sample of solid naphthalene (a single pure substance) is heated steadily. The solid melts at precisely 80°C . Notice that, while the solid is melting, the temperature stops rising. It will only begin to rise again when all the




Figure 2.7 Apparatus for measuring the melting point of a solid. A water bath can be used for melting points below 100°C and an oil bath for those above 100°C .




Figure 2.8 The heating curves for naphthalene (a pure substance) and wax (a mixture of substances).

naphthalene has melted. Generally, the heating curve for a pure solid stops rising at its melting point. The heating curve for wax, which is a mixture of substances, shows the solid wax melting over a **range** of temperatures.

It is possible to heat a liquid in the same apparatus until its boiling point is reached. Again, the temperature stays the same until all the liquid has boiled. The reverse processes can be shown if a sample of gas is allowed to cool. This produces a cooling curve (Figure 2.9). The level portions of the curve occur where the gas condenses to a liquid, and when the liquid freezes.

These experiments show that heat energy is needed to change a solid into a liquid, or a liquid into a gas. During the reverse processes, heat energy is given out.




Figure 2.9 The cooling curve for a substance. The temperature stays constant while the gas condenses, and while the liquid freezes. A cooling mixture of ice and salt could be used to lower the temperature below 0°C.

When a solid is melted, or a liquid is boiled, the temperature stays constant until the process is complete. The same is true in reverse when a gas condenses or a liquid freezes.

Activity 2.1 Plotting a cooling curve

In this experiment, you will plot cooling curves for two different substances.

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

A worksheet, with a self-assessment checklist, is included on the accompanying CD-ROM.

Adaptations of this experiment and details of the use of it in assessing practical skills A03.3 and A03.4 are given in the Notes on Activities for teachers/technicians.

Types of mixture

Our world is very complex, owing to the vast range of pure substances available and to the variety of ways in which these pure substances can mix with each other. In everyday life, we do not 'handle' **pure** substances very often. The air we breathe is not a single, pure substance – and we could not live in it if it were! Water would be rather tasteless if we drank it pure (distilled).

Each **mixture** must be made from at least two parts, which may be solid, liquid or gas. There are a number of different ways in which the three states can be combined. In some, the states are completely mixed to become one single state or phase – 'you cannot see the join.' Technically, the term **solution** is used for this type of mixture.

Solid salt dissolves in liquid water to produce a liquid mixture – a salt solution (Figure 2.10). In general terms, the solid that dissolves in the




Figure 2.10 When a solute dissolves in a solvent, the solute particles are completely dispersed in the liquid.

liquid is called the **solute**. The liquid in which the solid dissolves is called the **solvent**. In other types of mixture, the states remain separate. One phase is broken up into small particles, droplets, or bubbles, within the main phase. Perhaps the most obvious example of this type of mixture is a **suspension** of fine particles of a solid in a liquid, such as we often get after a precipitation reaction.

Solutions

There are various ways in which substances in different states can combine. Perhaps the most important idea here is that of one substance dissolving in another – the idea of a **solution**. We most often think of a solution as being made of a solid dissolved in a liquid. Two-thirds of the Earth's surface is covered by a solution of various salts in water. The salts are totally dispersed in the water and cannot be seen. However, other substances that are not normally solid are dissolved in seawater. For example, the dissolved gases, oxygen and carbon dioxide, are important for life to exist in the oceans.

Less obvious perhaps, but quite common, are solutions of one liquid in another. Alcohol mixes (dissolves) completely with water. Beer, wine and whisky do not separate out into layers of alcohol and water (even when the alcohol content is quite high). Alcohol and water are completely **miscible**: they make a solution.

Alloys are similar mixtures of metals, though we do not usually call them solutions. They are made by mixing the liquid metals together (dissolving one metal in the other) before solidifying the alloy.

Questions

- 2.1 Give the names for the following physical changes:
 - a liquid to solid
 - b liquid to gas at a precise temperature
 - c gas to liquid
 - d solid to gas directly.
- 2.2 What effect does the presence of an impurity have on the freezing point of a liquid?
- 2.3 Sketch a cooling curve for water from 80°C to -20°C , noting what is taking place in the different regions of the graph.
- 2.4 What do you understand by the word **volatile** when used in chemistry?
- 2.5 Put these three liquids in order of **volatility**, with the most volatile first: water (b.p. 100°C), ethanoic acid (b.p. 128°C), ethanol (b.p. 78°C).

2.2 Separating and purifying substances

To make sense of the material world around us, we need methods for physically separating the many and varied mixtures that we come across. Being able to purify and identify the many substances present in these mixtures not only satisfies our curiosity but is crucial to our well-being and health. There is a range of physical techniques available to make the necessary separations (Table 2.3, overleaf). They all depend in some way on a difference in the physical properties of the substances in the mixture.

The most useful separation method for a particular mixture depends on:

- ♦ the type of mixture, and
- ♦ which substance in the mixture we are most interested in.

Separating insoluble solids from liquids

In some ways these are the easiest mixtures to separate. Quite often, just leaving a suspension of a solid in a liquid to stand achieves a separation – especially if the particles of solid are large enough. Once the solid has settled to the bottom, the liquid can be carefully poured off – a process called **decanting**.

Mixture	Method of separation
solid + solid (powdered mixture)	use some difference in properties, e.g. density, solubility, sublimation, magnetism
suspension of solid in liquid	filtration or centrifugation
liquid + liquid (immiscible)	use a separating funnel or decantation
solution of solid in liquid	to obtain solid: use evaporation (crystallisation) to obtain liquid: use distillation
two (or more) liquids mixed together (miscible)	fractional distillation
solution of two (or more) solids in a liquid	chromatography

Table 2.3 Separating different types of mixture.

A more generally useful method for separating solids from liquids is **filtration** (Figure 2.11a). Here the insoluble material is collected as a **residue** on filter paper. Filtration is useful because both phases can be obtained in one process. The liquid phase is collected as the **filtrate**. The process can be speeded up by using a vacuum pump to 'suck' the liquid through the filter paper in a Buchner funnel and flask (Figure 2.11b). Various large-scale filtration methods are used in industry. Perhaps the most useful of these are the filter beds used to treat water for household use.

Another method of separating an insoluble solid from a liquid is **centrifugation** where the mixture is spun at high speed in a centrifuge. This causes the solid to be deposited at the bottom of the centrifuge tube. The liquid can be carefully decanted off.

Separating immiscible liquids

Mixtures of two **immiscible** liquids can be separated if the mixture is placed in a separating funnel and allowed to stand. The liquids separate into different layers. The lower, denser layer is then 'tapped' off at the bottom (Figure 2.12). This type of separation is useful in industry. For example, at the base of the blast furnace the molten slag forms a separate layer on top of the liquid iron. The two can then be 'tapped' off separately.




Figure 2.11 Filtration separates an insoluble solid from a liquid.

Separating mixtures of solids

The separation of a solid from a mixture of solids depends largely on the particular substance being purified. Some suitable difference in physical properties needs to be found. Usually it helps if the mixture is ground to a powder before any separation is attempted.

Separations based on differences in density

'Panning' for gold is still carried out in the search for new deposits. In Amazonia, river-beds are mechanically sifted ('vacuum-cleaned') to collect gold dust. These methods depend on the gold dust being denser than the other substances in the river sediment. This type of method is also used in purifying the ores of zinc and copper, although in these cases the metals are less dense than the ores and so float on the surface.

Separations based on magnetic properties

Magnetic iron ore can be separated from other material in the crushed ore by using an electromagnet. In the Amazonian gold diggings, magnets are used to clean away iron-containing, red-brown dust from the powdered gold. In the environmentally and economically important




Figure 2.12 **a** A separating funnel can be used to separate two immiscible liquids. **b** Oil and water in a separating funnel.

processes of recycling metals, iron objects can be picked out from other scrap metal using electromagnets.

Activity 2.2 Separating common salt and sand

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

The aim of this activity is to separate a mixture of salt and sand. The method uses the difference in solubility of the two solids and the technique of filtration.

A worksheet, with a self-assessment checklist, is included on the accompanying CD-ROM.

Separations based on differences in solubility

One very useful way of separating a soluble substance from a solid mixture is as follows. The mixture is first ground to a powder. A suitable liquid solvent is added. The solvent must dissolve one of the solid substances present, but not the others. The solvent is often water, but other liquids can be useful. The mixture in the solvent is then warmed and stirred. Care must be taken at the warming stage when using solvents other than water. The warm mixture is then filtered (Figure 2.11). This leaves the insoluble substances as a residue on the

filter paper, which can be dried. The soluble substance is in the liquid filtrate. Dry crystals can be obtained by evaporation and **crystallisation**, see Figure 2.14.

Separations based on sublimation

A solid that sublimates can be separated from others using this property (Figure 2.13).

Separating solutions

The separation of this type of mixture is often slightly more complicated because there is no physical separation of the phases in the original mixture. The methods of separation usually depend on solubility properties or on differences in boiling point (or volatility).




Figure 2.13 Ammonium chloride can be separated from a mixture because it sublimates. The crystals condense on the cooled surface.




Figure 2.14 An evaporation method. This method should not be used if the solvent is flammable. Instead, use an electrical heating element and an oil or water bath.

Separating a solid from solution in a liquid can be carried out by evaporation or crystallisation. Evaporation gives only a powder, but crystallisation can result in proper crystals. Both processes begin by evaporating away the liquid but, when crystals are needed, evaporation is stopped when the solution has been concentrated enough. Figure 2.14 shows how this can be judged and done safely. The concentrated solution is allowed to cool slowly. The crystals formed can then be filtered off and dried.

Separating a liquid from a solution is usually carried out by **distillation** (Figure 2.15). The boiling point of the liquid is usually very much lower than that of the dissolved solid. The liquid is more volatile than the dissolved solid and can easily be evaporated off in a distillation flask. It is condensed by passing it down a water-cooled condenser, and then collected as the **distillate**.

Separating the liquids from a mixture of two (or more) miscible liquids is again based on the fact that




Figure 2.15 The distillation of seawater.

the liquids will have different boiling points. However, the boiling points are closer together than for a solid-in-liquid solution and **fractional distillation** must be used (Figure 2.16). In fractional distillation the most volatile liquid in the mixture distils over first and the least volatile liquid boils over last.

For example, ethanol boils at 78°C whereas water boils at 100°C . When a mixture of the two is heated, ethanol and water vapours enter the **fractionating column**. Glass beads in the column provide a large surface area for condensation (Figure 2.16b). Evaporation and condensation take place many times as the vapours rise up the column. Ethanol passes through the condenser first as the temperature of the column is raised above its




Figure 2.16 **a** Separating a mixture of ethanol (alcohol) and water by fractional distillation. **b** A close-up of the glass beads in the column.

boiling point. Water condenses in the column and flows back into the flask because the temperature of the column is below its boiling point of 100°C .

The temperature on the thermometer stays at 78°C until all the ethanol has distilled over. Only then does the temperature on the thermometer rise to 100°C and the water distil over. By watching the temperature carefully, the two liquids (**fractions**) can be collected separately.

Fractional distillation is used to separate any solution containing liquids with different boiling points. The liquid in the mixture with the lowest boiling point (the most volatile) distils over first. The final liquid to distil over is the one with the highest boiling point (the least volatile). Fractional distillation can be adapted as a continuous process and is used industrially to separate:

- ♦ the various fractions from petroleum (page 276),
- ♦ the different gases from liquid air (page 7).

Study tip

In fractional distillation remember that it is the liquid with the lowest boiling point that distils over first.

Activity 2.3 Distillation of mixtures

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates

In this experiment, several mixtures will be separated using different types of distillation apparatus, including a microscale distillation apparatus.

A worksheet is included on the CD-ROM.

Separating two or more dissolved solids in solution can be carried out by **chromatography**. There are

several types of chromatography, but they all follow the same basic principles. Paper chromatography is probably the simplest form to set up and is very useful if we want to analyse the substances present in a solution. For example, it can tell us whether a solution has become contaminated. This can be very important because contamination of food or drinking water, for instance, may be dangerous to our health.

A drop of concentrated solution is usually placed on a **pencil** line near the bottom edge of a strip of chromatography paper. The paper is then dipped in the solvent. The level of the solvent must start below the sample. Figure 2.17 (overleaf) shows the process in action.

Many different solvents are used in chromatography. Water and organic solvents (carbon-containing solvents) such as ethanol, ethanoic acid solution and propanone are common. Organic solvents are useful because they dissolve many substances that are insoluble in water. When an organic solvent is used, the process is carried out in a tank with a lid to stop the solvent evaporating.

Activity 2.4 Investigation of food dyes by chromatography

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

This experiment involves testing some food colours with paper chromatography to find out if they are pure colours or mixtures of several dyes. These food colours are used in cake making, for instance, and there is quite a wide range of permitted colours readily available.

A worksheet is included on the CD-ROM.

Adaptations of this experiment are given in the Notes on Activities for teachers/technicians.




Figure 2.17 **a** Various stages during paper chromatography. The sample is separated as it moves up the paper. **b** A paper chromatogram.

S The substances separate according to their solubility in the solvent. As the solvent moves up the paper, the substances are carried with it and begin to separate. The substance that is most soluble moves fastest up the paper. An insoluble substance would remain at the origin. The run is stopped just before the **solvent front** reaches the top of the paper.

The distance moved by a particular spot is measured and related to the position of the solvent front. The ratio of these distances is called the **R_f value**, or retention factor. This value is used to identify the substance:

$$R_f = \frac{\text{distance moved by the substance}}{\text{distance moved by the solvent front}}$$

Originally, paper chromatography was used to separate solutions of coloured substances (dyes and pigments) since they could be seen as they moved up the paper. However, the usefulness of chromatography has been greatly increased by the use of **locating agents** (Figure 2.18). These mean that the method can also be used for separating substances that are not coloured. The paper is treated with locating agent after the chromatography

run. The agent reacts with the samples to produce coloured spots.

Chromatography has proved very useful in the analysis of biologically important molecules such as sugars, amino acids and nucleotide bases. In fact, molecules such as amino acids can be 'seen' if the paper **chromatogram** is viewed under ultraviolet light.

The purity and identity of substances

Paper chromatography is one test that can be used to check for the **purity** of a substance. If the sample is pure, it should only give **one** spot when run in several different solvents. The **identity** of the sample can also be checked by comparing its R_f value to that of a sample we know to be pure.

Probably the most generally used tests for purity are measurements of melting point or boiling point. As we saw earlier, impurities would lower the melting point or raise the boiling point of the substance. They would also make these temperatures less precise. These temperatures have been measured for a very wide range of substances. The identity of an unknown substance can be found by checking against these measured values for known pure substances.




Figure 2.18 Chromatography using a locating agent to detect the spots on the paper. Alternatively, the locating agent can be sprayed on the paper.

The process of purification is of crucial importance in many areas of the chemical industry. Medicinal **drugs** (pharmaceuticals) must be of the highest possible purity. Any contaminating substances, even in very small amounts, may have harmful side effects. Coloured dyes (food colourings) are added to food and drinks to improve their appearance. The colourings added need to be carefully controlled. In Europe the permitted colourings are listed as E100 to E180. Many dyes that were once added are now banned. Even those which are permitted may still cause problems for some people. The yellow colouring tartrazine (E102) is found in many drinks, sauces, sweets and snacks. To most people it is harmless, but in some children it appears to cause hyperactivity and allergic reactions, for example asthma. Even where there is overall government regulation, individuals need to be aware of how particular foods affect them.

A closer look at solutions

The solubility of solids in liquids

Probably the most important and common examples of mixtures are solutions of solids in liquids.

Key definition

A **solution** is made up of two parts:

- ◆ the **solute** – the solid that dissolves
- ◆ the **solvent** – the liquid in which it dissolves.

Water is the commonest solvent in use, but other liquids are also important. Most of these other solvents are organic liquids, such as ethanol, propanone and

trichloroethane. These organic solvents are important because they will often dissolve substances that do not dissolve in water. If a substance dissolves in a solvent, it is said to be **soluble**; if it does not dissolve, it is **insoluble**.

If we try to dissolve a substance such as copper(II) sulfate in a fixed volume of water, the solution becomes more concentrated as we add more solid. A **concentrated** solution contains a high proportion of solute; a **dilute** solution contains a small proportion of solute. The **concentration** of a solution is the mass of solute dissolved in a particular volume of solvent, usually 1 dm^3 .

If we keep adding more solid, a point is reached when no more will dissolve at that temperature. This is a **saturated solution**. To get more solid to dissolve, the temperature must be increased. The concentration of solute in a saturated solution is the **solubility** of the solute at that temperature.

The solubility of most solids increases with temperature. The process of crystallisation depends on these observations. When a saturated solution is cooled, it can hold less solute at the lower temperature, and some solute crystallises out.

The solubility of gases in liquids

Unlike most solids, gases become less soluble in water as the temperature rises. The solubility of gases from the air in water is quite small, but the amount of dissolved oxygen is enough to support fish and other aquatic life. Interestingly, oxygen is more soluble in water than nitrogen is. So when air is dissolved in water, the proportions of the two gases become 61% nitrogen and 37% oxygen. This is an enrichment in life-supporting oxygen compared to air (78% nitrogen and 21% oxygen).

The solubility of gases increases with pressure. Sparkling drinks contain carbon dioxide dissolved under pressure. They 'fizz' when the pressure is released by opening the container. They go 'flat' if the container is left to stand open, and more quickly if left to stand in a warm place.

Carbon dioxide is more soluble than either nitrogen or oxygen. This is because it reacts with water to produce carbonic acid. The world is not chemically static. Substances are not only **mixing** with each other but also chemically **reacting**. This produces a world that is continuously changing. To gain a better understanding of this, we need to look more deeply into the 'make-up' of chemical substances.

Questions

- 2.6** How would you separate the following?
- a** water from seawater
 - b** ethanol from an ethanol/water mixture
 - c** sugar crystals from a sugar solution
- 2.7** What do you understand by the term **sublimation**?
- 2.8** What type of substance was chromatography originally designed to separate?
- 2.9** How can we now extend the use of chromatography to separate colourless substances?
- 2.10** Define the term R_f value in connection with chromatography.

2.3 Atoms and molecules

Elements and compounds

Earlier in this chapter you were introduced to pure substances, and to ways of purifying and identifying them. But what are 'pure substances'?

Key definition

There are two types of **pure substance** – elements and compounds:

- ◆ **elements** – substances that cannot be chemically broken down into simpler substances
- ◆ **compounds** – pure substances made from two, or more, elements chemically combined together.

Figure 2.19 summarises what we now know about matter in simple terms. Elements are the 'building blocks' from which the Universe is constructed. There are over 100 known elements, but most of the Universe consists of just two. Hydrogen (92%) and helium (7%) make up most of the mass of the Universe, with all the other elements contributing only 1% to the total. The concentration, or 'coming together', of certain of these elements to make the Earth is of great interest and significance. There are a total of 94 elements found naturally on Earth but just eight account for more than 98% of the mass of the Earth's crust. Two elements, silicon and oxygen, which are bound together in silicate rocks, make up almost three-quarters of the crust. Only certain elements are able to form the complex compounds that are found in living things. For example, the human body contains 65% oxygen, 18% carbon, 10% hydrogen, 3% nitrogen, 2% calcium and 2% of other elements.

Chemical reactions and physical changes

Substances can mix in a variety of ways, and they can also react chemically with each other. In a reaction, one substance can be transformed (changed) into another. Copper(II) carbonate is a green solid, but on heating it is changed into a black powder (Figure 2.20). Closer investigation shows that the gas carbon dioxide is also produced. This type of chemical reaction, where a compound breaks down to form two or more substances, is known as **decomposition**.




Figure 2.19 Schematic representation of the different types of matter, including elements and compounds.




Figure 2.20 Heating copper(II) carbonate.

Decomposition can also be brought about by electricity. Some substances, although they do not conduct electricity when solid, **do** conduct when they are melted or in solution. In the process of conduction, they are broken down into simpler substances. Thus, lead(II) bromide, which is a white powder, can be melted. When a current is passed through molten lead(II) bromide, a silver-grey metal (lead) and a brown vapour (bromine) are formed. Neither of these products can be split into any simpler substances.

The opposite type of reaction, where the substance is formed by the combination of two or more other substances, is known as **synthesis**. For example, if a piece of burning magnesium is plunged into a gas jar of oxygen, the intensity (brightness) of the brilliant white flame increases. When the reaction has burnt out, a white ash remains (Figure 2.21). The ash has totally different properties from the original silver-grey metal strip and colourless gas we started with. A new compound, magnesium oxide, has been formed from magnesium and oxygen.

Although many other reactions are not as spectacular as this, the burning of magnesium shows the general features of chemical reactions.

In a chemical reaction:

- ◆ new chemical substance(s) are formed
- ◆ usually the process is not easily reversed
- ◆ energy is often given out.

These characteristics of a chemical reaction contrast with those of a simple physical change such as melting



Figure 2.21 Burning magnesium produces a brilliant white flame.

or dissolving. In a **physical change** the substances involved do not change identity. They can be easily returned to their original form by some physical process such as cooling or evaporation. Sugar dissolves in water, but we can get the solid sugar back by evaporating off the water.

Another synthesis reaction takes place between powdered iron and sulfur. The two solids are finely ground and well mixed. The mixture is heated with a Bunsen burner. The reaction mixture continues to glow after the Bunsen burner is removed. Heat energy is given out. There has been a reaction and we are left with a black non-magnetic solid, iron(II) sulfide, which cannot easily be changed back to iron and sulfur. This example also illustrates some important differences between a mixture (in this case the powders of iron and sulfur) and a compound (in this case the final product of the reaction). The general differences between making a mixture of substances and forming a new compound are shown in Table 2.4, overleaf.

Atomic theory

Elements and compounds mix and react to produce the world around us. They produce massive objects such as the 'gas giants' (the planets Jupiter and Saturn), and tiny highly structured crystals of solid sugar. How do the elements organise themselves to give this variety? How can any one element exist in the three different states of matter simply through a change in temperature?

When a mixture forms ...	When a compound forms ...
the substances are simply mixed together; no reaction takes place	the substances chemically react together to form a new compound
the composition of the mixture can be varied	the composition of the new compound is always the same
the properties of the substances present remain the same	the properties of the new compound are very different from those of the elements in it
the substances in the mixture can be separated by physical methods such as filtration, distillation or magnetic attraction	the compound cannot easily be separated into its elements

Table 2.4 The differences between mixtures and pure compounds.

Our modern understanding is based on the atomic theory put forward by John Dalton in 1807. His theory reintroduced the ideas of Democritus (460–370 BCE) and other Greek philosophers who suggested that all matter was infinitely divided into very small particles known as **atoms**. These ideas were not widely accepted at the time. They were only revived when Dalton developed them further and experimental observations under the microscope showed the random motion of dust particles in suspension in water or smoke particles in air (Brownian motion).

Dalton suggested that:

- ◆ a pure element is composed of atoms
- ◆ the atoms of each element are different in size and mass
- ◆ atoms are the smallest particles that take part in a chemical reaction
- ◆ atoms of different elements can combine to make **molecules** of a compound.

Certain parts of the theory may have needed to change as a result of what we have discovered since Dalton's time. However, Dalton's theory was one of the great leaps of understanding in chemistry. It meant that we

could explain many natural processes. Whereas Dalton only had theories for the existence of atoms, modern techniques (such as scanning tunnelling microscopy) can now directly reveal the presence of individual atoms. It has even been possible to create an 'atomic logo' (Figure 2.22) by using individual atoms, and it may soon be possible to 'see' a reaction between individual atoms.

A chemical language

Dalton suggested that each element should have its own **symbol** – a form of chemical shorthand. He could then write the formulae of compounds without writing out the name every time. Our modern system uses letters taken from the name of the element. This is an international code. Some elements have been known for a long time and their symbol is taken from their Latin name.

The symbol for an element consists of one or two letters. Where the names of several elements begin with the same letter, the second letter of the name is usually included in lower case (Table 2.5). As more elements were discovered, they were named after a wider range of people, cities, countries and even particular universities. We shall see in Chapter 3 how useful it is to be able to use symbols, and how they can be combined to show the formulae of complex chemical compounds. A full list of the elements and their symbols is found in the Periodic Table (see the Appendix).

The kinetic model of matter

The idea that all substances consist of very small particles begins to explain the structure of the three different states of matter. The kinetic theory of matter describes these states, and the changes between them, in terms of the movement of particles.




Figure 2.22 An 'atomic logo' produced by xenon atoms on a nickel surface 'seen' using scanning tunnelling microscopy.

Element	Latin name	Symbol
hydrogen		H
helium		He
carbon		C
calcium		Ca
copper	cuprum	Cu
chlorine		Cl
nitrogen		N
sodium	natrium	Na
phosphorus		P
potassium	kalium	K
iron	ferrum	Fe
lead	plumbum	Pb
silver	argentum	Ag
gold	aurum	Au

Table 2.5 The symbols of some chemical elements.

The main points of the kinetic model

- ◆ All matter is made up of very small particles (different substances contain different types of particles – such as atoms or molecules).
- ◆ The particles are moving all the time (the higher the temperature, the higher the average energy of the particles). In a gas, the faster the particles are moving, the higher the temperature.
- ◆ The freedom of movement and the arrangement of the particles is different for the three states of matter (Figure 2.23).
- ◆ The pressure of a gas is produced by the atoms or molecules of the gas hitting the walls of the container. The more often the particles collide with the walls, the greater the pressure.

Figure 2.23 is a summary of the organisation of the particles in the three states of matter, and helps to explain their different overall physical properties. The highly structured, ordered microscopic arrangements (**lattices**) in solids can produce the regular crystal structures seen in this state. The ability of the particles to move in the liquid and gas phases




Figure 2.23 Applying the kinetic model to changes in physical state.

produces their fluid properties. The particles are very widely separated in a gas, but are close together in a liquid or solid. The space between the particles can be called the **intermolecular space (IMS)**. In a gas, the intermolecular space is large and can be reduced by increasing the external pressure – gases are compressible. In liquids, this space is very much smaller – liquids are not very compressible.

Study tip

It's important to realise that even in a liquid, the particles are still close together, although they can move around and past each other.




Figure 2.24 The energy changes taking place during heating and cooling.

The way the particles in the three states are arranged also helps to explain the temperature changes when a substance is heated or cooled. Figure 2.24 (overleaf) summarises the energy changes taking place at the different stages of a heating-curve or cooling-curve experiment.

Diffusion in fluids

The idea that fluids are made up of moving particles helps us to explain processes involving **diffusion**.

Dissolving

A potassium manganate(VII) crystal is placed at the bottom of a dish of water. It is then left to stand. At first the water around the crystal becomes purple as the solid dissolves (Figure 2.25). Particles move off the surface of the crystal into the water. Eventually the crystal dissolves completely and the whole solution becomes purple. The particles from the solid become evenly spread throughout the water.

Whether a solid begins to break up like this in a liquid depends on the particular solid and liquid involved. But the spreading of the solute particles throughout the liquid is an example of diffusion. Diffusion in solution is also important when the solute is a gas. This is especially important in breathing! Diffusion contributes to the



Figure 2.25 The diffusion of potassium manganate(VII) in water as it dissolves.

movement of oxygen from the lungs to the blood, and of carbon dioxide from the blood to the lungs.

The diffusion of gases

A few drops of liquid bromine are put into a gas jar and the lid is replaced. After a short time the jar becomes full of brown gas. Bromine vaporises easily and its gas will completely fill the container (Figure 2.26). Gases diffuse to fill all the space available to them. Diffusion is important for our 'sensing' of the world around us. It is the way smells reach us, whether they are pleasant or harmful.




Figure 2.26 Bromine vapour diffuses (spreads) throughout the container to fill all the space.

Study tip

The key idea about diffusion is the idea of particles spreading to fill the space available to the molecules.

Key definition

diffusion – the process by which different fluids mix as a result of the random motions of their particles.

- ◆ Diffusion involves the movement of particles from a region of higher concentration towards a region of lower concentration. Eventually, the particles are evenly spread – their concentration is the same throughout.
- ◆ It does not take place in solids.
- ◆ Diffusion in liquids is much slower than in gases.




Figure 2.27 Ammonia and hydrochloric acid fumes diffuse at different rates.

a white 'smoke ring' of ammonium chloride. The fact that the ring is not formed halfway along the tube shows that ammonia, the lighter molecule of the two, diffuses faster.

The speeds of gas atoms or molecules are high. We are being bombarded constantly by nitrogen and oxygen molecules in the air, which are travelling at about 500 m/s (1800 km/h). However, these particles collide very frequently with other particles in the air (many millions of collisions per second), so their path is not particularly direct! (Figure 2.28a). These very frequent collisions slow down the overall rate of diffusion from one place to another.

The movement of individual gas molecules or atoms in the air cannot be seen: the particles are far too small. However, the effect of their presence and motion can

Not all gases diffuse at the same rate. This is shown by the experiment in Figure 2.27. The ammonia and hydrochloric acid fumes react when they meet, producing




Figure 2.28 **a** Diffusion of an individual gas molecule or atom; the particle collides with many others, deflecting its path. **b** Demonstrating Brownian motion using a smoke cell; the smoke particles show a random motion.

S be shown using a smoke cell (Figure 2.28b). The smoke particles are hit by the invisible molecules in the air. The jerky, random motion produced by these hits can be seen under a microscope. This is known as **Brownian motion**.

Three important points derived from **kinetic theory** are relevant here:

- ◆ Heavier particles move more slowly than lighter particles at the same temperature; larger molecules diffuse more slowly than smaller ones.
- ◆ The pressure of a gas is the result of collisions of the fast-moving particles with the walls of the container.
- ◆ The average speed of the particles increases with an increase in temperature.

Activity 2.5

Investigating diffusion – a demonstration

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This is the classic demonstration of the diffusion of gases in which ammonia and hydrogen chloride meet in a long tube. The demonstration shows how the progress of the gases can be tracked using indicator. Measurements can be made to give an estimate of the rate of diffusion of the two gases.

Worksheets are included on the accompanying CD-ROM for both the teacher demonstration and a microscale version of the experiment which could be carried out by students.

Details of other demonstrations and experiments on diffusion are given in the Notes on Activities for teachers/technicians.

Atoms and molecules

The behaviour of some gaseous elements (their diffusion and pressure) shows that they are made up of molecules, not separate atoms. This is true of hydrogen (H_2), nitrogen (N_2), oxygen (O_2) and others. But, as we discussed on page 36, Dalton had originally introduced the idea of molecules to explain the particles making up **compounds** such as water, carbon dioxide and methane. Molecules of these compounds consist of atoms of different **elements** chemically bonded together. Water is made up of two atoms of hydrogen bonded to one atom of oxygen, giving the formula H_2O . Methane (CH_4) has one atom of carbon bonded to four atoms of hydrogen, and hydrogen chloride (HCl) has one atom of hydrogen and one atom of chlorine bonded together. Models of these are shown in Figure 2.29.




Figure 2.29 Simple compounds consisting of molecules made up of atoms of two different elements.

Questions

- 2.11** Define an element.
- 2.12** Define a compound.
- 2.13** Summarise the differences between the three states of matter in terms of the arrangement of the particles and their movement.
- 2.14** Which gas diffuses faster, ammonia or hydrogen chloride? Briefly describe an experiment that demonstrates this difference.
- 2.15** Which gas will diffuse fastest of all?

2.4 The structure of the atom

Atomic structure

How can atoms join together to make molecules?
What makes certain atoms more ready to do this?
Why do hydrogen atoms pair up but helium atoms remain single?

To find answers to questions like these, we need first to consider the structure of atoms in general. Dalton thought they were solid, indivisible particles. But research since then has shown that atoms are made up of various subatomic particles. J. J. Thompson discovered the electron (in 1897) and the proton. Crucial experiments were then carried out in Rutherford's laboratory in Manchester in 1909 that showed that the atom is largely empty space. Rutherford calculated that an atom is mostly space occupied by the negatively charged electrons, surrounding a very small, positively charged **nucleus**. The nucleus is at the centre of the atom and contains almost all the mass of the atom. By 1932, when the neutron was discovered, it was clear that atoms consisted of three **subatomic particles** – **protons**, **neutrons** and **electrons**. These particles are universal – all atoms are made from them. The atom remains the smallest particle that shows the characteristics of a particular element.

Measuring the size of atoms

Modern methods such as scanning tunnelling microscopy have allowed us to 'see' individual atoms in a structure. However, atoms are amazingly small! A magnification of 100 million times is necessary to show the stacking pattern of the atoms that make up a gold bar.

A single atom is so small that it cannot be weighed on a balance. However, the mass of one atom can be compared with that of another using a **mass spectrometer**. The element carbon is chosen as the standard. The masses of atoms of all other elements are compared to the mass of a carbon atom. This gives a series of values of **relative atomic mass** for the elements. Carbon is given a relative atomic mass of exactly 12, which can be written as carbon-12. Table 2.6 gives some examples of the values obtained for other

Activity 2.6

Discovering the structure of the atom

Skills

Research skills

ICT skills

The discovery of the nature of the subatomic particles that make up all atoms took place in a relatively short space of time around the beginning of the twentieth century.

Investigate this key period in the history of science using library and internet sources. Devise a PowerPoint or poster presentation on the significant discoveries and the scientists involved.

Key scientists to research are J. J. Thompson, Ernest Rutherford and James Chadwick.

Questions

- A1 What was remarkable about the structure of the atom suggested by the Geiger–Marsden experiments?
- A2 What is it about the nature of the neutron that made it the last of the particles to be discovered?

Element	Atomic symbol	Relative atomic mass
carbon	C	12
hydrogen	H	1
oxygen	O	16
calcium	Ca	40
copper	Cu	64
gold	Au	197

Table 2.6 The relative atomic masses of some elements.

elements. It shows that carbon atoms are 12 times as heavy as hydrogen atoms, which are the lightest atoms of all. Calcium atoms are 40 times as heavy as hydrogen atoms.

Subatomic particles

To get some idea of just how small the nucleus is in comparison to the rest of the atom, here is a simple comparison. If the atom were the size of a football stadium, the nucleus (at the centre-spot) would be the size of a pea!

Protons and neutrons have almost the same mass. Electrons have virtually no mass at all ($\frac{1}{1840}$ of the mass of a proton). The other important feature of these particles is their electric charge. Protons and electrons have equal and opposite charges, while neutrons are electrically neutral (have no charge). The characteristics of these three subatomic particles are listed in Table 2.7.

A single atom is electrically neutral (it has no overall electric charge). This means that in any atom there must be equal numbers of protons and electrons. In this way the total positive charge on the nucleus (due to the protons) is balanced by the total negative charge of the orbiting electrons. The simplest atom of all has one proton in its nucleus. This is the hydrogen atom. It is the only atom that has no neutrons; it consists of one proton and one electron. Atoms of different elements are increasingly complex.

The next simplest atom is that of helium. This has two protons and two neutrons in the nucleus, and two orbiting electrons (Figure 2.30).

The next, lithium, has three protons, four neutrons and three electrons. The arrangements in the following atoms get more complicated with the addition of more protons and electrons. The number of neutrons required to hold the nucleus together increases as the atomic size increases. Thus, an atom of gold consists of 79 protons (p^+), 118 neutrons (n^0) and 79 electrons (e^-).

Subatomic particle	Relative mass	Relative charge	Location in atom
proton	1	+1	in nucleus
neutron	1	0	in nucleus
electron	$\frac{1}{1840}$ (negligible)	-1	outside nucleus

Table 2.7 Properties of the subatomic particles.




Figure 2.30 The structure of a helium atom.

Proton (atomic) number and nucleon number

Only hydrogen atoms have one proton in their nuclei. Only helium atoms have two protons. Indeed, only gold atoms have 79 protons. This shows that the number of protons in the nucleus of an atom decides which element it is. This very important number is known as the **proton number** (or **atomic number**, given the symbol Z) of an atom.


Protons alone do not make up all the mass of an atom. The neutrons in the nucleus also contribute to the total mass. The mass of the electrons can be regarded as so small that it can be ignored. Because a proton and a neutron have the same mass, the mass of a particular atom depends on the total number of protons and neutrons present. This number is called the **nucleon number** (or **mass number**, given the symbol A) of an atom.

The atomic number Z and mass number A of an atom of an element can be written alongside the symbol for that element, in the general way as ${}_Z^AX$. So the symbol for an atom of lithium is ${}_3^7\text{Li}$. The symbols for carbon, oxygen and uranium atoms are ${}_6^{12}\text{C}$, ${}_8^{16}\text{O}$ and ${}_{92}^{238}\text{U}$.

If these two important numbers for any atom are known, then its subatomic composition can be worked out.

For proton number and nucleon number we have:

- ♦ proton (atomic) number (Z)
= number of protons in the nucleus
- ♦ nucleon (mass) number (A)
= number of protons + number of neutrons



These two relationships are useful:

- ♦ number of electrons = number of protons
= atomic (proton) number
- ♦ number of neutrons
= nucleon number – proton number
= $A - Z$

Table 2.8 shows the numbers of protons, neutrons and electrons in some different atoms. Note that the rules apply even to the largest, most complicated atom found naturally in substantial amounts.

Study tip

Remember that you can use the Periodic Table you have in the exam for information on these numbers for any atom. Magnesium is the twelfth atom in the table, so it must have 12 protons and 12 electrons in its atoms.

Isotopes

Measurements of the atomic masses of some elements using the mass spectrometer were puzzling. Pure samples of elements such as carbon, chlorine and many others were found to contain atoms with different masses even though they contained the same numbers of protons and electrons. The different masses were caused by different numbers of neutrons in their nuclei. Such atoms are called **isotopes**.

Study tip

Remember that it is just the number of neutrons in the atoms that is the difference between isotopes. They have the same number of protons and electrons.

Atom	Symbol	Atomic number, Z	Mass number, A	Inside the nucleus:		Outside the nucleus: Electrons (Z)
				Protons (Z)	Neutrons ($A - Z$)	
hydrogen	H	1	1	1	0	1
helium	He	2	4	2	2	2
lithium	Li	3	7	3	4	3
beryllium	Be	4	9	4	5	4
carbon	C	6	12	6	6	6
oxygen	O	8	16	8	8	8
sodium	Na	11	23	11	12	11
calcium	Ca	20	40	20	20	20
gold	Au	79	197	79	118	79
uranium	U	92	238	92	146	92

Table 2.8 The subatomic composition and structure of certain atoms.

Element	Isotopes		
Hydrogen	hydrogen (99.99%)	deuterium (0.01%)	tritium ^(a)
	${}^1_1\text{H}$	${}^2_1\text{H}$	${}^3_1\text{H}$
	1 proton	1 proton	1 proton
	0 neutrons	1 neutron	2 neutrons
	1 electron	1 electron	1 electron
Carbon	carbon-12 (98.9%)	carbon-13 (1.1%)	carbon-14 ^(a) (trace)
	${}^{12}_6\text{C}$	${}^{13}_6\text{C}$	${}^{14}_6\text{C}$
	6 protons	6 protons	6 protons
	6 neutrons	7 neutrons	8 neutrons
	6 electrons	6 electrons	6 electrons
Neon	neon-20 (90.5%)	neon-21 (0.3%)	neon-22 (9.2%)
	${}^{20}_{10}\text{Ne}$	${}^{21}_{10}\text{Ne}$	${}^{22}_{10}\text{Ne}$
	10 protons	10 protons	10 protons
	10 neutrons	11 neutrons	12 neutrons
	10 electrons	10 electrons	10 electrons
Chlorine	chlorine-35 (75%)	chlorine-37 (25%)	
	${}^{35}_{17}\text{Cl}$	${}^{37}_{17}\text{Cl}$	
	17 protons	17 protons	
	18 neutrons	20 neutrons	
	17 electrons	17 electrons	

^(a)Tritium and carbon-14 atoms are radioactive isotopes because their nuclei are unstable.

Table 2.9 Several elements that exist as mixtures of isotopes.

Key definition

isotopes – atoms of the same element which have the same proton number but a different nucleon number.

- ◆ The atoms have the same number of protons and electrons, but different numbers of neutrons in their nuclei.
- ◆ Isotopes of an element have the same chemical properties because they have the same electron structure.
- ◆ Some isotopes have unstable nuclei; they are **radioisotopes** and emit various forms of radiation.

The isotopes of an element have the same chemical properties because they contain the same number of electrons. It is the number of electrons in an atom that decides the way in which it forms bonds and reacts with other atoms. However, some physical properties of the isotopes are different. The masses of the atoms differ and therefore other properties, such as density and rate of diffusion, also vary. The modern mass spectrometer shows that most elements have several different isotopes that occur naturally. Others, such as tritium – an isotope of hydrogen (Table 2.9) – can be made artificially.

Tritium and carbon-14 illustrate another difference in physical properties that can occur between isotopes, as they are **radioactive**. The imbalance of

neutrons and protons in their nuclei causes them to be unstable so the nuclei break up spontaneously (that is, without any external energy being supplied), emitting certain types of radiation. They are known as **radioisotopes**.

Relative atomic masses

Most elements exist naturally as a mixture of isotopes. Therefore, the value we use for the atomic mass of an element is an average mass. This takes into account the proportions (abundance) of all the naturally occurring isotopes. If a particular isotope is present in high proportion, it will make a large contribution to the average. This average value for the mass of an atom of an element is known as the relative atomic mass (A_r).

Key definition

relative atomic mass (A_r) – the average mass of naturally occurring atoms of an element on a scale where the carbon-12 atom has a mass of exactly 12 units.

Because there are several isotopes of carbon, the standard against which all atomic masses are measured has to be defined precisely. The isotope carbon-12 is used as the standard. One atom of carbon-12 is given the mass of 12 precisely. From this we get that 1 atomic mass unit (a.m.u.) = $\frac{1}{12} \times$ mass of one atom of carbon-12.

The existence of isotopes also explains why most relative atomic masses are not whole numbers. But, to make calculations easier, in this book they are rounded to the nearest whole number. There is one exception, chlorine, where this would be misleading. Chlorine contains two isotopes, chlorine-35 and chlorine-37, in a ratio of 3 : 1 (or 75% : 25%). If the mixture were 50% : 50%, then the relative atomic mass of chlorine would be 36. The fact that there is more of the lighter isotope moves the value lower than 36. The actual value is 35.5. The relative atomic mass of chlorine can be calculated by finding the total mass of 100 atoms:

$$\begin{aligned}\text{mass of 100 atoms} &= (35 \times 75) + (37 \times 25) \\ &= 3550\end{aligned}$$

Then,

$$\text{average mass of one atom} = \frac{3550}{100} = 35.5$$

Thus, for chlorine:

$$A_r(\text{Cl}) = 35.5$$

Radioactivity

Some elements have unstable isotopes, such as tritium and carbon-14. The extra neutrons in their nuclei cause them to disintegrate or decay spontaneously. This is **radioactivity** and takes place through nuclear fission. The result of these disintegrations is the release of heat energy and various forms of radioactive radiation. Uranium-235 is a radioactive isotope which is used as a controlled source of energy in nuclear power stations.

The decay is a completely random process and is unaffected by temperature or whether the isotope is part of a compound or present as the free element. Radioactive decay is a nuclear process and not a chemical reaction.

The uses of radioactivity

Radioactive dating

Each radioactive isotope decays at its own rate. However, the time taken for the radioactivity in a sample to halve is constant for a particular radioisotope. This time is called the **half-life**. Some isotopes have very short half-lives of only seconds: for example, oxygen-14 has a half-life of 71 s. Other half-lives are quite long: for example, carbon-14 has a half-life of 5730 years.

One important use of half-life values is in radioactive dating. Radiocarbon dating (which uses carbon-14) can be used to date wooden and organic objects.

Industrial uses of radioisotopes

Despite the need to handle them with strict safety precautions, radioactive isotopes are widely used in industry and medicine. Most important is the use of an isotope of uranium, ^{235}U , in nuclear power stations. Here, as the isotope splits into smaller parts, as a result

of being bombarded with neutrons, huge amounts of energy are produced. This nuclear fission reaction is the same as that used in the atomic bomb. The difference is that in a nuclear power station, the reaction is controlled.

Other industrial uses of radioisotopes include monitoring the level of filling in containers, checking the thickness of sheets of plastic, paper or metal foil (for example, aluminium baking foil) during continuous production, and detecting leaks in gas or oil pipes (Figure 2.31).

Medical and food-safety uses of radioisotopes

The ease of detection of radioisotopes gives rise to several of their other uses, and in medicine some of their most dangerous properties can be turned to advantage. Several medical uses of radiation depend on the fact that biological cells are sensitive to radioactive emissions. Cells that are growing and dividing are particularly likely to be damaged. Cancer cells are cells that are growing out of control in a tissue of the body. Because of this they are more easily killed by radiation than are healthy

cells. Penetrating γ -radiation from the radioisotope cobalt-60 is used to treat internal cancer tumours. Skin cancer tumours can be treated with less-penetrating radiation. This is done by strapping sheets containing phosphorus-32 or strontium-90 to the affected area of the skin.

Bacterial cells grow and divide rapidly. They are particularly sensitive to radiation. Medical instruments, dressings and syringes can be sterilised by sealing them in polythene bags and exposing them to intense doses of γ -radiation. This has proved a very effective method of killing any bacteria on them.

Study tip

The syllabus specifies that you simply need to know a medical and an industrial use for radioactivity. Do be clear about the difference between radiotherapy and chemotherapy in the treatment of cancer. It is radiotherapy that involves the use of radioactivity to kill the tumour cells.




Figure 2.31 Uses of radioactivity: **a** detecting the level of liquid in a container, **b** detecting leaks in underground pipes, and **c** controlling the thickness of metal sheets.

Questions

- 2.16** What are the relative masses of a proton, neutron and electron given that a proton has a mass of 1?
- 2.17** How many protons, neutrons and electrons are there in an atom of phosphorus, which has a proton number of 15 and a nucleon number of 31?
- 2.18** What is the difference in terms of subatomic particles between an atom of chlorine-35 and an atom of chlorine-37?
- 2.19** Give **one** medical and **one** industrial use of radioactivity.

2.5 Electron arrangements in atoms

The aurora borealis (Figure 2.32) is a spectacular display seen in the sky in the far north (a similar phenomenon – the aurora australis – occurs in the night sky of the far south). It is caused by radiation from the Sun moving the electrons in atoms of the gases of the atmosphere.

Similar colour effects can be created in a simpler way in the laboratory by heating the compounds of some metals in a Bunsen flame (see page 208). These colours are also seen in fireworks. The colours produced are due to electrons in the atom moving between two different **energy levels**.

In 1913, Niels Bohr, working with Rutherford in Manchester, developed a theory to explain how



Figure 2.32 The aurora borealis or northern lights as seen from Finland.

electrons were arranged in atoms. This theory helps to explain how the colours referred to above come about.

A simplified version of **Bohr's theory** of the arrangement of electrons in an atom can be summarised as follows (see also Figure 2.33):

- ◆ Electrons are in orbit around the central nucleus of the atom.
- ◆ The electron orbits are called **shells** (or **energy levels**) and have different energies.
- ◆ Shells which are further from the nucleus have higher energies.
- ◆ The shells are filled starting with the one with lowest energy (closest to the nucleus).
- ◆ The first shell can hold only 2 electrons.
- ◆ The second and subsequent shells can hold 8 electrons to give a stable (noble gas) arrangement of electrons.

Other evidence was found that supported these ideas of how the electrons are arranged in atoms. The number and arrangement of the electrons in the atoms of the first 20 elements in the Periodic Table (see the Appendix) are shown in Table 2.10 (overleaf).

When the two essential numbers describing a particular atom are known, the numbers of protons and neutrons, a subatomic picture can be drawn. Figure 2.34 (overleaf) shows such a picture for perhaps the most versatile atom in the Universe, an atom of carbon-12. Studying the organisation of the electrons of an atom is valuable. It begins to explain the patterns in properties of the elements that are the basis of the Periodic Table. This will be discussed in the next chapter.




Figure 2.33 Bohr's theory of the arrangement of electrons in an atom.

Element	Symbol	Atomic number, Z	First shell	Second shell	Third shell	Fourth shell	Electron configuration
hydrogen	H	1	●				1
helium	He	2	●●				2
lithium	Li	3	●●	●			2,1
beryllium	Be	4	●●	●●			2,2
boron	B	5	●●	●●●			2,3
carbon	C	6	●●	●●●●			2,4
nitrogen	N	7	●●	●●●●●			2,5
oxygen	O	8	●●	●●●●●●			2,6
fluorine	F	9	●●	●●●●●●●			2,7
neon	Ne	10	●●	●●●●●●●●			2,8
sodium	Na	11	●●	●●●●●●●●	●		2,8,1
magnesium	Mg	12	●●	●●●●●●●●	●●		2,8,2
aluminium	Al	13	●●	●●●●●●●●	●●●		2,8,3
silicon	Si	14	●●	●●●●●●●●	●●●●		2,8,4
phosphorus	P	15	●●	●●●●●●●●	●●●●●		2,8,5
sulfur	S	16	●●	●●●●●●●●	●●●●●●		2,8,6
chlorine	Cl	17	●●	●●●●●●●●	●●●●●●●		2,8,7
argon	Ar	18	●●	●●●●●●●●	●●●●●●●●		2,8,8
potassium	K	19	●●	●●●●●●●●	●●●●●●●●	●	2,8,8,1
calcium	Ca	20	●●	●●●●●●●●	●●●●●●●●	●●	2,8,8,2

Table 2.10 The electron arrangements of the first 20 elements.




Figure 2.34 Possibly the most versatile atom in the Universe – the carbon-12 atom.

Questions

- 2.20** What are the maximum numbers of electrons that can fill the first and the second shells (energy levels) of an atom?
- 2.21** What is the electron arrangement of a calcium atom, which has an atomic number of 20?
- 2.22** How many electrons are there in the outer shells of the atoms of the noble gases, argon and neon?
- 2.23** Carbon-12 and carbon-14 are different isotopes of carbon. How many electrons are there in an atom of each isotope?

Study tip

Make sure that you remember how to work out the electron arrangements of the first 20 elements and can draw them in rings (shells) as in Figure 2.35. Also remember that you can give the electron arrangement or **electronic structure** simply in terms of numbers: 2,8,4 for silicon, for example.

You can see from these elements that the number of outer electrons in an atom is the same as the number of the group in the Periodic Table that the element is in. The number of shells of electrons in an atom tells you the period (row) of the element in the table. We will look at this further in the next chapter.




Figure 2.35 Different ways of showing electron structure.

Summary


You should know:

- ◆ that there are three different physical states in which a substance can exist
- ◆ about the different changes in state that can take place, including sublimation, where the liquid phase is bypassed
- ◆ how these changes of state can be produced by changing conditions of temperature and/or pressure
- ◆ how the kinetic model describes the idea that the particles of a substance are in constant motion and that the nature and amount of motion of these particles differs in a solid, liquid or gas
- ⑤ ◆ how changing physical state involves energy being absorbed or given out, the temperature of the substance staying constant while the change takes place
- ◆ how pure substances have precise melting and boiling points – their sharpness can be taken as an indication of the degree of purity of the substance
- ◆ that different separation methods – such as filtration, distillation and chromatography – can be used to purify a substance from a mixture
- ◆ how pure chemical substances can be either elements or compounds
- ◆ that elements are the basic building units of the material world – they cannot be chemically broken down into anything simpler
- ◆ how compounds are made from two or more elements chemically combined together, and that their properties are very different from those of the elements they are made from

- ◆ how each element is made from atoms and that atoms can join together to make the molecules either of an element or of a compound
- ◆ how the atoms of the elements are made up of different combinations of the subatomic particles – protons, neutrons and electrons
- ◆ the electrical charges and relative masses of these subatomic particles
- ◆ how, in any atom, the protons and neutrons are bound together in a central nucleus, and the electrons ‘orbit’ the nucleus in different energy levels (or shells)
- ◆ that the number of protons in an atom is defined as the proton (atomic) number (Z) of the element
- ◆ that the nucleon (mass) number (A) is defined as the total number of protons and neutrons in any atom
- ◆ how isotopes of the same element can exist which differ only in the number of neutrons in their nuclei
- ◆ how some isotopes of many elements have unstable nuclei and this makes them radioactive
- ◆ that the different forms of radiation from radioisotopes have scientific, industrial and medical uses
- ◆ how the electrons in atoms are arranged in different energy levels that are at different distances from the nucleus of the atom
- ◆ how each energy level has a maximum number of electrons that it can contain and that the electrons fill the shells closest to the nucleus first.

End-of-chapter questions

- 1 Substances can be categorised in two ways: as an **element, mixture or compound** or as a **solid, liquid or gas**. Which of these methods is of most use to a chemist?
- 2 The word **particle** can be used to describe a speck of dust, a molecule, an atom or an electron. How can we avoid confusion in using the word particle?
- 3 Stearic acid is a solid at room temperature. The diagram below shows the apparatus used for finding the melting point of stearic acid. The apparatus was heated at a steady rate and the temperature recorded every minute.




- a State the names of the pieces of apparatus labelled A, B.
- b Suggest why the water needs to be kept stirred during this experiment.

[2]

[1]

c A graph of temperature of stearic acid against time of heating is shown below.




- i What was the temperature of the stearic acid after 3 minutes heating? [1]
- ii Use the information on the graph to determine the melting point of stearic acid. [1]
- d Describe the arrangement and motion of the particles in liquid stearic acid. [2]
- e A sample of stearic acid contained 1% of another compound with a higher relative molecular mass.
 - i Which one of the following statements about this sample of stearic acid is correct?
 - Its density is exactly the same as that of pure stearic acid.
 - Its boiling point is the same as that of pure stearic acid.
 - Its melting point is different from pure stearic acid.
 - Its melting point is the same as that of pure stearic acid. [1]
 - ii Describe **one** area of everyday life where the purity of substances is important. [1]

[Cambridge IGCSE® Chemistry 0620/21, Question 1(a, b(i), c–e), June 2012]

4 Sand and salt (sodium chloride) are both solids.

- a
 - i Describe the arrangement and movement of the particles in a solid. [2]
 - ii Describe how you could separate the sand from a mixture of sand and salt. Give full details of how this is carried out. [3]
- b The diagram below shows the apparatus used to separate ethanol and water from a mixture of ethanol and water.



Write out and complete the following sentences about this separation using words from the list below.


condenser crystallisation distillation flask heavy
higher lower solid volatile vapour

Fractional is used to separate a mixture of water and ethanol. The temperature at the top of the fractionating column is than the temperature at the bottom. The more liquid evaporates and moves further up the column. It eventually reaches the where the changes to a liquid.

[5]

[Cambridge IGCSE® Chemistry 0620/21, Question 3(c, d), November 2012]

- 5 A student placed a crystal of silver nitrate and a crystal of potassium iodide in a dish of water. After an hour she observed that
- ◆ the crystals had disappeared,
 - ◆ a yellow precipitate had appeared near the middle of the dish.



Use your knowledge of the kinetic particle theory and reactions between ions to explain these observations.

[4]

[Cambridge IGCSE® Chemistry 0620/21, Question 6(a), November 2012]

- 6 Vanadium has two isotopes.



- a Define the term isotope.
- b An atom contains protons, electrons and neutrons.
Complete the table to show the number of protons, electrons and neutrons in these two isotopes of vanadium.

[1]

Isotope	Number of protons	Number of electrons	Number of neutrons
${}_{23}^{50}\text{V}$	23	23	
${}_{23}^{51}\text{V}$			28

[3]

- c Write out and complete these sentences using words from the list.

cancer extra industry influenza medicine non

Two types of isotopes are radioactive and -radioactive. Radioactive isotopes are used in for treating patients with

[3]


[Cambridge IGCSE® Chemistry 0620/21, Question 2(a-c), June 2011]

7 Helium and argon are noble gases.

a State **one** use of helium.

[1]

b The atomic structures of helium and argon are shown below.



i State the name of the central part of the atom, labelled X.

[1]

ii Which **one** of these statements about helium and argon is correct?

Argon has an incomplete inner shell of electrons.

An atom of argon has 16 electrons.

Helium has a complete outer shell of electrons.

Helium has an incomplete outer shell of electrons.

[1]

iii How many protons are there in an atom of argon?

[1]

iv The symbol for a particular isotope of helium is written as ${}^4_2\text{He}$.


Write a similar symbol for the isotope of argon which has 16 neutrons.

[1]

c Argon is a liquid at a temperature of -188°C .

Complete the diagram below to show how the atoms of argon are arranged at -188°C .


○ represents one atom of argon



[2]

[Cambridge IGCSE® Chemistry 0620/21, Question 3, November 2010]


- S** 8 a A small amount of liquid bromine is added to a container which is then sealed.



Use the ideas of the Kinetic Theory to explain why, after about an hour, the bromine molecules have spread uniformly to occupy the whole container.

[3]

- b The diagrams below show simple experiments on the speed of diffusion of gases.



Write explanations for what is occurring in each diagram. Diagram 1 has been done for you.

Diagram 1

There is air inside and outside the porous pot so the rate of diffusion of air into the pot is the same as the rate of diffusion of air out of the pot. The pressure inside and outside the pot is the same so the coloured liquid is at the same level on each side of the tube.

Diagram 2

[3]

Diagram 3

[3]

[Cambridge IGCSE® Chemistry 0620/33, Question 3, November 2012]

3

Elements and compounds

In this chapter, you will find out about:

- ◆ the structure of the Periodic Table
- ◆ metals and non-metals in the Periodic Table
- ◆ electron arrangement in the Periodic Table
- ◆ trends in Group I – the alkali metals
- ◆ trends in Group VII – the halogens
- ◆ the noble gases
- ◆ trends across a period
- ◆ the transition elements
- ◆ bonding in metals
- ◆ bonding in covalent compounds
- ◆ bonding in ionic compounds
- ◆ formulae and names of ionic compounds
- ◆ formulae and names of covalent compounds
- ◆ the nature of metal crystals and alloys
- ◆ the nature of ionic crystals
- ◆ the nature of giant covalent structures.

Organising the building blocks!

Building up the modern **Periodic Table** has been a major scientific achievement! The first steps towards working out this table were taken long before anyone had any ideas about the structure of atoms. The number of elements discovered increased steadily during the nineteenth century. Chemists began to find patterns in their properties. Döbereiner, Newlands and Meyer all described groupings of elements with similar chemical and physical characteristics. But, although they were partly successful, these groupings were limited or flawed. The breakthrough came in 1869 when Mendeleev put forward his ideas of a periodic table. In his first attempt he used 32 of the 61 elements known at that time (Figure 3.1).

He drew up his table based on atomic masses, as others had done before him. But his success was mainly due to his leaving **gaps** for possible elements still to be discovered. He did not try to force the elements into patterns for which there was no evidence.

Mendeleev's great achievement lay in **predicting** the properties of elements that had not yet been discovered.



Figure 3.1 Mendeleev's early Periodic Table carved on the wall of a university building in St Petersburg, with a statue of Mendeleev in front.

3.1 The Periodic Table – classifying the elements

All modern versions of the Periodic Table are based on the one put forward by Mendeleev. An example is given in Figure 3.2.

In the **Periodic Table**:

- ◆ the elements are arranged in order of increasing proton number (atomic number)
- ◆ the vertical columns of elements with similar properties are called **groups**
- ◆ the horizontal rows are called **periods**.

The main distinction in the table is between **metals** and **non-metals**. Metals are clearly separated from non-metals. The non-metals are grouped into the top right-hand region of the table, above the thick stepped line in Figure 3.2. One of the first uses of the Periodic Table now becomes clear. Although we may never have seen

a sample of the element hafnium (Hf), we know from a glance at the table that it is a metal. We may also be able to predict some of its properties.

Metals and non-metals

There are 94 naturally occurring elements. Some are very rare. Francium, for instance, has never been seen. The radioactive metals neptunium and plutonium, which we make artificially in quite large amounts, occur only in very small (trace) quantities naturally. Most of the elements (70) can be classified as metals. Together they form a group of elements whose structures are held together by a particular type of bonding between the atoms. The metals have a number of physical properties that are broadly the same for all of them (Table 3.1).

The chemical properties of metals and non-metals are also very different, as is the type of bonding present in their compounds. The distinction is therefore a very important one.

The Periodic Table does not list substances such as steel, bronze and brass, which in everyday terms we call




Figure 3.2 The Periodic Table, showing the major regions. (Except for chlorine, the relative atomic masses are given to the nearest whole number.)

Metals	Non-metals
They are usually solids (except for mercury, which is a liquid) at room temperature. Their melting and boiling points are usually high.	They are solids or gases (except for bromine, which is a liquid) at room temperature. Their melting and boiling points are often low.
They are usually hard and dense.	Most non-metals are softer than metals (but diamond is very hard). Their densities are often low.
All metals are good conductors of electricity. ^(a)	They are poor conductors of electricity (except graphite, a form of carbon). They tend to be insulators.
They are good conductors of heat.	They are generally poor thermal conductors.
Their shape can be changed by hammering (they are malleable). They can also be pulled out into wires (they are ductile).	Most non-metals are brittle when solid.
They are grey in colour (except gold and copper). They can be polished.	They vary in colour. They often have a dull surface when solid.
They usually make a ringing sound when struck (they are sonorous).	They are not sonorous.

^(a)Electrical conductivity is usually taken as the simplest test of whether a substance is metallic or not.

Table 3.1 Comparison of the physical properties of metals and non-metals.

metals and which share the properties listed for metals. They are **not** elements! They are in fact **alloys**, mixtures of elements (usually metals) designed to have properties that are useful for a particular purpose.

Non-metals are a less uniform group of elements. They show a much wider range of properties. This reflects the wider differences in the types of structure shown by non-metals.

Activity 3.1 Testing metals and non-metals

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

The key test to distinguish between metals and non-metals is electrical conductivity. A simple circuit is set up using either a light bulb or an ammeter. Power is supplied by batteries or a power pack. Examine a range of solid elements and alloys including magnesium, zinc, tin, iron, nickel, roll sulfur, graphite, brass and solder.

A worksheet is included on the CD-ROM.

Key definition

- ◆ **metal** – an element that conducts electricity and is malleable and ductile.
- ◆ **non-metal** – is an element that does not conduct electricity well and is neither malleable nor ductile.

The change from metallic to non-metallic properties in the elements is not as clear-cut as suggested by drawing the line between the two regions of the Periodic Table. The elements close to the line show properties that lie between these extremes. These elements are now often referred to as **metalloids** (or **semi-metals**). Such elements have some of the properties of metals and others that are more characteristic of non-metals. There are eight elements that are called metalloids. They often look like metals, but are brittle like non-metals. They are neither conductors nor insulators, but make excellent

Study tip

If asked to say how you would test to see whether an element was a metal or a non-metal, the key test is **electrical conductivity**. Describe the setting up of a simple circuit using a battery and a light bulb, and then connect in a sample of the element and see if the bulb lights up (Figure 3.3).

The other properties which are most clearly those of a metal are **malleability** and **ductility**. These, and electrical conductivity, are the properties where there are fewest exceptions.




Figure 3.3 Testing the electrical conductivity of a possible metal.



Figure 3.4 A sample of the element silicon, the basis of the semiconductor industry.

semiconductors. The prime example of this type of element is silicon (Figure 3.4)

Groups and periods in the Periodic Table

The Periodic Table allows us to make even more useful subdivisions of elements than simply deciding which are metals and which are non-metals. The

elements present in Groups I to VIII / 0 of the table are sometimes known as the **main-group elements**. These vertical groups show most clearly how elements within the same group have similar chemical and physical properties. Some of these groups have particular names as well as numbers. These are given in Figure 3.2. Between Groups II and III of these main groups of elements is a block of metals known as the **transition elements** (or **transition metals**). The first row of these elements occurs in Period 4. This row includes such important metals as iron, copper and zinc.

The noble gases, in Group VIII / 0 on the right-hand side of the table, are the least reactive elements in the table. However, the group next to them, Group VII which are also known as the halogens, and the group on the left-hand side of the table, Group I or the alkali metals, are the most reactive elements. The more unreactive elements, whether metals or non-metals, are in the centre of the table.

Study tip

If you are asked a question about an element in the Periodic Table, use the table at the back of the examination paper to help you answer it.

Electron arrangement and the Periodic Table

When the first attempts were made to construct a Periodic Table, nobody knew about the structure of the atom. We can now directly link the properties of an element with its position in the table and its electron arrangement (Figure 3.5). The number of outer electrons in the atoms of each element has been found. Elements in the same group have the same number of outer electrons. We also know that, as you move across a period in the table, a shell of electrons is being filled.

There is a clear relationship between electron arrangement and position in the Periodic Table for the main-group elements. The elements in Group II have two outer electrons. The elements in Period 3

have three shells of electrons. A magnesium atom has two electrons in its third, outer, shell, and is in Group II. An argon atom has an outer shell containing eight electrons – a very stable arrangement – and is in Group VIII / 0. A potassium atom has one electron in its fourth, outer shell, and is in Group I and Period 4.

It is the outer electrons of an atom that are mainly responsible for the chemical properties of any element. Therefore, elements in the same group will have similar properties.

The **electron arrangements** of atoms are linked to position in the Periodic Table.

- ◆ Elements in the same group have the same number of electrons in their outer shell.
- ◆ For the main-group elements, the number of the group is the number of electrons in the outer shell.
- ◆ The periods also have numbers. This number shows us how many shells of electrons the atom has.




Figure 3.5 The relationship between an element's position in the Periodic Table and the electron arrangement of its atoms.

Certain electron arrangements are found to be more stable than others. This makes them more difficult to break up. The most stable arrangements are those of the **noble gases**, and this fits in with the fact that they are so unreactive.

There are links between the organisation of particles in the atom and the regular variation in properties of the elements in the Periodic Table. This means that we can see certain broad trends in the table (Figure 3.6). These trends become most obvious if we leave aside the




Figure 3.6 General trends in the Periodic Table, leaving aside the noble gases in Group VIII / 0.

noble gases in Group VIII / 0. Individual groups show certain 'group characteristics'. These properties follow a trend in particular groups.

Questions

- 3.1 What is the name of the most reactive non-metal?
- 3.2 What is the similarity in the electron arrangement in the noble gases?
- 3.3 How many elements are there in Period 1?
- 3.4 Where, in the Periodic Table, will the largest atom be found?
- 3.5 Sort the following properties into those characteristic of a metal, and those typical of a non-metal.

is an insulator	can be beaten into sheets
gives a ringing sound when hit	conducts heat
has a dull surface	conducts electricity

3.2 Trends in groups

Group I – the alkali metals

The metals in Group I are often called the **alkali metals**. They are soft solids with relatively low melting points and low densities (Figure 3.7). They are highly reactive and are stored in oil to prevent them reacting with the oxygen and water vapour in the air. When freshly cut with a knife, all these metals have a light-grey, silvery surface, which quickly tarnishes (becomes dull). Reactivity increases as we go down the group. All Group I metals react with water to form hydrogen and an alkaline solution of the metal hydroxide. The reactions range from vigorous in the case of lithium



Figure 3.7 The alkali metals are all soft and can be cut with a knife. This is a sample of lithium.

to explosive in the case of caesium. You might predict that francium, at the bottom of Group I, would be the most reactive of all the metals. However, it is highly radioactive and very rare because it decays with a half-life of 5 minutes. It has been estimated that there are only 17 atoms of francium in existence on Earth at any one moment in time.

The physical properties of the alkali metals also change as we go down the group. The melting points become lower while the density of the metals increases.

The **alkali metals** (Group I) are the most reactive metals that occur. They are known as the alkali metals because they react vigorously with water to produce hydrogen and an alkaline solution.

Group VII – the halogens

The most reactive non-metals are the **halogens** in Group VII of the table (Figure 3.8). In contrast with Group I, here reactivity decreases **down** the group. For example, fluorine is a dangerously reactive, pale yellow gas at room temperature. There is a steady increase in melting points and boiling points as we go

	Chlorine (Cl₂) - dense pale-green gas - smelly and poisonous - occurs as chlorides, especially sodium chloride in the sea - relative atomic mass 35.5
	Bromine (Br₂) - deep-red liquid with red-brown vapour - smelly and poisonous - occurs as bromides, especially magnesium bromide in the sea - relative atomic mass 80
	Iodine (I₂) - grey solid with purple vapour - smelly and poisonous - occurs as iodides and iodates in some rocks and in seaweed - relative atomic mass 127

Figure 3.8 The general properties of some of the halogens (Group VII).

down the group, and the elements change from gases to solids as the atomic number increases. Interestingly, the lowest element in this group is also a highly radioactive and rare element, astatine. The actual properties of astatine remain a mystery to us, but we could make a good guess at some of them.

The halogen family found in Group VII of the Periodic Table shows clearly the similarities of elements in the group.

Common properties of the halogens


- ◆ They are all poisonous and have a similar strong smell.
- ◆ They are all non-metals.
- ◆ They all form diatomic molecules (for example Cl_2 , Br_2 , I_2).
- ◆ They all have a **valency** (combining power) of 1 and form compounds with similar formulae, for example hydrogen chloride (HCl), hydrogen bromide (HBr), hydrogen iodide (HI).
- ◆ Their compounds with hydrogen are usually strong acids when dissolved in water, for example hydrochloric acid (HCl), hydrobromic acid (HBr), hydriodic acid (HI).
- ◆ They each produce a series of compounds with other elements: chlorides, bromides and iodides. Together these are known as **halides**.
- ◆ The halogens themselves can react directly with metals to form metal halides (or **salts**).
- ◆ They all form negative ions carrying a single charge, for example chloride ions (Cl^-), bromide ions (Br^-), iodide ions (I^-).

There are gradual changes in properties between the halogens (see Figure 3.8). As you go down the group, the boiling points increase. Also there is a change from gas to liquid to solid. The intensity of the colour of the element also increases, from pale to dark. Following these trends, it should not surprise you to know that fluorine is a pale yellow gas at room temperature.

The chemical reactivity of the halogens


Fluorine and chlorine are very reactive. They combine strongly with both metals and non-metals. A piece of Dutch metal foil – an alloy of copper and zinc – will burst into flames when placed in a

gas jar of chlorine. When chlorine is passed over heated aluminium, the metal glows white and forms aluminium chloride:



Aluminium also reacts strongly with bromine and iodine. The reaction between a dry mixture of powdered aluminium and iodine can be triggered by adding just a few drops of water. The reaction is highly exothermic and some of the iodine is given off as purple fumes before it has a chance to react.

Hydrogen will burn in chlorine to form hydrogen chloride. Carried out a different way, the reaction can be explosive:



Chlorine dissolves in water to give an acidic solution. This mixture is called **chlorine water** and contains two acids:



Chlorine water acts as an **oxidising agent** – hypochlorous acid can give up its oxygen to other substances. It also acts as a bleach because some coloured substances lose their colour when they are oxidised. This reaction is used as the chemical test for chlorine gas. Damp litmus or **Universal Indicator** paper is bleached when held in the gas. The halogens become steadily less reactive as you go down the group. Table 3.3 (overleaf) gives some examples of the reactivity of the halogens.


The **displacement reactions** shown in the lower part of Table 3.2 demonstrate the order of reactivity of the three major halogens. For example, if you add chlorine to a solution of potassium bromide, the chlorine displaces bromine (Figure 3.9, overleaf). Chlorine is more reactive than bromine, so it replaces it and potassium chloride is formed. Potassium bromide solution is colourless. It turns orange when chlorine is bubbled through it:



Reaction with	Chlorine	Bromine	Iodine
coloured dyes	bleaches easily	bleaches slowly	bleaches very slowly
iron wool	iron wool reacts strongly to form iron(III) chloride; needs heat to start	iron reacts steadily to form iron(III) bromide; needs continuous heating	iron reacts slowly, even with continuous heating, to form iron(III) iodide
chlorides	—	no reaction	no reaction
bromides	displaces bromine, e.g. $\text{Cl}_2 + 2\text{KBr} \rightarrow 2\text{KCl} + \text{Br}_2$	—	no reaction
iodides	displaces iodine, e.g. $\text{Cl}_2 + 2\text{KI} \rightarrow 2\text{KCl} + \text{I}_2$	displaces iodine, e.g. $\text{Br}_2 + 2\text{KI} \rightarrow 2\text{KBr} + \text{I}_2$	—

Table 3.2 Some reactions of the halogens.

Chlorine will also displace iodine from potassium iodide:



You will find more information about the halogens and their uses in Chapter 9, Table 9.3.

Study tip

If you are asked to put elements from a group in order of reactivity, you must be very careful when reading the question to see whether the answer should be in order of increasing or decreasing reactivity.

Group VIII / 0 – the noble gases

When Mendeleev first constructed his table, part of his triumph was to predict the existence and properties of some undiscovered elements. However, there was no indication that a whole **group** of elements (Group VIII / 0) remained to be discovered! Because of their lack of reactivity, there was no clear sign of their existence. However, analysis of the gases in air led to the discovery of argon. There was no suitable place in the table for an individual element with argon's properties. This pointed to the existence of an entirely new group! In the 1890s, helium, which had first been detected by spectroscopy of light from the Sun during an eclipse, and the other noble gases in the group (Group VIII / 0) were isolated. The radioactive gas, radon, was the last to be purified,




Figure 3.9 Bromine is displaced by chlorine from a colourless solution of potassium bromide.

in 1908. One man, William Ramsay, was involved in the isolation of all the elements in the group. He was awarded the Nobel Prize for this major contribution.

All the noble gases are present in the Earth's atmosphere. Together they make up about 1% of the total, though argon is the most common. These gases are particularly unreactive. They were sometimes referred to as the **inert gases**, meaning they did not react at all. However, since the 1960s, some compounds of xenon and krypton have been made and their name was changed to the **noble gases**. The uses of

the noble gases depend on this unreactivity. Helium is used in airships and balloons because it is both light and unreactive. Argon is used to fill light bulbs because it will not react with the filament even at high temperatures. The best known use of the noble gases is, perhaps, its use in 'neon' lights (Figure 3.10). The brightly coloured advertising lights work when an electric discharge takes place in a tube containing a little of a noble gas. Different gases give different colours.

The atoms of the noble gases do not combine with each other to form molecules or any other form of structure. Their melting points and boiling points are extremely low (Figure 3.11). Helium has the lowest

melting point of any element, and cannot be solidified by cooling alone (pressure is needed also). All these properties point to the atoms of the noble gases being particularly stable.

- ◆ The electron arrangements of the atoms of the **noble gases** are very stable.
- ◆ This means that they do not react readily with other atoms.
- ◆ In many situations where atoms of other elements bond or react chemically, they are trying to achieve that stable arrangement of electrons found in the noble gases.




Figure 3.10 'Neon' lights give colour to our city centres by their use in advertising displays. The different colours are caused by different gases.



Figure 3.11 A small piece of rapidly melting 'argon ice' the melting point is -189°C .

The elements of Group VIII / 0 are between the two most reactive groups of elements (Groups I and VII). Indeed, it is their closeness to this group with stable electron arrangements that makes the alkali metals and the halogens so reactive. They can fairly easily achieve a noble-gas electron structure. The Group VII elements **gain** or **share** electrons and the Group I elements **lose** electrons to reach a noble-gas electron arrangement.

Questions

- 3.6 What is the name of the alkali formed when potassium reacts with water?
- 3.7 Write a word equation for the reaction between lithium and water.
- 3.8 Which halogen(s) will displace bromine from a solution of potassium bromide?
- 3.9 Give a use and a test for chlorine.

3.3 Trends across a period

The vertical groups of elements show similar properties, but following a period across the table highlights the trend from metallic to non-metallic properties. This can be explored by looking across a period. The first period of the table contains just two elements, hydrogen and helium, both of which are distinctive in different ways. The final period in the table is as yet incomplete. Each of the five remaining periods of elements starts with a

atomic size decreasing →							
				IV			
				C			
3	Na	Mg	Al	Si	P	S	Cl Ar
				Ge			
				Sn			
				Pb			
↑ atomic size decreasing							
metals (blue) metalloids (orange) non-metals (yellow)				gases (Cl, Ar) All elements except Cl and Ar are solids at room temperature.			

Figure 3.12 The changes in properties of the elements in Period 3 and in Group IV of the Periodic Table.

reactive alkali metal and finishes with an unreactive, non-metallic, noble gas. In Period 3, for example, from sodium to argon, there appears to be a gradual change in physical properties across the period. The change in properties seems to centre around silicon; elements before this behave as metals and those after it as non-metals (Figure 3.12).

The changeover in properties is emphasised if we look at Group IV as well. As we go down this group, the change is from non-metal to metal. The metalloids, silicon and germanium, are in the centre of the group (Figure 3.12).

The transition elements

If we look at Period 4 in the Periodic Table, we see that there is a whole 'block' of elements in the centre of the table. This block of elements falls outside the main groups of elements that we have talked about so far. They are best considered not as a vertical group of elements but as a row or block. They are usually



Figure 3.13 Some everyday objects made from transition metals.

referred to as the **transition elements** (or **transition metals**). Their properties make them among the most useful metallic elements available to us (Figure 3.13). They are much less reactive than the metals in Groups I and II. Many have excellent corrosion resistance, for example chromium. The very high melting point of tungsten (3410°C) has led to its use in the filaments of light bulbs.

Many familiar objects are made from transition metals. Figure 3.13 shows a range of these: steel nails, chrome bottle stopper, copper pipe joints, iron horseshoe magnet, cupro-nickel coins (a mix of 75% copper, 25% nickel) and copper-plated steel coins.

These general properties mean that the transition metals are useful in a number of different ways. In addition, there are **particular** properties that make these metals distinctive and useful for more specific purposes. One important feature of transition metals is that their compounds are often coloured (Figure 3.14).



Figure 3.14 Many of the compounds of transition metals are coloured and, when they dissolve, they give coloured solutions.

Transition metals (or transition elements) General features:

- ♦ They are hard and strong.
 - ♦ They have high density.
 - ♦ They have high melting and boiling points.
- Two of their distinctive properties:
- ♦ Many of their compounds are coloured.
 - ♦ They often show more than one **valency** (variable oxidation state)– they form more than one type of ion. For example, iron can form compounds containing iron(II) ions (Fe^{2+}) or iron(III) ions (Fe^{3+}).

The position of hydrogen in the Periodic Table

Hydrogen is difficult to place in the Periodic Table. Different versions place it above Group I or Group VII. More often, in modern tables, it is left by itself (Figure 3.15). This is because, as the smallest atom of all, its properties are distinctive and unique. It does not fit easily into the trends shown in any one group (Table 3.3).

1 H hydrogen Hydrogen doesn't belong to any group.								
Group	I	II	III	IV	V	VI	VII	2
	3 Li lithium	4 Be beryllium	5 B boron	6 C carbon	7 N nitrogen	8 O oxygen	9 F fluorine	10 Ne neon
	11 Na sodium	12 Mg magnesium	13 Al aluminium	14 Si silicon	15 P phosphorus	16 S sulfur	17 Cl chlorine	18 Ar argon
	19 K potassium	20 Ca calcium						

Figure 3.15 The position of hydrogen in the Periodic Table.

Questions

- 3.10 In which direction does the change in element type run, when going across a period from left to right?
- 3.11 Which metal has the highest melting point in Period 3?
- 3.12 Which metal is the softest and least dense in Period 3?
- 3.13 What is the formula of chlorine?
- 3.14 Which of the elements in Period 3 has the highest melting point?
- 3.15 Why is copper(II) sulfate blue?

Lithium	Hydrogen	Fluorine
solid at room temperature	gas	gas
metal	non-metal; forms diatomic molecules (H_2)	non-metal; forms diatomic molecules (F_2)
has one electron in outer shell	has one electron in outer shell	has seven electrons in outer shell
can lose one electron to achieve a noble-gas arrangement (forms a positive ion)	can form either a positive or a negative ion; can gain one electron to achieve a noble-gas arrangement, or lose its only electron	can gain one electron to achieve a noble-gas arrangement (forms a negative ion)

Table 3.3 A comparison of hydrogen atoms with those of lithium (Group I) and fluorine (Group VII).

3.4 Chemical bonding in elements and compounds

We live on the 'water planet'. The surface of the Earth is distinctive because so much of it is covered with water. From space, it is the blue colours of water in seas and oceans and the white of the moisture-laden clouds that distinguish the Earth from other planets. The Earth is unique in being the only planet in our solar system where conditions allow water to exist in all three states of matter.

Simple compounds such as water, ammonia and methane begin to show the variety that can be achieved when the atoms of elements combine together. Water is formed from hydrogen and oxygen. Each water molecule contains two hydrogen atoms bonded to an oxygen atom. In fact, the formula of water (H_2O) is perhaps the best known chemical formula.

Chemical bonding involves the outer electrons of each atom. As we examine a range of substances, we shall see that, whatever type of bonding holds the structure together, it is the outer electrons that are used. The diversity of the material world is produced by the different ways in which atoms can join together.

Activity 3.2


Boiling water in a cup of ice!

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

This experiment can be carried out as a demonstration or as a class activity in groups.

- 1 Fill a large mug with water and float a small plastic cup in it – adjust the cup so that it just floats by using some small coins. The cup should be placed centrally in the mug, not touching the side. Use sticky tape to keep the cup in a central position.



- 2 Place the mug overnight in a freezer to make sure the water is completely frozen.

- 3 Take the 'apparatus' out of the freezer and remove the coins.
- 4 Leave the mug to stand out of the freezer for a few minutes. This allows you to take the 'ice cup' out of the mug. If necessary, the ice cup can be put back in the freezer until it is to be used.
- 5 Fill the plastic insert of the ice cup with water and place it in the microwave oven. Microwave for about 30 seconds until the water boils. You have water in all three states of matter at once – ice, water and steam. The temperature of the water can be checked with a thermometer.

A worksheet is included on the CD-ROM.

Questions

- 1 Write brief notes on the organisation and movement of the water molecules in the three states of matter.
- 2 Research how a microwave oven heats the water when it is liquid and comment on why the ice does not heat up as quickly as the liquid.

Bonding in the elements

Earlier we saw that some elements are not simply made up of separate atoms individually arranged. Elements such as oxygen (O_2) and hydrogen (H_2) consist of **diatomic molecules**. Indeed, the only elements that are made up of individual atoms moving almost independently of each other are the noble gases (Group VIII / 0). These are the elements whose electron arrangements are most stable and so their atoms do not combine with each other.

Most of the elements do form structures. Their atoms are linked by some type of bonding. Most elements are metals. The structures in this case are held together by **metallic bonding**. The non-metallic elements to the right of the Periodic Table are held together by **covalent bonding**. Both these types of bonding use the outer electrons in some way.

Bonding in the elements

- ♦ Metallic elements are held together by **metallic bonding**, which results in **metallic lattices**.
- ♦ Non-metallic elements are held together by **covalent bonding** or exist as **separate atoms** (the noble gases). Covalent bonding results in **simple molecules** or **giant molecular lattices**.

Bonding in metals

Metal atoms have relatively few electrons in their outer shells. When they are packed together, each metal atom loses its outer electrons into a 'sea' of free electrons (or mobile electrons). Having lost electrons, the atoms are no longer electrically neutral. They become positive **ions** because they have lost electrons




Figure 3.16 Metallic bonding – the metal ions are surrounded by a ‘sea’ of mobile electrons.

but the number of protons in the nucleus has remained unchanged.

Therefore the structure of a metal is made up of positive ions packed together. These ions are surrounded by electrons, which can move freely between the ions. These free electrons are **delocalised** (not restricted to orbiting one positive ion) and form a kind of electrostatic ‘glue’ holding the structure together (Figure 3.16). In an electrical circuit, metals can conduct electricity because the mobile electrons can move through the structure, carrying the current. This type of bonding (called **metallic bonding**) is present in alloys as well. Alloys such as solder and brass, for example, will conduct electricity.

Key definition

ion – a charged particle made from an atom by the loss or gain of electrons.

Metal atoms more easily lose electrons than gain them. So, they become **positive ions**. In doing so, they achieve a more stable electron arrangement, usually that of the nearest noble gas.

Bonding in non-metals

Hydrogen normally exists in the form of diatomic molecules (H_2). Two atoms bond together by sharing their electrons. The orbits overlap and a molecule is formed (Figure 3.17).




Figure 3.17 The hydrogen molecule is formed by **sharing** the electrons from the atoms. A space-filling model can be used to show the atoms overlapping.

Through this sharing, each atom gains a share in two electrons. This is the number of electrons in the outer shell of helium, the nearest noble gas to hydrogen. (Remember that the electron arrangement of helium is very stable; helium atoms do **not** form He_2 molecules.) Sharing electrons like this is known as **covalent bonding**. It has been shown that in a hydrogen molecule, the electrons are more likely to be found between the two nuclei. The forces of attraction between the shared electrons and the nuclei are greater than any repulsive forces. The molecule is held together by the bond.

Features of covalent bonding

- ◆ The bond is formed by the sharing of a pair of electrons between two atoms.
- ◆ Each atom contributes one electron to each bond.
- ◆ Molecules are formed from atoms linked together by covalent bonds.

Many non-metallic elements form diatomic molecules. However, elements other than hydrogen form bonds in order to gain a share of **eight** electrons in their outer shells. This is the number of electrons in the outer shell of all the noble gases apart from helium. Thus, the halogens (Group VII) form covalent molecules (Figure 3.18, overleaf).

Molecules of hydrogen and the halogens are each held together by a single covalent bond. Such a single




Figure 3.18 **a** The formation of the covalent bond in chlorine molecules (Cl_2). Each atom gains a share in eight electrons in its outer shell. The diagram can be drawn showing the outer electrons only, because the inner electrons are not involved in the bonding. **b** Molecules of Br_2 and I_2 are formed in the same way. They are larger because the original atoms are bigger.

bond uses two electrons, one from each atom. The bond can be drawn as a single line between the two atoms.

Note that, when we draw diagrams showing the overlap of the outer shells, we can show the outer electrons only, because the inner electrons are not involved in the bonding. Each atom gains a share in eight electrons in its outer shell.

When molecules of oxygen (O_2) or nitrogen (N_2) are formed, more electrons have to be used in bonding if the atoms are to gain a share of eight electrons. These molecules are held together by a double bond (O_2) or a triple bond (N_2) (Figure 3.19). Note that the structure of oxygen is not required for the syllabus.

The non-metals in the middle of the main-group elements, for example carbon and silicon, do not form simple molecules. They exist as giant molecular structures held together by single covalent bonds. In these structures, the atoms are joined to each other in an extensive network or **giant molecular lattice** (see Figure 3.42, page 83). Such structures are very strong because all the atoms are interlinked by strong covalent bonds. The structure of the carbon atoms in diamond is a three-dimensional lattice structure in which each




Figure 3.19 The structures of oxygen (O_2) and nitrogen (N_2) molecules involve multiple covalent bonding. An oxygen molecule contains a double bond; a nitrogen molecule contains a triple bond.

carbon atom is joined to four others by strong covalent bonds. A similar structure exists in silicon, which is an important element in the electronics industry.

Chemical bonding in compounds

Different elements combine together to form the vast range of compounds that make up our world. They vary from inert and heat-resistant ceramic materials to high explosives, and from lethal poisons to the molecules of life. All depend on the means of chemical bonding. Two major types of bond hold compounds together. The first is covalent bonding, which, as we have seen, involves **sharing** electrons between atoms. However, the behaviour of metal plus non-metal compounds arises from a different type of bonding. Here electrons are **transferred** from one atom to another. These compounds are held together by **electrostatic forces** between separate ions: **ionic bonding**.

Bonding in compounds

- ◆ Non-metal plus non-metal compounds are held together by **covalent bonding**, which results in **simple molecules** or **giant molecular lattices**.
- ◆ Metal plus non-metal compounds are held together by **ionic bonding**, which results in **giant ionic lattices**.

Covalent compounds

In covalent compounds, bonds are again made by sharing electrons between atoms. In simple molecules, the atoms combine to achieve a more stable arrangement of

electrons, most often that of a noble gas. The formation of hydrogen chloride (HCl) involves the two atoms sharing a pair of electrons (Figure 3.20).

The examples shown in Figure 3.21 illustrate different ways of representing this sharing. They also show how the formula of the compound corresponds to the numbers of each atom in a molecule.

In each case, the atoms achieve a share in the same number of electrons as the noble gas nearest to that element in the Periodic Table. In all but the case of hydrogen, this means a share of eight electrons in their outer shell.

Earlier we saw that multiple covalent bonds can exist in molecules of the elements oxygen and nitrogen. They can exist in compounds too. The carbon dioxide molecule is held together by double bonds between the atoms (Figure 3.22, overleaf). This figure also shows some other examples of bonding in compounds that you will meet again in Chapter 10.




Figure 3.20 Hydrogen and chlorine atoms share a pair of electrons to form a molecule of hydrogen chloride.




Figure 3.21 Examples of the formation of simple covalent molecules. Again, only the outer electrons of the atoms are shown. More complex examples are shown in Figure 3.22.




carbon dioxide (CO₂)**ethene (C₂H₄)****ethanol (C₂H₅OH)**

Figure 3.22 The formation of the carbon dioxide, ethene and ethanol molecules, showing the outer electrons only. Ball-and-stick models can be used to show the structure.

Activity 3.3

Modelling the bonding in covalent substances

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

In this activity, you will make models of simple molecular structures of certain elements and compounds to demonstrate the importance of single, double and triple covalent bonds in molecules.

The modelling can be extended to show the processes of bond breaking and bond making that take place during a chemical reaction. This serves as an introduction to balancing chemical equations.

A worksheet is included on the CD-ROM.

Ionic compounds

Compounds of a metal plus a non-metal generally adopt a third type of bonding. This involves the transfer of electrons from one atom to another. This transfer of electrons results in the formation of positive and negative ions. The oppositely charged ions are then attracted to each other by **electrostatic forces**.

- ◆ The electrons involved in the formation of ions are those in the outer shell of the atoms.
- ◆ Metal atoms lose their outer electrons to become positive ions. In doing so they achieve the more stable electron arrangement of the nearest noble gas.
- ◆ Generally, atoms of non-metals gain electrons to become negative ions. Again, in doing so, they achieve the stable electron arrangement of the nearest noble gas to them in the Periodic Table.

A common example of a compound that involves ionic bonding is sodium chloride (Figure 3.23). Each of the sodium atoms, which have an electron arrangement of 2,8,1, loses its one outer electron to form a sodium ion (Na^+) (Figure 3.24).




Figure 3.23 The transfer of electrons from a sodium atom to a chlorine atom to form ions.




Figure 3.24 A sodium atom loses an electron to become a sodium ion.




Figure 3.25 A chlorine atom gains an electron to become a chloride ion.

The sodium ion then has the stable electron arrangement (2,8) of a neon atom – the element just before it in the Periodic Table. The electron released is transferred to a chlorine atom. The sodium ion has a single positive charge because it now has just 10 electrons in total, but there are still 11 protons in the nucleus of the atom.

The chlorine atoms, electron arrangement 2,8,7, each gain an electron released from the sodium atoms and they become chloride ions (Cl^-) (Figure 3.25). The chloride ion (electron arrangement 2,8,8) has the electron arrangement of an argon atom. The chloride ion has a negative charge because it has one more electron (18) than there are protons in the nucleus.

The positive and negative ions in sodium chloride are held together by the electrostatic attraction between opposite charges.

Study tip

For the Core syllabus, the examples of ionic bonding you need to be familiar with are those between Group I metals and Group VII non-metals – the alkali metals and the halogens. Try drawing diagrams like the one in Figure 3.23 for compounds such as lithium fluoride or potassium bromide. You will see that there is a great similarity in the diagrams.

S More complex ionic compounds than those formed between the alkali metals and the halogens require care in working out the transfer of a greater number of electrons. Figure 3.26 shows two examples of such compounds.

Features common to ionic bonding

- ◆ Metal atoms always lose their outer electrons to form positive ions.
- ◆ The number of positive charges on a metal ion is equal to the number of electrons lost.
- ◆ Non-metal atoms, with the exception of hydrogen, always gain electrons to become negative ions.
- ◆ The number of negative charges on a non-metal ion is equal to the number of electrons gained.
- ◆ In both cases, the ions formed have a more stable electron arrangement, usually that of the noble gas nearest to the element concerned.
- ◆ Ionic (electrovalent) bonds result from the attraction between oppositely charged ions.

Study tip

Do practise drawing the diagrams for both covalent and ionic bonding so that you can draw them accurately in the examination.

When you draw the diagrams of ionic bonding, make sure you remember to put in the charges outside the brackets on each ion.

S Ionic compounds (such as sodium chloride) are solids at room temperature. The ions arrange themselves into a regular lattice (Figure 3.27). In the




Figure 3.26 Diagrams showing the formation of ionic bonds in magnesium oxide and calcium chloride. Again, only the outer electrons are shown.




Figure 3.27 A giant ionic lattice where each ion is surrounded by ions of opposite charge.

lattice, each ion is surrounded by ions of the opposite charge. The whole **giant ionic structure** is held together by the electrostatic forces of attraction that occur between particles of opposite charge (see Section 3.6).

Polyatomic (compound) ions

The ionic compounds mentioned so far have been made from simple ions, for example Na⁺, K⁺, Mg²⁺, Cl⁻, O²⁻. However, in many important ionic compounds the metal ion is combined with a negative ion containing a **group** of atoms (for example SO₄²⁻, NO₃⁻, CO₃²⁻). These **polyatomic ions** (or **compound ions** or **groups**) are made up of atoms covalently bonded together. These groups have a negative charge because they have gained electrons to make a stable structure. Examples of such ions are shown in Figure 3.28. In addition to these negative compound ions, there is one important polyatomic ion that is positively charged, the ammonium ion, NH₄⁺ (Figure 3.28). Table 3.4 gives a summary of some simple and polyatomic ions.




Figure 3.28 Three examples of negatively charged polyatomic ions and a positively charged polyatomic ion. The numbers of atoms and the overall charge carried by each group of atoms are shown.

Valency	Simple metal ions (+ve)	Simple non-metallic ions		Polyatomic (or compound) ions	
		(+ve)	(-ve)	(+ve)	(-ve)
1	sodium, Na^+	hydrogen, H^+	hydride, H^-	ammonium, NH_4^+	hydroxide, OH^-
	potassium, K^+		chloride, Cl^-		nitrate, NO_3^-
	silver, Ag^+		bromide, Br^-		hydrogencarbonate, HCO_3^-
	copper(I), Cu^+		iodide, I^-		
2	magnesium, Mg^{2+}		oxide, O^{2-}		sulfate, SO_4^{2-}
	calcium, Ca^{2+}		sulfide, S^{2-}		carbonate, CO_3^{2-}
	zinc, Zn^{2+}				
	iron(II), Fe^{2+}				
	copper(II), Cu^{2+}				
3	aluminium, Al^{3+}		nitride, N^{3-}		phosphate, PO_4^{3-}
	iron(III), Fe^{3+}				

Table 3.4 Some common simple and polyatomic ions.

Through our discussion of elements and compounds we have seen that there are three major types of **chemical bonding**:

- ♦ **metallic bonding**
- ♦ **ionic bonding**
- ♦ **covalent bonding.**

The types of structure based on these methods of bonding are summarised in Figure 3.29 (overleaf).

The physical properties of ionic and covalent compounds

Knowledge of how atoms combine to make different types of structure helps us begin to understand why substances have different physical properties. Table 3.5 (overleaf) shows the broad differences in properties of ionic and simple covalent compounds.




Figure 3.29 An overall summary of the bonding in elements and compounds.

Properties of typical ionic compounds	Reason for these properties
They are crystalline solids at room temperature.	There is a regular arrangement of the ions in a lattice. Ions with opposite charge are next to each other.
They have high melting and boiling points.	Ions are attracted to each other by strong electrostatic forces. Large amounts of energy are needed to separate them.
They are often soluble in water (not usually soluble in organic solvents, e.g. ethanol, methylbenzene).	Water is attracted to charged ions and therefore many ionic solids dissolve.
They conduct electricity when molten or dissolved in water (not when solid).	In the liquid or solution, the ions are free to move about. They can move towards the electrodes when a voltage is applied.
Properties of simple covalent compounds	Reason for these properties
They are often liquids or gases at room temperature.	These substances are made of simple molecules. The atoms are joined together by covalent bonds.
They have low melting and boiling points.	The forces between the molecules (intermolecular forces) are only very weak. Not much energy is needed to move the molecules further apart.
They are soluble in organic solvents such as ethanol or methylbenzene (very few are soluble in water).	Covalent molecular substances dissolve in covalent solvents.
They do not conduct electricity.	There are no ions present to carry the current.

Table 3.5 The properties of ionic and simple covalent compounds.

Questions

- 3.16** What type of bond would be found between the following pairs of elements?
- sulfur and chlorine
 - carbon and oxygen
 - magnesium and nitrogen
 - zinc and copper
- 3.17** Why is the formula of hydrogen always written as H_2 ?
- 3.18** What force holds the sodium and chlorine together in sodium chloride?
- 3.19** Draw diagrams of the covalent bonding in the following elements and compounds (showing the outer electrons only in your diagrams):

- hydrogen
- water
- ammonia
- methane.

3.20 Draw diagrams of the ionic bonding in the following compounds:

- sodium chloride
- lithium fluoride.

3.21 Why is it true to say that calcium carbonate has both ionic and covalent bonds?

3.22 Draw diagrams of the ionic bonding in the following compounds:

- magnesium oxide
- calcium chloride.

3.5 The chemical formulae of elements and compounds

The chemical 'shorthand' of representing an element by its symbol can be taken further. It is even more useful to be able quickly to sum up the basic structure of an element or compound using its chemical **formula**.

The formulae of elements

Those elements which are made up of individual atoms or small molecules (up to three atoms covalently bonded together) are represented by the formula of the particle present (Figure 3.30). Where elements exist as giant structures, whether held together by metallic or covalent bonding, the formula is simply the symbol of the element (for example Cu, Mg, Fe, Na, K, etc., and C, Si, Ge). For convenience,

				H_2						He			
Li	Be					B	C	N_2	O_2	F_2	Ne		
Na	Mg					Al	Si	P (P_4)	S (S_8)	Cl_2	Ar		
K	Ca	Sc	Ti			Cu	Zn	Ga	Ge	As	Se	Br_2	Kr
giant metallic lattice				giant molecular lattice		simple molecules				single atoms			

Figure 3.30 The formulae of the elements are linked to their structure and their position in the Periodic Table.

the same applies to elements such as phosphorus (P) or sulfur (S). In these cases, the molecules contain more than three atoms.

The formulae of ionic compounds

Ionic compounds are solids at room temperature, and their formulae are simply the whole-number ratio of the positive to negative ions in the structure. Thus, in magnesium chloride, there are two chloride ions (Cl^-) for each magnesium ion (Mg^{2+}).

ions present	Mg^{2+}	Cl^-
		Cl^-
total charge	2+	2-


The formula is $MgCl_2$. The overall structure must be neutral. The positive and negative charges must balance each other.

The size of the charge on an ion is a measure of its valency, see Table 3.4 on page 73, or combining power. Mg^{2+} ions can combine with Cl^- ions in a ratio of 1 : 2, but Na^+ ions can only bond in a 1 : 1 ratio with Cl^- ions. This idea of valency can be used to ensure that you always use the correct formula for an ionic compound. Follow the examples of aluminium oxide and calcium oxide below, and make sure you understand how this works.

S Formula for aluminium oxide

Write down the correct symbols


Write down the charges on the ions



Formula for calcium oxide

Write down the correct symbols

Write down the charges on the ions




The same rules apply when writing the formulae of compounds containing polyatomic ions because each of them has an overall charge (see Table 3.4 on page 73). It is useful to put the formula of the polyatomic ion in brackets. This emphasises that it cannot be changed. For example, the formula of the carbonate ion is always CO_3^{2-} . Work through the examples for sodium carbonate and ammonium sulfate below.

Formula of sodium carbonate

Write down the correct 'symbols'

Write down the charges on the ions



Formula of ammonium sulfate

Write down the correct 'symbols'

Write down the charges on the ions




Table 3.6 summarises the formulae of some important ionic compounds.

Study tip

Be very careful when writing chemical formulae to get the symbols of the elements correct. Remember the unusual symbols: that sodium is Na and not So, for example.

Remember that the second letter in any symbol is lower case, not a capital letter: Na not NA, Cl not CL and Co not CO, for instance.

Name	Formula	Ions present		Ratio
sodium chloride	NaCl	Na^+	Cl^-	1 : 1
ammonium nitrate	NH_4NO_3	NH_4^+	NO_3^-	1 : 1
potassium sulfate	K_2SO_4	K^+	SO_4^{2-}	2 : 1
calcium hydrogen-carbonate	$\text{Ca}(\text{HCO}_3)_2$	Ca^{2+}	HCO_3^-	1 : 2
copper(II) sulfate	CuSO_4	Cu^{2+}	SO_4^{2-}	1 : 1
magnesium nitrate	$\text{Mg}(\text{NO}_3)_2$	Mg^{2+}	NO_3^-	1 : 2
aluminium chloride	AlCl_3	Al^{3+}	Cl^-	1 : 3

Table 3.6 The formulae of some ionic compounds.

The formulae of covalent compounds


The idea of an atom having a valency, or combining power, can also be applied to working out the formulae of covalent compounds. Here the valency of an atom is the number of covalent bonds it can form. The 'cross-over' method for working out chemical formulae can be applied to covalent compounds in two situations:

- ♦ simple molecules with a central atom, for example water, methane, carbon dioxide and ammonia:

Formula of carbon dioxide

Write down the symbols

Write down the valencies



- ♦ giant covalent molecules, where the formula is simply the whole-number ratio of the atoms present in the giant lattice, for example silica.

The valency of an element in the main groups of the Periodic Table can be worked out from the group number of the element. The relationship is shown on the next page.

Working out valency

For elements in Groups I–IV,

valency = group number

For elements in Groups V–VII,

valency = 8 – the group number

Elements in Group VIII / 0 have a valency of 0.

This trend in valency with the group number can be seen by looking at typical compounds of the elements of Period 3. You can see that the valency rises to a value of 4 and then decreases to zero as we cross the period.

Group	I	II	III	IV	V	VI	VII	VIII / 0
Valency	1	2	3	4	3	2	1	0
Typical compound	NaCl	MgCl ₂	AlCl ₃	SiCl ₄	PH ₃	H ₂ S	HCl	—

For example, carbon is in Group IV, so its valency is 4, and oxygen is in Group VI, so its valency is 8 – 6 = 2.

Examples of writing formulae

The method for working out formulae above does **not** work for the many covalent molecules that do not have a single central atom, for example H₂O₂, C₂H₆, C₃H₈, etc. The formulae of these compounds still obey the valency rules. However, the numbers in the formula represent the actual number of atoms of each element present in a molecule of the compound (Figure 3.31).




Figure 3.31 The structures of hydrogen peroxide (H₂O₂) and ethane (C₂H₆), showing the bonds made.

'What's in a name?' – naming chemical compounds

Giving a name to a compound is a way of classifying it. Not all names are as informative as others, but modern systems do aim to be consistent. Some common and important compounds have historical names that do not seem to fit into a system. Examples of these include water (H₂O), ammonia (NH₃) and methane (CH₄). These apart, there are some basic generalisations that are useful.

- ◆ If there is a metal in the compound, it is named first.
- ◆ Where the metal can form more than one ion, then the name indicates which ion is present; for example, iron(II) chloride contains the Fe²⁺ ion, while iron(III) chloride contains the Fe³⁺ ion.
- ◆ Compounds containing only two elements have names ending in **-ide**; for example, sodium chloride (NaCl), calcium bromide (CaBr₂), magnesium nitride (Mg₃N₂). The important exception to this is the hydroxides, which contain the hydroxide (OH⁻) ion.
- ◆ Compounds containing a polyatomic ion (usually containing oxygen) have names that end with **-ate**; for example, calcium carbonate (CaCO₃), potassium nitrate (KNO₃), magnesium sulfate (MgSO₄), sodium ethanoate (CH₃COONa).
- ◆ The names of some compounds use prefixes to tell you the number of that particular atom in the molecule. This is useful if two elements form more than one compound; for example, carbon **monoxide** (CO) and carbon **dioxide** (CO₂), nitrogen **dioxide** (NO₂) and **dinitrogen tetroxide** (N₂O₄), sulfur **dioxide** (SO₂) and sulfur **trioxide** (SO₃).

The names for the important mineral acids are **systematic but are best simply learnt at this stage**; for example, sulfuric acid (H₂SO₄).

Two important oxidising agents contain polyatomic negative ions involving metal and oxygen atoms. Their modern names (potassium manganate(VII) (KMnO₄) and potassium dichromate(VI) (K₂Cr₂O₇)) include the oxidation state of the metal. At this stage you will not need to write equations using these compounds, but you will need to recognise their names and formulae.

Questions

3.23 What names would you give these compounds?

- a** NaI **b** MgS **c** K₂O **d** Li₃N
e Ca(OH)₂ **f** NO **g** NO₂ **h** SO₃

3.24 Use your Periodic Table to help you give the formula of these compounds:

- a** silicon chloride **b** carbon sulfide
c phosphorus chloride **d** silicon oxide.

3.25 a How many atoms of the different elements are there in the formulae of these compounds?

- i** sodium hydroxide, NaOH
ii ethane, C₂H₆
iii sulfuric acid, H₂SO₄
iv copper nitrate, Cu(NO₃)₂
v sucrose (sugar), C₁₂H₂₂O₁₁

b What are the names of the compounds that have the following formulae?


- i** KBr **vi** HNO₃
ii Al(OH)₃ **vii** SiCl₄
iii CuCO₃ **viii** FeSO₄
iv Mg₃N₂ **ix** CH₄
v PCl₃ **x** H₂SO₄

c Give the formulae for the following compounds:

- i** potassium sulfate
ii aluminium fluoride
iii iron(III) oxide
iv calcium nitrate
v zinc chloride

- vi** ammonia
vii hydrochloric acid
viii copper(II) sulfate
ix sulfur trioxide.

3.26 The diagram shows the arrangement of the outer electrons only in a molecule of ethanoic acid.



- a** Name the different elements found in this compound.
b What is the total number of atoms present in this molecule?
c Between which two atoms is there a double covalent bond?
d How many covalent bonds does each carbon atom make?
e Would you expect this compound to be a solid or a liquid at room temperature? Give a reason for your answer.
f Ethanoic acid will dissolve in methylbenzene. Would you expect the solution to conduct electricity? Give a reason for your answer.

3.6 Metals, alloys and crystals

The hexagonal shapes of snowflake crystals demonstrate how simple molecules can combine to produce complex and beautiful solid structures (Figure 3.32). The regularity of a snowflake suggests that the water molecules it contains are arranged in an organised way. In general, there are three basic units from which solids are constructed – atoms, ions and molecules. These different particles produce a range of structures in the solid state, which can be classified into four broad types.

Key definition

The four different types of solid physical structure are:

- ◆ **giant metallic lattice** – a lattice of positive ions in a ‘sea’ of electrons
- ◆ **giant ionic lattice** – a lattice of alternating positive and negative ions
- ◆ **giant molecular lattice** – a giant molecule (macromolecule) making the lattice
- ◆ **simple molecular substances** – consisting of simple molecules in a lattice held together by weak forces (Figure 3.33).




Figure 3.32 A snowflake crystal.

Substances that consist of simple molecules have relatively low melting points and boiling points.

This is because there are only weak forces between the molecules. They don't conduct electricity.




Figure 3.33 Simple molecular substances have low melting points.

Structures of these different types surround us in the real world. In some cases, we use and adapt their physical properties to engineer materials to suit a particular purpose.

Metal crystals

The idea of the regular packing of metal ions into a lattice surrounded by a 'sea' of mobile electrons helps to explain many of the physical properties of metals. In most metals, the packing is as close as possible. This explains why metals usually have a high density. In some metals the ions are less closely packed. These metals, for example the alkali metals, have the lowest densities of all metals. So, lithium and sodium will float on water.




Figure 3.34 The layers in a metal lattice can slide over each other.

The layers of identical ions in a pure metal can be moved over one another without breaking the structure (Figure 3.34). This flexibility in the layered structure means that metals can be beaten or rolled into sheets (they are **malleable**). Metals are more malleable when hot, and steel, for instance, is rolled when hot. They can also be stretched into wires (they are **ductile**). The strength of the metallic bonds means that the metal does not easily break under these forces. The bonds are strong but not rigid. This means that metals generally have a high tensile strength.

The mobility of the delocalised electrons in a metal means that metals conduct electricity very well. Copper is a particularly good conductor, and most electrical wires are made from it. For overhead power lines, aluminium is used, as it is lighter. However, because aluminium is not strong, a steel core has to be used.

Metals have a crystalline structure. You can see this if you look at a metal surface under the microscope. Look, too, at the surface of a galvanised iron lamp-post, some railings or the inside of a dustbin or iron bucket (Figure 3.35). Irregular-shaped zinc crystals can be seen (zinc is coated on iron in the galvanisation process). These crystalline areas are called **grains**. The boundaries between them are the **grain boundaries**. Figure 3.36 describes their formation. In general, the smaller the grain size, the stronger and harder the metal is.

Activity 3.4


Modelling metallic crystal structure

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

A surface layer of small air bubbles floating on water can be used to model the grain boundaries present in metallic crystals. Fill a shallow Petri dish with water and add a few drops of detergent. Use a gas syringe

fitted with a bent pipette to create an extensive layer of air bubbles on the surface.



In this model, each bubble represents a metal atom. The bubbles are seen to arrange themselves regularly but in some places there are 'grain boundaries' where the direction of the bubbles in the layer changes.

A worksheet is included on the CD-ROM.



Figure 3.35 A photograph of zinc grains on a galvanised post.

Alloys

Making alloys with other metals is one of the commonest ways of changing the properties of metals. Alloys are formed by mixing the molten metals together thoroughly and then allowing them to cool and form a solid.

Alloying often results in a metal that is stronger than the original individual metals. 'Silver' coins are minted from cupro-nickel alloy, which is much harder than copper itself (Figure 3.37). Aluminium is a low-density metal that is not very strong. When mixed with 4% copper and smaller amounts of other elements, it gives a metal (duralumin) that combines strength and lightness and is ideal for aircraft building. Other examples of alloys and their properties are given in Table 3.7.

Figure 3.38 shows how the presence of the 'impurity' atoms makes it more difficult for the metal ions to slip over each other. This makes the alloy stronger but more brittle than the metals it is made from.

Strength is not the only property to think about when designing an alloy. For example, solder is an alloy of tin and lead. It is useful for making electrical connections because its melting point is lower than that of either of the two separate metals. Also, steel, which rusts when in contact with oxygen and water, can be prevented from doing so when




Figure 3.36 The process of formation of grains as a molten metal cools.



Figure 3.37 Many different coins are made from cupro-nickel alloys.




Figure 3.38 **a** The positions of atoms in a pure metal crystal before a force is applied. **b** After the force is applied, slippage has taken place. The layers in a pure metal can slide over each other. **c** In an alloy, slippage is prevented because the atoms of different size cannot slide over each other.

alloyed with chromium and nickel. This forms stainless steel (see Table 3.7).

Study tip

It is important that you learn which elements are present in certain alloys, such as brass, bronze, mild steel and stainless steel, and you should be familiar with certain key uses for each alloy. The syllabus gives uses for mild steel (car bodies and machinery) and stainless steel (chemical plant and cutlery) – make sure you are aware of these.

Alloy	Typical composition		Particular properties
brass	copper	70%	harder than pure copper; 'gold' coloured
	zinc	30%	
bronze	copper	90%	harder than pure copper
	tin	10%	
mild steel	iron	99.7%	stronger and harder than pure iron
	carbon	0.3%	
stainless steel	iron	74%	harder than pure iron; does not rust
	chromium	18%	
	nickel	8%	
solder	tin	50%	lower melting point than either tin or lead
	lead	50%	

Table 3.7 Some important alloys.

Activity 3.5 Intriguing alloys!

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity consists of three sections, each of which illustrates how the combination of metal elements into an alloy results in useful and novel properties. The alloys investigated are solder, Field's metal and nitinol.

A worksheet is included on the CD-ROM.

S Ionic crystals

Ionic compounds form lattices consisting of positive and negative ions. In an ionic lattice, the nearest neighbours of an ion are always of the opposite charge. Thus, in sodium chloride, each sodium (Na^+) ion is surrounded by six chloride (Cl^-) ions (Figure 3.39), and each Cl^- ion is surrounded by six Na^+ ions. Overall, there are equal numbers of Na^+ and Cl^- ions, so the charges balance.

The actual arrangement of the ions in other compounds depends on the numbers of ions involved and on their sizes. However, it is important to remember that all ionic compounds are electrically neutral.

Ionic crystals are hard but much more brittle than metallic crystals. This is a result of the structure of the layers. In a **metallic** crystal, the ions are identical and held together by the mobile electrons. This remains true if one layer is slid against the next. However, pushing one layer against another in an **ionic** crystal brings ions of the same charge next to each other. The repulsions force the layers apart (Figure 3.40).

Disruption of an ionic lattice is also brought about by water. Many ionic compounds dissolve in water. Water molecules are able to interact with both positive and negative ions. When an ionic crystal dissolves, each ion becomes surrounded by water molecules. This breaks up the lattice and keeps the ions apart (Figure 3.41). For those ionic compounds that do not dissolve in water, the forces between the ions must be very strong.

Ions in solution are able to move, so the solution can carry an electric current. Ionic compounds can




Figure 3.40 In ionic crystals, when one layer is forced to slide against another, repulsions cause the crystal to fracture.




Figure 3.41 Water molecules form 'shells' around metal (yellow) and non-metal (green) ions. This helps ionic substances (like sodium chloride, NaCl) to dissolve in water.

conduct electricity when dissolved in water. This is also true when they are melted because, here again, the ions are able to move through the liquid and carry the current.




Figure 3.39 The arrangement of the positive and negative ions in a sodium chloride crystal.

Giant molecular crystals (macromolecules)

Giant molecular crystals are held together by strong covalent bonds. This type of structure is shown by some elements (such as carbon, in the form of diamond and graphite), and also by some compounds (for example, SiO_2).

The properties of diamond are due to the fact that the strong covalent bonds extend in all directions through the whole crystal. Each carbon atom is attached to four others – the atoms are arranged tetrahedrally (Figure 3.42a). Diamond has a very high melting point and, because the bonding extends throughout the whole structure, it is very hard and is used in cutting tools. The bonds are rigid, however, and these structures are much more brittle than giant metallic lattices. All the outer electrons of the atoms in these structures are used to form covalent bonds. There are no electrons free to move. Diamond is therefore a typical non-metallic element. It does not conduct electricity.

Graphite is a different form of carbon that does conduct electricity (Table 3.8). The carbon atoms are arranged in a different way in the molecular structure of graphite. They are arranged in flat layers of linked hexagons (Figure 3.42b). Each graphite layer is a two-dimensional giant molecule. Within these layers, each carbon atom is bonded to three others by strong covalent bonds. Between the layers there are weaker forces of attraction. The layers are able to slide over each other easily. This means that graphite feels slippery and can be used as a lubricant. Pencil 'lead' is, in fact, graphite. When




Figure 3.42 a The tetrahedral structure of diamond and silicon(IV) oxide (silicon dioxide). b The layered structure of graphite.

we write with a pencil, thin layers of graphite are left stuck to the paper. The most distinctive property, however, arises from the free electrons not used by the layered atoms in covalent bonding. These electrons can move between the layers, carrying charge, so that graphite can conduct electricity in a similar way to metals.

The giant structures of diamond and silicon(IV) oxide are very similar (Figure 3.42a). As a result, they

	Diamond		Graphite	
	Properties	Uses	Properties	Uses
appearance	colourless, transparent crystals that sparkle in light	in jewellery and ornamental objects	dark grey, shiny solid	
hardness	the hardest natural substance	in drill bits, diamond saws and glass-cutters	soft – the layers can slide over each other – and solid has a slippery feel	in pencils, and as a lubricant
density	more dense than graphite (3.51 g/cm^3)		less dense than diamond (2.25 g/cm^3)	
electrical conductivity	does not conduct electricity		conducts electricity	as electrodes and for the brushes in electric motors

Table 3.8 A comparison of the properties and uses of diamond and graphite.

Study tip

It is important that you can recognise the structures of diamond and graphite if you are presented with the diagrams in an exam question. Make sure that you can describe the essential features of the two structures and link them to the properties of the two forms. So you should be able to explain the hardness of diamond in terms of the strongly bonded three-dimensional network of the structure.

The electrical conductivity of graphite is explained in terms of the mobile electrons not used in the bonding of the layers. It is these 'free' electrons that are able to move and carry the current, not those involved in the covalent bonding of the layers.

The use of graphite as a solid lubricant is a result of the molecular layers in graphite being able to slide over each other.

S show similar physical properties. They are both very hard and have high melting points. Sand and quartz are examples of silica (silicon(IV) oxide or silicon dioxide, SiO_2). The whole structure of silicon and oxygen atoms is held together throughout by strong covalent bonds.

Molecular crystals


Some non-metals (e.g. iodine and sulfur) and some covalently bonded compounds exist as solids with low melting points. In these crystals, molecules of these elements or compounds are held together by weak

intermolecular forces to form a crystal that is easily broken down by heat. The molecules are then free to move but, unlike the particles in an ionic crystal, they have no charge. Neither the liquid nor the solid forms of these substances conduct electricity.


A summary of the physical properties of the different types of structure

The properties of a substance can be related to the type of structure it has. The four different types of structure are summarised in Figure 3.43.

Atoms that share electrons can form giant covalent structures called macromolecules. These have very **high melting points** because their atoms are linked together with strong covalent bonds.




Metals **conduct heat and electricity** because their structures contain delocalised (free) electrons. The layers of atoms in metals are able to slide over each other. This is why **we can bend and shape metals**.



Substances that consist of simple molecules have relatively **low melting points and boiling points**.

This is because there are only weak forces between the molecules. They **don't conduct electricity**.



Compounds made from ions are called ionic compounds. The ions are arranged in a giant lattice. Ionic compounds have very **high melting points and boiling points**.

When they are dissolved in water or melted, they can **conduct electricity**. This is because their ions are free to move about and carry the current.




Figure 3.43 Summary of the different types of structure.

Questions

- 3.27** How does molten sodium chloride conduct electricity?
- 3.28** Why does sodium chloride not conduct when it is solid?
- 3.29** Why can graphite:
- a** conduct electricity, and
 - b** be used as a lubricant?
- 3.30** Why is diamond much harder than graphite?
- 3.31** Why do molecular crystals never conduct electricity?
- 3.32** Why can metals conduct electricity?
- 3.33** How is the structure of silicon(IV) oxide similar to that of diamond?


Summary

You should know:

- ◆ how the Periodic Table lists the elements of the Universe in order of increasing proton number
- ◆ about the different characteristics of metallic and non-metallic elements
- ◆ how the Periodic Table is divided into vertical groups and horizontal periods, with clear trends in properties as we move down a group or across a period
- ◆ that certain groups, such as the alkali metals (Group I) and the halogens (Group VII), have distinctive names and contain the most reactive metals and non-metals respectively
- ◆ how the structures of all substances are made up of atoms, ions or molecules
- ◆ about the three main types of bonding that hold these structures together:
 - metallic bonding
 - ionic bonding
 - covalent bonding
- ◆ about covalent bonding, which occurs in some elements and non-metallic compounds and involves the ‘sharing’ of electrons between atoms to form stable molecules
- ◆ how covalent bonding produces two types of structure – simple molecules and giant molecular (macromolecular) structures
- ◆ that electrostatic forces of attraction between positive and negative ions are the basis of ionic bonding in compounds between metals and non-metals
- ◆ how the physical properties of a substance are related to the type of bonding present
- ◆ that diamond and graphite are two different forms of carbon with different giant molecular structures and distinctly different properties
- ◆ that alloys can be made to show properties that are adapted to a particular purpose; for example, strength (steel), resistance to corrosion (stainless steel) or low melting point
- S** ◆ about metallic bonding in which the closely packed metal atoms lose their outer electrons into a ‘sea’ of mobile electrons
- S** ◆ how the closely packed structure of metals can explain the characteristic properties of metals and how one metal can strengthen another when the two form an alloy
- S** ◆ about the nature of ionic lattices and how it gives rise to the properties of salts
- S** ◆ about the differences in structure and properties between simple molecular and giant molecular covalent structures.

End-of-chapter questions

- 1 When Mendeleev developed the Periodic Table, he knew nothing about electrons and electron shells. How did he manage to arrange the elements into groups and periods in the way we see?
- 2 Why do some substances conduct electricity and some not?
- 3 Lithium, sodium and potassium are in Group I of the Periodic Table.
 - a The equation for the reaction of lithium with water is



- i Write a word equation for this reaction. [2]
 - ii Sodium reacts with water in a similar way to lithium.
Write a symbol equation for the reaction of sodium with water. [1]
- b Describe the reactions of lithium, sodium and potassium with water. In your description, write about:
 - ◆ the difference in the reactivity of the metals
 - ◆ the observations you would make when these metals react with water. [5]
- [Cambridge IGCSE® Chemistry 0620/21, Question 6(a, b), June 2012]*
- 4 The diagram below shows the elements in a period of the Periodic Table.

Li	Be	B	C	N	O	F	Ne
----	----	---	---	---	---	---	----

- a To which period of the Periodic Table do these elements belong? [1]
 - b Answer these questions using only the elements shown in the diagram. Each element can be used once, more than once or not at all.
Write down the symbol for the element which:
 - i has six electrons in its outer shell
 - ii is a halogen
 - iii is a metal which reacts rapidly with cold water
 - iv has two forms, graphite and diamond
 - v is in Group II of the Periodic Table
 - vi makes up about 80% of the air. [6]
- c Write out and complete the following sentence using words from the list below.


atoms electrons molecules neutrons protons

The of the elements in the Periodic Table are arranged in order of increasing number of [2]

[Cambridge IGCSE® Chemistry 0620/21, Question 1, November 2010]

5 Bromine is an element in Group VII of the Periodic Table.


- a Write the formula for a molecule of bromine. [1]
- b A teacher placed a small amount of liquid bromine in the bottom of a sealed gas jar of air. After two minutes, brown fumes were seen just above the liquid surface. After one hour the brown colour had spread completely throughout the gas jar.



Use the kinetic particle theory to explain these observations.

[3]


- c Magnesium salts are colourless but Group VII elements are coloured.
An aqueous solution of magnesium bromide reacts with an aqueous solution of chlorine.



State the colour change in this reaction.

[2]

- d A solution of magnesium bromide will not react with iodine. Explain why there is no reaction. [1]
- e The structures of some compounds containing bromine are shown below.



- i Write the simplest formula for the substance with structure A. [1]
- ii State the name of the substance with structure D. [1]
- iii State the type of bonding within a molecule of structure C. [1]
- iv Which **two** structures are giant structures? [1]
- v Why does structure A conduct electricity when it is molten? [1]

[Cambridge IGCSE® Chemistry 0620/2, Question 6(a, c-f), June 2009]

- S** 6 The following is a list of the electron distributions of atoms of unknown elements.

Element	Electron distribution
A	2,5
B	2,8,4
C	2,8,8,2
D	2,8,18,8
E	2,8,18,8,1
F	2,8,18,18,7

- a Choose an element from the list for each of the following descriptions.
- i It is a noble gas.
 - ii It is a soft metal with a low density.
 - iii It can form a covalent compound with element A.
 - iv It has a giant covalent structure similar to diamond.
 - v It can form a negative ion of the type X^{3-} . [5]
- b Elements C and F can form an ionic compound.
- i Draw a diagram that shows the formula of this compound, the charges on the ions and the arrangement of the valency electrons around the negative ion. Use $\bullet$ to represent an electron from an atom of C. Use $\times$ to represent an electron from an atom of F. [3]
 - ii Predict two properties of this compound. [2]

[Cambridge IGCSE® Chemistry 0620/31, Question 3, June 2009]

4

Chemical reactions

In this chapter, you will find out about:

- ◆ the differences between physical and chemical changes
- ◆ how to write word and chemical equations
- ◆ the different types of chemical reaction
- ◆ the definition of oxidation and reduction
- ◆ how to use state symbols in an equation
- ◆ the writing of ionic equations
- ◆ electricity and chemistry – conductivity of metals
- ◆ the electrolysis of ionic compounds
- ◆ some major industrial applications of electrolysis.

Powerful reactions!

The chemical reaction between hydrogen and oxygen is a simple one. The reacting substances are gaseous elements, easy to mix. There is a single, simple non-polluting product: water. The reaction gives out a great amount of energy. Spectacularly so!

This is what makes the prospect of using hydrogen as a fuel for cars so attractive. This seems the best current option to reduce our dependence on fossil fuels and car makers are experimenting with hydrogen-powered prototypes.

Figure 4.1 shows the refuelling of a hydrogen fuel cell car. Such a car is just one type of hydrogen-powered car. The alternative is to use a hydrogen internal combustion engine. The BMW Hydrogen 7 is the first production vehicle with a hydrogen combustion engine. The current model has a bi-fuel engine which can run on either liquid hydrogen or gasoline. This is so that the car can be used while the large-scale infrastructure of hydrogen filling stations is put in place.

When planning the development of such cars, the amount of energy released by the reaction poses its own problems. It can be explosive. Research into



Figure 4.1 A car filling up with liquid hydrogen fuel at a solar hydrogen filling station. The hydrogen storage tank is on the right. Water is split into hydrogen and oxygen using power from the solar panels.

how hydrogen can be stored safely in filling stations and cars is important. Results suggest that storage may be possible by forcing the very small hydrogen molecules into spaces within the crystal lattice of metal blocks.

The search for reliable fuels shows one way in which we are dependent on chemical reactions for life and the way we live it. Some reactions are immensely important and research into them demands vast economic commitment so that we can reap the benefits. The simple reaction between two elements can be both importantly productive and devastatingly damaging.

4.1 Chemical reactions and equations

The Chinese character for 'chemistry' literally means 'change study' (Figure 4.2). Chemistry deals with how substances react with each other. Chemical reactions range from the very simple through to the interconnecting reactions that keep our bodies alive.

But what is a chemical reaction? How does it differ from a simple physical change?

Physical change

Ice, snow and water may look different, but they are all made of water molecules (H_2O). They are different **physical** forms of the same substance – water – existing under different conditions of temperature and pressure. One form can change into another if those conditions change. In such changes, no new **chemical** substances are formed. Dissolving sugar in ethanol or water is another example of a physical change. It produces a solution, but the substances can easily be separated again by distillation.

This is what we know about **physical changes**:

- ◆ In a physical change, the substances present remain chemically the same: no new substances are formed.
- ◆ Physical changes are often easy to reverse. Any mixtures produced are usually easy to separate.

Chemical change

When magnesium burns in oxygen (Figure 4.3), the white ash produced is a new substance – the compound, magnesium oxide. Burning magnesium produces a brilliant white flame. Energy is given out in the form of heat and light. The reaction is an **exothermic** change. The combination of the

two elements, magnesium and oxygen, to form the new compound is difficult to reverse. Some other chemical reactions, such as those in fluorescent 'glow bracelets' (Figure 4.4), produce **chemiluminescence**. They give out energy in the form of light.

The reaction between nitrogen and oxygen to make nitrogen monoxide is an example of another type of reaction. During this reaction, heat energy is **taken in** from the surroundings. The reaction is an **endothermic** change. Such reactions are much less common than exothermic ones.

This is what we know about **chemical changes**:

- ◆ The major feature of a chemical change, or reaction, is that new substance(s) are made during the reaction.
- ◆ Many reactions, but not all of them, are difficult to reverse.
- ◆ During a chemical reaction, energy can be given out or taken in:
 - when energy is given out, the reaction is **exothermic**
 - when energy is taken in, the reaction is **endothermic**.
- ◆ There are many more exothermic reactions than endothermic reactions.



Figure 4.2 The Chinese symbols for 'change'.



Figure 4.3 Magnesium burns strongly in oxygen.



Figure 4.4 Glow-in-the-dark bracelets. Glow bracelets are single-use, see-through, plastic tubes containing isolated chemicals. When the tube is squeezed, a glass partition keeping the chemicals apart breaks, and a reaction takes place that produces chemiluminescence.

Questions

- 4.1** State whether the following changes are physical or chemical:
- a the melting of ice
 - b the burning of magnesium
 - c the sublimation of solid carbon dioxide
 - d the dissolving of sugar in water.
- 4.2** State whether the following changes are exothermic or endothermic:
- a the condensation of steam to water
 - b the burning of magnesium
 - c the addition of concentrated sulfuric acid to water
 - d the evaporation of a volatile liquid.
- 4.3** What is the most important thing that shows us that a chemical reaction has taken place?

4.2 Equations for chemical reactions

When some chemical reactions occur, it is obvious that 'something has happened'. But this is not the case for others. When a solid explosive reacts to produce large

amounts of gas products, the rapid expansion may blast the surroundings apart. The 'volcano reaction', in which ammonium dichromate is decomposed, gives out a large amount of energy and produces nitrogen gas (Figure 4.5). Other reactions produce gases much less violently. The neutralisation of an acid solution with an alkali produces no change that you can see. However, a reaction has happened. The temperature of the mixture increases, and new substances have formed which can be separated and purified.

Word equations

We can write out descriptions of chemical reactions, but these would be quite long. To understand and group similar reactions together, it is useful to have a shorter way of describing them. The simplest way to do this is in the form of a **word equation**.

This type of equation links together the names of the substances that react (the **reactants**) with those of the new substances formed (the **products**). The word equation for burning magnesium in oxygen would be:





Figure 4.5 The decomposition of ammonium dichromate – the 'volcano experiment' – produces heat, light and an apparently large amount of powder.

The reaction between hydrogen and oxygen is another highly exothermic reaction. The reaction has been used to fuel rockets, most notably the now-retired Space Shuttle. Large tanks beneath the Shuttle contained liquid hydrogen and oxygen. In 1986, cracked rubber seals on the fuel tanks of the shuttle Challenger caused a catastrophic explosion and loss of life. The word equation for this reaction is:



Note that, although a large amount of energy is produced in this reaction, it is **not** included in the equation. An equation includes only the chemical substances involved, and energy is not a chemical substance.

This type of equation gives us **some** information. But equations can be made even more useful if we write them using **chemical formulae**.

Balanced symbol equations

From investigations of a large number of different chemical reactions, a very important point about all reactions has been discovered. It is summed up in a law, known as the **law of conservation of mass**.

Key definition



law of conservation of mass – the total mass of all the products of a chemical reaction is equal to the total mass of all the reactants.

No matter how spectacular the reaction, this statement is always true – though it is easier to collect all the products in some cases than in others!

This important law becomes clear if we consider what is happening to the atoms and molecules involved in a reaction. During a chemical reaction, the atoms of one element are not changed into those of another element. Nor do atoms disappear from the mixture, or appear from nowhere. A reaction involves the breaking of some bonds between atoms, and then the making of new bonds between atoms to give the


new products. During a chemical reaction, some of the atoms present ‘change partners’, sometimes spectacularly (Figure 4.6).

Look more closely at the reaction between hydrogen and oxygen molecules:



Each molecule of water (formula H_2O) contains only one oxygen atom (O). It follows that one molecule of oxygen (O_2) has enough oxygen atoms to produce two molecules of water (H_2O). Therefore, two molecules of hydrogen (H_2) will be needed to provide enough hydrogen atoms (H) to react with each oxygen molecule. The numbers of hydrogen and oxygen atoms are then the same on both sides of the equation.

The symbol equation for the reaction between hydrogen and oxygen is therefore written:



This is a **balanced equation**. The numbers of each type of atom are the same on both the reactant side and the product side of the equation: four hydrogen atoms and two oxygen atoms on each side (Figure 4.7).




Figure 4.6 a A balloon filled with hydrogen and oxygen b is ignited spectacularly.




Figure 4.7 Summary of the reaction between hydrogen and oxygen.



Figure 4.8 Potassium reacts strongly with water to produce hydrogen.

Writing balanced equations

A balanced equation gives us more information about a reaction than we can get from a simple word equation. Below is a step-by-step approach to working out the balanced equation for a reaction.

Worked example


What is the balanced equation for the reaction between magnesium and oxygen?

Step 1: Make sure you know what the reactants and products are. For example, magnesium burns in air (oxygen) to form magnesium oxide.

Step 2: From this you can write out the word equation:


magnesium + oxygen $\rightarrow$ magnesium oxide

Step 3: Write out the equation using the formulae of the elements and compounds:



Remember that oxygen exists as diatomic molecules. This equation is not balanced: there are two oxygen atoms on the left, but only one on the right.

Step 4: Balance the equation:



Remember that we cannot alter the formulae of the substances involved in the reaction. These are fixed by the bonding in the substance itself. We can only put multiplying numbers in front of each formula where necessary.


Chemical reactions do not only involve **elements** reacting together. In most reactions, **compounds** are involved. For example, potassium metal is very reactive and gives hydrogen gas when it comes into contact with water. Potassium reacts with water to produce potassium hydroxide and hydrogen (Figure 4.8). All the alkali metals do this. So, if you know one of these reactions, you know them all. In fact, you could learn the general equation:



Therefore:



Then:



This symbol equation needs to be balanced. An even number of H atoms is needed on the product

side, because on the reactant side the hydrogen occurs as H_2O . Therefore, the amount of KOH must be doubled. Then the number of potassium atoms and water molecules must be doubled on the left:



This equation is now balanced. Check for yourself that the numbers of the three types of atom are the same on both sides.

Study tip

It is important to remember that you cannot change the formulae of the substances themselves when balancing equations. These are fixed by the nature of the atoms and their bonding.

The only things that you can change when balancing are the numbers in front of the formulae.

Questions

4.4 Write word equations for the reactions described below.

- a** Iron rusts because it reacts with oxygen in the air to form a compound called iron(III) oxide.
- b** Sodium hydroxide neutralises sulfuric acid to form sodium sulfate and water.
- c** Sodium reacts strongly with water to give a solution of sodium hydroxide; hydrogen gas is also given off.

4.5 Copy out and balance the following equations:

- a** $\dots\text{Cu} + \text{O}_2 \rightarrow \dots\text{CuO}$
- b** $\text{N}_2 + \dots\text{H}_2 \rightleftharpoons \dots\text{NH}_3$
- c** $\dots\text{Na} + \text{O}_2 \rightarrow \dots\text{Na}_2\text{O}$
- d** $\dots\text{NaOH} + \text{H}_2\text{SO}_4 \rightarrow \text{Na}_2\text{SO}_4 + \dots\text{H}_2\text{O}$
- e** $\dots\text{Al} + \dots\text{Cl}_2 \rightarrow \dots\text{AlCl}_3$
- f** $\dots\text{Fe} + \dots\text{H}_2\text{O} \rightarrow \dots\text{Fe}_3\text{O}_4 + \dots\text{H}_2$


4.3 Types of chemical reaction

There are very many different chemical reactions. To make sense of them, it is useful to try to group certain types of reaction together (Figure 4.9). These types do not cover all reactions; and some reactions, such as redox reactions, may fit into more than one category. Organic reactions such as polymerisation have been left until later chapters.

Synthesis and decomposition

It is possible to distinguish reactions in which complex compounds are built from simpler substances (synthesis) from those where the reverse happens (decomposition).


Synthesis (or direct combination) reactions occur where two or more substances react together to form just **one** product. The reaction between iron and sulfur is an example of this (Figure 4.10):



Heat is required to start the reaction but, once started, it continues exothermically.

Various salts can be prepared by this method, for example aluminium iodide. The reaction between aluminium and iodine powders is quite spectacular. If the two powders are mixed well, then the reaction can be started by a few drops of water.

No heating is needed:



The synthesis reaction between aluminium foil and bromine liquid is similarly **spontaneous** (Figure 4.11).

Reactions such as the burning of magnesium and the explosive reaction of a hydrogen–oxygen mixture could also be included in this category. Synthesis reactions such as those above are usually **exothermic**, though they often require an input of heat energy to start them.




Figure 4.9 A summary of some of the different types of chemical reaction.




Figure 4.10 The synthesis reaction between iron and sulfur.

However, there is one very important synthesis reaction, which is **endothermic**: namely **photosynthesis**. This reaction is essential for life on Earth. It takes place in the green leaves of plants and requires energy from sunlight. It is a **photochemical reaction**. Small molecules of carbon dioxide and water are used to make glucose:






Figure 4.11 The reaction between aluminium and bromine is very vigorous, producing aluminium bromide. This experiment should not be attempted in the laboratory.

The green pigment **chlorophyll** is essential for this reaction because it traps energy from the Sun.

Decomposition reactions have just one reactant, which breaks down to give two or more simpler products. Joseph Priestley (in 1774) first made oxygen by heating mercury(II) oxide:




Lime for agriculture and for making cement is manufactured industrially by the decomposition of limestone (calcium carbonate):



These reactions are endothermic. They require heat energy. Decomposition caused by heat energy is called **thermal decomposition**.

Decomposition can also be caused by light energy. For example, silver chloride, a white solid, turns grey in sunlight because silver metal is formed:




Silver bromide and silver iodide behave in the same way. These photochemical reactions are the basis of photography.

Neutralisation and precipitation

Salts are a useful type of chemical compound that we will meet in detail in Chapter 5. A few salts, mainly chlorides, bromides and iodides, can be made by synthesis (direct combination) as mentioned above. The majority, though, have to be made either by neutralisation or by precipitation.

Neutralisation reactions involve acids. When acids react with bases or alkalis, their acidity is destroyed. They are neutralised and a **salt** is produced. Such reactions are known as neutralisation reactions. An example is:




Precipitation reactions involve the formation of an insoluble product.

Key definition


precipitation – the sudden formation of a solid, either when two solutions are mixed or when a gas is bubbled into a solution.

This type of reaction can be used to prepare insoluble salts. For example, lead(II) iodide can be made by mixing solutions of lead(II) nitrate and potassium iodide. A yellow precipitate of lead(II) iodide is formed (Figure 4.12a):



Potassium nitrate is soluble in water, so it stays in solution. The lead(II) iodide precipitates because it is insoluble; a downward arrow has, and can still, be used to show this. Lead(II) nitrate solution can be used as an analytical test for iodides (although the scheme for this exam uses silver nitrate as the test for iodide – see page 297).

The **limewater** test for carbon dioxide also depends on precipitation. Here the insoluble product is calcium carbonate (Figure 4.12b). A milky suspension of insoluble calcium carbonate is formed:



Precipitation reactions are very useful in analysis and are also used in the paint industry for making insoluble pigments.





Figure 4.12 Precipitation reactions produce an insoluble product. **a** Yellow lead(II) iodide is precipitated from lead(II) nitrate solution by potassium iodide. **b** Calcium carbonate is precipitated from limewater by carbon dioxide.

Displacement reactions

Displacement reactions are useful in working out the patterns of reactivity of elements of the same type. A **displacement reaction** occurs because a more reactive element will displace a less reactive one from a solution of one of its compounds.

Zinc is a more reactive metal than copper. If a piece of zinc is placed in a copper(II) sulfate solution, a red-brown deposit of copper forms on the zinc (Figure 4.13a). The blue colour of the copper(II) sulfate solution fades. Zinc displaces copper from copper(II) sulfate solution:



A similar reaction takes place when reactive metals are placed in acids. Hydrogen is displaced from the acid solution by the metal. For example:








Figure 4.13 Displacement reactions. **a** Zinc will displace copper from copper(II) sulfate solution, and the colour of the solution fades as the copper forms on the zinc surface. **b** Chlorine displaces iodine from a potassium iodide solution. The colourless solution turns yellow-brown.

Some metals are so reactive that they will displace hydrogen from water (see Figure 4.8 on page 93). For example:



The halogens can be placed in order of reactivity using displacement reactions. Thus, chlorine gas will displace iodine from potassium iodide solution. The colourless solution turns yellow-brown as iodine appears (Figure 4.13b):



Combustion, oxidation and reduction


Combustion reactions are of great importance and can be very useful or destructive.

Key definition

combustion – the reaction of a substance with oxygen causing the release of energy. The reaction is exothermic and often involves a flame.

burning – combustion in which a flame is produced.


The combustion of natural gas is an important source of energy for homes and industry. Natural gas is mainly methane. Its complete combustion produces carbon dioxide and water vapour:



Substances such as methane, which undergo combustion readily and give out a large amount of energy, are known as **fuels**.


Our bodies need energy to make the reactions that take place in our cells possible. These reactions allow us to carry out our everyday activities. We need energy to stay alive. We get this energy from food. During **digestion**, food is broken down into simpler substances. For example, the carbohydrates in rice,

potatoes and bread are broken down to form glucose. The combustion of glucose with oxygen in the cells of our body provides energy:



This reaction is exothermic and is known by a special name: **respiration**.


In combustion reactions, the substance involved is **oxidised**. Oxygen is added and oxides are formed. Not all reactions with oxygen produce a great amount of energy. For example, when air is passed over heated copper, the surface becomes coated with black copper(II) oxide. There is no flame, nor is the reaction very exothermic. But it is still an **oxidation** reaction (Figure 4.14a):



This process can be reversed, and the copper surface regenerated, if hydrogen gas is passed over the heated material. The black coating on the surface turns pink as the reaction takes place (Figure 4.14b):





During this reaction, the copper(II) oxide is losing oxygen. The copper(II) oxide is undergoing **reduction** – it is losing oxygen and being reduced. The hydrogen is gaining oxygen. It is being oxidised:



- ◆ If a substance gains oxygen during a reaction, it is oxidised.
- ◆ If a substance loses oxygen during a reaction, it is reduced.

Notice that the two processes of oxidation and reduction take place together during the same reaction. This is true for a whole range of similar reactions. Consider the following reaction:



Again, in this reaction, the two processes occur together. Since oxidation never takes place without




Figure 4.14 a The oxidation of copper to copper(II) oxide. b The reduction of copper(II) oxide back to copper using hydrogen.

reduction, it is better to call these reactions oxidation–reduction reactions or **redox reactions**.

In this last example, carbon removes oxygen from zinc oxide. Carbon is an example of a reducing agent.

Key definition

reducing agent – an element or compound that will remove oxygen from other substances. The commonest reducing agents are hydrogen, carbon and carbon monoxide.

Reduction is very important in industry as it provides a way of extracting metals from the metal oxide ores that occur in the Earth's crust. A good example is the blast furnace for extracting iron from hematite (Fe_2O_3) (Chapter 9).

Some substances are capable of giving oxygen to others. These substances are known as oxidising agents.

Key definition

oxidising agent – a substance that will add oxygen to another substance. The commonest oxidising agents are oxygen (or air), hydrogen peroxide, potassium manganate(VII) and potassium dichromate(VI).

Study tip

Remember that, in the process of acting as a reducing agent, that substance will itself be oxidised. The reducing agent will gain the oxygen it is removing from the other compound. The reverse is true for an oxidising agent.

There are two common examples of oxidation reactions that we might meet in our everyday lives.

- ◆ **Corrosion.** If a metal is reactive, its surface may be attacked by air, water or other substances around it. The effect is called **corrosion**. When iron or steel slowly corrodes in damp air, the product is a brown, flaky substance we call **rust**. Rust is a form of iron(III) oxide. Rusting weakens structures such as car bodies, iron railings, ships' hulls and bridges. Rust prevention is a major economic cost.
- ◆ **Rancidity.** Oxidation also has damaging effects on food. When the fats and oils in butter and margarine are oxidised, they become **rancid**. Their taste and smell change and become very unpleasant. Manufacturers sometimes add antioxidants to fatty foods and oils to prevent oxidation. Keeping foods in a refrigerator can slow down the oxidation process. Storage in airtight containers also helps. Crisp (chip) manufacturers fill bags of crisps with nitrogen to prevent the crisps being oxidised.

Questions

- 4.6 The halogens are a group of elements showing trends in colour, state and reaction with other halide ions.
- a Copy and complete the word equation for the reaction of chlorine with aqueous potassium bromide.
chlorine + potassium bromide →
 - b Explain why an aqueous solution of iodine does not react with potassium chloride.
- 4.7 Some types of chemical reaction are listed below.

decomposition neutralisation
combustion oxidation–reduction (redox)

Which reaction type best describes the following changes?

- a hexane + oxygen → carbon dioxide + water
- b calcium carbonate
→ calcium oxide + carbon dioxide
- c magnesium + copper oxide
→ magnesium oxide + copper
- d hydrochloric acid + sodium hydroxide
→ sodium chloride + water

- 4.8 Write word and balanced chemical equations for the reactions between:

- a sodium and water
- b magnesium and steam
- c calcium and oxygen
- d bromine and potassium iodide solution
- e zinc and copper sulfate solution.

4.4 A closer look at reactions, particularly redox reactions

State symbols




So far, our equations have told us nothing about the physical state of the reactants and products.

Chemical equations can be made more useful by including symbols that give us this information. These are called **state symbols**. They show clearly whether a gas is given off or a solid precipitate is formed during a reaction. The four symbols used are shown in Table 4.1.

Symbol	Meaning
s	solid
l	liquid
g	gas
aq	aqueous solution, i.e. dissolved in water

Table 4.1 The state symbols used in chemical equations.

The following examples show how they can be used. They can show clearly when a gas or a precipitate is produced in a reaction (the points of particular interest are shown in **bold type**). Note that, when water itself is produced in a reaction, it has the symbol (l) for liquid, not (aq).




Ionic equations


The last two examples above are useful for showing a further modification in writing equations. This

modification identifies more clearly those particles that are actually taking part in a particular reaction. These two reactions involve mixing solutions that contain ions. Only some of the ions present actually change their status – by changing either their bonding or their physical state. The other ions present are simply **spectator ions** to the change; they do not take part in the reaction.


The equation given above for neutralising hydrochloric acid with sodium hydroxide solution is:



Writing out all the ions present, we get:



The use of state symbols clearly shows which ions have not changed during the reaction. They have been crossed out (~~like this~~) and can be left out of the equation. This leaves us with the essential **ionic equation** for all neutralisation reactions:



Applying the same principles to a precipitation reaction again gives us a clear picture of which ions are reacting (Figure 4.15).






Figure 4.15 A precipitation reaction in which two solutions containing ions are mixed: **a** the overall reaction, and **b** the net reaction with the spectator ions not shown.

S The equation:




for the precipitation of copper(II) hydroxide, which was given above, becomes:



This is the essential ionic equation for the precipitation of copper(II) hydroxide; the spectator ions (sulfate and sodium ions) have been left out.

Redox reactions

Chemists' ideas about oxidation and reduction have expanded as a wider range of reactions have been studied. Look again at the reaction between copper and oxygen:



It is clear that copper has been oxidised; but what has been reduced? We can apply the ideas behind ionic equations to analyse the changes taking place during this reaction. It then becomes clear that:

- ◆ the copper atoms in the metal have become copper ions (Cu^{2+}) in copper(II) oxide
- ◆ the oxygen molecules in the gas have split and become oxide ions (O^{2-}) in the black solid copper(II) oxide.

The copper atoms, which clearly were oxidised during the reaction, have in the process **lost** electrons. The oxygen atoms have **gained** electrons in the process.

A new, broader definition of oxidation and reduction can now be put forward.

- ◆ Oxidation is the loss of electrons.
- ◆ Reduction is the gain of electrons.


We can remember this by using the memory aid 'OIL RIG':




OIL RIG

Oxidation **I**s the **L**oss of electrons
Reduction **I**s the **G**ain of electrons

This new definition of redox changes increases the number of reactions that can be called redox reactions. For instance, displacement reactions where there is no transfer of oxygen are now included. This is best seen by looking at an ionic equation. For example:




As an ionic equation this becomes:




Zinc has lost two electrons and copper has gained them. This reaction is a redox reaction as there has been both loss and gain of electrons by different elements during the reaction.

It is on the basis of this definition that chlorine, for instance, is a good oxidising agent. It displaces iodine from potassium iodide solution (see Figure 4.13b on page 97). Is this reaction a redox reaction?




From the ionic equation we can see that chlorine atoms have gained electrons to become chloride ions. They have been reduced. The iodide ions have lost electrons to form iodine. They have been oxidised.

If we look closely at these reactions we can see that a further definition of oxidation is possible. In the metal displacement reaction, each zinc atom has lost two electrons and the copper ions have gained them. The loss or gain of electrons in the reaction means that changes in **oxidation state** have taken place:



During the reaction, the oxidation state of zinc has increased by 2, from 0 to +2. Meanwhile the oxidation state of copper has decreased by 2, from +2 to 0.

- S** In the halogen displacement reaction, chlorine displaces iodine from potassium iodide solution. Consider the changes in oxidation state during the reaction:



- ◆ The oxidation state of iodine changes from -1 to 0 . It has increased. Iodide ions are **oxidised** to iodine.
 - ◆ The oxidation state of chlorine changes from 0 to -1 . It has decreased. Chlorine is **reduced** to chloride ions.
- ◆ Oxidation is the **increase** in oxidation state of an atom or ion.
 - ◆ Reduction is the **decrease** in oxidation state of an atom or ion.

For this syllabus, this definition is usually only referred to in connection with the following tests for oxidising and reducing agents.

Tests for oxidising and reducing agents


Reactions involving potassium iodide can be very useful as a test for any oxidising agent, because a colour change is produced. The iodide ion (I^-) is oxidised to iodine (I_2). The colour of the solution changes from colourless to yellow-brown. If starch indicator is added, then a dark blue colour is produced.

Reactions involving acidified potassium manganate(vii) are useful for detecting a reducing agent. The manganese is in a very high oxidation state ($+7$) in the manganate(vii) ion (MnO_4^-). A solution containing the manganate(vii) ion has a purple colour. When it is reduced, the manganate(vii) ion loses its purple colour and the solution appears colourless because of the formation of the pale pink Mn^{2+} ion.

Acidified potassium dichromate solution could also be used as a test. In this case, the colour change seen is from orange to green.

Questions

- 4.9 a** Explain the meaning of the symbols (s), (l), (aq) and (g) in the following equation, with reference to each reactant and product:



- b** Write an ionic equation, including state symbols, for each of the following reactions:
- silver nitrate solution + sodium chloride solution
 $\rightarrow$ silver chloride + silver nitrate solution
 - sodium sulfate solution + barium nitrate solution
 $\rightarrow$ sodium nitrate solution + barium sulfate
 - dilute hydrochloric acid + potassium hydroxide solution
 $\rightarrow$ potassium chloride solution + water
 - dilute hydrochloric acid + copper carbonate
 $\rightarrow$ copper chloride solution + water + carbon dioxide

- 4.10** Copy and complete the following statement:

..... is the gain of electrons;
 is the loss of electrons.
 During a redox reaction the oxidising agent electrons; the oxidising agent is itself during the reaction.

4.5 Electrolysis

Electricity has had a great effect on our way of living. Large urban areas, such as Hong Kong, could not function without the electricity supply. The results of the large-scale supply of electricity can be seen in the pylons and power lines that mark our landscape. But electricity is also important on the very small scale. The silicon chip enables a vast range of products to work, and many people now have access to products containing electronic circuits – from MP3 players to washing machines.

Conductivity in solids – conductors and insulators

The ability to conduct electricity is the major simple difference between elements that are metals and elements that are non-metals. All metals conduct electricity, but carbon in the form of graphite is the only non-metallic element that conducts electricity. A simple circuit can be used to test whether any solid conducts or not (Figure 4.16). The circuit is made up of a battery (a source of direct current), some connecting copper wires fitted with clips, and a light bulb to show when a current is flowing. The material to be tested is clipped into the circuit. If the bulb lights up, then the material is an **electrical conductor**.

For a solid to conduct, it must have a structure that contains 'free' electrons that are able to flow through it. There is a flow of electrons in the completed circuit. The battery acts as an 'electron pump'. Electrons are repelled (pushed) into the circuit from the negative terminal of the battery. They are attracted to the positive terminal. Metals (and graphite) conduct electricity because they have mobile free electrons in their structure. The battery 'pumps' all the free electrons in one direction. Metallic alloys are held together by the same type of bonding as the metal elements, so they also can conduct electricity. Solid covalent non-metals do not conduct electricity. Whether they are giant molecular or simple molecular structures, there are no electrons that are not involved in bonding – there are no free electrons. Such substances are called non-conductors or **insulators** (Table 4.2).

There is no chemical change when an electric current is passed through a metal or graphite. The copper wire is still copper when the current is switched off!




Figure 4.16 Testing a solid material to see if it conducts electricity, by whether it lights a bulb.

Conductors	Insulators (non-conductors)	
	Giant molecular	Simple molecular
copper	diamond	sulfur
silver	poly(ethene)	iodine
aluminium	poly(chloroethene), PVC	
steel	poly(tetrafluoroethene), PTFE	
brass		
graphite		

Table 4.2 Solid electrical conductors and insulators.

Key definition

electrical conductor – a substance that conducts electricity but is not chemically changed in the process.

Supplying electricity

Electricity is transmitted along power cables. Many of these cables are made of copper, because copper is a very good electrical conductor – it has very high electrical conductivity. Overhead power cables are made from aluminium (Figure 4.17), which not only conducts electricity well but has a low density, preventing sagging. Aluminium is also very resistant to corrosion. The cables are then strengthened with a steel core.

Domestic cables are covered (sheathed) in plastic, which is a non-conductor. This cover (or insulation) is needed for safety reasons. Leakage of power from overhead cables is prevented by using **ceramic** materials between the cable and the pylons. These plastic and ceramic materials are examples of insulators.

Study tip

The steel core in overhead power cables is present to strengthen the cable.





Figure 4.17 Overhead power lines are made of steel-cored aluminium cables. Note the ceramic plates that insulate the pylons from the cables.

Conductivity in liquids – electrolytes and non-electrolytes

The conductivity of liquids can be tested in a similar way to solids, but the simple testing circuit is changed (Figure 4.18). Instead of clipping the solid material to be tested into the circuit, graphite rods are dipped into the test liquid. Liquid compounds, solutions and molten materials can all be tested in this way. Molten metals, and mercury, which is liquid at room temperature, conduct electricity. Electrons are still able to move through the liquid metal to carry the charge. As in solid metals, no chemical change takes place when liquid metals conduct electricity.

If liquid compounds or solutions are tested using the apparatus in Figure 4.18, then the result will depend on the type of bonding holding the compound together.




Figure 4.18 The apparatus for testing the conductivity of liquids.

Electrolytes	Non-electrolytes
sulfuric acid	distilled water
molten lead bromide	ethanol
sodium chloride solution	petrol
hydrochloric acid	paraffin
copper(II) chloride solution	molten sulfur
sodium hydroxide solution	sugar solution

Table 4.3 Some electrolytes and non-electrolytes.


If the compound is bonded covalently, then it will **not** conduct electricity as a liquid or as a solution. Examples of such liquids are ethanol, petrol, pure water and sugar solution (Table 4.3). Ionic compounds **will** conduct electricity if they are either molten or dissolved in water. Examples of these are molten lead bromide, sodium chloride solution and copper(II) sulfate solution.

When these liquids conduct, they do so in a different way from metals. In this case, they conduct because the ions present can move through the liquid; when metals conduct, electrons move through the metal.

Ionic compounds will not conduct electricity when they are solid because their ions are fixed in position and cannot move. Liquids that conduct electricity by movement of ions are called **electrolytes**. Liquids that do not conduct in this way are called **non-electrolytes**.

When electrolytes conduct electricity, chemical change takes place and the ionic compound is split up.

For example, lead bromide is changed to lead and bromine:



This type of change is called **electrolysis** and is described in more detail below.

Key definition

electrolysis – the breakdown of an ionic compound, molten or in aqueous solution, by the use of electricity.

In summary, the following substances are electrolytes:

- ◆ molten salts
- ◆ solutions of salts in water
- ◆ solutions of acids
- ◆ solutions of alkalis.

The two distinct types of electrical conductivity are called metallic and electrolytic conductivity. They differ from each other in important ways.

Metallic conductivity:

- ◆ electrons flow
- ◆ a property of elements (metals, and carbon as graphite) and alloys
- ◆ takes place in solids and liquids
- ◆ no chemical change takes place.

Electrolytic conductivity:

- ◆ ions flow
- ◆ a property of ionic compounds
- ◆ takes place in liquids and solutions (not solids)
- ◆ chemical decomposition takes place.

The movement of ions

The conductivity of ionic compounds is explained by the fact that ions move in a particular direction in an electric field. This can be shown in experiments with coloured salts.

For example, copper(II) chromate(VI) (CuCrO_4) dissolves in water to give a green solution. This solution

Activity 4.1

The conductivity of liquids and aqueous solutions

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates

This experiment tests which of a series of liquids and solutions will conduct electricity, i.e. whether they are electrolytes or non-electrolytes.

A worksheet, with a self-assessment checklist, is included on the CD-ROM.

is placed in the lower part of a U-tube. A colourless solution of dilute hydrochloric acid is then layered on top of the salt solution in each arm, and graphite rods are fitted (Figure 4.19). These rods carry the current into and out of the solution. They are known as **electrodes**. In electrolysis, the negative electrode is called the **cathode**; the positive electrode is the **anode**.

After passing the current for a short time, the solution around the cathode becomes blue. Around the




Figure 4.19 An experiment to show ionic movement by using a salt solution containing coloured ions. The acid solution was colourless at the start of the experiment.

anode the solution becomes yellow. These colours are produced by the movement (migration) of the ions in the salt. The positive copper ions (Cu^{2+}) are blue in solution. They are attracted to the cathode (the negative electrode). The negative chromate ions (CrO_4^{2-}) are yellow in solution. They are attracted to the anode (the positive electrode). The use of coloured ions in solution has shown the direction that positive and negative ions move in an electric field.

During **electrolysis**:

- ♦ **positive ions** (metal ions or H^+ ions) move towards the **cathode**; they are known as **cations**
- ♦ **negative ions** (non-metal ions) move towards the **anode**; they are known as **anions**.

Study tip

It is important to remember that it is the electrons that move through the wire when a metal conducts. However, when a salt solution conducts, it is the ions in the solution that move to the electrodes. They are then discharged at the electrodes.

A solid ionic compound will not conduct electricity, because the ions are in fixed positions in a solid; they cannot move. The electrolyte must be melted or dissolved in water for it to conduct.


The electrolytic cell

The apparatus in which electrolysis is carried out is known as an **electrolytic cell**. The direct current is supplied by a battery or power pack. Graphite electrodes carry the current into and out of the liquid electrolyte. Graphite is chosen because it is quite unreactive (inert). It will not react with the electrolyte or with the products of electrolysis. Electrons flow from the negative terminal of the battery around the circuit and back to the positive terminal. In the electrolyte it is the **ions** that move to carry the current.


Electrolysis of molten compounds

An electrolytic cell can be used to electrolyse molten compounds. Heat must be supplied to keep the salt molten. Figure 4.20 shows the electrolysis of molten zinc chloride.

When the switch is closed, the current flows and chlorine gas (which is pale green) begins to bubble off at the anode. After a little time, a bead of molten zinc collects at the cathode. The electrical energy from the cell has caused a chemical change (decomposition). The cell decomposes the molten zinc chloride because the ions present move to opposite electrodes where they lose their charge (they are **discharged**). Figure 4.20 shows this movement. The chloride ions (Cl^-) move to the anode. Each chloride ion gives up (donates) one electron to become a chlorine atom:



Then two chlorine atoms bond together to make a chlorine molecule:



The zinc ions (Zn^{2+}) move to the cathode. There, each zinc ion picks up (accepts) two electrons and becomes a zinc atom:



During electrolysis, the flow of electrons continues through the circuit. For every two electrons taken from the cathode by a zinc ion, two electrons are set free at the anode by two chloride ions. So, overall,




Figure 4.20 The movement of ions in the electrolysis of a molten salt, zinc chloride.

the electrons released at the anode flow through the circuit towards the cathode. During the electrolysis of molten salts, the metal ions, which are always positive (cations), move to the cathode and are discharged. Non-metal ions (except hydrogen), however, are always negative. They are anions and move to the anode to be discharged.

When a molten ionic compound is electrolysed:

- ♦ the metal is always formed at the cathode
- ♦ the non-metal is always formed at the anode.

Table 4.4 (overleaf) shows some further examples of this type of electrolysis, and the electrolysis of lead(II) bromide to form lead and bromine vapour is summarised diagrammatically in Figure 4.21. Electrolysis of molten salts is easier if the melting point of the salt is not too high.

Industrial electrolysis of molten compounds

Electrolysis is important industrially because it is the only method of extraction available for the most reactive metals. Metals in Groups I and II, and aluminium, are too reactive to be extracted by chemical reduction using carbon like other metals. Metals such




Figure 4.21 The electrolysis of lead(II) bromide.

Electrolyte	Decomposition products	Cathode reaction	Anode reaction ^(a)
lead bromide, PbBr ₂	lead (Pb) and bromine (Br ₂)	$\text{Pb}^{2+} + 2\text{e}^- \rightarrow \text{Pb}$	$2\text{Br}^- \rightarrow \text{Br}_2 + 2\text{e}^-$
sodium chloride, NaCl	sodium (Na) and chlorine (Cl ₂)	$\text{Na}^+ + \text{e}^- \rightarrow \text{Na}$	$2\text{Cl}^- \rightarrow \text{Cl}_2 + 2\text{e}^-$
potassium iodide, KI	potassium (K) and iodine (I ₂)	$\text{K}^+ + \text{e}^- \rightarrow \text{K}$	$2\text{I}^- \rightarrow \text{I}_2 + 2\text{e}^-$
copper(II) bromide, CuBr ₂	copper (Cu) and bromine (Br ₂)	$\text{Cu}^{2+} + 2\text{e}^- \rightarrow \text{Cu}$	$2\text{Br}^- \rightarrow \text{Br}_2 + 2\text{e}^-$

^(a)These anode reactions are the sum of the two stages written in the text. The loss of an electron from a negative ion like Cl⁻ can also be written $2\text{Cl}^- - 2\text{e}^- \rightarrow \text{Cl}_2$

Table 4.4 Some examples of the electrolysis of molten salts.

as sodium and magnesium are obtained by electrolysis of their molten chlorides. The metal is produced at the cathode.

One of the most important discoveries in industrial electrolysis was finding suitable conditions for extracting aluminium from its mineral ore, bauxite. The bauxite ore is first treated to produce pure aluminium oxide. This is then dissolved in molten cryolite (sodium aluminium fluoride). The melting point of the mixture is much lower than that of pure aluminium oxide. The mixture is electrolysed between graphite electrodes (Figure 4.22). Molten aluminium is attracted to the cathode and collects at the bottom of the cell:



Oxygen is released at the anodes:





Figure 4.22 The industrial electrolysis of molten aluminium oxide to produce aluminium.

At the operating temperature of about 1000 °C, the graphite anodes burn away in the oxygen to give carbon dioxide. So they have to be replaced regularly.

Activity 4.2 Web researching the extraction of aluminium

Skills

Research skills


Use the features of the following website to produce a report or poster on the smelting of aluminium and its uses:

<http://www.rsc.org/Education/Teachers/Resources/Alchemy/index2.htm>

Electrolysis of solutions

The electrolysis of ionic solutions also produces chemical change. However, the products from electrolysis of a solution of a salt may be different from those obtained by electrolysis of the molten salt. This is because water itself produces ions.

Although water is a simple molecular substance, a very small fraction of its molecules split into hydrogen ions (H⁺) and hydroxide ions (OH⁻):



Not enough ions are produced for pure water to conduct electricity very well. During electrolysis,

however, these hydrogen and hydroxide ions are also able to move to the electrodes. They compete with the ions from the acid or salt to be discharged at the electrodes. But at each electrode just **one** type of ion gets discharged.

At the **cathode**:

- ◆ The more reactive a metal, the more it tends to stay as ions and not be discharged. The H^+ ions will accept electrons instead. Hydrogen molecules will be formed, leaving the ions of the reactive metal, for example Na^+ ions, in solution.
- ◆ In contrast, the ions of less reactive metals, for example Cu^{2+} ions, will accept electrons readily and form metal atoms. In this case, the metal will be discharged, leaving the H^+ ions in solution (Figure 4.23).



Figure 4.23 Copper is quite unreactive so it can be seen deposited on the cathode when copper(II) sulfate solution is electrolysed.

At the **anode**:

- ◆ If the ions of a halogen (Cl^- , Br^- or I^-) are present in a high enough concentration, they will give up electrons more readily than OH^- ions will. Molecules of chlorine, bromine or iodine are formed. The OH^- ions remain in solution.
- ◆ If no halogen ions are present, the OH^- ions will give up electrons more easily than any other non-metal anion. Sulfate and nitrate ions are not discharged in preference to OH^- ions. When OH^- ions are discharged, oxygen is formed.

Activity 4.3

The electrolysis of concentrated sodium chloride solution

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

Investigate the products formed when a solution of sodium chloride is electrolysed. The experiment is summarised in Figure 4.24.

A worksheet is included on the CD-ROM. Details of a microscale version of the experiment are given on the Teacher's Resource CD-ROM.

Electrolysis of concentrated sodium chloride solution

A concentrated solution of sodium chloride can be electrolysed in the laboratory (Figure 4.24). There are four different ions present in the solution. The positive ions (cations), Na^+ and H^+ , flow to the cathode, attracted by its negative charge. The negative ions (anions), Cl^- and OH^- , travel to the anode.






Figure 4.24 The movement and discharge of ions in the electrolysis of concentrated sodium chloride solution.


At the **cathode**, it is the H^+ ions that accept electrons, as sodium is more reactive than hydrogen:




Then two hydrogen atoms combine to form a hydrogen molecule:



So, overall, hydrogen gas bubbles off at the cathode:




At the **anode**, the Cl^- ions are discharged more readily than the OH^- ions:



Then two chlorine atoms combine to make a chlorine molecule:



So, overall, pale green chlorine gas bubbles off at the anode:



Left behind in solution are Na^+ and OH^- ions; this is sodium hydroxide solution. The solution therefore becomes alkaline. This can be shown by adding indicator to the solution. These products – hydrogen, chlorine and sodium hydroxide – are very important industrially as the basis for the chlor-alkali industry. So the electrolysis of concentrated brine (salt water) is a very important manufacturing process.

Study tip

Remember that the electrolysis of molten sodium chloride and a dilute sodium chloride solution will give different products.

S Several different types of electrolytic cell have been used for the electrolysis of brine. The modern membrane cell (Figure 4.25) is the safest for the environment and uses the least electricity. Other types of cell use either a flowing mercury cathode, or a diaphragm (partition) made from asbestos.

The **membrane cell** has a titanium anode and a nickel cathode. Titanium is chosen for the anode as it is not attacked by chlorine. The anode and cathode compartments are separated by a membrane. This membrane is selective; it allows Na^+ ions and water to flow through, but no other ions. This means that the




Figure 4.25 The membrane cell for the electrolysis of concentrated brine. The selective ion-exchange membrane allows only Na^+ ions to pass through it.

products are kept separate and cannot react with each other. The Na^+ and OH^- ions collect in the cathode compartment. The sodium hydroxide solution is removed and purified.

Study tip


In these examples of industrial electrolysis, you will not be expected to draw a diagram. You will need to be able to recognise and label a diagram and give the electrode half-equations.

You will also be expected to know the major reasons for the distinctive aspects of the process.


Electrolysis of acid solutions

Pure water is a very poor conductor of electricity. However, it can be made to decompose if some dilute sulfuric acid is added. A cell such as the one shown in Figure 4.24 or a Hofmann voltameter (Figure 4.26) can be used to keep the gases produced separate. After a short time, the volume of gas in each arm can be measured and tested. The gas collected above the cathode is hydrogen. Oxygen collects at the anode. The ratio of the volumes is approximately 2 : 1. Effectively this experiment is the electrolysis of water:

at the cathode
at the anode



The electrolysis of concentrated hydrochloric acid can also be carried out in this apparatus. Again two gases are collected, this time hydrogen and chlorine:



Electroplating

The fact that an unreactive metal can be coated on to the surface of the cathode by electrolysis (see Figure 4.23) means that useful metal objects can be 'plated' with a chosen metal.

Electroplating can be used to coat one metal with another.

Activity 4.4 Electroplating copper with nickel

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates

The aim of this experiment is to demonstrate electroplating and observe the changes taking place during the process. It should help establish the basic requirements of the electroplating method.

A worksheet is included on the CD-ROM.




Figure 4.26 The Hofmann voltameter for the electrolysis of dilute sulfuric acid.

For electroplating, the electrolysis cell is adapted from the type usually used. The cathode is the object to be plated and the anode is made from the metal being used to plate it. The electrolyte is a salt of the same metal. As the process proceeds, the anode dissolves away into the solution, replacing the metal plated on to the object, and the concentration of the solution remains the same.

Study tip

Usually the electrodes used in electrolysis are inert (graphite or platinum). However, in electroplating the anode is made of the metal to be plated. It is not inert, and it reacts. The anode decreases in size as it dissolves away.

The most commonly used metals for electroplating are copper, chromium, silver and tin. One purpose of electroplating is to give a protective coating to the metal underneath; an example is the tin-plating of steel cans to prevent them rusting. This is also the idea behind chromium-plating articles such as car bumpers, kettles and bath taps, etc. Chromium does not corrode; it is a hard metal that resists scratching and wear, and it can also be polished to give an attractive finish.



Figure 4.27 The industrial electroplating of metal objects.

The attractive appearance of silver can be achieved by electroplating silver on to an article made from a cheaper metal such as nickel silver (Figure 4.27). The 'EPNS' seen on cutlery and other objects stands for 'electroplated nickel silver'. 'Nickel silver' is an alloy of copper, zinc and nickel – it contains no silver at all! It is often used as the base metal for silver-plated articles.

The basic rules for electroplating an object with a metal M:

- ◆ The object must be made the cathode.
- ◆ The electrolyte must be a solution of a salt of metal M.
- ◆ The anode is made of a strip of metal M.

Questions


4.11 An experiment was carried out to investigate the effect of electricity on molten lead(II) bromide (PbBr_2).

- a What happens to a compound during electrolysis?
- b Why does solid lead(II) bromide not allow the passage of electricity?
- c What colour is the vapour seen at the positive electrode?
- d Give one reason why this electrolysis should be carried out in a fume cupboard.
- e What is the alternative name for the negative electrode?

4.12 A metal object is to be copper plated.

- a Which electrode should the object be made?
- b Name a solution that could be used as the electrolyte.

4.13 In the electrolysis of molten lead(II) bromide, the reaction occurring at the negative electrode was:



- a Write the equation for the reaction taking place at the positive electrode.
- b Why is the reaction taking place at the negative electrode viewed as a reduction reaction?

4.14 The tables list the results of the electrolysis of a number of aqueous solutions using inert electrodes.

Use the information in the first table to complete the second table. The solutions were electrolysed under exactly the same conditions as the ones above.

Solution (electrolyte)	Gas given off at the anode	Gas given off or metal deposited at the cathode	Substance left in solution at the end of electrolysis
copper(II) sulfate	oxygen	copper	sulfuric acid
sodium sulfate	oxygen	hydrogen	sodium sulfate
silver nitrate	oxygen	silver	nitric acid
concentrated sodium chloride	chlorine	hydrogen	sodium hydroxide
copper(II) nitrate	oxygen	copper	nitric acid

Solution (electrolyte)	Gas given off at the anode	Gas given off or metal deposited at the cathode	Substance left in solution at the end of electrolysis
silver sulfate	oxygen		
sodium nitrate		hydrogen	sodium nitrate

4.6 A closer look at electrode reactions

The electrolysis of hydrochloric acid demonstrates one factor that is important in electrolysis: the **concentration** of the ions present.

When the concentration of the acid is lowered, the gas given off at the anode changes. As the solution becomes very dilute, chloride ions are not discharged. At these low concentrations, oxygen is produced from the discharge of hydroxide ions. The different products of the electrolysis of hydrochloric acid are shown in Table 4.5.

There is a similar change in the product at the anode for very dilute solutions of sodium chloride. Again, oxygen is given off rather than chlorine. These results suggest that the discharge of Cl^- ions over OH^- ions (called preferential discharge) only applies if the concentration of Cl^- is sufficiently high.

Oxidation and reduction during electrolysis

The reactions that take place at the electrodes during electrolysis involve the loss and gain of electrons. Negative ions always travel to the anode, where they lose electrons. In contrast, positive ions always flow to the cathode, where they gain electrons. As we saw earlier, oxidation can be defined as the loss of electrons, and reduction as the gain of electrons. Therefore, electrolysis can be seen as a process in which oxidation and reduction are physically separated.

During **electrolysis**:

- ♦ the oxidation of non-metal ions always takes place at the anode
- ♦ the reduction of metal or hydrogen ions always takes place at the cathode.

Electrolyte	Product at anode	Product at cathode
concentrated hydrochloric acid	chlorine $2\text{Cl}^- \rightarrow \text{Cl}_2 + 2\text{e}^-$	hydrogen $2\text{H}^+ + 2\text{e}^- \rightarrow \text{H}_2$
very dilute hydrochloric acid	oxygen $4\text{OH}^- \rightarrow 2\text{H}_2\text{O} + \text{O}_2 + 4\text{e}^-$	hydrogen $2\text{H}^+ + 2\text{e}^- \rightarrow \text{H}_2$


Table 4.5 Electrolysis of dilute and concentrated hydrochloric acid.

Just as in redox reactions, where both oxidation and reduction occur at the same time, the two processes must take place together to produce electrolytic decomposition.


The refining (purification) of copper by electrolysis

Closer examination of an electroplating cell suggests an interesting method of purifying a metal. During electroplating, the oxidation process at the anode involves the metal anode actually dissolving. Metal atoms lose electrons and pass into solution as positive metal ions. In turn, metal ions are discharged at the cathode as the object becomes plated.

A cell can be set up to electrolyse copper(II) sulfate solution using **copper** electrodes (not graphite). As electrolysis takes place, the cathode gains mass as copper is deposited on it (Figure 4.28):



The anode, however, loses mass as copper dissolves from it:



So, overall, there is a transfer of copper from the anode to the cathode. The colour of the copper(II) sulfate solution does not change because the concentration of the Cu^{2+} ions remains the same.




Figure 4.28 The purification of copper by electrolysis. The movement of ions effectively transfers copper from one electrode to another.

Activity 4.5

Electrolysis of copper(II) sulfate solution

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

This experiment is designed to demonstrate the different products obtained when the electrolysis of copper(II) sulfate solution is carried out first with inert graphite electrodes and then with copper electrodes. The use of copper electrodes illustrates how copper is refined industrially.

A worksheet is included on the CD-ROM.

The copper used in electrical wiring must be very pure (99.99%). Copper made by roasting its sulfide ore in air is about 99.5% pure (so it has an impurity level of 0.5%). This level of impurity cuts down its electrical conductivity significantly. Blocks of this impure metal are used as the anodes in a cell containing acidified copper(II) sulfate solution (Figure 4.29). The cathodes are made of thin sheets of pure copper. During the refining process, pure copper is removed from the impure anodes and deposited on the cathodes. Any impurities fall to the bottom of the cell. This material, or **anode**



Figure 4.29 A copper refinery worker removes electrodes with extracted copper from an electrolytic bath in a Chilean copper refinery.


sludge, contains precious metals such as gold, silver and platinum. These can be purified from this sludge.

Study tip

Remember the key observations during electroplating. The object thickens as it becomes plated. The anode dissolves away. The electrolyte solution maintains the same concentration (thus, if it is coloured, the intensity of the colour stays the same).

Questions

- 4.15 a** The apparatus below was used to plate a strip of metal with copper. One electrode was made of copper and the other was the metal strip to be plated.



- i** Which electrode, X or Y, is the metal strip?
 - ii** Is the metal strip an anode or a cathode?
 - b** If graphite were used instead of the copper electrode in **a**, what change would you notice to the electrolyte during the experiment?
 - c** In industry, some plastics are electroplated. Why must the plastic be coated with a thin film of graphite before plating?
- 4.16** An electrolysis cell is one method of physically separating the processes involved in a redox reaction.
- a** At which electrode does the oxidation process take place?
 - b** At which electrode does the reduction process take place?
 - c** Why can we use these terms in connection with the electrode processes taking place?


Summary

You should know:

- ◆ about the nature of chemical reactions and how they differ from physical changes
- ◆ how to represent the changes in a reaction using word equations and balanced chemical equations
- S ◆ how equations can be made more informative by including state symbols
- S ◆ how equations for reactions involving ions can be simplified to include only those ions taking part in the reaction
- ◆ about the exothermic or endothermic energy changes involved in reactions
- ◆ about the variety of different types of chemical reaction such as combustion, neutralisation, and displacement reactions
- ◆ about the importance of oxidation and reduction reactions (redox)
- S ◆ how the definitions of oxidation and reduction can be extended to include reactions involving the transfer of electrons – oxidation being the loss of electrons and reduction the gain of electrons
- ◆ about the electrical conductivity of metals and graphite
- ◆ about the conductivity of ionic compounds when molten or dissolved in water that results in a chemical change (electrolysis)
- ◆ that electrolytic cells consist of positive (anode) and negative (cathode) electrodes and an electrolyte
- S ◆ about the factors that decide which ions are discharged at the electrodes
- S ◆ how to write the reactions taking place at the electrodes as ionic half-equations
- ◆ about electroplating, which can be used to produce a protective and/or decorative layer of one metal on another
- S ◆ how electrolysis is industrially important for the extraction of very reactive metals such as aluminium and the production of sodium hydroxide and chlorine
- S ◆ how electrolysis provides a method of purifying (refining) copper.

End-of-chapter questions

- 1 A group of students is conducting an experiment investigating the action of heat on solid copper carbonate and zinc carbonate. The two experiments gave them the results summarised here:



- a What evidence is there that a chemical reaction has taken place in both cases?
 - b What is the major and most reliable evidence of a reaction here?
 - c Write word equations for the two reactions.
 - d Write a brief description of what you would see happen if zinc oxide powder were heated strongly and then allowed to cool down.
 - e Would this change have been a chemical reaction?
- 2 'Redox' means **reduction and oxidation**. It can be defined by loss and gain of oxygen or by loss and gain of electrons.
- a Which definition is more useful?
 - b Is it possible to have oxidation without reduction in a chemical reaction?
- 3 When a strip of burning magnesium ribbon is lowered into a gas jar of carbon dioxide, the following reaction takes place:
- $$2\text{Mg} + \text{CO}_2 \rightarrow 2\text{MgO} + \text{C}$$
- a What observation would show that carbon had been produced? [1]
 - b Write a word equation for this reaction. [1]
 - c Which substances have been:
 - i reduced in this reaction? [1]
 - ii oxidised in this reaction? [1]
 - d Magnesium oxide reacts with hydrochloric acid to make the salt magnesium chloride and water. Write the symbol equation for this reaction. [2]
 - e Magnesium sulfate is produced when magnesium is added to zinc sulfate solution.

$$\text{Mg} + \text{ZnSO}_4 \rightarrow \text{MgSO}_4 + \text{Zn}$$
 - i Write an ionic equation for this reaction. [2]
 - ii Explain why magnesium is a reducing agent in this reaction. [2]
- 4 The equations A and B below show two reactions which lead to the formation of acid rain.
- A $\text{S} + \text{O}_2 \rightarrow \text{SO}_2$
- B $\text{SO}_2 + \text{O}_3 \rightarrow \text{SO}_3 + \text{O}_2$
- a Write a word equation for reaction A. [2]
 - b Which two of the following statements about reaction B are correct?

SO_2 is oxidised to SO_3 ; SO_2 is reduced to SO_3

O_3 is reduced to O_2 ; O_3 is oxidised to O_2
 - c Complete the equation to show how an aqueous solution of sulfuric acid, H_2SO_4 , is formed from SO_3 .

$$\text{SO}_3 + \text{.....} \rightarrow \text{H}_2\text{SO}_4$$
 [1]

[Cambridge IGCSE® Chemistry 0620/21, Question 7(a), June 2012]

5 Some substances conduct electricity, others do not.

a Which **three** of the following conduct electricity?


aqueous sodium chloride; ceramics; copper;
graphite; sodium chloride crystals; sulfur

[3]

b State the name given to a substance, such as plastic, which does not conduct electricity.

[1]

c Molten zinc chloride was electrolysed using the apparatus shown below.



i Choose a word from the list below which describes the positive electrode.

anion anode cathode cation

[1]

ii State the name of the product formed during this electrolysis at

- ♦ the negative electrode
- ♦ the positive electrode.


[2]

iii Suggest the name of a non-metal which can be used for the electrodes in this electrolysis.

[1]

[Cambridge IGCSE® Chemistry 0620/21, Question 8, June 2010]

6 The diagram shows the apparatus used to electrolyse concentrated aqueous sodium chloride.



Give a description of this electrolysis. In your description include:

a what substance the electrodes are made from and the reason for using this substance

[2]

b what you would observe during the electrolysis


[2]

c the names of the substances produced at each electrode.

[2]

[Cambridge IGCSE® Chemistry 0620/22, Question 5(c), November 2011]

- S** 7 Until recently, arsenic poisoning, either deliberate or accidental, has been a frequent cause of death. The symptoms of arsenic poisoning are identical with those of a common illness, cholera. A reliable test was needed to prove the presence of arsenic in a body.
- a In 1840, Marsh devised a reliable test for arsenic.




Hydrogen is formed in this reaction. Any arsenic compound reacts with this hydrogen to form arsine, which is arsenic hydride, AsH_3 . The mixture of hydrogen and arsine is burnt at the jet and arsenic forms as a black stain on the glass.

Write an equation for the reaction that forms hydrogen. [2]

- b In the 19th century, a bright green pigment, copper(II) arsenate(V), was used to kill rats and insects. In damp conditions, micro-organisms can act on this compound to produce the very poisonous gas, arsine.

- i Suggest a reason why it is necessary to include the oxidation states in the name of the compound. [1]
- ii The formula for the arsenate(V) ion is AsO_4^{3-} . Complete the ionic equation for the formation of copper(II) arsenate(V). [2]



[Cambridge IGCSE® Chemistry 0620/33, Question 6(a(i)& d), November 2012]

5

Acids, bases and salts

In this chapter, you will find out about:

- ◆ common acids – where and how they occur
- ◆ the pH scale and indicators
- ◆ the colour changes of useful indicators
- ◆ the ions present in acid and alkali solutions
- ◆ the differences between acids, bases and alkalis
- ◆ the acid–base properties of non-metal oxides and metal oxides
- S** ◆ neutral and amphoteric oxides
- ◆ uses of common alkalis, bases and ‘antacids’, including indigestion treatments, the treatment of acid soils and waste water treatment
- ◆ the characteristic reactions of acids
- ◆ acids and alkalis in the analysis of salts
- ◆ the nature and solubility of salts
- ◆ the preparation of soluble salts by various methods, including titration
- S** ◆ the preparation of insoluble salts by precipitation
- S** ◆ the nature of strong and weak acids and alkalis
- S** ◆ acids as proton donors and bases as proton acceptors

Nature's defences – stings galore!

Over history, acids have contributed significantly to our understanding of the world around us. Methanoic acid – the simplest organic acid – used to be known as formic acid. This name comes from the Latin word for ant, *formica*, and the connection comes from the fact that the acid was originally made by the distillation of ant bodies. The acid is part of their defence mechanism. When an ant stings you, it injects the methanoic acid under your skin (Figure 5.1a). You can neutralise the sting by rubbing on baking soda (sodium hydrogencarbonate) from the kitchen, or calamine lotion (which contains zinc carbonate). Bee

stings may also contain methanoic acid, although they also contain other highly acidic chemicals. In contrast, a wasp sting is alkaline and can be neutralised using lemon juice, which contains citric acid. Bee and wasp stings can be dangerous for people who develop an allergic reaction to the proteins in the venom.

Some plants have a similar defence mechanism. Nettle leaves have impressive-looking stinging hairs (Figure 5.1b). These hairs act like a hypodermic needle if touched. They too inject methanoic acid under the skin. The irritating sting can be neutralised in the same way as an ant sting, or by rubbing your skin with dock leaves.




Figure 5.1 a A scanning electron microscope picture of an ant sting.
b The stinging hairs of a nettle.

5.1 What is an acid?

The major acids

The word **acid** was originally applied to substances with a 'sour' taste. Vinegar, lemon juice, grapefruit juice and spoilt milk are all sour tasting because of the presence of acids (Figure 5.2). These acids are present in animal and plant material and are known as **organic acids** (Table 5.1).

Carbonic acid from carbon dioxide dissolved in water is present in Coca Cola®, Pepsi® and other fizzy drinks. The acids present in these circumstances are weak and dilute. But taste is not a test that should be tried – some acids would be dangerous, even deadly, to taste!

A number of acids are also **corrosive**. They can eat their way through clothing, are dangerous on the skin, and some are able to attack stonework and metals. These powerful acids are often called **mineral acids** (Table 5.1). Table 5.1 also gives us some idea of how commonly acids occur.

The easiest way to detect whether a solution is acidic or not is to use an **indicator**. Indicators are substances that change colour if they are put into an acid or alkaline solution. Two commonly used indicators are **litmus** and **methyl orange**.

What are indicators?

Certain coloured substances (many extracted from plants) have been found to change colour if added to an



Figure 5.2 Citrus fruits have a sour or sharp taste because they contain acids.

acid solution. This colour change is reversed if the acid is 'cancelled out' or neutralised. Substances that do this are known as **indicators**. Coloured extracts can be made from red cabbage or blackberries, but probably the most used indicator historically is litmus. This is extracted from lichens.

Litmus is purple in neutral solution. When added to an acidic solution, it turns **red**. This colour change of litmus needs a chemical reaction. The molecules of the indicator are actually changed in the presence of the acid. Substances with the opposite chemical effect to acids are needed to reverse the change, and these are called **alkalis**. They turn litmus solution **blue**.

Type	Name	Formula	Strong or weak?	Where found or used
Organic acids	ethanoic acid	CH_3COOH	weak	in vinegar
	methanoic acid	HCOOH	weak	in ant and nettle stings; used in kettle descaler
	lactic acid	$\text{CH}_3\text{CH}(\text{OH})\text{CO}_2\text{H}$	weak	in sour milk
	citric acid	$\text{C}_6\text{H}_8\text{O}_7$	weak	in lemons, oranges and other citrus fruits
Mineral acids	carbonic acid	$\text{H}_2\text{CO}_{3\text{t}}$	weak	in fizzy soft drinks
	hydrochloric acid	HCl	strong	used in cleaning metal surfaces; found as the dilute acid in the stomach
	nitric acid	HNO_3	strong	used in making fertilisers and explosives
	sulfuric acid	H_2SO_4	strong	in car batteries; used in making fertilisers, paints and detergents
	phosphoric acid	H_3PO_4	strong	in anti-rust paint; used in making fertilisers

Table 5.1 Some common acids.

You can also use litmus paper. This is paper that has been soaked in litmus solution. It comes in blue and red forms. The blue form of litmus paper changes colour to red when dipped into acid solutions. Red litmus paper turns blue in alkali solutions. Note that litmus just gives a single colour change.

Study tip

It may seem simple to remember the colour change that litmus shows in acid and alkali, but it is important. This simple visual memory aid may help you to remember:

r
e
acid / base
l
u
e

The presence of water is very important in the action of acids and alkalis. One practical consequence of this is that, when we use litmus paper to test gases, it **must always be damp**. The gas needs to dissolve in the moisture to bring about the colour change. This is important in your practical work.

Indicator	Colour in acid	Neutral colour	Colour in alkali
litmus	red	purple	blue
phenolphthalein	colourless	colourless	pink
methyl orange	red	orange	yellow

Table 5.2 Some common indicator colour changes.

Litmus is not the only single indicator that chemists find useful. Others that have been frequently used are phenolphthalein and methyl orange. They give different colour changes from litmus (Table 5.2). These changes are sometimes easier to 'see' than that of litmus.

Universal Indicator

Another commonly used indicator, **Universal Indicator** (or full-range indicator), is a **mixture** of indicator dyes. The idea of a Universal Indicator mixture is to imitate the colours of the rainbow when measuring acidity. Such an indicator is useful because it gives a range of colours (a 'spectrum') depending on the strength of the acid or alkali added (Figure 5.3). When you use Universal Indicator, you see that solutions of different acids produce different colours. Indeed, solutions of the same acid with different concentrations will also give different colours.

The more acidic solutions (for example, battery acid) turn Universal Indicator bright red. A less acidic solution




Figure 5.3 How the colour of Universal Indicator changes in solutions of different pH values.

Activity 5.1

Extracting an indicator from red cabbage

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates

Dye is extracted from chopped-up red cabbage leaves (or other coloured plant material) and then tested to see the colour change when it is added to acidic and alkaline solutions.

A worksheet is included on the CD-ROM.

(for example, vinegar) will only turn it orange-yellow. There are also colour differences produced with different alkali solutions. The most alkaline solutions give a violet colour.

The pH scale

The most useful measure of the strength of an acid solution was worked out by the Danish biochemist Søren Sørensen. He worked in the laboratories of the Carlsberg breweries and was interested in checking the acidity of beer. The scale he introduced was the **pH scale**. The scale runs from 1 to 14, and the following general rules apply.

Rules for the pH scale

- ◆ Acids have a pH less than 7.
- ◆ The more acidic a solution, the lower the pH.
- ◆ Neutral substances, such as pure water, have a pH of 7.
- ◆ Alkalis have a pH greater than 7.

The pH of a solution can be measured in several ways. Universal Indicator papers that are sensitive over the full range of values can be used. Alternatively, if the approximate pH value is known, then we can use a more accurate test paper that is sensitive over a narrow range. The most accurate method is to use a pH meter (Figure 5.4), which uses an electrode to measure pH electrically. The pH values of some common solutions are shown in Table 5.3.



Figure 5.4 pH meters in use **a** in the laboratory and **b** for testing soil.

Study tip

It's very important to remember that the 'reference point' when measuring pH is neutrality, pH 7 – the mid-point of the scale.

- ◆ As we move **down** from 7, the solution is getting **more acidic**.
- ◆ Moving **up** from pH 7, the solution is getting **more alkaline**.

Activity 5.2 Rainbow fizz!

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

A03.3 Make and record observations, measurements and estimates

This activity creates a Universal Indicator pH scale in a boiling tube. Set up a test-tube rack containing the following:

- ◆ Tube A: A boiling tube containing half a spatula of sodium hydrogencarbonate
- ◆ Tube B: A test tube containing 5 cm³ of distilled water
- ◆ Tube C: A test tube containing 0.5 cm³ of Universal Indicator solution
- ◆ Tube D: A test tube containing 5 cm³ of dilute ethanoic acid
- ◆ Tube E: A test tube containing 5 cm³ of dilute sulfuric acid

Then follow this sequence, making careful observations at each stage.

- 1 Add the water from tube B to the solid in tube A.
- 2 Then add the indicator solution from tube C to tube A.
- 3 Tilt tube A. Very carefully pour the ethanoic acid from tube D into tube A down the side of the tube. Do not shake the tube.
- 4 Finally, add the sulfuric acid from tube E to tube A. Again, pour this acid very carefully down the side of the tilted tube A. Do not shake the tube.

A worksheet is included on the CD-ROM.

? Questions

- A1 Explain the colour changes you observe at each addition.



	Substance	pH
strongly acidic ↑	hydrochloric acid (HCl)	0.0
	gastric juices	1.0
	lemon juice	2.5
	vinegar	3.0
	wine	3.5
	tomato juice	4.1
	black coffee	5.0
	acid rain	5.6
	urine	6.0
	rainwater	6.5
weakly acidic	milk	6.5
	pure water, sugar solution	7.0
NEUTRAL weakly alkaline ↓	blood	7.4
	baking soda solution	8.5
	toothpaste	9.0
	borax solution	9.2
	Milk of Magnesia	10.5
	limewater	11.0
	household ammonia	12.0
	sodium hydroxide (NaOH)	14.0
strongly alkaline		

Table 5.3 The pH values of some common solutions.

? Questions

- 5.1 What do you understand by the word **corrosive**?
- 5.2 Which acid is present in orange or lemon juice?
- 5.3 Is a solution acidic, alkaline or neutral if its pH is:
a 11 b 7 c 8 d 3?
- 5.4 Methyl orange is an **indicator**. What does this mean?
- 5.5 Which solution is more acidic: one with a pH of 4, or one with a pH of 1?
- 5.6 What colour is Universal Indicator in a sugar solution?
- 5.7 What acid is present in vinegar?

5.2 Acid and alkali solutions

The importance of hydrogen ions

If we look again at the chemical formulae of some of the best known acids (Table 5.1, page 120), we see that one element is common to them all. They all contain **hydrogen**. If solutions of these acids are checked to see if they conduct electricity, we find that they all do. Also, they conduct electricity much better than distilled water does. This shows that the solutions contain **ions**. Water itself contains very few ions. In pure water, the concentrations of hydrogen ions (H^+) and hydroxide ions (OH^-) are equal. All acids dissolve in water to produce hydrogen ions (H^+ ions). Therefore, all acid solutions contain more H^+ ions than OH^- ions. The pH scale is designed around the fact that acid solutions have this excess of hydrogen ions. The term pH is taken from the German '*potenz H*(ydrogen)', meaning the power of the hydrogen-ion concentration of a solution.

Alkali solutions also conduct electricity better than distilled water. All alkalis dissolve in water to produce hydroxide ions (OH^- ions). Therefore, all alkali solutions contain an excess of OH^- ions. An indicator, like litmus, is affected by the presence of H^+ or OH^- ions (Figure 5.5).

- ◆ The hydrogen ions (H^+) in acid solutions make litmus go red.
- ◆ The hydroxide ions (OH^-) in alkali solutions make litmus go blue.




Figure 5.5 pH and the balance of hydrogen ions and hydroxide ions in solution.

	Name	Ions present
Acids	hydrochloric acid	$\text{H}^+(\text{aq})$ and $\text{Cl}^-(\text{aq})$
	nitric acid	$\text{H}^+(\text{aq})$ and $\text{NO}_3^-(\text{aq})$
	sulfuric acid	$\text{H}^+(\text{aq})$, $\text{HSO}_4^-(\text{aq})$ and $\text{SO}_4^{2-}(\text{aq})$
Alkalis	sodium hydroxide	$\text{Na}^+(\text{aq})$ and $\text{OH}^-(\text{aq})$
	potassium hydroxide	$\text{K}^+(\text{aq})$ and $\text{OH}^-(\text{aq})$
	calcium hydroxide	$\text{Ca}^{2+}(\text{aq})$ and $\text{OH}^-(\text{aq})$
	ammonia solution	$\text{NH}_4^+(\text{aq})$ and $\text{OH}^-(\text{aq})$

Table 5.4 The ions present in solutions of some acids and alkalis.

The ions present in some important acid and alkali solutions are given in Table 5.4.

The importance of water

When is an acid not an acid, but simply an 'acid-in-waiting'? Hydrochloric acid is a good example to illustrate this problem. The gas hydrogen chloride is made up of covalently bonded molecules. If the gas is dissolved in an organic solvent, such as methylbenzene, it does not show any of the properties of an acid. For example, it does not conduct electricity. However, when the gas is dissolved in water, a strongly acidic solution is produced. The **acidic oxides** of sulfur, phosphorus and carbon listed in Table 5.5 (page 126) are similar. They are covalent molecules when pure, but produce acids when dissolved in water.

Key definition

acid – a substance that dissolves in water to produce hydrogen ions (H^+). This solution:

- ◆ contains an excess of H^+ ions
- ◆ turns litmus red
- ◆ has a pH lower than 7.

alkali – a substance that dissolves in water to produce hydroxide ions (OH^-). This solution:

- ◆ contains an excess of OH^- ions
- ◆ turns litmus blue
- ◆ has a pH higher than 7.

Thus, in our most useful definition of an acid, the characteristic properties of an acid are shown when dissolved in water. Alkalis are also normally used in aqueous

solution. Both acids and alkalis can be used in dilute or concentrated solutions. If a large volume of water is added to a small amount of acid or alkali, then the solution is **dilute**; using less water gives a more **concentrated** solution.

? Questions


- 5.8 Which element do all acids contain?
- 5.9 Which ion is in excess in an alkali solution?
- 5.10 Which ions are present in:
- nitric acid solution
 - calcium hydroxide solution
 - ammonia solution?
- 5.11 What is the formula for:
- sulfuric acid
 - hydrochloric acid?
- 5.12 What statement can we make about the concentrations of hydrogen ions and hydroxide ions in water?

5.3 Metal oxides and non-metal oxides

Acidic and basic oxides

Venus, the Earth's nearest neighbour, is identical in size and density to the Earth. But Venus has yielded its secrets reluctantly, because it is veiled in clouds and has an atmosphere that destroys space probes. Magellan, the latest space probe to Venus, has looked from a distance. If it went into the atmosphere, it would meet with thick clouds of sulfuric acid and temperatures similar to those in a self-cleaning oven – acid rain with a vengeance! The probe would not last long!

The sulfuric acid clouds of Venus are the product of great volcanic activity (Figure 5.6). This has thrown out huge amounts of water vapour and the oxides of sulfur into the planet's atmosphere. Similar acidic clouds can be made in a gas jar by lowering burning sulfur into oxygen (Figure 5.7):



Other burning non-metals (carbon, for example) react in the same way to produce acidic gases:




Figure 5.6 Image of the European Space Agency probe orbiting above the clouds of the Venus atmosphere. The Venus Express spacecraft was launched to study the thick atmosphere responsible for the intense greenhouse effect on the planet.




Figure 5.7 Burning sulfur in a gas jar of oxygen.

When water is added to the gas jars, it dissolves the gases and gives solutions that **turn blue litmus paper red**.

Metals burning in oxygen produce solid products. Some of these dissolve in water to give solutions that **turn red litmus paper blue**. You might be able to work out a pattern in the reactions of some elements with oxygen, as shown in Table 5.5 (overleaf).

Turning litmus paper red shows that some of these solutions contain acids. These solutions are the product of burning non-metals to produce **acidic oxides**. Burning metals produces oxides that, if they dissolve, give solutions that turn litmus paper blue. The metal oxides produced in these reactions react with acids to neutralise them – they are said to be **basic oxides**.

Element	How it reacts	Product	Effect of adding water and testing with litmus
Non-metals			
sulfur	burns with bright blue flame	colourless gas (sulfur dioxide, SO_2)	dissolves, turns litmus red
phosphorus	burns with yellow flame	white solid (phosphorus(v) oxide, P_2O_5)	dissolves, turns litmus red
carbon	glows red	colourless gas (carbon dioxide, CO_2)	dissolves slightly, slowly turns litmus red
Metals			
sodium	burns with yellow flame	white solid (sodium oxide, Na_2O)	dissolves, turns litmus blue
magnesium	burns with bright white flame	white solid (magnesium oxide, MgO)	dissolves slightly, turns litmus blue
calcium	burns with red flame	white solid (calcium oxide, CaO)	dissolves, turns litmus blue
iron	burns with yellow sparks	blue-black solid (iron oxide, FeO)	insoluble
copper	does not burn, turns black	black solid (copper oxide, CuO)	insoluble

Table 5.5 The reactions of certain elements with oxygen.

The characteristics of oxides:

- ◆ Non-metals generally form **acidic oxides** that dissolve in water to form **acidic solutions**.
- ◆ Metals form oxides that are solids. If they dissolve in water, these oxides give **alkaline solutions**. These metal oxides neutralise acids and are **basic oxides**.

monoxide (CO), noted for being poisonous. The 'rule' that most non-metal oxides are acidic remains useful and important, however.

Of more importance is the unusual behaviour of some metal oxides. These metal oxides react and neutralise acids, which would be expected. However, they also neutralise alkalis, which is unusual.

S Neutral and amphoteric oxides

Water can be thought of as hydrogen oxide. It has a pH of 7 and is therefore a **neutral oxide**. It is an exception to the broad 'rule' that the oxides of non-metals are acidic oxides. Neutral oxides do not react with either acids or alkalis. There are a few other exceptions to this 'rule' (see Figure 5.8). The most important is carbon

Key definition

amphoteric hydroxide (or amphoteric metal oxide) – a hydroxide or metal oxide that reacts with both an acid and an alkali to give a salt and water.







Figure 5.8 The classification of non-metal and metal oxides.

The most important examples of metals that have amphoteric compounds are zinc and aluminium. The fact that zinc hydroxide and aluminium hydroxide are amphoteric helps in the identification of salts of these metals using sodium hydroxide. If sodium hydroxide solution is added to a solution of a salt of either of these metals, a white precipitate of the metal hydroxide is formed. For example:



S However, this precipitate will re-dissolve if excess sodium hydroxide is added, because zinc hydroxide is amphoteric:





Aluminium salts will give a similar set of reactions. This test distinguishes zinc and aluminium salts from others, but not from each other (see Sections 5.7 and 12.1).

Study tip

In these last reactions, the zinc hydroxide and aluminium hydroxide precipitates re-dissolve in excess sodium hydroxide because they are **amphoteric**.

They are reacting as acids with the sodium hydroxide and producing a salt and water as the products.



Do notice how these rather unusual salts are named.

5.4 Acid reactions in everyday life

Indigestion, headaches and neutralisation

The dilute hydrochloric acid in our stomach is there to help digest our food. However, excess acid causes indigestion, which can be painful and eventually give rise to ulcers. To ease this, we can take an antacid treatment. **Antacids** (or 'anti-acids') are a group of compounds with no toxic effects on the body. They are used to neutralise the effects of acid indigestion. Some of these antacids, such as 'Milk of Magnesia', contain insoluble material to counteract the acid. 'Milk of Magnesia' contains insoluble magnesium hydroxide.

Other effervescent or 'fizzy' antacids, such as Alka-Seltzer[®], contain soluble material, including sodium hydrogencarbonate. These tablets also contain some citric acid – a solid acid. On adding water, the acid and some of the sodium hydrogencarbonate react, producing carbon dioxide gas – the 'fizz' in the glass (see Figure 5.9). This helps to spread and dissolve the other less soluble material. When the mixture is drunk,



Figure 5.9 Soluble antacid tablets dissolving and giving off carbon dioxide.

? Questions

- 5.13 What colour is the flame when sulfur burns?
- 5.14 What colour flame is produced when magnesium burns?
- 5.15 Write the word equation for the reaction when sulfur burns in oxygen.
- 5.16 What is the chemical equation for the reaction in question 5.15?
- 5.17 Write the word equation for magnesium burning in air.
- 5.18 Which oxide of carbon is neutral?
- 5.19 Name one amphoteric metal hydroxide and write the word and symbol equations for its reaction with sodium hydroxide solution.

more sodium hydrogencarbonate neutralises the excess hydrochloric acid in the stomach, thus easing the indigestion.

Some antacid tablets also contain a painkiller to relieve headaches. Vitamin C (ascorbic acid – another soluble acid) can also be added to the tablet. Note the importance of adding water to start the action of the acid. The tablets do not react in the packet!

'Soluble aspirin' tablets dissolve in a similar way to Alka-Seltzer® tablets.

Descaling kettles

Limescale collects inside kettles and water heaters in hard-water areas. Hard-water areas tend to be geographically located in limestone areas. Hard water contains more dissolved calcium ions than normal water. Calcium carbonate forms when the water is boiled (Figure 5.10). This limescale can be removed by treatment with an acid that is strong enough to react with calcium carbonate but not strong enough to damage the metal. Vinegar can be used to descale kettles. Commercial 'descalers' use other acid solutions such as methanoic acid.



Figure 5.10 A build-up of white 'limescale' in a kettle.

Vegetables	Preferred pH range
potatoes	4.5–6.0
chicory, parsley	5.0–6.5
carrot, sweet potato	5.5–6.5
cauliflower, garlic, tomato	5.5–7.5
broad bean, onion, cabbage and many others	6.0–7.5

Table 5.6 Preferred soil pH conditions for different vegetables.

Activity 5.3 Testing the pH of everyday substances

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates

In this introductory experiment to the ideas of acids and alkalis, household and everyday products are tested for their pH using Universal Indicator.

A worksheet is included on the CD-ROM.

A follow-up experiment on neutralising vinegar with slaked lime or powdered limestone is included on the Teacher's Resource CD-ROM.

Soil pH and plant growth

Plant growth is affected by the acidity or alkalinity of the soil. Soils with high peat content, or with minerals such as iron compounds, or with rotting vegetation and lack of oxygen, tend to be acidic. Their soil pH can reach as low as pH 4. Soils in limestone or chalky areas are alkaline – up to pH 8.3. The soil pH is also affected by the use of fertilisers and the acidity of rainfall. Different plants prefer different pH conditions (Table 5.6). Farmers and gardeners can test the soil pH to see whether it suits the needs of particular plants.

If the soil is too **acidic**, it is usually treated by 'liming'. 'Lime' here is a loose term meaning either calcium oxide, calcium hydroxide, or powdered chalk or limestone (calcium carbonate). These compounds all have the effect of neutralising the acidity of the soil. If the soil is too **alkaline**, it helps to dig in some peat or decaying organic matter (compost or manure).



Figure 5.11 The colour of the flowers of some types of hydrangea depend on soil pH. Here the flowers are showing signs of the colour change between pink and blue.



Figure 5.12 Controlled addition of lime to a stream in Sweden to neutralise the effects of acidity.

Some flowering plants carry their own 'built-in' pH indicator. The flowers of a hydrangea bush are blue when grown on acid soil and pink when the soil pH is alkaline (Figure 5.11).

Effluent and waste water treatment

Liquid waste from factories is often acidic. If such waste gets into a river, the acid will kill fish and other river life. Slaked lime is often added to the waste to neutralise it. Slaked lime is similarly used to treat streams, rivers and lakes affected by acid rain (Figure 5.12).

To reduce emissions of sulfur dioxide, many modern factories and power stations now spray acidic waste gases with jets of slaked lime in a **flue-gas desulfuriser** (or 'scrubber') to neutralise them before they leave the chimneys.

Activity 5.4

Comparing the effectiveness of different antacid tablets

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity involves titrating powdered samples of antacid tablets with dilute hydrochloric acid.

A worksheet is included on the CD-ROM.

Questions

- 5.20** Ant stings contain methanoic acid. What household substance could be used to ease the effect of the sting?
- 5.21** Which acid is present in our stomachs, and why is it there?
- 5.22** Indigestion tablets contain antacid. Name two compounds that we use in these tablets.

5.5 Alkalis and bases


What types of substance are alkalis and bases?

In Section 5.4 we saw that the effects of acids could be neutralised by alkalis. Alkalis are substances that dissolve in water to give solutions with a pH greater than 7 and turn litmus blue. The solutions contain an excess of hydroxide, OH^- , ions.

However, among the antacids we use to relieve indigestion is **insoluble** magnesium hydroxide, which also neutralises acids. As we investigate further, it is found that **all** metal oxides and hydroxides will neutralise acids, whether they dissolve in water or not. Therefore the soluble alkalis are just a small part of a group of substances – the oxides and hydroxides of metals – that neutralise acids. These substances are known as **bases**. These bases all react in the same way with acids.

The relationship of alkalis to bases can be summed up in a mathematical device known as a Venn diagram (Figure 5.13, overleaf). In more general terms it is something like the difference between our immediate family and our extended family. The bases are the extended family of compounds. The alkalis are a particular small group within that extended family.

A base will neutralise an acid, and in the process a **salt** is formed. This type of reaction is known as a **neutralisation** reaction. It can be summed up in a general equation:



Therefore a base can be defined in the following way.



Figure 5.13 This Venn diagram shows the relationship between bases and alkalis. All alkalis are bases, but not all bases are alkalis.

Key definition

base – a substance that reacts with an acid to form a salt and water only.

Most bases are insoluble in water. This makes the few bases that **do** dissolve in water more significant. They are given a special name – **alkalis**.

Key definition

alkali – a base that is soluble in water. Alkalis are generally used in the laboratory as aqueous solutions.

The common alkalis are:

- ◆ sodium hydroxide solution
- ◆ potassium hydroxide solution
- ◆ calcium hydroxide solution (often known as limewater)
- ◆ ammonia solution (also known as ammonium hydroxide).

These solutions contain OH^- ions, turn litmus blue and have a pH higher than 7. The first two are stronger alkalis than the others.

Study tip

The four solutions listed above are the alkalis you will need to know for your course. They are by far and away the commonest, and they are likely to be the only ones you refer to.

It is worth making sure that you learn their names and formulae! And you should do the same for the four commonest acids you'll need to know: hydrochloric acid, sulfuric acid, nitric acid and ethanoic acid.

Properties and uses of alkalis and bases

Alkalis feel soapy to the skin. They convert the oils in your skin into soap. They are used as degreasing agents because they convert oil and grease into soluble soaps, which can be washed away easily. The common uses of some alkalis and bases are shown in Table 5.7.

The properties of bases, alkalis and antacids can be summarised as follows.

Bases:

- ◆ neutralise acids to give a salt and water only
- ◆ are the oxides and hydroxides of metals
- ◆ are mainly insoluble in water.

Alkalis are bases that dissolve in water, and:

- ◆ feel soapy to the skin
- ◆ turn litmus blue
- ◆ give solutions with a pH greater than 7
- ◆ give solutions that contain OH^- ions.

Antacids are compounds that are used to neutralise acid indigestion and include:

- ◆ magnesium oxide and magnesium hydroxide
- ◆ sodium carbonate and sodium hydrogencarbonate
- ◆ calcium carbonate and magnesium carbonate.

Type	Name	Formula	Strong or weak?	Where found or used
Alkalis	sodium hydroxide (caustic soda)	NaOH	strong	in oven cleaners (degreasing agent); in making soap and paper; other industrial uses
	potassium hydroxide (caustic potash)	KOH	strong	in making soft soaps and biodiesel
	calcium hydroxide (limewater)	Ca(OH) ₂	strong	to neutralise soil acidity and acidic gases produced by power stations; has limited solubility
	ammonia solution (ammonium hydroxide)	NH ₃ (aq) or NH ₄ OH	weak	in cleaning fluids in the home (degreasing agent); in making fertilisers
Bases	calcium oxide	CaO		for neutralising soil acidity and industrial waste; in making cement and concrete
	magnesium oxide	MgO		in antacid indigestion tablets

Table 5.7 Some common alkalis and bases.

Questions

- 5.23** Give the names of two examples of insoluble bases and two examples of alkalis.
- 5.24** Write word and balanced symbol equations for the reaction between:
- sodium hydroxide and hydrochloric acid
 - potassium hydroxide and sulfuric acid
 - copper oxide and nitric acid.
- 5.25** Name the four main alkalis.
- 5.26** Which of the four alkalis in question 5.25 is only a weak alkali?

replaced by a metal to give the salt. The acid from which the salt is made is often called the parent acid of the salt.

Normally, we use the word 'salt' to mean 'common salt', which is sodium chloride. This is the salt we put on our food, the main salt found in seawater, and the salt used over centuries to preserve food. However, in chemistry, the word has a more general meaning.

Key definition

salt – a compound made from an acid when a metal takes the place of the hydrogen in the acid.

5.6 Characteristic reactions of acids

The reactions of acids

All acids can take part in neutralisation reactions. But are there any other reactions that are characteristic of all acids? The answer is 'Yes'. There are three major chemical reactions in which all acids will take part. These reactions are best seen using dilute acid solutions. In these reactions, the acid reacts with:

- ◆ a reactive metal (for example, magnesium or zinc – Figure 5.14)
- ◆ a base (or alkali) – a neutralisation reaction
- ◆ a metal carbonate (or metal hydrogencarbonate).

One type of product is common to all these reactions. They all produce a metal compound called a **salt**. In all of them, the hydrogen present in the acid is





Figure 5.14 **a** Magnesium ribbon and **b** zinc granules, reacting with hydrochloric acid – giving off hydrogen.

The reaction of acids with metals

Metals that are quite reactive (not the very reactive ones, see pages 207 and 219) can be used to displace the hydrogen from an acid safely. Hydrogen gas is given off. The salt made depends on the combination of metal and acid used:





It is unsafe to try this reaction with very reactive metals such as sodium or calcium. The reaction is too violent. No reaction occurs with metals, such as copper, which are less reactive than lead. Even with lead, it is difficult to see any reaction in a short time.

The salt made depends on the acid:

- ◆ hydrochloric acid always gives a chloride
- ◆ nitric acid always gives a nitrate
- ◆ sulfuric acid always gives a sulfate
- ◆ ethanoic acid always gives an ethanoate.

For example:



Study tip

You may be asked a question where you have to suggest a metal that will react with an acid to give hydrogen. Do not give any of the very reactive metals, such as calcium, as an answer. You will not gain the mark as this reaction is unsafe!


The reaction of acids with bases and alkalis

This is the neutralisation reaction that we saw on page 129:



The salt produced by this reaction will again depend on the combination of reactants used. To make a particular

salt, you choose a suitable acid and base to give a solution of the salt you want. For example:




Other examples of salts made from different combinations of acid and base are shown in Table 5.8.


Study tip

It's useful to realise the origins of a salt because it helps you predict which salt you get from a particular combination of acid and base. The cubic crystals of sodium chloride come from the neutralisation of hydrochloric acid with sodium hydroxide solution.

For example:




SODIUM CHLORIDE



The reaction of acids with carbonates

All carbonates give off carbon dioxide when they react with acids (Figure 5.15). We have seen that this reaction occurs with effervescent antacid tablets. The result is to neutralise the acid and produce a salt solution:



The normal method of preparing carbon dioxide in the laboratory is based on this reaction. Dilute

Base	Salt made with ...		
	Hydrochloric acid (HCl)	Nitric acid (HNO ₃)	Sulfuric acid (H ₂ SO ₄)
sodium hydroxide (NaOH)	sodium chloride, NaCl	sodium nitrate, NaNO ₃	sodium sulfate, Na ₂ SO ₄
potassium hydroxide (KOH)	potassium chloride, KCl	potassium nitrate, KNO ₃	potassium sulfate, K ₂ SO ₄
magnesium oxide (MgO)	magnesium chloride, MgCl ₂	magnesium nitrate, Mg(NO ₃) ₂	magnesium sulfate, MgSO ₄
copper oxide (CuO)	copper chloride, CuCl ₂	copper nitrate, Cu(NO ₃) ₂	copper sulfate, CuSO ₄

Table 5.8 Some examples of making salts.

Activity 5.5

The reaction between an acid and an alkali

Skills


- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

 Wear eye protection.

This activity investigates what happens to pH and temperature as an acid reacts with an alkali.

- 1 Measure 10 cm³ of aqueous sodium hydroxide into a beaker using a measuring cylinder.
- 2 Add a few drops of Universal Indicator – sufficient to produce an obvious colour.
- 3 Place a thermometer in the solution and record its temperature.
- 4 Use a pH chart to record the pH of the solution.
- 5 Using a plastic pipette, add 1 cm³ of hydrochloric acid to the mixture.

- 6 Stir and record the new temperature and pH.
- 7 Add a further 1 cm³ of acid and again record the temperature and pH.
- 8 Repeat this process until a total of 20 cm³ of acid have been added.
- 9 Plot a graph with volume of acid added on the x-axis and temperature on the y-axis.
- 10 Indicate using colour or a bar chart how the pH changed during the experiment.



Estimate the volume of acid needed to neutralise the alkali. Explain how you arrived at your answer.

A worksheet is included on the CD-ROM.

The Notes on Activities for teachers/technicians contain details of how this experiment can be used as an assessment of skill A03.3, and ways in which the experiment can be made more accurate.

Questions


- A1 Explain how and why the temperature changed during the experiment.
- A2 How could the experiment be changed to obtain more accurate results?

Study tip

It is important for students to be able to give word equations for the reactions in this section.

Being able to give balanced chemical equation will be even more useful.

hydrochloric acid is reacted with marble chips (calcium carbonate):






Figure 5.15 Limestone (calcium carbonate) reacting with acid.

Questions

- 5.27 What are the names and formulae of the three most important mineral acids?
- 5.28 Write word equations for the reaction of hydrochloric acid with:
- a potassium hydroxide b copper oxide
c zinc d sodium carbonate.
- 5.29 Write balanced chemical equations for the reactions listed in question 5.28.

5.7 Acids and alkalis in chemical analysis

One important part of chemistry is the analysis of unknown substances to find out what they are. There is a series of tests that are important for this (see Section 12.1). Acids and alkalis play an important part in some of these tests. The chemistry of these tests is discussed here.

Study tip

These analytical tests are very important – particularly the tests for metal ions that give coloured precipitates. Also important is the way that we can identify zinc and aluminium salts using alkali.

These tests come up frequently in exams because they are so distinctive, so it would be good to learn them. The ability to tell an iron(II) salt from an iron(III) salt is important.

The test for carbonates using acid

All carbonates will react with acids to give off carbon dioxide. We can use this as a test to find out if an unknown substance is a carbonate or not. A piece of rock that we think is limestone can be checked by dripping a few drops of vinegar on it. If it 'fizzes', then it could be limestone. A more usual test would be to add dilute hydrochloric acid to the powdered substance. Any gas given off would be passed into limewater (calcium hydroxide solution) to see if it went cloudy. If the limewater **does** turn cloudy, the gas is carbon dioxide, and the substance is a carbonate. Figure 5.16 shows how an antacid tablet can be tested to see if it contains a carbonate.

Tests for metal ions in salts using alkalis

All salts are ionic compounds. They are made up of a positive metal ion, combined with a negative non-metal ion. Thus, common salt, sodium chloride, is made up of sodium metal ions (Na^+ ions) and chloride non-metal ions (Cl^- ions). Table 5.9 shows the ions that form certain important salts.

In analysis it would be useful to have tests for the metal ions in salts. We have seen that most metal hydroxides are insoluble. By adding an alkali to a solution of the unknown salt we can begin to identify the salt.




Figure 5.16 Testing an antacid tablet containing a carbonate as the active ingredient.

Salt	Positive ion	Negative ion
sodium chloride	Na^+	Cl^-
potassium nitrate	K^+	NO_3^-
copper(II) sulfate	Cu^{2+}	SO_4^{2-}
calcium carbonate	Ca^{2+}	CO_3^{2-}
sodium ethanoate	Na^+	CH_3COO^-


Table 5.9 The ions making up certain important salts.

Coloured hydroxide precipitates

Some of the hydroxide precipitates are coloured. As a result, a solution of a salt can be tested by adding an alkali to it and checking the colour of the precipitate (Figure 5.17):

- ◆ Copper(II) salts give a light blue precipitate of copper(II) hydroxide.
- ◆ Iron(II) salts give a light green precipitate of iron(II) hydroxide.
- ◆ Iron(III) salts give a red-brown precipitate of iron(III) hydroxide.
- ◆ Chromium(III) salts give a grey-green precipitate of chromium(III) hydroxide.


For example:



White hydroxide precipitates

Certain hydroxide precipitates are white. They are the hydroxides of calcium, zinc and aluminium. The addition of sodium hydroxide to a solution of a salt of these metals produces a white precipitate in each case.

For example:



Even though the precipitates are all white, the test is still useful. When an excess of sodium hydroxide is added, the zinc and aluminium hydroxide precipitates re-dissolve to give colourless solutions. The calcium hydroxide precipitate does not re-dissolve.





Figure 5.17 a The precipitation of iron(II) hydroxide. b The precipitation of iron(III) hydroxide. Note the different colour of the precipitates.

To identify a zinc or aluminium salt, the test needs to be repeated with ammonia solution. The same white precipitates of zinc or aluminium hydroxide are produced. However, with excess ammonia solution it is only the zinc hydroxide precipitate that re-dissolves, not the aluminium hydroxide. Therefore we can tell the two apart using ammonia solution.

The test for ammonium salts using alkali

Ammonium salts are important as fertilisers. For example, ammonium nitrate and ammonium sulfate are used extensively as fertilisers. These are industrially important chemicals made by reacting ammonia with nitric acid or sulfuric acid, respectively. They are salts containing ammonium ions, NH_4^+ ions. These salts react with alkali solutions to produce ammonia gas, which can be detected because it turns damp red litmus paper blue:



This reaction occurs because ammonia is a more **volatile** base than sodium hydroxide. Ammonia is therefore easily displaced from its salts by sodium hydroxide. The reaction can be used to test an unknown substance for ammonium ions. It can also be used to prepare ammonia in the laboratory.

Questions

- 5.30 Write the word equation for the reaction between a carbonate and hydrochloric acid.
- 5.31 What colour precipitate is produced when testing for copper ions with sodium hydroxide solution? What is the name of this precipitate?
- 5.32 Which alkali solution must be used to distinguish between zinc ions and aluminium ions in solution? What is the observation that distinguishes between the two?

5.8 Salts

The importance of salts – an introduction

A salt is a compound formed from an acid by the replacement of the hydrogen in the acid by a metal. Salts are ionic compounds. There is a wide range of types of salt. A great number of them play an important part in our everyday life (Table 5.10).

Many important minerals are single salts, for example fluorite (calcium fluoride) and gypsum (calcium sulfate). Common salt (sodium chloride) is mined from underground in many parts of the world including Britain and Ireland. The Detroit Salt Company in the USA has a mining complex directly under the city. It has an area of 10 km²! The Wieliczka salt mine in Poland is one of the world's oldest mines and is a UNESCO World Heritage site. The mine is noted for the statues, rooms and ornaments carved underground (Figure 5.18), and is visited by millions of people each year.

These salt deposits were formed by the evaporation of ancient seas millions of years ago. Solid 'rock salt' is mined directly in some of these, including the Winsford mine in the UK. In other mines a technique known as solution mining is used. In these cases, the salt is dissolved underground and the solution, known as 'brine', is pumped up to the surface.



Figure 5.18 A chandelier carved out of salt in the Wieliczka salt mine, Poland.

In hotter regions where the land is flat, for example the west coast of France, Lanzarote and the coast near Adelaide in Australia, the sea can be fed into shallow inland pools. Here the water slowly evaporates in the sun and crystals of 'sea salt' form (Figure 5.19). These crystals are then scraped up from the surface. 'Sea salt' is not just sodium chloride; it also contains magnesium chloride, calcium sulfate, potassium bromide and other salts.

Salt	Parent acid	Colour and other characteristics	Uses
ammonium chloride	hydrochloric acid	white crystals	fertilisers; dry cells (batteries)
ammonium nitrate	nitric acid	white crystals	fertilisers; explosives
ammonium sulfate	sulfuric acid	white crystals	fertilisers
calcium carbonate (marble, limestone, chalk)	carbonic acid	white	decorative stones; making lime and cement and extracting iron
calcium sulfate (gypsum, plaster of Paris)	sulfuric acid	white crystals	wall plaster; plaster casts
sodium carbonate (washing soda)	carbonic acid	white crystals or powder	in cleaning; water softening; making glass
magnesium sulfate (Epsom salts)	sulfuric acid	white crystals	health salts (laxative)
copper(II) sulfate	sulfuric acid	blue crystals	fungicides
calcium phosphate	phosphoric acid	white	making fertilisers

Table 5.10 Salts in common use.



Figure 5.19 Salt flats beside the ocean in Lanzarote. Seawater is allowed to evaporate and then the salt is harvested. Piles of collected salt can be seen on the far right.

Sodium chloride is essential for life and is an important raw material for industries. Biologically, it has a number of functions: it is involved in muscle contraction; it enables the conduction of nerve impulses in the nervous system; it regulates osmosis (the passage of solvent molecules through membranes); and it is converted into the hydrochloric acid that aids digestion in the stomach. When we sweat, we lose both water and sodium chloride. Loss of too much salt during sport and exercise can give us muscle cramp. Isotonic drinks are designed to replace this loss of water and to restore energy and the balance of mineral ions in our body.

While a number of salts can be obtained by mining, others must be made by industry. Therefore, it is worth considering the methods available to make salts. Some of these can be investigated in the laboratory.

Two things are important in working out a method of preparation:

- ◆ Is the salt soluble or insoluble in water?
- ◆ Do crystals of the salt contain water of crystallisation?

The first point influences the preparation method chosen. The second point affects how the crystals are handled at the end of the experiment.

The solubility of salts

Soluble salts are made by neutralising an acid. Insoluble salts are made by other methods. Table 5.11 outlines the general patterns of solubility for the more usual salts.

Salts	Soluble	Insoluble
sodium salts	all are soluble	none
potassium salts	all are soluble	none
ammonium salts	all are soluble	none
nitrates	all are soluble	none
ethanoates	all are soluble	none
chlorides	most are soluble	silver chloride, lead(II) chloride
sulfates	most are soluble	barium sulfate, lead(II) sulfate, calcium sulfate
carbonates	sodium, potassium and ammonium carbonates	most are insoluble

Table 5.11 The patterns of solubility for various types of salts.

Study tip

This information about solubility may seem complicated to learn – but there are certain key features to understand and then it is easier. Table 5.11 is organised to help you to remember:

- ◆ All the common sodium, potassium and ammonium salts are soluble.
- ◆ All nitrates and ethanoates are soluble.
- ◆ Most chlorides and sulfates are soluble. The most important exceptions are silver chloride and barium sulfate, which are important precipitates in chemical analysis.
- ◆ Almost all carbonates are insoluble.

We shall look at the preparation of both soluble salts and insoluble salts. But first we consider the second point mentioned above.

Water of crystallisation

The crystals of some salts contain **water of crystallisation**. This water gives the crystals their shape. In some cases it also gives them their colour (copper sulfate crystals, for instance, Figure 5.20). Such salts are known as **hydrated salts** (Table 5.12, overleaf).

When these hydrated salts are heated, their water of crystallisation is driven off as steam. The crystals lose




Figure 5.20 Crystals of hydrated copper(II) sulfate are blue. They contain water of crystallisation in their structure ($\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$).

Hydrated salt	Formula	Colour
copper(II) sulfate	$\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$	blue
cobalt(II) chloride	$\text{CoCl}_2 \cdot 6\text{H}_2\text{O}$	pink
iron(II) sulfate	$\text{FeSO}_4 \cdot 6\text{H}_2\text{O}$	green
magnesium sulfate	$\text{MgSO}_4 \cdot 7\text{H}_2\text{O}$	white
sodium carbonate	$\text{Na}_2\text{CO}_3 \cdot 10\text{H}_2\text{O}$	white
calcium sulfate	$\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$	white

Table 5.12 Some hydrated salts.

their shape and become a powder. Copper(II) sulfate crystals are blue, but, when they are heated, they are dehydrated to form a white powder:



Crystals that have lost their water of crystallisation are said to be **anhydrous**. If water is added back to the white anhydrous copper(II) sulfate powder, the powder turns blue again and heat is given out. This can be used as a test for the presence of water.


Study tip

When preparing crystals of a hydrated salt, we must be careful not to heat them too strongly when drying them. If we do, the product is a dehydrated powder, not crystals.

Be careful, then, when you describe the method of drying crystals in an exam question.

Questions

5.33 The diagram shows some reactions of dilute sulfuric acid. Use the information in it to answer the questions that follow.



Name or give the formula of each of the following:

- a** gas A
- b** solution B
- c** gas C
- d** substance D
- e** solution E

5.9 Preparing soluble salts

Soluble salts can be made from their parent acid using any of the three characteristic reactions of acids we outlined earlier (Section 5.6).

Method A – Acid plus solid metal, base or carbonate

Method A is essentially the same whether you are starting with a solid metal, a solid base or a solid carbonate. The method can be divided into four stages (Figure 5.21).

- ◆ **Stage 1:** An excess (more than enough) of the solid is added to the acid and allowed to react. Using an excess of the solid makes sure that all the acid is used up. If it is not used up at this stage, the acid would become more concentrated when the water is evaporated later (stage 3).
- ◆ **Stage 2:** The excess solid is filtered out.
- ◆ **Stage 3:** The filtrate is gently evaporated to concentrate the salt solution. This can be done on a heated water bath (Figure 5.21) or sand tray (Figure 5.22).
- ◆ **Stage 4:** When crystals can be seen forming (crystallisation point), heating is stopped and the solution is left to crystallise.




Figure 5.21 Method A for preparing a soluble salt. **a** Stage 1: the acid is reacted with either **(i)** a metal, **(ii)** a base or **(iii)** a carbonate. **b** Stage 2: the excess solid is filtered out. **c** Stage 3: the solution is carefully evaporated. **d** Stage 4: the crystals are allowed to form.



Figure 5.22 Evaporating off the water to obtain salt crystals. Here a sand tray is being used to heat the solution carefully.

- ◆ **Stage 5:** The concentrated solution is cooled to let the crystals form. The crystals are filtered off and washed with a little distilled water. Then the crystals are dried carefully between filter papers (Figure 5.23).

Study tip

Always remember to finish your description of a method of preparing salt crystals with at least the words 'filter, wash and carefully dry the crystals' to cover the final stages of the preparation.



Figure 5.23 Dried crystals of zinc nitrate.

Activity 5.6

Quick and easy copper(II) sulfate crystals

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

! Wear eye protection. Note that sulfuric acid is an irritant at the concentration used.

This activity is an adaptation of the larger-scale method of preparing a soluble salt (see Figure 5.21).

- 1 Pour 15 cm³ of 2 mol/dm³ sulfuric acid into a boiling tube.
- 2 Place the tube in a beaker half-filled with boiling water from a kettle.
- 3 Weigh out between 1.8 g and 2.0 g of copper(II) oxide.
- 4 Add half the copper(II) oxide to the acid in the boiling tube. Agitate the boiling tube and return it to the hot water.
- 5 When the solid has dissolved, add the remaining portion of copper(II) oxide.
- 6 Keep the tube in the hot water for 5 more minutes, taking it out occasionally to agitate.
- 7 Filter off the unreacted solid, collecting the clear blue solution in a 100 cm³ conical flask. A fluted filter paper can be used to speed up the filtration.
- 8 Boil the solution for 2–3 minutes.
- 9 Pour the hot solution into a clean, dry dish and watch the crystals grow!

Questions

- A1 Write word and balanced chemical equations for the reaction taking place.
- A2 What does the fact that there is some unreacted solid left after the reaction tell you about the proportions of reactants used? Why is it useful that the reaction is carried out with these proportions?

The preparation of magnesium sulfate crystals (Epsom salts) is included in the Notes on Activities for teachers/technicians.

Method B – Acid plus alkali by titration

Method B (the **titration** method) involves the neutralisation of an acid with an alkali (for example, sodium hydroxide) or a soluble carbonate (for example, sodium carbonate). Since both the reactants and the products are colourless, an indicator is used to find the neutralisation point or **end-point** (when all the acid has just been neutralised). The method is divided into three stages (Figure 5.24).

- ◆ **Stage 1:** The acid solution is poured into a burette. The burette is used to accurately measure the volume of solution added. A known volume of alkali solution is placed in a conical flask using a pipette. The pipette delivers a fixed volume accurately. A few drops of an indicator (for example phenolphthalein or methyl orange, Figure 5.25) are added to the flask.
- ◆ **Stage 2:** The acid solution is run into the flask from the burette until the indicator just changes colour. Having found the end-point for the reaction, the volume of acid run into the flask is noted. The experiment is then repeated without using the indicator. The same known volume of alkali is used in the flask. The same volume of acid as noted in the first part is then run into the flask. Alternatively, activated charcoal can be added to remove the coloured indicator. The charcoal can then be filtered off.




Figure 5.24 Method B (the titration method) for preparing a soluble salt. **a** Stage 1: the burette is filled with acid and a known volume of alkali is added to the conical flask. **b** Stage 2: the acid is added to the alkali until the end-point is reached. **c** Stage 3: the solution is evaporated and crystallised as for method A.




Figure 5.25 **a** The colour changes for the indicators methyl orange and phenolphthalein. **b** The actual colours of methyl orange in acid and alkali.

♦ **Stage 3:** The salt solution is evaporated and cooled to form crystals as described in method A. This titration method is very useful not simply for preparing salts but also for finding the concentration of a particular acid or alkali solution (see page 168).

Questions

- 5.34 What colour is the indicator methyl orange in alkali?
- 5.35 In the methods of preparing a salt using a solid metal, base or carbonate, why is the solid used in excess?
- 5.36 In such methods, what method is used to remove the excess solid once the reaction has finished?
- 5.37 Name the two important pieces of graduated glassware used in the titration method of preparing a salt.
- 5.38 Why should the crystals prepared at the end of these experiments not be heated too strongly when drying them?

5.10 Preparing insoluble salts

Choosing a method of salt preparation

The choice of method for preparing a soluble salt (see Section 5.9) depends on two things:

- ♦ Is the metal reactive enough to displace the hydrogen in the acid? If it is, is it too reactive and therefore unsafe?

♦ Is the base or carbonate soluble or insoluble? Figure 5.26 (overleaf) shows a flow chart summarising the choices.

Making salts by precipitation

The reaction between marble chips (calcium carbonate) and sulfuric acid would be expected to produce a strong reaction, with large amounts of carbon dioxide being given off. However, the reaction quickly stops after a very short time. This is caused by the fact that calcium sulfate is insoluble. It soon forms a layer on the surface of the marble chips, stopping any further reaction (Figure 5.27 (overleaf)).

This reaction emphasises that some salts are insoluble in water (for example, silver chloride and barium sulfate – see Table 5.11 on page 137). Such salts cannot be made by the crystallisation methods we have described earlier. They are generally made by ionic precipitation.

Key definition

precipitation – the sudden formation of a solid, either:

- ♦ when two solutions are mixed, or
- ♦ when a gas is bubbled into a solution.

For example, barium sulfate can be made by taking a solution of a soluble sulfate (such as sodium sulfate).




Figure 5.26 Flow chart showing which method to use for preparing soluble salts. The two methods A and B are described in the text and in Figures 5.21 and 5.24.





Figure 5.27 The formation of a layer of insoluble calcium sulfate stops the reaction of marble chips with sulfuric acid by forming a protective layer over the surface of the solid.

This is added to a solution of a soluble barium salt (for example, barium chloride). The insoluble barium sulfate is formed immediately. This solid ‘falls’ to the bottom of the tube or beaker as a precipitate (Figure 5.28). The precipitate can be filtered off. It is then washed with distilled water and dried in a warm oven. The equation for this reaction is:



This equation shows how important state symbols can be – it is the only way we can tell that this equation shows a precipitation.

The equation can be simplified to show **only** those ions that take part in the reaction and their products:







Figure 5.28 The precipitation of barium sulfate. The solid can be collected by filtration or centrifugation.

This type of equation is known as an **ionic equation**. The ions that remain in solution are left out of the equation. They are known as **spectator ions**.

The diagram below shows the formation of a precipitate of silver chloride when solutions of silver nitrate and sodium chloride are mixed.



silver nitrate + sodium chloride
→ silver chloride + sodium nitrate
 $\text{AgNO}_3(\text{aq}) + \text{NaCl}(\text{aq}) \rightarrow \text{AgCl}(\text{s}) + \text{NaNO}_3(\text{aq})$



Precipitation reactions are often used in analysis to identify salts such as chlorides, iodides and sulfates (see page 297). Figure 4.12a on page 96 shows the precipitation of yellow lead iodide by mixing lead nitrate and potassium iodide solutions.

Activity 5.7

Making sparkling crystals of lead(II) iodide

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates

Lead nitrate solution and sodium iodide solution react to produce solid lead iodide, leaving soluble sodium nitrate in solution. The yellow precipitate of lead iodide (see Figure 4.12a) can be recovered by filtration. If the precipitate is washed, dissolved in hot water and re-crystallised, some quite spectacular crystals can be obtained.

A worksheet is included on the CD-ROM.

Study tip

You should not be put off writing ionic equations for precipitation reactions because there is a quite straightforward 'trick' to writing them. The approach is essentially to work backwards.

First write down the formula for the solid product on the right-hand side. Then, on the left-hand side, write down the ions that combine together to form the precipitate. Finally, write in the state symbols.

Questions

- 5.39** There are three methods of preparing salts:
- Method A – use a burette and an indicator.
- Method B – mix two solutions and obtain the salt by precipitation.
- Method C – add an excess of base or metal to a dilute acid and remove the excess by filtration.
- For each of the following salt preparations, choose one of the methods A, B or C, name any additional reagent needed and then write or complete the equation asked for.
- a** the soluble salt, zinc sulfate, from the insoluble base, zinc oxide
- method
 - reagent
 - word equation.
- b** the soluble salt, potassium chloride, from the soluble base, potassium hydroxide
- method
 - reagent
 - copy and complete the following symbol equation
..... + $\rightarrow \text{KCl} + \text{H}_2\text{O}$
- c** the insoluble salt, lead(II) iodide, from the soluble salt, lead(II) nitrate
- method
 - reagent
 - ionic equation.

5.11 Strong and weak acids and alkalis


Strong and weak acids

Not all acids are equally strong. The vinegar used in salad dressing and to pickle vegetables is significantly less acidic than a hydrochloric acid solution of the same concentration. If differences in concentration are not the reason for this, then what does cause the difference? After all, we can eat fruit and drink wine or carbonated drinks without damage. Yet our bodies are not as resistant to all acids.



The difference lies in the ionic nature of acid solutions; more precisely, in the concentration of hydrogen ions (H^+ ions) in a solution. In Section 5.2

S we stressed the importance of water as the necessary solvent for acid solutions. There is a relationship between H^+ ion concentration, acidity and pH: the higher the H^+ ion concentration, the higher the acidity and the lower the pH. We saw in Section 5.1 that the pH scale goes from 1 to 14. Each pH unit means a ten-fold difference in H^+ ion concentration. An acid of pH 1.0 has ten times the H^+ ion concentration of an acid of pH 2.0.

When hydrochloric acid is formed in water, the hydrogen chloride molecules completely separate into ions:



In a similar way, sulfuric acid and nitric acid molecules completely separate into ions when dissolved in water:




Study tip

In general, two equivalent terms are used instead of 'separate into ions': we say that the acids 'ionise' or 'dissociate into ions'. Also, for various substances the separation into ions may or may not be complete. In this book, if the separation is complete, we say the substance is 'completely ionised'. If the separation is not complete, we say the substance is 'partially dissociated into ions'.

Complete separation into ions (complete ionisation) produces the maximum possible concentration of H^+ ions, and so the lowest possible pH for that solution.

When pure ethanoic acid is dissolved in water, only a small fraction of the covalently bonded molecules are dissociated into hydrogen ions and ethanoate ions:



Thus an ethanoic acid solution will have far fewer hydrogen ions present in it than a hydrochloric acid

S solution of the same concentration, and its pH will be higher. In school laboratory ethanoic acid solution, only one molecule in 250 is dissociated into ions.

Carbonic acid (H_2CO_3) is an example of a weak mineral acid. The other organic acids, such as methanoic acid, citric acid, etc. (see Table 5.1 on page 120), also only partially dissociate into ions when dissolved in water.


Key definition

Strong acids and **strong alkalis** are completely ionised in solution in water.

Weak acids and **weak alkalis** are partially dissociated into ions in solution in water.


Strong and weak alkalis

Alkalis can also differ in the way that they are ionised when dissolved in water. Sodium hydroxide and potassium hydroxide are ionic solids. When they dissolve in water, the crystal lattice is broken down and the ions are spread throughout the solution. These alkalis are completely ionised in water:



This means that a solution contains the maximum possible concentration of OH^- ions, and therefore has the maximum possible pH. The pH of calcium hydroxide as an alkali is limited by its poor solubility.

Ammonia solution, on the other hand, is a weak alkali because it is only partially dissociated into ions:



Such a solution contains only a low concentration of ammonium (NH_4^+) ions and hydroxide (OH^-) ions. Solutions of ammonia only have a moderately high pH value.

Because of their high concentration of ions, solutions of strong acids and strong alkalis conduct electricity well. Compounds such as nitric acid, sulfuric acid and sodium hydroxide are **strong electrolytes** in solution. Ethanoic acid and ammonia

S solution are only **weak electrolytes**. The large difference in conductivity between weak and strong acids and alkalis shows clearly the differences in ionisation in these solutions.

In solutions of weak acids and weak alkalis, only a small number of molecules are dissociated into ions at any given time. For weak acids and weak alkalis, the process of dissociation is **reversible**: it can go in either direction. In an ethanoic acid solution, molecules are constantly dissociating into ions. At the same time, ethanoate ions and hydrogen ions are also re-combining, hence the use of the reversible arrows in the equations above.


Study tip

When comparing two acids (or alkalis) and trying to decide whether they are weak or strong, it is very important to compare two solutions of the **same concentration**.


If the concentrations are the same, then you can use the pH, the conductivity or the rate of a particular reaction to help you make a judgement as to the extent of ionisation.

What happens to the ions in neutralisation?

An acid can be neutralised by an alkali to produce a salt and water only, according to the general equation:




For example:




All these compounds are completely ionised, except for the water produced.

The hydrogen ions from the acid and the hydroxide ions from the alkali have combined to form water molecules.



We can show this in the following equation:



This is the ionic equation for this neutralisation reaction. The spectator ions (chloride and sodium ions) remain in solution – which becomes a solution of sodium chloride (Figure 5.29).




Figure 5.29 The reactions of the ions when hydrochloric acid is mixed with sodium hydroxide.

S By evaporating some of the water, the salt can be crystallised out. In fact, the **same** ionic equation can be used for **any** reaction between an acid and an alkali.

In these reactions, the acid is providing hydrogen ions to react with the hydroxide ions. In turn, the base is supplying hydroxide ions to accept the H^+ ions and form water. This leads to a further definition of an acid and a base in terms of hydrogen ion (proton) transfer:

Key definition

acid – a molecule or ion that is able to **donate** a proton (H^+ ion) to a base.

base – a molecule or ion that is able to **accept** a proton.

Study tip

It is important to realise that a hydrogen ion (H^+) is simply a proton. Once the single electron of a hydrogen atom has been removed to form the positive ion, all that is left is the proton of the nucleus (Figure 5.30).






Figure 5.30 A hydrogen ion is simply a proton.

The 'basicity' of acids

Sodium carbonate and sodium hydrogencarbonate are both salts of carbonic acid (H_2CO_3). Two different salts of this acid exist because there are two hydrogen atoms present that can be replaced by a metal. Carbonic acid is said to be a **dibasic acid** because it has two replaceable hydrogen atoms per molecule.

S Sulfuric acid is the most important dibasic acid in the laboratory. It too forms two different salts, depending on the amount of alkali used to react with the acid:



Hydrochloric acid, nitric acid and ethanoic acid are all **monobasic acids**. They have **one** replaceable hydrogen atom per molecule and they each produce only one salt. Phosphoric acid (H_3PO_4) is a **tribasic acid**, producing three salts (Table 5.13). Since the acidity of a solution depends on the number of hydrogen ions (protons) released by each acid molecule, a dibasic acid can also be known as a **diprotic acid** (see Table 5.13).

Study tip

If you are in doubt about the basicity of a particular acid, simply ask yourself how many moles of sodium hydroxide one mole of the acid would react with.

Note that not all the hydrogens in a structure count in this – there are four hydrogens in an ethanoic acid molecule, but only one is replaceable by a metal (the H in the $-\text{COOH}$ group). Ethanoic acid is just a monobasic acid.

Questions

- 5.40** Write an equation to show what happens when hydrogen chloride dissolves in water.
- 5.41** Write an equation to show what happens when ammonia gas dissolves in water.
- 5.42** Why does ethanoic acid have a lower conductivity than hydrochloric acid?
- 5.43** Explain why an H^+ ion is simply a proton.
- 5.44** Define an acid and a base using the ideas of proton (H^+ ion) transfer.
- 5.45** What is **a** an ionic equation, **b** a spectator ion?
- 5.46** Write the ionic equations that correspond to:
 - a** magnesium oxide reacting with nitric acid
 - b** sodium carbonate reacting with hydrochloric acid
 - c** potassium hydroxide reacting with nitric acid.

Acid type	Name	Formula	Normal salts	Acid salts
Monobasic (monoprotic) acids	hydrochloric acid	HCl	chlorides, e.g. NaCl	
	nitric acid	HNO ₃	nitrates, e.g. NaNO ₃	
	ethanoic acid	CH ₃ COOH	ethanoates, e.g. CH ₃ COONa	
Dibasic (diprotic) acids	carbonic acid	H ₂ CO ₃	carbonates, e.g. Na ₂ CO ₃	hydrogencarbonates, e.g. NaHCO ₃
	sulfuric acid	H ₂ SO ₄	sulfates, e.g. Na ₂ SO ₄	hydrogensulfates, e.g. NaHSO ₄
Tribasic (triprotic) acids	phosphoric acid	H ₃ PO ₄	phosphates, e.g. Na ₃ PO ₄	dihydrogenphosphates, e.g. NaH ₂ PO ₄ , and hydrogenphosphates, e.g. Na ₂ HPO ₄

Table 5.13 The basicity of some common acids.

Summary

You should know:

- ◆ how the oxides of non-metals usually form acidic solutions when dissolved in water and that metal oxides, if they dissolve, usually form alkaline solutions
- ◆ how all acids contain hydrogen and dissolve in water to give solutions with a pH below 7
- ◆ that pH is a measure of the acidity or alkalinity of an aqueous solution; acids have a pH below 7, alkalis above 7 and a neutral solution a pH of 7
- ◆ that acid solutions have an excess of H⁺ ions, while alkali solutions have an excess of OH⁻ ions
- ◆ that indicators change colour depending on the pH of the solution they are added to; some show a single colour change, while Universal Indicator shows a range of colours depending on the solution tested
- ◆ that bases are the 'chemical opposites' of acids and they neutralise the effects of acids; alkalis are bases that dissolve in water
- ◆ that neutralisation between an acid and a base produces a salt and water only
- ◆ that acids have certain characteristic reactions with some metals to give a salt and hydrogen gas, and with metal carbonates to give a salt, water and carbon dioxide gas
- ◆ how salts are produced when the hydrogen in the acid is replaced by a metal
- ◆ that salts are prepared in the laboratory by a series of methods depending on the compound reacted with the acid and whether the salt is soluble or not
- S ◆ how acids can be strong or weak depending on whether they are fully dissociated into ions in water or not
- S ◆ that the pH of a solution depends on the balance of the H⁺ and OH⁻ ion concentrations present; water is neutral because these concentrations are equal in pure water
- S ◆ how the neutralisation reaction between any acid and alkali can be represented by the ionic equation:


$$\text{H}^+(\text{aq}) + \text{OH}^-(\text{aq}) \rightarrow \text{H}_2\text{O}(\text{l})$$
- S ◆ that acids are defined as molecules or ions that can donate a proton
- S ◆ that bases are defined as molecules or ions that can accept a proton
- S ◆ how some non-metal oxides are neutral, and some metal oxides and hydroxides are amphoteric.

End-of-chapter questions


- 1 Why do only some salts dissolve? Are there any rules which tell you which will?
- 2 What is the meaning of the word 'strong' in 'strong coffee' and 'strong acid'? How do we deal with this difference?
- 3 A solution of calcium hydroxide in water is alkaline.
 - a Which **one** of the pH values below is alkaline?

pH 3 pH 6 pH 7 pH 11 [1]

- b Which of the following is the common name for calcium hydroxide?
cement limestone quicklime slaked lime [1]
- c Some farmers use calcium hydroxide to control soil acidity.
 - i Why is it important to control soil acidity? [1]
 - ii Acid rain can cause soil to become acidic. Describe how acid rain is formed. [3]
- d Calcium hydroxide reacts with hydrochloric acid.



- i State the name of this type of chemical reaction. [1]
- ii A dilute solution of calcium hydroxide can be titrated with hydrochloric acid using the apparatus shown.



Describe how you would carry out this titration. [3]

[Cambridge IGCSE® Chemistry 0620/21, Question 5, November 2010]

- 4 Hydrochloric acid and ethanoic acid are both acidic in nature.
- a Which one of the following and ethanoic acid are both a pH value for an acidic solution?
- pH 3 pH 7 pH 9 pH 13 [1]
- b Describe how you would use litmus to test if a solution is acidic. [3]
- c Acids react with metal carbonates.
- i Write a word equation for the reaction of calcium carbonate with hydrochloric acid. [3]
- ii Calcium carbonate can be used to treat acidic soil. State **one** other use of calcium carbonate. [1]
- iii Name **one** other compound that can be used to treat acidic soil. [1]
- d Hydrochloric acid reacts with iron to form iron(II) chloride and hydrogen. Complete the equation for this reaction.
- $\text{Fe} + \dots\text{HCl} \rightarrow \text{FeCl}_2 + \dots$ [2]

[Cambridge IGCSE® Chemistry 0620/21, Question 3(a–d), June 2012]

- 5 Oxides are classified as acidic, basic, neutral and amphoteric.

- a Copy and complete the table.

Type of oxide	pH of solution of oxide	Example
acidic		
basic		
neutral		

[6]

- b i Explain the term *amphoteric*. [1]
- ii Name two reagents that are needed to show that an oxide is amphoteric. [2]

[Cambridge IGCSE® Chemistry 0620/31, Question 2, November 2009]

- 6 Soluble salts can be made using a base and an acid.

Complete the method of preparing dry crystals of the soluble salt cobalt(II) chloride-6-water from the insoluble base cobalt(II) carbonate. The method involves four steps. The first is as follows:

Step 1: Add an excess of cobalt(II) carbonate to hot dilute hydrochloric acid.

What are **Steps 2, 3 and 4**?

[4]

[Cambridge IGCSE® Chemistry 0620/31, Question 8(a), November 2010]

- S** 7 Three ways of making salts are:
- ◆ titration using a soluble base or carbonate
 - ◆ neutralisation using an insoluble base or carbonate
 - ◆ precipitation.
- a Copy and complete the following table of salt preparations.

Method	Reagent 1	Reagent 2	Salt
titration			sodium nitrate
neutralisation	nitric acid		copper(II) nitrate
precipitation			silver(I) chloride
neutralisation	sulfuric acid	zinc(II) carbonate	

[6]

- b i Write an ionic equation with state symbols for the preparation of silver(I) chloride. [2]
- ii Complete the following equation.



[2]

[Cambridge IGCSE® Chemistry 0620/31, Question 2, June 2012]

6

Quantitative chemistry

In this chapter, you will find out about:

- ◆ the relative atomic mass of elements
- ◆ the relative formula mass of compounds
- ◆ calculating the percentage by mass of an element in a compound
- ◆ that substances react in fixed proportions by mass
- ◆ the mole as the 'accounting unit' in chemistry
- ◆ simple calculations involving the mole
- ◆ the empirical formula of a compound
- ◆ the molecular formula of a compound
- ◆ calculations involving the mole and reacting masses
- ◆ percentage yield and percentage purity
- ◆ calculations involving gases
- ◆ the concentration of solutions
- ◆ the titration of acid and alkali solutions.

Chemical 'accountancy'

Over the years, the wine industry has survived several scandals. Perhaps the most notorious were those hitting the headlines in the mid 1980s: the Austrian antifreeze incidents of 1985 and the Italian methanol scandal one year later. In the first of these, ethane-1,2-diol was added to sweeten wine. Although potentially dangerous, there were no recorded examples of ill health resulting from this tampering. However, the addition of methanol to increase the alcohol content of some Italian wine was tragic: 23 people died and more than 90 were hospitalised after being poisoned.

It is important to know not only what is in a chemical product but also how much of each substance there is. The fertiliser bags found around a farm often carry three numbers (Figure 6.1). The numbers tell the farmer the amounts of the three key elements present in the fertiliser: that is, the percentages of nitrogen (N), phosphorus (P) and potassium (K). The same idea lies behind the rules controlling the food industry. For instance, European Union regulations require all breakfast cereal packets to show the amounts of various chemical substances (such as protein, fat and vitamins) present in the cereal.



Figure 6.1 NPK fertiliser contains the plant nutrients nitrogen, phosphorus and potassium. The 5-10-5 on the bag refers to the ratio of these nutrients in the fertiliser: 5% nitrogen; 10% phosphorus; 5% potassium.

The same demands apply in many areas of chemistry. Environmental chemists need to check levels of pollutants in the air caused by burning a particular fuel. Polymer chemists require an estimate of how much material a new and different reaction method will yield. They need to check on losses through the purification process. Medical researchers must find a safe dose for an experimental drug. They must consider its possible side effects by measuring the amounts of its metabolic products in cells. A chemical formula or equation not only tells us what happens but puts 'numbers' to it. This is vital to modern chemistry.

6.1 Chemical analysis and formulae

We need to be able to predict the amounts of substances involved in chemical reactions. To do this, we must have a good understanding of the atom. For some time now we have been able to use the **mass spectrometer** as a way of 'weighing' atoms.

Relative atomic mass

The mass of a single hydrogen atom is incredibly small when measured in grams (g):

$$\begin{aligned}\text{mass of one hydrogen atom} &= 1.7 \times 10^{-24} \text{ g} \\ &= 0.000\,000\,000\,000\,000\,000\,001\,7 \text{ g}\end{aligned}$$

It is much more useful and convenient to measure the masses of atoms **relative** to each other (Table 6.1). To do this, a standard atom has been chosen, against which all others are then compared. This **standard atom** is an atom of the carbon-12 isotope, the 'mass' of which is given the value of exactly 12 (Figure 6.2).

The use of the mass spectrometer first showed the existence of isotopes. These are atoms of the same element that have different masses because they have different numbers of neutrons in the nucleus (see page 43). The majority of elements have several isotopes (Figure 6.3).

This must be taken into account. The relative atomic mass (A_r) of an element is the average mass of an atom of the element, taking into account the different natural isotopes of that element (Table 6.2). So most relative atomic masses are not whole numbers. But in this book, with the exception of chlorine, they are rounded to the nearest whole number to make our calculations easier.

Key definition

relative atomic mass (A_r) of an element – the average mass of naturally occurring atoms of the element on a scale where the carbon-12 atom has a mass of exactly 12 units.

Atom	Mass in grams	Whole-number ratio
hydrogen	1.7×10^{-24}	1
carbon-12	2.0×10^{-23}	12
fluorine	3.2×10^{-23}	19

Table 6.1 The relative masses of some atoms.




Figure 6.2 The relative mass of atoms. Twelve hydrogen atoms have the same mass as one atom of carbon-12. A helium atom has the same mass as four hydrogens.




Figure 6.3 Many different elements have more than one isotope. These bars show the proportions of different isotopes for some elements. Fluorine is rare in having just one.

It is important to note that the mass of an ion will be the same as that of the parent atom. The mass of the electron(s) gained or lost in forming the ion can be ignored in comparison to the total mass of the atom.

Relative formula mass

Atoms combine to form molecules or groups of ions. The total masses of these molecules or groups of ions

Element	Symbol	Relative atomic mass, $A_{r(1)}$
hydrogen	H	1
carbon	C	12
nitrogen	N	14
oxygen	O	16
fluorine	F	19
sodium	Na	23
magnesium	Mg	24
aluminium	Al	27
sulfur	S	32
chlorine	Cl	35.5
copper	Cu	64

^(a)Except for chlorine, all values have been rounded to the nearest whole number.

Table 6.2 The relative atomic masses of some elements.

provide useful information on the way the elements have combined with each other. The **formula** of an element or compound is taken as the basic unit (the formula unit). The masses of the atoms or ions in the formula are added together. The mass of a substance found in this way is called the **relative formula mass** (M_r). Here we illustrate the method by calculating the relative formula masses of three simple substances.

- ◆ **Hydrogen:** Hydrogen gas is made up of H_2 molecules ($H-H$). Each molecule contains two hydrogen atoms. So its relative formula mass is twice the relative atomic mass of hydrogen:

$$M_r(H_2) = 2 \times 1 = 2$$

- ◆ **Water:** Water is a liquid made up of H_2O molecules ($H-O-H$). Each molecule contains two hydrogen atoms and one oxygen atom. So its relative formula mass is twice the relative atomic mass of hydrogen plus the relative atomic mass of oxygen:

$$M_r(H_2O) = (2 \times 1) + 16 = 18$$

- ◆ **Sodium chloride:** Sodium chloride is an ionic solid. It contains one chloride ion for each sodium ion present. The formula unit of sodium chloride

is therefore Na^+Cl^- . So its relative formula mass is the relative atomic mass of sodium plus the relative atomic mass of chlorine:

$$M_r(NaCl) = 23 + 35.5 = 58.5$$

Key definition

relative formula mass (M_r) of a substance – the sum of the relative atomic masses of the elements present in a formula unit.

If the substance is made of simple molecules, this mass may also be called the **relative molecular mass** (M_r).

The practical result of these definitions can be seen by looking at further examples (Table 6.3, overleaf).

The **percentage by mass** of a particular element in a compound can be found from calculations of relative formula mass. Figure 6.4 shows how this works for the simple case of sulfur dioxide (SO_2), whose mass is made up of 50% each of the two elements.

This type of calculation is useful, for instance, in estimating the efficiency of one fertiliser compared with another. Ammonium nitrate is a commonly used fertiliser. It is an important source of nitrogen.




Figure 6.4 The percentage composition by mass of sulfur dioxide.

Substance	Formula	Atoms in formula	Relative atomic masses			Relative formula mass, M_r		
hydrogen	H_2	2H	H	=	1	2×1	=	2
carbon dioxide	CO_2	1C	C	=	12	1×12	=	12
		2O	O	=	16	2×16	=	<u>32</u>
								44
calcium carbonate	$CaCO_3$ (one Ca^{2+} ion, one CO_3^{2-} ion)	1Ca	Ca	=	40	1×40	=	40
		1C	C	=	12	1×12	=	12
		3O	O	=	16	3×16	=	<u>48</u>
								100
ammonium sulfate ^(a)	$(NH_4)_2SO_4$ (two NH_4^+ ions, one SO_4^{2-} ion)	2N	N	=	14	2×14	=	28
		8H	H	=	1	8×1	=	8
		1S	S	=	32	1×32	=	32
		4O	O	=	16	4×16	=	<u>64</u>
								132
hydrated magnesium sulfate ^(b)	$MgSO_4 \cdot 7H_2O$ (one Mg^{2+} ion, one SO_4^{2-} ion, seven H_2O molecules)	1Mg	Mg	=	24	1×24	=	24
		1S	S	=	32	1×32	=	32
		4O	O	=	16	4×16	=	64
		14H	H	=	1	14×1	=	14
		7O	O	=	16	7×16	=	<u>112</u>
								246

^(a)The figure 2 outside the brackets multiplies everything in the brackets; there are two ammonium ions in this formula.

^(b)The 7 means there are seven H_2O molecules per $MgSO_4$ formula unit.

Table 6.3 The relative formula masses of some compounds.

Worked example 6.1

What percentage of the mass of the compound is nitrogen?

The formula of ammonium nitrate is NH_4NO_3 (it contains the ions NH_4^+ and NO_3^-). Using the A_r values for N, H and O we get:

$$M_r = (2 \times 14) + (4 \times 1) + (3 \times 16) = 28 + 4 + 48 = 80$$

Then:

mass of nitrogen in the formula = 28

mass of nitrogen as a fraction of the total = $\frac{28}{80}$

mass of nitrogen as percentage of total mass
 $= \frac{28}{80} \times 100 = 35\%$

Similar calculations can be used to work out the **percentage by mass of water of crystallisation** in crystals of a hydrated salt, for example magnesium sulfate (Epsom salts).

Worked example 6.2

What is the percentage mass of water in crystals of hydrated magnesium sulfate?

The formula of magnesium sulfate is $MgSO_4 \cdot 7H_2O$. Using the A_r values for Mg, S, O and H we get:

$$M_r = 24 + 32 + (4 \times 16) + (7 \times 18) = 246$$

Then:

mass of water in formula = 126

mass of water as a fraction of the total = $\frac{126}{246}$

percentage mass of water in the crystals

$$= \frac{126}{246} \times 100 = 51.2\%$$

Study tip

Pay particular attention to the example of ammonium sulfate in Table 6.3. This is an example of a formula that has brackets. Remember to take into account the number outside the bracket when counting up all the atoms of a particular type.

Activity 6.1

Reacting marble chips with acid

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

When marble is reacted with acid, it decomposes, giving off carbon dioxide. This activity is designed to find the percentage of the mass of marble released as carbon dioxide.

A worksheet, with a self-assessment checklist, is included on the CD-ROM.

Follow-up experiment: Is eggshell pure calcium carbonate? A worksheet on this activity is included in the Notes on Activities for teachers/technicians.

Compound formation and chemical formulae

The idea that compounds are made up of elements combined in fixed amounts can be shown experimentally. Samples of the **same compound** made in different ways always contain the **same elements**. Also, the masses of the elements present are always in the **same ratio**.

Several different groups in a class can prepare magnesium oxide by heating a coil of magnesium in a crucible (Figure 6.5). The crucible must first be weighed empty, and then re-weighed with the magnesium in it. The crucible is then heated strongly. Air is allowed in by occasionally lifting the lid very carefully. Solid must not




Figure 6.5 Heating magnesium in a crucible.

be allowed to escape as a white smoke. After a while, the lid may be taken off and the open crucible heated strongly. The crucible and products are then allowed to cool before re-weighing.

Study tip

Make sure you are familiar with this type of quantitative experiment, particularly the need to re-weigh until there is no further change in mass. This 'heating to constant mass' is a way of making sure the reaction has completely finished.

The increase in mass is due to the oxygen that has now combined with the magnesium. The mass of magnesium used and the mass of magnesium oxide produced can be found from the results.

Worked example 6.3

How much magnesium oxide is produced from a given mass of magnesium?

Here are some results obtained from this experiment:

- a mass of empty crucible + lid = 8.52 g
- b mass of crucible + lid + magnesium = 8.88 g
- c mass of crucible + lid + magnesium oxide = 9.12 g
- d mass of magnesium $(b - a) = 0.36$ g
mass of magnesium oxide $(c - a) = 0.60$ g
mass of oxygen combined with magnesium
 $= 0.60 - 0.36 = 0.24$ g

0.60 g of magnesium oxide is produced from heating 0.36 g of magnesium




Figure 6.6 A graph of the results obtained from heating magnesium in air. The graph shows the mass of oxygen (from the air) that reacts with various masses of magnesium.

The results of the various experiments in the class can be plotted on a graph. The mass of oxygen combined with the magnesium (y -axis) is plotted against the mass of magnesium used (x -axis). Figure 6.6 (overleaf) shows some results obtained from this experiment.

The results show that:

- the more magnesium used, the more oxygen combines with it from the air and the more magnesium oxide is produced
- the graph is a straight line, showing that the ratio of magnesium to oxygen in magnesium oxide is fixed. A definite compound is formed by a chemical reaction.

- A particular compound always contains the same elements.
- These elements are always present in the same proportions by mass.
- It does not matter where the compound is found or how it is made.
- These proportions cannot be changed.

For example, magnesium oxide always contains 60% magnesium and 40% oxygen by mass; and ammonium nitrate always contains 35% nitrogen, 60% oxygen and 5% hydrogen by mass.

Similar experiments can be done to show that the water of crystallisation present in a particular hydrated salt, such as hydrated copper(II) sulfate ($\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$), is always the same fraction of the total mass of the salt.

Activity 6.2

Finding the composition of magnesium oxide

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

Calculate the formula of magnesium oxide formed when magnesium is heated in a crucible. Group results can be processed as shown in the text and compared with a novel method using a 'bottle-top crucible' rather than the conventional apparatus.

A worksheet is included on the CD-ROM.

Reacting amounts of substance

Relative formula masses can also be used to calculate the amounts of compounds reacted together or produced in reactions. Here is an example.

Worked example 6.4

If 0.24 g of magnesium react with 0.16 g of oxygen to produce 0.40 g of magnesium oxide (Figure 6.5), how much magnesium oxide (MgO) will be produced by burning 12 g of magnesium?

We have:

0.24 g Mg producing 0.40 g MgO

$$\text{so } 1 \text{ g Mg produces } \frac{0.40}{0.24} \text{ g MgO}$$

$$= 1.67 \text{ g MgO}$$

$$\text{so } 12 \text{ g Mg produces } 12 \times 1.67 \text{ g MgO}$$


$$= 20 \text{ g MgO}$$

Calculations of quantities like these are a very important part of chemistry. These calculations show


Questions

6.1 The diagrams represent the structure of six different compounds (A–F).


- What type of bonding is present in compounds A, C, D, E and F?
- What type of bonding is present in compound B?
- State the simplest formula for each compound A to F.




A




B



C



D



E



F

6.2 Calculate the relative formula masses (M_r) of the following substances:

- oxygen, O_2
- ammonia, NH_3
- sulfur dioxide, SO_2
- octane, C_8H_{18}
- sulfuric acid, H_2SO_4
- potassium bromide, KBr
- copper nitrate, $Cu(NO_3)_2$
- aluminium chloride, $AlCl_3$

(Relative atomic masses: $H = 1$, $C = 12$, $N = 14$, $O = 16$, $Al = 27$, $S = 32$, $Cl = 35.5$, $K = 39$, $Cu = 64$, $Br = 80$)

6.3 Calculate the percentage by mass of nitrogen in the following fertilisers and nitrogen-containing compounds:

- ammonium sulfate, $(NH_4)_2SO_4$
 - ammonium phosphate, $(NH_4)_3PO_4$
 - urea, $CO(NH_2)_2$
 - calcium cyanamide, $CaCN_2$
 - glycine, $CH_2(NH_2)COOH$ (an amino acid)
- (Relative atomic masses: $H = 1$, $C = 12$, $N = 14$, $O = 16$, $P = 31$, $S = 32$, $Ca = 40$)

6.4 A class of students carry out an experiment heating magnesium in a crucible (as described on page 155). The table shows the results of the experiments from the different groups in the class.

Experiment	Mass/g		
	Magnesium	Magnesium oxide	Oxygen
1	0.06	0.10	0.04
2	0.15	0.25	0.10
3	0.22	0.38	0.16
4	0.24	0.40	0.16
5	0.30	0.50	
6	0.28	0.46	
7	0.10	0.18	
8	0.20	0.32	

- Write down the correct mass of oxygen that reacts with the magnesium in the last four experiments.
- Plot a graph of the mass of oxygen reacted against the mass of magnesium used. Draw in the line of best fit for these points.
- Comment on what this graph line shows about the composition of magnesium oxide.

how there is a great deal of information 'stored' in chemical formulae and equations. The equation for the reaction between magnesium and oxygen defines the proportions in which the two elements always react (Figure 6.7).

Magnesium reacts with oxygen to form magnesium oxide. Work out the reacting masses and the product mass.		
$2\text{Mg} + \text{O}_2 \rightarrow 2\text{MgO}$		
2 magnesium atoms	$\rightarrow$	2 magnesium atoms
+		+
2 oxygen atoms		2 oxygen atoms
$\text{Mg} = 24$		$\text{O} = 16$
$(2 \times 24) + (2 \times 16) = [(2 \times 24) + (2 \times 16)]$		
48	+	32
$= [48 + 32]$		
48	+	32
$= 80$		
For the product, work out the inner brackets first.		
$48 + 32 \rightarrow 80$		
48 grams of magnesium react with 32 grams of oxygen to form 80 grams of magnesium oxide.		

Figure 6.7 The proportions in which magnesium and oxygen react are defined by the chemical equation for the reaction.

Activity 6.3

The effect of varying the quantity of a reactant

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This investigation uses the reaction between magnesium and dilute sulfuric acid to study the effect of varying the amount of one reactant on the amount of product formed.

A worksheet is included on the CD-ROM.

6.2 The mole and chemical formulae

A particular compound always contains the same elements. They are always present in a fixed ratio by mass (Figure 6.8). These two experimental results were of great historical importance in developing the ideas of chemical formulae and the bonding of atoms. How can we make the link between mass ratios and the chemical formula of a compound? To do this, we need to use the idea of the **mole**.

The mole – the chemical counting unit

When carrying out an experiment, a chemist cannot weigh out a single atom or molecule and then react it with another one. Atoms and molecules are simply too small. A 'counting unit' must be found that is useful in practical chemistry. This idea is not unusual when dealing with large numbers of small objects. For example, banks weigh coins rather than count them – they know that a fixed number of a particular coin will always have the same mass. The number of sweets in a jar can be estimated from their mass. Assuming that you know the mass of one sweet, you could calculate how many sweets were in the jar from their total mass. How can we estimate the number of iron atoms in an iron block? Again, we can try to link mass to the number of items present.

Chemists count atoms and molecules by weighing them. The standard 'unit' of the 'amount' of a substance is taken as the relative formula mass of the substance in grams. This 'unit' is called one mole (1 mol) of the




Figure 6.8 Experiments on heating iron with sulfur show that the two elements react in a fixed ratio by mass to produce iron sulfide.

S substance (mol is the symbol or shortened form of mole or moles). The unit 'moles' is used to measure amounts of elements and compounds. The idea becomes clearer if we consider some examples (Table 6.4).

One mole of each of these different substances contains the **same** number of atoms, molecules or formula units. That number per mole has been worked out by several different experimental methods. It is named after the nineteenth-century Italian chemist, Amedeo Avogadro, and is 6.02×10^{23} per mole (this is called the **Avogadro constant**, and it is given the symbol L). The vast size of this constant shows just how small atoms are! For instance, it has been estimated that 6.02×10^{23} soft-drink cans stacked together would cover the surface of the Earth to a depth of 200 miles.

One **mole** of a substance:

- ♦ has a mass equal to its relative formula mass in grams
- ♦ contains 6.02×10^{23} (the **Avogadro constant**) atoms, molecules or formula units, depending on the substance considered.

Calculations involving the mole

You can find the **molar mass** (mass of one mole) of any substance by following these steps.


- 1 Write down the formula of the substance; for example, ethanol is C_2H_5OH .

- 2 Work out its relative formula mass; for example, ethanol contains two carbon atoms ($A_r = 12$), six hydrogen atoms ($A_r = 1$) and one oxygen atom ($A_r = 16$). So for ethanol $M_r = (2 \times 12) + (6 \times 1) + 16 = 46$.

- 3 Express this in grams per mole; for example, the molar mass of ethanol is 46 g/mol.
For any given mass of a substance:

$$\text{number of moles} = \frac{\text{mass}}{\text{molar mass}}$$

where the mass is in grams and the molar mass is in grams per mole. The triangle shown below can be a useful aid to memory: cover the quantity to be found and you are left with how to work it out.



This shows that, if we need to calculate the mass of one mole of some substance, the straightforward way is to work out the relative formula mass of the substance and write the word 'grams' after it. Using the above equation it is possible to convert any mass of a particular substance into moles, or vice versa. We shall look at two examples.

Substance	Formula	Relative formula mass, M_r	Mass of one mole (molar mass)	This mass (1 mol) contains
carbon	C	12	12 g	6.02×10^{23} carbon atoms
iron	Fe	56	56 g	6.02×10^{23} iron atoms
hydrogen	H_2	$2 \times 1 = 2$	2 g	6.02×10^{23} H_2 molecules
oxygen	O_2	$2 \times 16 = 32$	32 g	6.02×10^{23} O_2 molecules
water	H_2O	$(2 \times 1) + 16 = 18$	18 g	6.02×10^{23} H_2O molecules
magnesium oxide	MgO	$24 + 16 = 40$	40 g	6.02×10^{23} MgO 'formula units'
calcium carbonate	$CaCO_3$	$40 + 12 + (3 \times 16) = 100$	100 g	6.02×10^{23} $CaCO_3$ 'formula units'
silicon(IV) oxide	SiO_2	$28 + (2 \times 16) = 60$	60 g	6.02×10^{23} SiO_2 'formula units'

Table 6.4 Calculating the mass of one mole of various substances.


Worked examples 6.5

1 How many moles are there in 60 g of sodium hydroxide?

We have: the relative formula mass of sodium hydroxide is:

$$M_r(\text{NaOH}) = 23 + 16 + 1 = 40$$

$$\text{molar mass of NaOH} = 40 \text{ g/mol}$$



$$\begin{aligned} \text{number of moles} &= \frac{\text{mass}}{\text{molar mass}} \\ &= \frac{60 \text{ g}}{40 \text{ g/mol}} \end{aligned}$$


$$\text{number of moles} = 1.5$$

2 What is the mass of 0.5 mol of copper(II) sulfate crystals?

We have: the relative formula mass of hydrated copper(II) sulfate is:

$$M_r(\text{CuSO}_4 \cdot 5\text{H}_2\text{O}) = 64 + 32 + (4 \times 16) + (5 \times 18) = 250$$

$$\text{molar mass of CuSO}_4 \cdot 5\text{H}_2\text{O} = 250 \text{ g/mol}$$



$$\text{number of moles} = \frac{\text{mass}}{\text{molar mass}}$$

Therefore,

$$0.5 \text{ mol} = \frac{\text{mass}}{250 \text{ g/mol}}$$

$$\text{mass} = 0.5 \times 250 = 125 \text{ g}$$

Working out chemical formulae

The idea of the mole means that we can now work out chemical formulae from experimental data on combining masses. It provides the link between the

mass of an element in a compound and the number of its atoms present.

In the experiment to make magnesium oxide (see Section 6.1), a constant ratio was found between the reacting amounts of magnesium and oxygen. If 0.24 g of magnesium is burnt, then 0.40 g of magnesium oxide is formed. This means that 0.24 g of magnesium combines with 0.16 g of oxygen ($0.40 - 0.24 = 0.16 \text{ g}$). We can now use these results to find the formula of magnesium oxide (Figure 6.9).

The formula of magnesium oxide tells us that 1 mol of magnesium atoms combine with 1 mol of oxygen atoms. The atoms react in a 1 : 1 ratio to form a **giant ionic structure** (lattice) of Mg^{2+} and O^{2-} ions.

For giant structures, the formula of the compound is the simplest whole-number formula – in this example, MgO . A formula found by this method is also known as an **empirical formula**.

Silicon(IV) oxide is a **giant molecular structure**. A sample of silicon oxide is found to contain 47% by mass of silicon. How can we find its empirical formula? This is done in Figure 6.10. The empirical formula of silicon(IV) oxide is SiO_2 . It consists of a giant molecular lattice of covalently bonded silicon and oxygen atoms in a ratio 1 : 2. Since it is a giant structure, the formula we use for this compound is SiO_2 .

Empirical formulae and molecular formulae

Not all compounds are giant structures – some are made up of simple molecules. Here we sometimes have to make a distinction between the empirical formula and the actual formula of the molecule, the **molecular formula**.

Phosphorus burns in air to produce white clouds of phosphorus oxide. From experiments it is found that the oxide contains 44% phosphorus. The empirical formula of phosphorus oxide is P_2O_5 (Table 6.5). However, it is found experimentally that its relative molecular mass (M_r) is 284. The sum of the relative atomic masses in the empirical formula (P_2O_5) is $(2 \times 31) + (5 \times 16) = 142$. The actual relative molecular mass is twice this value. Therefore the molecular formula of phosphorus oxide is $(\text{P}_2\text{O}_5)_2$ or P_4O_{10} . The empirical formula is not the actual molecular formula of phosphorus oxide. A molecule of phosphorus oxide contains four P atoms and ten O atoms (Figure 6.11).




Figure 6.9 Calculating the empirical formula of magnesium oxide from experimental data on the masses of magnesium and oxygen that react together.




Figure 6.10 Finding the empirical formula of silicon(IV) oxide from percentage mass data.

- ◆ The empirical formula of a compound is the simplest whole-number formula.
- ◆ For simple molecular compounds, the empirical formula may not be the actual molecular formula. The molecular formula must be calculated using the relative molecular mass (M_r) of the compound as found by experiment.

	P	O
percentage by mass	44%	100 – 44 = 56%
mass in 100 g	44 g	56 g
molar mass	31 g/mol	16 g/mol
number of moles	1.4 mol	3.5 mol
simplest ratio	1	2.5
or	2	5
Formula	P ₂ O ₅	

Table 6.5 Calculating the empirical formula of phosphorus oxide.




Figure 6.11 Phosphorus oxide, P₄O₁₀.

Hydrated salts

The mass of water present in crystals of hydrated salts is always a fixed proportion of the total mass. The formula of such a salt can be worked out by a method similar to that used to calculate the empirical formula of a compound.

If 5.0 g of hydrated copper(II) sulfate crystals are heated to drive off the water of crystallisation, the remaining solid has a mass of 3.2 g. The ratio of the salt and water in the crystal can be calculated. This gives the formula of the crystals (Table 6.6).

	CuSO ₄	H ₂ O
mass	3.2 g	5.0 – 3.2 = 1.8 g
molar mass	160 g/mol	18 g/mol
number of moles	0.02 mol	0.10 mol
simplest ratio	1	5
Formula	CuSO ₄ ·5H ₂ O	


Table 6.6 Calculating the formula of hydrated copper(II) sulfate.

Questions


- 6.5** One of the ores of copper is the mineral chalcopyrite. A laboratory analysis of a sample showed that 15.15 g of chalcopyrite had the following composition by mass: copper 5.27 g and iron 4.61 g. Sulfur is the only other element present. Use these figures to find the empirical formula of chalcopyrite.
(Relative atomic masses: S = 32, Fe = 56, Cu = 64)
- 6.6** A sample of antifreeze has the composition by mass: 38.7% carbon, 9.7% hydrogen, 51.6% oxygen.
(Relative atomic masses: H = 1, C = 12, O = 16)
- Calculate its empirical formula.
 - The relative molecular mass of the compound is 62. What is its molecular formula?
 - This compound is a diol. The molecule contains two alcohol (-OH) groups attached to different carbon atoms.

6.3 The mole and chemical equations

We can now see that the chemical equation for a reaction is more than simply a record of what is produced. In addition to telling us **what** the reactants and products are, it tells us **how much** product we can expect from particular amounts of reactants. When iron reacts with sulfur, the equation is:




This indicates that we need equal numbers of atoms of iron and sulfur to react. We know that 1 mol of iron (56 g) and 1 mol of sulfur (32 g) contain the same numbers of atoms. Reacting these amounts should give us 1 mol of iron(II) sulfide (88 g). The equation is showing us that:



The mass of the product is equal to the total mass of the reactants. This is the **law of conservation**

of mass, which we met in Chapter 4. Although the atoms have rearranged themselves, their total mass remains the same. A chemical equation must be balanced. In practice, we may not want to react such large amounts. We could scale down the quantities (that is, use **smaller** amounts). However, the mass of iron and the mass of sulfur must always be in the ratio 56 : 32.


We could use:



If we tried to react 5 g of sulfur with 5.6 g of iron, the excess sulfur would remain unreacted. Only 3.2 g of sulfur could react with 5.6 g of iron: 1.8 g of sulfur (5.0 – 3.2 = 1.8 g) would remain unreacted.

When we write a chemical equation, we are indicating the **number of moles** of reactants and products involved in the reaction.

The reacting amounts given by an equation can also be scaled up (that is, use **larger** amounts). In industry, tonnes of chemical reactants may be used, but the ratios given by the equation still apply. The manufacture of lime is important for the cement industry and agriculture. Lime is made by heating limestone in lime kilns. The reaction is an example of thermal decomposition:



This can be scaled up to work in tonnes:



Similarly, if 10 tonnes of calcium carbonate were heated, we should expect to produce 5.6 tonnes of lime (calcium oxide).

S Calculating reacting amounts – a chemical ‘footbridge’


We can use the idea of the mole to find reactant or product masses from the equation for a reaction. There are various ways of doing these calculations. The balanced equation itself can be used as a numerical ‘footbridge’ between the two sides of the reaction (Figure 6.12).

We shall consider an example.

Worked example 6.6

What mass of aluminium oxide is produced when 9.2 g of aluminium metal reacts completely with oxygen gas?

To answer this question, we first work out the balanced equation:



Then we work through the steps of the ‘footbridge’.

- ◆ **Step 1** (the ‘up’ stage): Convert 9.2 g of Al into moles:

$$\text{number of moles} = \frac{9.2 \text{ g}}{27 \text{ g/mol}} = 0.34 \text{ mol}$$

- ◆ **Step 2** (the ‘across’ stage): Use the ratio from the equation to work out how many moles of Al_2O_3 are produced:

4 mol of Al produce 2 mol of Al_2O_3

so

0.34 mol of Al produce 0.17 mol of Al_2O_3

- ◆ **Step 3** (the ‘down’ stage): Work out the mass of this amount of aluminium oxide (the relative formula mass of Al_2O_3 is 102):

$$0.17 \text{ mol} = \frac{\text{mass}}{102 \text{ g/mol}}$$

so

$$\begin{aligned} \text{mass of } \text{Al}_2\text{O}_3 \text{ produced} &= 0.17 \times 102 \text{ g} \\ &= 17.3 \text{ g} \end{aligned}$$




Figure 6.12 A chemical ‘footbridge’. Following the sequence ‘up–across–down’ helps to relate the mass of product made to the mass of reactant used. The ‘bridge’ can, of course, be used in the reverse direction.

Study tip

Remember to read questions on reacting masses carefully. If you set out the calculation carefully, using the equation as we have done here, you will be able to see which substances are relevant to your calculation.

Remember also to take the balancing numbers into account in making your calculation (this is called the **stoichiometry** of the equation).

Study tip

In carrying out a reaction, one of the reactants may be present in excess. Some of this reactant will be left over at the end of the reaction.

The **limiting reactant** is the one that is not in excess – there will be a smaller number of moles of this reactant present, taking into account the reacting ratio from the equation.

Percentage yield and percentage purity of product


A reaction may not always yield the total amount of product predicted by the equation. The loss may be due to several factors.

- ◆ The reaction may not be totally complete.
- ◆ Errors may be made in weighing the reactants or the products.
- ◆ Material may be lost in carrying out the reaction, or in transferring and separating the product.

- S** The equation gives us an ideal figure for the yield of a reaction; reality often produces less. This can be expressed as the **percentage yield** for a particular experiment.

Worked example 6.7

Heating 12.4 g of copper(II) carbonate in a crucible produced only 7.0 g of copper(II) oxide. What was the percentage yield of copper(II) oxide?



Therefore heating 12.4 g of copper(II) carbonate should have produced 8.0 g of copper(II) oxide. So

$$\begin{aligned}
 \text{expected yield} &= 8.0 \text{ g} \\
 \text{actual yield} &= 7.0 \text{ g} \\
 \text{and percentage yield} &= \frac{7.0}{8.0} \times 100 = 87.5\%
 \end{aligned}$$

In other, more complex, reactions, a particular product may be contaminated by other products or unreacted material. The 'crude' product may prove to contain less than 100% of the required substance.

The **percentage purity** of a chemical product can be calculated in a similar way to the percentage yield. The purity of a chemical for use in the laboratory is usually displayed on the container (Figure 6.13), for instance.

Information on the purity of a particular chemical is important in many situations. This is particularly true for compounds that are to be used medically. Preparations of such compounds undergo rigorous testing and repeated purifications, by methods such as recrystallisation or re-distillation, before they are marketed.

CALCIUM CARBONATE PRECIPITATED CP		CAS No: 471-34-1
QTY: 1kg BNO: C1042/R6 - 708717		EC No: 207-469-9
	Assay	99%
	Chloride (Cl)	0.005%
	Sulphate (SO ₄)	0.05%
	Iron (Fe)	0.002%
	Lead (Pb)	0.002%
EUROLAB SUPPLIES LTD		154205
UNIT 30, SKETCHLEY LANE IND. EST., HINCKLEY, LE10 3EN		
Tel: 01455 633333		

Figure 6.13 The percentage purity of a chemical product is displayed on the label. This preparation of calcium carbonate has a % purity of 99%. ('Sulphate' is an alternative spelling of 'sulfate'.)

In Chapter 4 we saw that the copper used for electrical circuits had to be exceptionally pure (page 114). The following calculation uses this example to show how percentage purity is calculated.

An initial crude sample of copper is prepared industrially and then tested for purity. A sample of 10.15 g of the crude copper is analysed by various methods and shown to contain 9.95 g of copper, with the remaining mass being made up of other metals. Generally,

$$\% \text{ purity} = \frac{\text{mass of pure product}}{\text{mass of impure product}} \times 100$$

Therefore:

$$\begin{aligned}
 \% \text{ purity of the copper sample} &= \frac{\text{mass of copper in sample}}{\text{mass of impure copper}} \times 100 \\
 &= \frac{9.95}{10.15} \times 100 \\
 &= 98.03\%
 \end{aligned}$$

This result shows that this batch of copper would need to be refined electrolytically before it could be used for electrical circuits such as those inside TVs, MP3 players and computers (Figure 6.14).




Figure 6.14 Very pure copper is required for printed circuit boards as the conductivity falls greatly with even a small amount of impurity.

Key definition


The percentage yield of a chemical reaction and the percentage purity of a chemical product are calculated in a similar way.

$$\text{percentage yield} = \frac{\text{actual yield}}{\text{predicted yield}} \times 100$$

$$\text{percentage purity} = \frac{\text{mass of pure product}}{\text{mass of impure product}} \times 100$$

Questions

- 6.7** Copper(II) oxide can be reduced to copper metal by heating it in a stream of hydrogen gas. Dry copper(II) oxide was placed in a tube which had previously been weighed empty. The tube was re-weighed containing the copper(II) oxide and then set up as in the diagram.



Hydrogen was passed through the tube for 15 seconds before the escaping gas was lit. The tube was heated for a few minutes. The apparatus was then allowed to cool with hydrogen still passing through. The tube was re-weighed. The process was repeated until there was no further change in mass.

- a**
- Where is the most suitable place to clamp the tube?
 - Why was the hydrogen passed through for 15 seconds before the gas was lit?
 - Why was it necessary to repeat the process until there was no further change in mass?

- b** The results for the experiment are given below.

A	Mass of empty tube	= 46.12 g
B	Mass of tube + copper(II) oxide	= 47.72 g
C	Mass of copper(II) oxide (B – A)	= g
D	Mass of tube + copper	= 47.40 g
E	Mass of copper produced (D – A)	= g
F	Mass of oxygen in the copper(II) oxide	= g

- Copy out and complete the results table above.
- How many moles of copper atoms are involved in the reaction? (Relative atomic mass: Cu = 64)
- How many moles of oxygen atoms are involved in the reaction? (Relative atomic mass: O = 16)
- From the results of the experiment, how many moles of oxygen atoms have combined with one mole of copper atoms?
- From the results of the experiment, what is the formula of copper(II) oxide?
- Write a word equation for the reaction and then, using the calculated formula for copper(II) oxide, write a full balanced equation for the reaction with hydrogen.

6.4 Calculations involving gases

The volume of one mole of a gas

Many reactions, including some of those we have just considered, involve gases. Weighing solids or liquids is relatively straightforward. In contrast, weighing a gas is quite difficult. It is much easier to measure the volume of a gas. But how does gas volume relate to the number of atoms or molecules present?

In a gas, the particles are relatively far apart. Indeed, any gas can be regarded as largely empty space. Equal volumes of gases are found to contain the same number of particles (Table 6.7); this is **Avogadro's law**. This leads to a simple rule about the volume of one mole of a gas.

- ◆ One mole of any gas occupies a volume of approximately 24 dm^3 (24 litres) at room temperature and pressure (r.t.p.).
- ◆ The **molar volume** of any gas therefore has the value $24 \text{ dm}^3/\text{mol}$ at r.t.p.
- ◆ Remember that 1 dm^3 (1 litre) = 1000 cm^3 .


Study tip

Remember that the molar gas volume is given at the bottom of the Periodic Table you are given in the exam. The value is given as 24 dm^3 at r.t.p. Do not forget that $1 \text{ dm}^3 = 1000 \text{ cm}^3$.

This rule applies to all gases. This makes it easy to convert the volume of any gas into moles, or moles into volume:

$$\text{number of moles} = \frac{\text{volume}}{\text{molar volume}}$$

where the volume is in cubic decimetres (dm^3) and the molar volume is $24 \text{ dm}^3/\text{mol}$.




Reactions involving gases

For reactions in which gases are produced, the calculation of product volume is similar to those we have seen already.

Worked example 6.8

If 8 g of sulfur are burnt, what volume of SO_2 is produced?


First consider the reaction of sulfur burning in oxygen.




We have:

$$\begin{aligned}\text{number of moles of sulfur burnt} &= \frac{8 \text{ g}}{32 \text{ g/mol}} \\ &= 0.25 \text{ mol}\end{aligned}$$

From the equation:




Therefore:



So, from the above rule:

$$\text{number of moles} = \frac{\text{volume}}{\text{molar volume}}$$



$$0.25 \text{ mol} = \frac{\text{volume}}{24 \text{ dm}^3/\text{mol}}$$

$$\begin{aligned}\text{volume of sulfur dioxide} &= 0.25 \times 24 \text{ dm}^3 \\ &= 6 \text{ dm}^3 \text{ at r.t.p.}\end{aligned}$$

The approach used is an adaptation of the 'footbridge' method used earlier for calculations involving solids. It is shown in Figure 6.15.

Some important reactions involve only gases. For such reactions, the calculations of expected yield are simplified by the fact that the value for molar volume applies to any gas.

Substance	Molar mass / g/mol	Molar volume / dm ³ /mol	Number of particles
hydrogen (H ₂)	2	24	6.02 × 10 ²³ hydrogen molecules
oxygen (O ₂)	32	24	6.02 × 10 ²³ oxygen molecules
carbon dioxide (CO ₂)	44	24	6.02 × 10 ²³ carbon dioxide molecules
ethane (C ₂ H ₆)	30	24	6.02 × 10 ²³ ethane molecules

Table 6.7 The molar mass and molar volume of various gases.






Figure 6.15 An outline of the 'footbridge' method for calculations involving gases.

For example:



The volumes of the gases involved are in the same ratio as the number of moles given by the equation:



So, if we react 20 cm³ of hydrogen with sufficient chlorine, it will produce 40 cm³ of hydrogen chloride gas.

6.5 Moles and solution chemistry

Colourful tricks can be played with chemical substances. A simple reaction can produce a 'water into wine' colour change – when two colourless solutions mixed together produce a wine-coloured mixture. These reactions all take place in solution, as do many others. The usual solvent is water. When setting up such reactions, we normally measure out the solutions by volume. To know how much of the reactants we are actually mixing, we need to know the **concentrations** of the solutions.

The concentration of solutions

When a chemical substance (the **solute**) is dissolved in a volume of **solvent**, we can measure the 'quantity' of solute in two ways. We can measure either its **mass** (in grams) or its **amount** (in moles). The final volume of the **solution** is normally measured in cubic decimetres, dm³ (1 dm³ = 1 litre or 1000 cm³). When we measure the mass of the solute in grams, it is the **mass concentration** that we obtain, in grams per cubic decimetre of solution (g/dm³).

But it is more useful to measure the amount in moles, in which case we get the **molar concentration** in moles per cubic decimetre of solution (mol/dm³):

$$\text{concentration} = \frac{\text{amount of solute}}{\text{volume of solution}}$$

- ◆ The **mass concentration** of a solution is measured in grams per cubic decimetre (g/dm³).
- ◆ The **molar concentration** of a solution is measured in moles per cubic decimetre (mol/dm³).
- ◆ When 1 mol of a substance is dissolved in water and the solution is made up to 1 dm³ (1000 cm³), a solution with a concentration of 1 mol/dm³ is produced.

For example, a 1 mol/dm³ solution of sodium chloride contains 58.5 g of NaCl (1 mol) dissolved in water and made up to a final volume of 1000 cm³. Figure 6.16 shows how the units are expressed for solutions of differing concentrations. It also shows how solutions of the same final concentration can be made up in different ways.





Figure 6.16 Making copper(II) sulfate solutions of different concentrations.

Calculations using solution concentrations

The following equation is useful when working out the number of moles present in a particular solution:

$$\text{number of moles in solution} = \text{molar concentration} \times \text{volume of solution (in dm}^3\text{)}$$


This equation can be represented by this triangle:



In practice, however, we are usually dealing with solution volumes in cubic centimetres (cm^3). The equation is therefore usefully adapted to:

$$\text{number of moles in solution} = \frac{\text{concentration}}{1000} \times \text{volume of solution (in cm}^3\text{)}$$

where concentration is in moles per cubic decimetre, but volume is in cubic centimetres.



For example, how many moles of sugar are there in 500 cm^3 of a 3.0 mol/dm^3 sugar solution?

We get:

$$\text{number of moles} = \frac{3.0}{1000} \times 500 = 1.5 \text{ mol}$$

In practice, a chemist still has to weigh out a substance in grams. So questions and experiments may also involve converting between moles and grams. We shall look at an example.

Worked example 6.9

Calculate the concentration of a solution of sodium hydroxide, NaOH , that contains 10 g of NaOH in a final volume of 250 cm^3 .

- ◆ Step 1: Find out how many moles of NaOH are present:

$$\text{relative formula mass of NaOH} = 23 + 16 + 1 = 40$$

$$\text{number of moles of NaOH} = \frac{10}{40} = 0.25 \text{ mol}$$

- ◆ Step 2: Find the concentration:

$$\text{number of moles} = \frac{\text{concentration}}{1000} \times \text{volume (in cm}^3\text{)}$$

$$0.25 = \frac{\text{concentration}}{1000} \times 250$$

$$\text{concentration} = \frac{0.25 \times 1000}{250} = 1 \text{ mol/dm}^3$$

Acid-base titrations

The concentration of an unknown acid solution can be found if it is reacted with a standard solution of an alkali. A **standard solution** is one that has been carefully made up so that its concentration is known precisely. The reaction is carried out in a carefully controlled way. The volumes are measured accurately using a pipette and a burette. Just sufficient acid is added to the alkali to neutralise the alkali. This end-point is found using an indicator. The method is known as **titration**, and can be adapted to prepare a soluble salt. It is summarised in Figure 6.17.

We shall now look at an example of the type of calculation that can be carried out.

Worked example 6.10

A solution of hydrochloric acid is titrated against a standard sodium hydroxide solution. It is found that 20.0 cm^3 of acid neutralise 25.0 cm^3 of 0.10 mol/dm^3 NaOH solution. What is the concentration of the hydrochloric acid solution?

The calculation goes like this.


- ◆ **Step 1:** Use information about the standard solution. How many moles of alkali are in the flask?

We have

$$\begin{aligned}\text{number of moles of NaOH} &= \frac{\text{concentration}}{1000} \times \text{volume (in cm}^3\text{)} \\ &= \frac{0.10}{1000} \times 25 = 2.5 \times 10^{-3} \text{ mol}\end{aligned}$$

- ◆ **Step 2:** Use the chemical equation. How many moles of acid are used?

The equation is:



1 mol 1 mol

1 mol of NaOH neutralises 1 mol of HCl and so:

$2.5 \times 10^{-3} \text{ mol}$ of NaOH neutralise
 $2.5 \times 10^{-3} \text{ mol}$ of HCl

- ◆ **Step 3:** Use the titration value. What is the concentration of the acid?

The acid solution contains $2.5 \times 10^{-3} \text{ mol}$ in 20.0 cm^3 .

So:

number of moles

$$\begin{aligned}&= \frac{\text{concentration}}{1000} \times \text{volume (in cm}^3\text{)} \\ 2.5 \times 10^{-3} &= \frac{\text{concentration}}{1000} \times 20.0\end{aligned}$$

$$\begin{aligned}\text{concentration of acid} &= \frac{2.5 \times 10^{-3} \times 1000}{20} \\ &= 0.125 \text{ mol/dm}^3\end{aligned}$$

The method uses a further variation of the 'footbridge' approach to link the reactants and products (Figure 6.18).

Study tip

Calculation questions are often structured for you, so make sure you work your way through the question as far as you can go.

Always show your working when responding to a calculation question, because you may still get credit even if you make a mistake in the final stage – it will also help you work out where you went wrong.

Activity 6.4

Determining the concentration of a hydrochloric acid solution

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

In this activity, a hydrochloric acid solution of unknown concentration is standardised against a solution of sodium carbonate of known concentration. This is done using the titration method.

A worksheet is included on the CD-ROM. Details of a microscale version of the experiment are given in the Notes on Activities for teachers/technicians.




Figure 6.17 Summary of the titration method.




Figure 6.18 A summary of the different ways in which a balanced equation acts as a 'footbridge' in calculations.

Concentration and solubility data

When working with solutions, it is most useful to express concentration in moles per cubic decimetre (mol/dm^3). However, there is one situation where concentration is measured in different units. That is when we are discussing solubility.

In general, water-soluble solids dissolve more with increasing temperature. The **solubility** of a particular solid in water can be measured over a range of temperatures up to 100°C . The **maximum** mass of solid that will dissolve in 100 g of water is found at each temperature. Such a solution is said to be **saturated** at that temperature – it is a **saturated solution**. The values at each temperature can then be plotted to give a **solubility curve**. Such curves can be useful in comparing the solubilities of different salts and for predicting the yields produced on crystallisation.

Activity 6.5 Interpreting data on the solubility of solids and gases in water

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity involves the plotting and interpretation of data in the different units used to express solubility for both solids and gases.

The practical side of the activity involves a simple experiment on how the solubility of carbon dioxide changes with temperature.

A worksheet is included on the CD-ROM.

Questions

6.8 Calculate the number of moles of gas there are in the following:

- a** 480 cm³ of argon
- b** 48 dm³ of carbon dioxide
- c** 1689 cm³ of oxygen.

6.9 Calculate the volume in cm³ of the following at r.t.p.

- a** 1.5 moles of nitrogen
- b** 0.06 moles of ammonia
- c** 0.5 moles of chlorine.

6.10 Calculate the concentration (in mol/dm³) of the following solutions.

- a** 1.0 mol of sodium hydroxide is dissolved in distilled water to make 500 cm³ of solution.
- b** 0.2 mol of sodium chloride is dissolved in distilled water to make 1000 cm³ of solution.
- c** 0.1 mol of sodium nitrate is dissolved in distilled water to make 100 cm³ of solution.
- d** 0.8 g of solid sodium hydroxide is dissolved in distilled water to a final volume of 1 dm³.

(Relative atomic masses: H = 1, O = 16, Na = 23, N = 14, Cl = 35.5)


Summary

You should know:

- ◆ how it has been possible to find the masses of the atoms of the elements, including isotopes
- ◆ that these atomic masses are measured relative to a standard – a carbon-12 atom is fixed as having a mass of 12 exactly
- ◆ how the relative atomic mass is the average mass of an atom of an element
- ◆ about calculating the relative formula mass as the sum of all the atomic masses in a formula
- ◆ how to calculate the percentage by mass of an element in a compound using the relative formula mass
- S** ◆ that the mole is the unit which contains Avogadro's number of constituent particles of a substance and is used to express the amount of a substance taking part in a reaction
- S** ◆ about calculating the empirical formula of a compound using the idea of the mole
- S** ◆ how the balanced chemical equation for a reaction can be used to calculate the reacting masses of substances involved and the amount of product formed
- S** ◆ that one mole of any gas has a volume of 24 dm³ at room temperature and pressure (r.t.p.)
- S** ◆ how the concentration of a solution can be expressed in moles per cubic decimetre (mol/dm³) and that these values are useful in calculating the results of titration experiments.

End-of-chapter questions

- 1** When working out the masses of solids that react with each other, we need to know their relative formula masses. When working out the quantities of gases in a reaction, this is not necessary. Explain why.
- 2** The equation below shows how the fertiliser ammonium sulfate is manufactured.




- a** Write a word equation for this reaction.
- b** How many hydrogen atoms are there in the formula for ammonium sulfate?


[1]
[1]

- c What is the formula mass of sulfuric acid? [1]
- d In this reaction, 17 g of ammonia produce 33 g of ammonium sulfate.
What mass would 3.4 g of ammonia produce? [2]

- S** 3 The formulae of insoluble compounds can be found by precipitation reactions.
To 12.0 cm³ of an aqueous solution of the nitrate of metal T was added 2.0 cm³ of aqueous sodium phosphate, Na₃PO₄. The concentration of both solutions was 1.0 mol/dm³. When the precipitate had settled, its height was measured.




The experiment was repeated using different volumes of the phosphate solution. The results are shown on the following graph.



What is the formula of the phosphate of metal T? Give your reasoning. [3]

[Cambridge IGCSE® Chemistry 0620/3, Question 5(b), June 2009]


- 4 Quantities of chemicals, expressed in moles, can be used to find the formula of a compound, to establish an equation and to determine reacting masses.
- a A compound contains 72% magnesium and 28% nitrogen. What is its empirical formula? [2]
- b A compound contains only aluminium and carbon. 0.03 moles of this compound reacted with excess water to form 0.12 moles of Al(OH)₃ and 0.09 moles of CH₄.
Write a balanced equation for this reaction. [2]
- c 0.07 moles of silicon reacts with 25 g of bromine.



- i Which one is the limiting reagent? Explain your choice. [3]
- ii How many moles of SiBr₄ are formed? [1]

[Cambridge IGCSE® Chemistry 0620/31, Question 9, June 2009]


- 5 A 5.00 g sample of impure lead(II) nitrate was heated. The volume of oxygen formed was 0.16 dm³ measured at r.t.p. The impurities did not decompose. Calculate the percentage of lead(II) nitrate in the sample.



- Number of moles of O_2 formed =
 Number of moles of $Pb(NO_3)_2$ in the sample =
 Mass of one mole of $Pb(NO_3)_2$ = 331 g
 Mass of lead(II) nitrate in the sample = g
 Percentage of lead(II) nitrate in sample = [4]

[Cambridge IGCSE® Chemistry 0620/32, Question 8(c), June 2010]

- 6 6.0 g of cobalt(II) carbonate was added to 40 cm³ of hydrochloric acid, concentration 2.0 mol/dm³. Calculate the maximum yield of cobalt(II) chloride-6-water and show that the cobalt(II) carbonate was in excess.



Maximum yield


- Number of moles of HCl used =
 Number of moles of $CoCl_2$ formed =
 Number of moles of $CoCl_2 \cdot 6H_2O$ formed =
 Mass of one mole of $CoCl_2 \cdot 6H_2O$ = 238 g
 Maximum yield of $CoCl_2 \cdot 6H_2O$ = g [4]

To show that cobalt(II) carbonate is in excess

- Number of moles of HCl used = (use value from above)
 Mass of one mole of $CoCO_3$ = 119 g
 Number of moles of $CoCO_3$ in 6.0 g of cobalt(II) carbonate = [1]
 Explain why cobalt(II) carbonate is in excess. [1]

[Cambridge IGCSE® Chemistry 0620/31, Question 8(b), November 2010]

- 7 Hydrocarbons are compounds that contain only carbon and hydrogen. 20 cm³ of a gaseous hydrocarbon was burned in 120 cm³ of oxygen, which is in excess. After cooling, the volume of the gases remaining was 90 cm³. Aqueous sodium hydroxide was added to remove carbon dioxide, 30 cm³ of oxygen remained. All volumes were measured at r.t.p.
- Explain why it is essential to use excess oxygen. [2]
 - Carbon dioxide is slightly soluble in water. Why does it dissolve readily in the alkali, sodium hydroxide? [1]
 - Calculate the following:
 volume of gaseous hydrocarbon = cm³
 volume of oxygen used = cm³
 volume of carbon dioxide formed = cm³ [2]
 - Use the above volume ratio to find the mole ratio in the equation below and hence find the formula of the hydrocarbon.



- hydrocarbon formula = [2]

[Cambridge IGCSE® Chemistry 0620/32, Question 8(a), June 2011]

7

How far? How fast?

In this chapter, you will find out about:

- ◆ exothermic and endothermic reactions
- ◆ experiments on heat of reaction
- S** ◆ breaking bonds in a reaction as an endothermic process
- S** ◆ making bonds as an exothermic process
- ◆ heat of reaction for burning fuels
- ◆ factors affecting the rate of reaction
 - surface area of reactants
 - reactant concentration
 - temperature
- ◆ the role of catalysts in a reaction
- ◆ experiments on rates of reaction
- ◆ enzymes as biological catalysts
- S** ◆ collision theory and activation energy
- S** ◆ photochemical reactions
 - photosynthesis
 - photography using silver salts
- ◆ some reactions are reversible
- S** ◆ chemical equilibrium
- S** ◆ the Haber process as an industrially important reversible reaction
 - the effect of changing conditions.

Crucial reactions!

There are possibly quite a few chemical reactions that could be described as absolutely crucial to the way we live our life in modern times. One candidate would be the combustion of fuel in a car engine. Such a reaction explosively generates energy. It also illustrates certain key features of how reactions happen in general:

- ◆ the importance of activation energy – the spark that starts the reaction
- ◆ the significance of concentration as the piston compresses the gases before ignition
- ◆ the energy given out by the reaction that turns the engine crankshaft.


The reaction is that of the hydrocarbons in petrol burning with the oxygen in the air as they are compressed by the movement of the piston (Figure 7.1). The gases are ignited by the spark plug. The explosion drives the piston down and that movement is transmitted to the wheels of the car. The exhaust gases are ejected through the exhaust valve.

The reaction is strongly exothermic and the exhaust gases are predominantly carbon dioxide



Figure 7.1 Computer graphic of the explosion within the cylinder of a petrol engine as the piston compresses the gases.

and water vapour. The word equation for one of the reactions taking place is:



Similar reactions take place inside a diesel engine but without the need for a spark plug. The operating temperature of a diesel engine is higher and the compression itself increases the concentration of the fuel mixture enough to cause the reaction to take place.

It is reactions such as this that have fuelled our modern energy economy based on fossil fuels. Finding alternative energy sources while maintaining our way of living is one of the major challenges of our time.


7.1 Energy changes in chemical reactions

Some chemical reactions are capable of releasing vast amounts of energy. For example, at the end of the Gulf War in 1991, oil and gas fires in the oilfields were left burning out of control. The heat given out was sufficient to turn the sand around the burning wells into glass. Forest fires can rage impressively, producing overpowering waves of heat (Figure 7.2). Bringing such fires under control requires great expertise, and a great deal of courage!

Yet we use similar reactions, under control, to provide heat for the home and for industry. Natural gas, which is mainly methane, is burnt under controlled conditions to produce heat for cooking in millions of homes (Figure 7.3).

The reaction between methane and oxygen

Hydrocarbon molecules contain only the elements carbon and hydrogen (see page 254). Methane is the simplest hydrocarbon molecule. When it burns, it reacts with oxygen. The products are carbon dioxide and water vapour:



During this reaction, as with all others, bonds are first broken and then new bonds are made (Figure 7.4, overleaf). In methane molecules, carbon atoms are

covalently bonded to hydrogen atoms. In oxygen gas, the atoms are held together in diatomic molecules. During the reaction, all these bonds must be broken. Chemical bonds are forces of attraction between atoms or ions. To break these bonds requires energy; energy must be taken in to pull the atoms apart.

Breaking chemical bonds takes in energy from the surroundings. This is an **endothermic process**.

New bonds are then formed: between carbon and oxygen to make carbon dioxide, and between hydrogen and oxygen to form water. Forming these bonds gives out energy.

Making chemical bonds gives out energy to the surroundings. This is an **exothermic process**.

When methane reacts with oxygen, the total energy given out is greater than the total energy taken in. So, overall, this reaction gives out energy – it is an exothermic reaction. The energy is released as heat.

The overall change in energy for this exothermic reaction can be shown in an **energy level diagram** (or energy profile) (Figure 7.5, overleaf). In this reaction, energy is given out because the bonds in the products (CO_2 and H_2O) are stronger than those in the reactants



Figure 7.2 A forest fire.




Figure 7.3 A lighted gas ring on a cooker.




Figure 7.4 The burning of methane first involves the breaking of bonds in the reactants. This is followed by the formation of the new bonds of the products.

(CH_4 and O_2). This means that the products are more stable than the reactants.

Some bonds are stronger than others. They require more energy to break them, but they give out more energy when they are formed.

Generally, the combustion reactions of fossil fuels such as oil and gas are exothermic. Indeed, the major characteristics that make these fuels so useful are that:

- ♦ they are easy to ignite and burn
- ♦ they are capable of releasing large amounts of energy as heat.




Figure 7.5 An energy profile for the burning of methane. The products are more stable than the reactants. Energy is given out to the surroundings. This is an exothermic reaction.

Other reactions are less obviously exothermic, but may have new and unusual uses. For example, the rusting reaction of iron generates heat for several hours and is used in pocket hand-warmers for expeditions to cold regions. Similar hand-warmers can be made using the heat given out by crystallisation of a solid from a super-saturated solution (Figure 7.6).


The reaction between nitrogen and oxygen

Endothermic reactions are far less common than exothermic ones. Here, energy is absorbed from the surroundings. The reaction between nitrogen and oxygen is endothermic. It is one of the reactions



Figure 7.6 This hand-warmer depends on the heat given out when the solid crystallises out from the super-saturated solution in the warmer.

that take place when fuel is burnt in car engines. The equation for this reaction is:



Here the bonding in the products is weaker than in the reactants. Overall, energy is taken in by the reaction (Figure 7.7).

Photosynthesis in green plants and the thermal decomposition of limestone are other important examples of endothermic reactions. They will be studied later in this chapter on pages 193 and 242.

Heat of reaction

The energy change in going from reactants to products in a chemical reaction is known as the **heat of reaction** (Figures 7.5 and 7.7). It is given the symbol ΔH (pronounced 'delta aitch' – the symbol Δ means 'change in'). The energy given out or taken in is measured in kilojoules (kJ); 1 kilojoule (1 kJ) = 1000 joules (1000 J). It is usually




Figure 7.7 An energy profile for the reaction between nitrogen and oxygen. The products are less stable than the reactants. Energy is taken in from the surroundings. This is an endothermic reaction.

calculated per mole of a specific reactant or product (kJ/mol).

The starting point for the calculation is the reacting mixture. If a reaction gives out heat to the surroundings, the mixture has lost energy. It is an exothermic reaction. In an EXothermic reaction, heat EXits the reaction mixture. An exothermic reaction has a negative value of ΔH .

If a reaction takes in heat from the surroundings, the mixture has gained energy. It is an endothermic reaction. In an ENdothermic reaction, heat ENters the reaction mixture. An endothermic reaction has a positive value of ΔH .

This is what we know about **heat of reaction**:


- ♦ for exothermic reactions, heat energy is given out (exits) and ΔH is **negative**
- ♦ for endothermic reactions, heat energy is taken in (enters) and ΔH is **positive**.

Study tip

When you try to remember these particular terms, concentrate on the first letters of the words involved:

EXothermic means that heat EXits the reaction; ENdothermic means that heat ENters the reaction.

These ideas fit with the direction of the arrows shown in the energy diagrams (Figures 7.5 and 7.7). The heat of reaction for the burning of methane is high. This makes it a useful fuel:



Activity 7.1

Exothermic and endothermic reactions


Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

 **Wear eye protection.**

There is always an overall energy change in any chemical reaction. This activity investigates whether heat is taken in (endothermic) or given out (exothermic) during three different reactions.

- 1 Prepare a results table like the one shown on the right.
- 2 Put 50 cm³ of water into a polystyrene cup. Measure its temperature and record it in the results table.
- 3 Add three spatula measures of anhydrous copper(II) sulfate to the water. Stir with a thermometer. Keep checking the temperature.
- 4 In your table, record the maximum temperature reached. This is the temperature when the reaction has just finished. Record your other observations too (experiment 1).
- 5 Allow the solution from step 4 to cool down. Then add three spatula measures of zinc powder to that solution. Stir the mixture. Note the maximum temperature and record your observations in the table, as before (experiment 2).



- 6 Empty and rinse the polystyrene cup and put 50 cm³ of water into it. Then add three spatula measures of sherbet. Record the temperature as before (experiment 3) together with your observations.

Results table

Experiment	Temperature / °C			Observations	Exothermic or endothermic
	Before	After	Change		
1					
2					
3					

A worksheet is included on the CD-ROM.

Details of a related teacher demonstration that results in the freezing of a beaker to a wooden board are given in the Notes on Activities for teachers/technicians.

Questions

- A1 Which of these reactions are exothermic and which are endothermic?
- A2 Why is an expanded polystyrene cup used for these reactions?
- A3 How would the temperature change be affected if the amount of water used was halved from 50 cm³ to 25 cm³?


Bond	Bond energy / kJ/mol	Comment
H—H	436	in hydrogen
C—H	435	average of four bonds in methane
O—H	464	in water
C—C	347	average of many compounds
O=O	498	in oxygen
C=O	803	in carbon dioxide
N≡N	945	in nitrogen

Table 7.1 The bond energies for some covalent bonds.

Making and breaking bonds

Experiments have been carried out to find out how much energy is needed to break various covalent bonds in compounds. The average value obtained for a particular bond is known as the **bond energy** (Table 7.1). It is a measure of the strength of the bond.

We can use these values to find the heat of reaction for the burning of methane. The equation is:



The left-hand side involves **bond breaking** and needs energy:

four C—H bonds $4 \times 435 = 1740 \text{ kJ/mol}$
 two O=O bonds $2 \times 498 = 996 \text{ kJ/mol}$
 total energy needed $= 2736 \text{ kJ/mol}$

The right-hand side involves **bond making** and gives out energy:

two C=O bonds $2 \times 803 = 1606 \text{ kJ/mol}$
 four O—H bonds $4 \times 464 = 1856 \text{ kJ/mol}$
 total energy given out $= 3462 \text{ kJ/mol}$

The heat of reaction, ΔH , is the energy change on going from reactants to products. So for the burning of methane:

$$\begin{aligned} \text{heat of reaction} &= \text{energy difference} \\ \Delta H &= (\text{energy needed to break bonds}) \\ &\quad - (\text{energy given out when bonds form}) \end{aligned}$$

$$2736 - 3462 = -726$$

$$\Delta H = 2736 - 3462$$

$$\Delta H = -726 \text{ kJ/mol}$$

Study tip

It is useful to remember that combustion reactions are always exothermic.

Experimental thermochemistry

Heat of combustion

The **heat of combustion** is the energy change of a reaction when a substance is burnt. For liquid fuels such as ethanol, it can be found using a metal calorimeter and a spirit burner (Figure 7.8).

The experiment involves heating a known volume of water with the flame from burning ethanol. The temperature rise of the water is measured. From this, the heat energy given to the water by burning a known amount of ethanol can be worked out. There is a method for working out a precise value for the heat of combustion of a fuel from this type of experiment. However, that is currently beyond the requirements of the syllabus.

This type of experiment can be useful, though, for comparing different fuels to see which would give the most heat to warm a known amount of water. The amount of liquid fuel put into the spirit burner would need to be controlled. The method could also be adapted to compare the heat produced by the same mass of different solid fuels.




Figure 7.8 Apparatus for finding the heat of combustion of ethanol.

Activity 7.2

Comparing the energy from different fuels

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity compares the energy given out by several liquid fuels by measuring the mass of each fuel that will heat a given volume of water to a given temperature.

A worksheet is included on the CD-ROM.

Heat of neutralisation

Polystyrene is a good heat insulator and is used to make disposable cups for warm drinks. These cups can be used as simple calorimeters to measure the temperature rise of exothermic reactions between solutions (Figure 7.9). The solutions are mixed in a polystyrene



Figure 7.9 Polystyrene cups can be used as 'calorimeters' because of their good heat insulation properties.

cup and the initial temperature is measured quickly. The mixture is then stirred well with the thermometer. The temperature is checked frequently during the reaction, and the maximum temperature is recorded.

This equipment can be used to measure the heat energy given out during the neutralisation reactions between acids and alkalis. This energy change is known as the **heat of neutralisation**. By using solutions whose concentrations are known, it can be calculated for a particular combination of acid and alkali. For a strong acid reacting with a strong alkali, this value is 57 kilojoules of heat given out per mole of water produced; that is -57 kJ/mol .

The method can also be adapted for reactions involving

- ♦ a solid base and an acid
- ♦ a solid carbonate and an acid, and
- ♦ displacement reactions between a metal and a solution of a salt of a less reactive metal.

Activity 7.3

Energy changes in metal displacement reactions

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

A more reactive metal will displace a less reactive one from solutions of its salts.

In this activity, you will plan an experiment to see which combination of metal and solution provided generates the most heat energy by observing the maximum temperature rise in each case. The order of heat evolved for the different combinations can be compared with the voltages generated by electrochemical cells involving the metals.

A worksheet is included on the CD-ROM.

Details of a data-logging version of this experiment using a temperature sensor are given in the Notes on Activities for teachers/technicians.

S Activation energy

Although the vast majority of reactions are exothermic, only a few are totally spontaneous and begin without help at normal temperatures; for example, sodium or potassium reacting with water. More usually, energy is required to start the reaction. When fuels are burnt, for example, energy is needed to ignite them (Figure 7.10). This energy may come from a spark, a match or sunlight. It is called the **activation energy** (given the symbol E_A). It is required because initially some bonds must be broken before any reaction can take place. Sufficient atoms or fragments of molecules must be freed for the new bonds to begin forming. Once started, the energy released as new bonds are formed causes the reaction to continue.

Study tip

For a chemical reaction to happen, some bonds in the reactants must first break before any new bonds can be formed. That is why all reactions have an **activation energy**.

All reactions require some activation energy. For the reaction of sodium or potassium with water, the activation energy is low, and there is enough energy available from the surroundings at room temperature for the reaction to begin spontaneously. Other exothermic reactions have a higher activation energy; for example, the burning of magnesium can be started with heat from a Bunsen burner. Reactions can be thought of as the result of collisions between atoms, molecules or ions. In many of these collisions, the colliding particles do not have enough energy to react,





Figure 7.10 An energy profile for the burning of methane, showing the need for activation energy to start the reaction.

and just bounce apart, rather like 'dodgem cars'. A chemical reaction will only happen if the total energy of the colliding particles is greater than the required activation energy of the reaction.

Questions

- 7.1 Which type of reaction takes in heat from its surroundings?
- 7.2 Is bond breaking an endothermic or an exothermic process?
- 7.3 Why is a polystyrene cup useful for carrying out thermochemistry experiments with solutions?
- 7.4 Hydrogen peroxide decomposes to produce water and oxygen. The equation is:



Using the following values, calculate the heat change for the reaction and say whether it is exothermic or endothermic.

Bond energies:


H—H = 436 kJ/mol

O—O = 144 kJ/mol

O=O = 498 kJ/mol

O—H = 464 kJ/mol

- 7.5 Draw a reaction profile for the following reaction, which is exothermic.



7.2 Rates of reaction

On 7 May 1915, the British liner *Lusitania* was sunk off the south-west coast of Ireland (Figure 7.11). The liner was




Figure 7.11 The sinking of the *Lusitania*.

torpedoed by a German submarine and 1198 passengers lost their lives. The sinking was accompanied by a second explosion. This explosion gave possible support to the idea that the ship was carrying explosives to Britain for use in the war. The wreck of the *Lusitania* has now been investigated by divers. Evidence suggests that the second explosion was caused by coal dust exploding in the hold. If so, this is a dramatic example of explosive combustion.

This type of explosion can also occur with fine powders in flour mills (Figure 7.12), in mines when dangerous gases collect, and with dust. Dust particles have a large surface area in contact with the air. A simple spark can set off an explosive reaction. For example, powdered *Lycopodium* moss piled in a dish does not burn easily – but if it is sprayed across a Bunsen flame, it produces a spectacular reaction. Even metal powders can produce quite spectacular effects (Figure 7.13).

The same idea does have a more positive use. In some modern coal-fired power stations, powdered coal is burnt instead of the usual lumps of coal because it burns very efficiently.

Factors affecting the rate of reaction

Explosive reactions represent one end of the ‘spectrum’ of reaction rates. Other reactions, such as rusting, take place over much longer time periods. What factors influence the speed of a reaction? Experiments have been carried out to study a wide range of reactions, and there seem to be five major influences on **reaction rate**:

- ◆ the **surface area** of any solid reactants
- ◆ the **concentration** of the reactants
- ◆ the **temperature** at which the reaction is carried out
- ◆ the use of a **catalyst**
- ◆ the influence of **light** on some reactions.

The surface area of solid reactants

Where one or more of the reactants is a solid, the more finely powdered (or finely divided) the solid(s) are, the greater is the rate of reaction. This is because reactions involving solids take place on the surface of the solids. A solid has a much larger surface area when it is powdered than when it is in larger pieces.

For reactions involving two solids, grinding the reactants means that they can be better mixed. The mixed powders are then in greater contact with each other and are more likely to react.

If a solid is being reacted with a liquid (or solution), the greater the surface area, the more the solid is exposed



Figure 7.12 A fireball produced by dropping powdered flour into a flame.



Figure 7.13 Iron dust ignited in a Bunsen flame.






Figure 7.14 Apparatus for experiments A and B: the reaction of marble chips with dilute hydrochloric acid. The loss of carbon dioxide from the flask produces a loss in mass. This is detected by the balance.

to the liquid. A good demonstration of this is the reaction between limestone or marble chips (two forms of calcium carbonate) and dilute hydrochloric acid:



The experiment can be done as shown in Figure 7.14. Using this arrangement, we can compare two samples of marble chips, one sample (B) being in smaller pieces than the other (A). The experiment is carried out twice, once with sample A and once with sample B. In each experiment the mass of sample used is the same, and the same volume and concentration of hydrochloric acid is used. The flask sits on the balance during the reaction. A loose cotton wool plug prevents liquid spraying out of the flask but allows the carbon dioxide gas to escape into the air. This means that the flask will lose mass during the reaction. Balance readings are taken at regular time intervals and the loss in mass can be worked out. When the loss in mass is plotted against time, curves such as those in Figure 7.15 (overleaf) are obtained.

There are several important points about the graph.

- (i) The reaction is fastest at the start. This is shown by the steepness of the curves over the first few minutes. Curve B is steeper than curve A. This means that gas (CO_2) is being produced faster with

sample B. The sample with smaller chips, with a greater surface area, reacts faster. Beyond this part of the graph, both reactions slow down as the reactants are used up (Figure 7.16, overleaf).

- (ii) The total volume of gas released is the same in both experiments. The mass of CaCO_3 and the amount of acid are the same in both cases. Both curves flatten out at the same final volume. Sample B reaches the horizontal part of the curve (the plateau) first.

These results show that:

the rate (speed) of a reaction increases when the surface area of a solid reactant is increased.

Study tip

It is important that you understand how to interpret the different regions of the graphs obtained in this area of study.

You should also be able to work out a value for the rate of reaction from these graphs.

The concentration of reactants

Reactions that produce gases are also very useful in studying the effect of solution concentration on the reaction rate. The reaction between marble chips and acid could be adapted for this. Another reaction




Figure 7.15 The graph shows the loss in mass against time for experiments A and B. The reaction is faster if the marble chips are broken into smaller pieces (curve B).

that can be used to study this is the reaction between magnesium and excess dilute hydrochloric acid:





Figure 7.16 A chemical reaction is fastest at the start. It slows down as the reactants are used up.

The apparatus is shown in Figure 7.17. As in the previous experiment, we will compare two different experiments, which we will call C and D. The acid in experiment C is twice as concentrated as in experiment D. Apart from changing the concentration of the acid, everything else must stay the same. So the volume of acid, the temperature and the mass of magnesium used must be the same in both experiments. The gas produced in this reaction is hydrogen and is collected in a gas syringe. The volume of gas produced is measured at frequent time intervals. We can then plot a graph of volume of gas collected against time, like that in Figure 7.18.




Figure 7.17 Apparatus for experiments C and D: the reaction of magnesium with dilute hydrochloric acid. The hydrogen given off can be collected and measured in a gas syringe.

Again the graph shows some important points.

- (i) The curve for experiment C is steeper than for D. This shows clearly that reaction C, using more concentrated acid, is faster than reaction D.
- (ii) The curve for experiment C starts off twice as steeply as for D. This means that the reaction in C is twice as fast as in experiment D initially. So doubling the concentration of the acid doubles the rate of reaction.
- (iii) The total volume of hydrogen produced is the same in both experiments. Both reactions produce the same volume of hydrogen, although experiment C produces it faster.

These results show that:

the rate (speed) of a reaction increases when the concentration of a reactant in solution is increased.

Temperature

A reaction can be made to go faster or slower by changing the temperature of the reactants. Some food is stored in a refrigerator, because the food 'keeps better'. The rate of decay and oxidation is slower at lower temperatures.

The previously described experiments (A/B or C/D) could be altered to study the effect of temperature on the rate of production of gas.




Figure 7.18 The graph shows the volume of hydrogen against time for experiments C and D. The reaction is faster if the acid solution is more concentrated (curve C).

Activity 7.4


The factors affecting reaction rate

Skills

- AO3.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- AO3.2 Plan experiments and investigations
- AO3.3 Make and record observations, measurements and estimates
- AO3.4 Interpret and evaluate experimental observations and data
- AO3.5 Evaluate methods and suggest possible improvements

 Wear eye protection. Sulfuric acid is corrosive.


You must plan an investigation to discover how one chosen factor affects the rate of a chemical reaction.



- 1 Measure 10 cm³ of 2 mol/dm³ sulfuric acid into a boiling tube.
- 2 Add a 5 cm strip of magnesium ribbon and start a stopclock.
- 3 When the reaction stops, record the time taken.
- 4 List the factors that could speed up or slow down this reaction.
- 5 Choose one of these factors and plan an investigation to discover how it affects the rate.
- 6 Your investigation should produce sufficient results to enable you to draw a graph.

A worksheet is included on the CD-ROM. The Notes on Activities for teachers/technicians contain details of how this experiment can be used as an assessment of skills AO3.2 and AO3.5.

An alternative approach is to use the reaction between sodium thiosulfate and hydrochloric acid. In this case (which we shall call experiment E), the formation of a precipitate is used to measure the rate of reaction.



The experiment is shown in Figure 7.19. A cross is marked on a piece of paper. A flask containing sodium thiosulfate solution is placed on top of the paper. Hydrochloric acid is added quickly. The yellow precipitate of sulfur produced is very fine and stays suspended in the liquid. With time, as more and more sulfur is formed, the liquid becomes cloudier and more difficult to see through. The time taken for the cross to 'disappear' is measured. The faster the reaction, the shorter the length of time during which the cross is visible. The experiment is carried out several times with solutions pre-warmed to different temperatures. The solutions and conditions of the experiment must remain the same; only the temperature is altered. A graph can then be plotted of the time taken for the cross to disappear against temperature, like that shown in Figure 7.20.

The graph shows two important points.

- (i) The cross disappears more quickly at higher temperatures. The shorter the time needed for the cross to disappear, the faster the reaction.
- (ii) The curve is not a straight line.

These results show that:
the rate of a reaction increases when the
temperature of the reaction mixture is increased.

To be more precise, the speed of the reaction is **inversely proportional** to the time taken for the reaction to finish:

$$\text{rate of reaction} \propto \frac{1}{\text{time}}$$

A graph of $1/\text{time}$ against temperature would show how the rate increases with a rise in temperature.

Study tip

It is important to realise in this experiment that the shorter the time taken for the cross to disappear, the faster the reaction has taken place.




Figure 7.19 Apparatus for experiment E: the reaction between hydrochloric acid and sodium thiosulfate. This can be studied by following the appearance of the precipitate. The cross drawn on the paper appears fainter with time. Time how long it takes for the cross to disappear.




Figure 7.20 The graph for experiment E. As the temperature is increased, the time taken for the cross to disappear is shortened. The reaction speeds up at higher temperature.

Activity 7.5

The effect of concentration on rate of reaction

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This microscale experiment investigates the effect of concentration on the rate of the reaction between sodium thiosulfate and dilute hydrochloric acid.

A worksheet is included on the CD-ROM.

Details of a scaled-up version of the experiment are given in the Notes on Activities for teachers/technicians.


Questions

- 7.6** What do we observe happen to the rate of a chemical reaction in response to the following?
- a** an increase in temperature
 - b** an increase in the surface area of a solid reactant
 - c** an increased concentration of a reacting solution
- 7.7** Why is perishable food kept in a refrigerator?
- 7.8** When is a chemical reaction at its fastest?
- 7.9** Why does the rate of a chemical reaction slow down at the end?

7.3 Catalysts

The decomposition of hydrogen peroxide

Hydrogen peroxide is a colourless liquid with the formula H_2O_2 . It is a very reactive oxidising agent. Hydrogen peroxide decomposes to form water and oxygen:



We can follow the rate of this reaction by collecting the oxygen in a gas syringe. The formation of oxygen is very slow at room temperature. However, the addition of 0.5 g of powdered manganese(IV) oxide (MnO_2) makes the reaction go much faster (we shall call this experiment F). The black powder does not disappear during the reaction (Figure 7.21, overleaf). Indeed, if the solid is filtered and dried at the end of the reaction, the same mass of powder remains. If the amount of MnO_2 powder added is doubled (experiment G), the rate of reaction increases (Figure 7.22, overleaf). If the powder is more finely divided (powdered), the reaction also speeds up. Both these results suggest that it is the surface of the manganese(IV) oxide powder that is important here. By increasing the surface area, the rate of reaction is increased. We say that manganese(IV) oxide is a **catalyst** for this reaction.




Figure 7.21 Apparatus for experiments F and G: the decomposition of hydrogen peroxide to water and oxygen. The decomposition is very slow at room temperature. **a** It can be speeded up by adding a catalyst, manganese(IV) oxide. **b** The catalyst is unchanged at the end, and can be separated from the water by filtration.




Figure 7.22 Increasing the amount of catalyst increases the rate of reaction. Here the amount of manganese(IV) oxide has been doubled in experiment G compared to F.

Key definition

catalyst – a substance that **increases** the rate of a chemical reaction. The catalyst remains **chemically unchanged** at the end of the reaction.

Many catalysts work by providing a surface on which other molecules or atoms can react. However, others work in more complex ways. Thus it is wrong to say that catalysts do not take part in the reaction: some do. But at the end of the reaction, there is the same amount of catalyst as at the beginning, and it is chemically unchanged.

Study tip

Remember to give a full definition of a catalyst. Include in your answer the fact that the catalyst itself remains unchanged at the end of the reaction.

Other examples of catalysts

Catalysts have been found for a wide range of reactions. They are useful because a **small** amount of catalyst can produce a **large** change in the rate of a reaction. Also, since they are unchanged at the end of a reaction, they can be re-used. Industrially, they are very important. Industrial chemists use catalysts to make everything from polythene and painkillers, to fertilisers and fabrics. If catalysts did not exist, many chemical processes would go very slowly and some reactions would need much higher temperatures and pressures to proceed at a reasonable rate. All these factors would make these processes more expensive, so that the product would cost much more. If it cost more than people wanted to pay for it, it would be uneconomic.

Table 7.2, shows some examples of industrial catalysts. You should notice that transition elements (see Chapter 8) or their compounds make particularly good catalysts.

Catalytic converters

One way to reduce the polluting effects of car exhaust fumes is to fit the car with a catalytic converter (Figure 7.23). In many countries these converters are a legal requirement. Car exhaust fumes contain gases such as carbon monoxide (CO), nitrogen monoxide (nitrogen(I) oxide, NO) and unburnt hydrocarbons (HC) from the fuel which cause pollution in the air. The catalytic converter converts these to less





Industrial process	Catalyst
ammonia manufacture (Haber process)	iron
sulfuric acid manufacture (Contact process)	vanadium(v) oxide
margarine production (hydrogenation of fats)	nickel
nitric acid manufacture (oxidation of ammonia)	platinum–rhodium
fermentation of sugars (alcoholic drinks industry)	enzymes (in yeast)
conversion of methanol to hydrocarbons	zeolite ZSM-5

Table 7.2 Some examples of industrial catalysts.



Figure 7.23 A catalytic converter can be fitted to a car exhaust system.

harmful products such as carbon dioxide (CO_2), nitrogen (N_2) and water (H_2O). Some of the reactions that occur are:



The catalytic converter therefore ‘removes’ polluting oxides and completes the oxidation of unburnt hydrocarbon fuel. It speeds up these reactions considerably by providing a ‘honeycombed’ surface on which the gases can react. The converter contains a thin coating of rhodium and platinum catalysts on a solid honeycomb surface. These catalysts have many tiny pores which provide a large surface area for the reactions.

Catalytic converters can only be used with unleaded petrol. The presence of lead would ‘poison’ the catalyst and stop it working. Other impurities do get deposited on the catalyst surface, so the converter eventually needs replacing after a number of years.

Study tip

The equations for the reactions taking place in the catalytic converter are quite difficult to remember but it will help you if you do remember that the reactions finish back at components that are present in normal air – carbon dioxide and nitrogen.

Biological catalysts (enzymes)

Living cells also produce catalysts. They are protein molecules called **enzymes** (Figure 7.24, overleaf). Many thousands of reactions happen in every kind of organism. Enzymes speed up these reactions. Each enzyme works only for a particular reaction. We say that it is **specific** for that reaction.

The general features of enzymes:

- ◆ Enzymes are **proteins**.
- ◆ They are very **specific** – each enzyme controls one reaction.
- ◆ They are generally **temperature-sensitive** – they are inactivated (denatured) by heat (most stop working above 45°C).
- ◆ They are sensitive to pH – most enzymes work best in neutral conditions around pH 7.

Enzymes are being used increasingly as catalysts in industry. Biological washing powders use enzymes to remove biological stains such as sweat, blood and




Figure 7.24 A computer image of an enzyme and the smaller molecule it is about to carry out a reaction with (the substrate).

food. The enzymes in these powders are those which break down proteins and fats. Because the enzymes are temperature-sensitive, these powders are used at a wash temperature of around 30–40 °C.

Surface catalysts and collision theory

Solid catalysts

Different chemical reactions need different catalysts. One broad group of catalysts works by adsorbing molecules on to a solid surface. This process of **adsorption** brings the molecules of reactants closer together. The process of adsorption is also thought to weaken the bonds in the reactant molecules. This makes them more likely to react. Some of the most important examples of industrial catalysts work in this way, for example iron in the **Haber process**, vanadium(v) oxide in the **Contact process**, and finely divided nickel where hydrogen is added to unsaturated hydrocarbons.

S Collision theory

The importance of surface area in reactions involving solids helps us understand how reactions take place. In these cases, reactions can only occur when particles




Figure 7.25 The effect of changing conditions on the frequency of collisions.

collide with the surface of a solid. If a solid is broken into smaller pieces, there is more surface exposed. This means there are more places where collisions can take place, and so there is more chance of a reaction taking place. Iron reacts more readily with oxygen if it is powdered (Figure 7.25a).

We can see how these ideas – sometimes referred to as the **collision theory** – apply in other situations. When solutions are more concentrated, the speed of a reaction is faster. A more concentrated solution means that there

are more reactant particles in a given volume. Collisions will occur more often. The more often they collide, the more chance the particles have of reacting. This means that the rate of a chemical reaction will increase if the concentration of the reactants is increased. A more concentrated acid reacts more vigorously with a piece of magnesium ribbon than a dilute one (Figure 7.25b).

For reactions involving gases, increasing the pressure has the same effect as increasing the concentration, so the rate of a reaction between gases increases with pressure (Figure 7.25c).

When the temperature is raised, a reaction takes place faster. At higher temperatures, the particles are moving faster. Again, this means that collisions will occur more often, giving more chance of reaction. Also, the particles have more energy at the higher temperature. This increases the chances that a collision will result in bonds in the reactants breaking and new bonds forming to make the products. If we look at the reaction between zinc and hydrochloric acid, we can see how the rate of reaction changes with changes in collision frequency (Figure 7.26).

When solutions are more concentrated, the speed of a reaction is faster. A more concentrated solution means that there are more reactant particles in a given volume. Collisions will occur more often. The more

often they collide, the more chance the particles have of reacting. This means that the rate of a chemical reaction will increase if the concentration of the reactants is increased (Figure 7.26b). When the temperature is raised, a reaction takes place faster. At higher temperatures, the particles are moving faster. Again, this means that collisions will occur more often, giving more chance of reaction. Also, the particles have more energy at the higher temperature. This increases the chances that a collision will result in bonds in the reactants breaking and new bonds forming to make the products (Figure 7.26c).

Study tip

When explaining the effects of concentration and temperature using the **collision theory**, remember that it is 'collision frequency' that is the key factor – don't talk vaguely about 'more collisions': it is the fact that there are **more frequent** collisions of the particles that is important.

A closer look at activation energy

Not every collision between particles in a reaction mixture produces a reaction. We have seen earlier that a certain amount of energy is needed to begin to break




Figure 7.26 The collision theory can be used to explain how various factors affect the rate of the reaction. Here we use the reaction between zinc and hydrochloric acid as an example.

S bonds. This minimum amount of energy is known as the **activation energy** of the reaction.

- ◆ Each reaction has its own different value of activation energy.
- ◆ When particles collide, they must have a combined energy greater than this activation energy, otherwise they will not react.
- ◆ Chemical reactions occur when the reactant particles collide with each other.

A catalyst increases the rate of reaction by reducing the amount of energy that is needed to break the bonds. This reduces the activation energy of the reaction and makes sure that more collisions are likely to give products. The rate of the reaction is therefore increased.

We can think of an 'analogy' for this. Suppose we are hiking in the Alps (Figure 7.27). We start on one side of a mountain and want to get to the other side. We **could** go right over the summit of the mountain. This would require us to be very energetic. What we might prefer to do would be to find an alternative route along a pass through the mountains. This would be less energetic. In our analogy, the starting point corresponds to the reactants and the

finishing point to the products. The route over the top of the mountain would be the uncatalysed path. The easier route through the pass would be a catalysed path.

? Questions

- 7.10** What is a catalyst?
- 7.11** What is an enzyme?
- 7.12** Which solid catalyst will speed up the decomposition of hydrogen peroxide?
- 7.13** What are the catalysts used in:
a the Haber process, and
b the Contact process?
- 7.14** What changes in physical conditions are enzymes particularly sensitive to?
- 7.15** Does the presence of a catalyst increase or decrease the activation energy for a reaction?
- 7.16** In terms of the collision theory, explain why the rate of a reaction increases with:
a an increase in temperature
b an increase in the surface area of a solid reactant
c an increased concentration of a reacting solution.




Figure 7.27 The barrier between reactant(s) and product(s) may be so high that it defeats all but the most energetic. The catalyst's route is an easy pass through the mountains.


S 7.4 Photochemical reactions

Photosynthesis

Heat is not the only form of energy that can break bonds and start chemical reactions. Some chemical reactions are affected by light energy. Life on this planet would be impossible without photochemical reactions.

Photosynthesis traps energy when sunlight falls on leaves containing the green pigment chlorophyll (Figure 7.28).

The reaction converts water and carbon dioxide into glucose and oxygen:



The glucose produced is used to make other sugars and starch. These are **carbohydrates**. It is estimated that the mass of carbon 'fixed' as carbohydrates is 2×10^{11} tonnes per year. Algae, some bacteria and marine microorganisms can also get their energy directly from sunlight by photosynthesis.

Photosynthesis is part of a global cycle of carbon atoms (page 2). It is counterbalanced in the natural world by the reaction known as **respiration**. Respiration is the reaction that takes place in biological cells when they use glucose molecules as a source of energy:






Figure 7.28 Green plants contain chlorophyll and take part in photosynthesis. This is a process that is crucial to the existence of life on Earth.


It has been estimated that, on average, all the carbon dioxide on Earth passes through the process of photosynthesis once every 300 years, and all the oxygen once every 2000 years. Every carbon atom in your body has been through the photosynthetic cycle many times. The energy stored directly by plant life through photosynthesis is called **biomass energy** and it provides us with important sources of food and warmth. As a result of heat and pressure over millions of years, biomass can be changed into fossil fuels. The energy stored in biomass and fossil fuels can be used to generate electricity, to manufacture clothing, to run cars and to pursue many other activities (Table 7.3).

Photography

People were aware that silver salts darken on exposure to light as long ago as the sixteenth century. The darkening is caused by the production of specks of silver metal. Precipitates of silver chloride (white) or silver bromide (cream) will darken if left to stand in sunlight for a few hours. For example:



The reaction is a redox reaction; bromide ions lose electrons (they are oxidised), and silver ions gain electrons (they are reduced):



This photochemical reaction, in which silver ions are converted to silver atoms, is used as the basis of both black-and-white and colour photography. The photographic film itself is simply a flexible plastic

Biomass	Fossil fuels
food	coal
biogas	oil
peat	natural gas
wood	
vegetable oils	
alcohols	

Table 7.3 Some of the end-products of photosynthesis.




Figure 7.29 Photographic film produces a negative image.

support for the light-sensitive 'emulsion'. An 'emulsion' in photography is not a true emulsion but a layer of gelatine with millions of microcrystals of silver bromide spread through it. Black-and-white film has a single layer of 'emulsion'. Colour film has three layers, each layer containing a different dye (Figure 7.29). The fine deposit of silver in the gelatine layer is black and is not washed away during development. Most silver is left where most light has fallen, so the film has a negative image.

Another important photochemical reaction, the chlorination of methane, is discussed on page 263.

Questions

- 7.17** What are the essential conditions for photosynthesis to take place?
- 7.18** Write the word and balanced symbol equations for photosynthesis.
- 7.19** What type of reaction are photosynthesis and the decomposition of silver bromide in a photographic emulsion?
- 7.20** Write the word equation for the respiration reaction.
- 7.21** Why does the use of photographic film produce a negative at first?

7.5 Reversible reactions and chemical equilibria

The physical and biological world is the product of a complex set of chemical interactions and reactions. Some reactions can even be reversed if we change the conditions.

Our life depends on the reversible attachment of oxygen to a protein called **haemoglobin**. This protein is found in our red blood cells (Figure 7.30). Oxygen is picked up as these cells pass through the blood vessels of the lungs. It is then carried to tissues in other parts of the body. As the conditions change in other regions of our body, for example the muscles and brain, the oxygen is detached and used by the cells of these organs.

Simpler reactions that can be reversed by changing the conditions include the re-formation of hydrated salts by adding back the water to the dehydrated powder.

However, there are **reversible reactions** that are more complex than this. In these reactions, under the same conditions in a **closed system**, the products can interact to reverse the reaction. No sooner are the products formed than some molecules of the product react to give back the original reactants. One industrially important example of this is the reaction between nitrogen and hydrogen to produce ammonia:





Figure 7.30 A false-colour scanning electron micrograph of red blood cells in a small branch off an artery.

A German chemist, Fritz Haber, was the first to show how this reaction could be controlled to make useful amounts of ammonia. The first industrial plant making ammonia by the **Haber process** opened in Germany in 1913. Now, over 100 million tonnes of ammonia are produced each year by this process.

The reversible hydration of salts

Thermal decomposition of salts such as hydrated copper(II) sulfate ($\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$) results in the dehydration of the salt:



In this case, the reaction results in a colour change from blue to white. The physical structure of the crystals is also destroyed. The water driven off can be condensed separately (Figure 7.31).

The white anhydrous copper(II) sulfate and the water are cooled down. Then the dehydration reaction can be reversed by slowly adding the water back to the powder (Figure 7.32). This reaction is strongly exothermic and the colour of the powder returns to blue.




Figure 7.31 Apparatus for condensing the water vapour driven off from blue crystals of hydrated copper(II) sulfate by heating. The change can be reversed by adding the liquid water back to the white anhydrous copper(II) sulfate.

Some reactions, for example the dehydration of hydrated salts, can be reversed if the conditions are changed.

The decomposition of ammonium chloride is a further example of this type of change (Figure 7.33). When



Figure 7.32 Adding water back to dehydrated copper(II) sulfate.




Figure 7.33 The reversible reaction involving ammonium chloride.

warmed in a test tube, the white solid decomposes to ammonia and hydrogen chloride:



However, on the cooler surface of the upper part of the tube, the white solid is re-formed:



Activity 7.6

A reversible reaction involving copper(II) sulfate

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

The water of crystallisation is removed from hydrated copper(II) sulfate by heating. Condensing the vapour produced in a second test tube collects the water. The white anhydrous copper(II) sulfate is then rehydrated and the blue colour returns.

A worksheet is included on the CD-ROM.


Chemical equilibria and Le Chatelier's principle

Imagine a hotel swimming pool on a hot, sunny day. Some people are by the pool sunbathing; others are swimming in the pool. Over the most popular part of the day, the number of people swimming remains approximately the same. However, it is not the same people all the time. Some stop swimming to sunbathe, while other sunbathers take a swim. The balance between the numbers of people entering and leaving the pool keeps the overall number swimming the same. This is a **dynamic equilibrium**. The pool and the sunbathing area are the system, and the system is in equilibrium. This example is an analogy to help you to understand dynamic equilibria in chemical reactions.


One other analogy that has been used to illustrate this idea is that of a fish swimming upstream (Figure 7.34).

The Haber process – making ammonia

The reaction to produce ammonia from nitrogen and hydrogen is a **reversible reaction**. That is why the symbol $\rightleftharpoons$ is used in the equation:



When nitrogen and hydrogen are mixed, they react to form ammonia – this is the **forward reaction**:



However, this reaction never goes to completion – the reactants are not all used up. This is because ammonia molecules collide and break down under the same conditions – this is the **reverse reaction**:



In the reaction mixture, these two competing reactions are going on at the same time.

As the reactions proceed, a dynamic equilibrium is reached. Ammonia molecules are breaking down as fast as they are being formed. The rate of the forward reaction is the same as the rate of the reverse reaction. The concentrations of N_2 , H_2 and NH_3 do not change even though molecules are reacting.

This reaction is a difficult one to get to work at a reasonable rate. A catalyst can be added. Chemists have




Figure 7.34 Dynamic equilibrium: the fish appears to be still. However, it is swimming upstream at the same speed as the stream is flowing in the opposite direction.

tried more than 2500 different combinations of metals and metal oxides as catalysts for this reaction. Finely divided iron has been found to be the best. However, the presence of a catalyst does not alter the equilibrium concentrations of N_2 , H_2 and NH_3 . The catalyst shortens the time taken to reach equilibrium by increasing the rates of both the forward and reverse reactions.

- ◆ A **reversible reaction** is in **equilibrium** when the rates of the forward and reverse reactions are equal.
- ◆ At equilibrium, the concentrations of reactants and products do not change.
- ◆ The equilibrium concentrations (the equilibrium position) for a particular reaction depend on the conditions used. Changing the temperature alters the equilibrium position. Changing the working pressure can also alter the equilibrium position for some reactions involving gases.
- ◆ For a reversible reaction, a **catalyst** does not alter the equilibrium concentrations of reactants and products. It does increase the rate at which equilibrium is reached.

Because of its importance, the Haber process for making ammonia has been studied under a wide range of conditions of temperature and pressure (Figure 7.35). The percentage amount of ammonia in the equilibrium




Figure 7.35 A wide range of conditions of temperature and pressure have been tried for the Haber process. The curves show the yields that would be obtained for some of them.

mixture depends on both the temperature and the pressure. Under the conditions Haber first used, only 8% of the equilibrium mixture was ammonia. Modern plants now use a temperature of about 450°C , a pressure of 200 atmospheres and an iron catalyst.

How could conditions be changed to improve this yield? The French chemist Le Chatelier put forward a generalisation that gives clues to chemists as to how this can be done.

Le Chatelier's principle states that:

when a change is made to the conditions of a system in dynamic equilibrium, the system moves so as to **oppose** that change.

So how can this reaction system be changed to produce more ammonia at equilibrium – to shift the equilibrium to the right (Figure 7.36)?

- ◆ **Changing the pressure:** How will increasing the pressure affect the amount of ammonia made? The pressure of a gas is caused by collisions of the gas particles with the walls of the container – the fewer molecules present, the lower the pressure. If we apply more pressure to the equilibrium, the system will shift to favour the side of the equation that has fewer molecules:







Figure 7.36 What shifts in the conditions will favour ammonia production in the Haber process? Increasing the pressure and lowering the temperature both move the equilibrium to the right to give more ammonia in the mixture.

- ◆ So there will be a shift to the right. More ammonia will form to reduce the number of molecules in the mixture. High pressures will increase the yield of ammonia (Figure 7.35). Modern industrial plants use a pressure of 200 atmospheres.

Higher pressures could be used, but high-pressure reaction vessels are expensive to build.

- ◆ **Changing the temperature:** The forward reaction producing ammonia is exothermic, and the reverse reaction is therefore endothermic:



- ◆ If we raise the temperature of the system, more ammonia will break down to take in the heat supplied. Less ammonia will be produced at high temperatures. Lowering the temperature will favour ammonia production (Figure 7.35). However, the rate at which the ammonia is produced will be so slow as to be uneconomical. In practice, a compromise or **optimum temperature** is used to produce enough ammonia at an acceptable rate. Modern plants use temperatures of about 450°C.
- ◆ **Reducing the concentration of ammonia:** If the system was at equilibrium and then some of the ammonia was removed, more ammonia would be produced to replace that removed. Industrially, it is easy to remove ammonia. It has a much higher boiling point than nitrogen or hydrogen (Table 7.4) and condenses easily, leaving the others still as gases. In modern plants, the gas mixture is removed from the reaction chamber when the percentage of ammonia is about 15%. The ammonia is condensed by cooling, and the remaining nitrogen and hydrogen are recycled.

Compound	Boiling point / °C
nitrogen (N ₂)	–196
hydrogen (H ₂)	–253
ammonia (NH ₃)	–33

Table 7.4 The boiling points of nitrogen, hydrogen and ammonia.

The conditions used in the **Haber process**:


- ◆ N₂ and H₂ are mixed in a ratio of 3 : 1.
- ◆ An optimum temperature of 450°C is chosen.
- ◆ A pressure of 200 atmospheres is applied.
- ◆ A catalyst of finely divided iron is used.
- ◆ The ammonia is condensed out of the reaction mixture and the remaining N₂ and H₂ recycled.

Conditions affecting a chemical equilibrium

The general ideas resulting from our discussion of the effects of changing the conditions of a reaction in equilibrium are summarised in Table 7.5. The effects are consistent with Le Chatelier's principle.

The Contact process – making sulfuric acid

In the manufacture of sulfuric acid, the main reaction that converts sulfur dioxide (SO₂) to sulfur trioxide (SO₃) is reversible:



The ideas of Le Chatelier can be applied to this equilibrium too. The reaction to produce sulfur trioxide is exothermic. This means that sulfur trioxide production would be favoured by low

Condition	Effect on equilibrium position
catalyst	Using a catalyst does not affect the position of equilibrium, but the reaction reaches equilibrium faster.
temperature	Increasing the temperature makes the reaction move in the direction that takes in heat (the endothermic direction). ^(a)
concentration	Increasing the concentration of one substance in the mixture makes the equilibrium move in the direction that produces less of that substance. ^(a)
pressure	This only affects reactions involving gases – increasing the pressure shifts the equilibrium in the direction that produces fewer gas molecules. ^(a)

^(a) The reverse of these statements is true when these factors are decreased.

Table 7.5 The effect of changing conditions on a chemical equilibrium.

temperatures. The reaction would be too slow to be economic if the temperature were too low. An optimum temperature of 450 °C is used. This gives sufficient sulfur trioxide at an economical rate. A catalyst of vanadium(v) oxide is also used to increase the rate. There are fewer gas molecules on the right of the equation. Therefore, increasing the pressure would favour the production of sulfur trioxide. In fact, the process is run at only slightly above atmospheric pressure because the conversion of sulfur dioxide to sulfur trioxide is about 96% complete under these conditions.

The conditions used in the **Contact process**:

- ◆ An optimum temperature of about 450 °C is chosen.
- ◆ A catalyst of vanadium(v) oxide is used.
- ◆ An operating pressure of about 1 atmosphere is applied.

Study tip


Remember that, when the equilibrium conditions are changed, the reaction always tends to oppose the change and act in the opposite direction.

Weak acids and alkalis

Dynamic equilibria are set up in solutions of weak acids such as ethanoic acid:



and in solutions of weak alkalis such as ammonia solution:



Because these molecules are only partially dissociated into ions in water, the pH values of the solutions are not as low as those of solutions of strong acids or as high as those of strong alkalis of the same concentration (see page 143).

Questions

- 7.22** What colour change do we see when water is added to anhydrous copper(II) sulfate powder?
- 7.23** What can this colour change be used as a test for?
- 7.24** What are the equations for the major reactions of the Haber process and the Contact process? Give both word and balanced symbol equations.
- 7.25** What are the conditions used for the Haber process?
- 7.26** Will increasing the pressure in the Haber process produce more or less ammonia?
- 7.27** What would be the effect of increasing the temperature in the Haber process on the level of ammonia produced?


Summary

You should know:

- ◆ how all chemical reactions involve changes in energy, with most giving out energy to the surroundings (exothermic)
- ◆ how some reactions take in energy and are endothermic
- ◆ that different chemical reactions occur at vastly different rates and that the rate of a particular reaction can be altered by changing conditions, including temperature
- ◆ how some reactions are speeded up by the presence of a catalyst
- ◆ that catalysts are significant in several key industrial processes
- ◆ how enzymes are proteins that act as biological catalysts
- ◆ how certain reactions can be reversed if the conditions are changed
- S ◆ that chemical reactions involve the initial breaking of bonds in the reactants so that new bonds can be formed, giving rise to products
- S ◆ how the breaking of bonds is an endothermic process requiring energy, while the making of bonds is an exothermic process releasing energy
- S ◆ that the activation energy of a reaction is the minimum energy required to start a particular reaction
- S ◆ that changes which increase the frequency of collision between reactant particles give rise to an increased rate of reaction
- S ◆ how reversible reactions in a closed system reach a position of dynamic equilibrium
- S ◆ that the rate of the reverse reaction is equal to the rate of the forward reaction at equilibrium
- S ◆ how several important industrial reactions – for example, the Haber process – are reversible reactions
- S ◆ that the conditions used in these industrial processes must be optimised to produce enough product at an economic rate.

End-of-chapter questions

- 1 Sometimes, in chemical factories, 'runaway reactions' occur. These are reactions which begin to take place much too quickly and can cause explosions which are very dangerous. In what ways can reactions be slowed down?
- 2 When iron(II) sulfate crystals are heated in a test tube, they change to a white powder and condensation collects at the top of the tube.




- a Write a word equation for the reaction. [1]
- b Is the reaction exothermic or endothermic? Explain your answer. [2]
- c What colour are iron(II) sulfate crystals? [1]

When water is added to the white iron sulfate, there is a hissing sound as steam is produced and the iron sulfate changes back to its original colour.



- d Explain these observations. [3]

This equation shows a similar reaction.




- e What is the meaning of the symbol $\rightleftharpoons$? [1]
- f Explain how this reaction can be used as a test for water. [2]

- 3 A student used the apparatus shown below to investigate the rate of reaction of calcium carbonate with dilute hydrochloric acid.



- a Use the information in the equation to suggest why the mass of the flask and contents decreases with time. [1]
- b The graph shows how the mass of the flask and its contents changes with time.



- i At what time was the reaction just complete? [1]
- ii On a copy of the graph, mark with an X the point where the speed (rate) of reaction was fastest. [1]
- iii The student repeated the experiment but altered the concentration of the hydrochloric acid so that it was half the original value. In both experiments, calcium carbonate was in excess and all other conditions were kept the same.
- On a copy of the graph, draw a curve to show how the mass of the flask and contents changes with time when hydrochloric acid of half the concentration was used. [2]
- c How does the speed (rate) of this reaction change when:
- i the temperature is increased [1]
- ii smaller pieces of calcium carbonate are used? [1]

- d Copy and complete the following sentence using words from the list.

combustion expansion large rapid slow small

In flour mills, there is often the risk of an explosion due to the rapid of the very..... particles which have a verysurface area to react.

[3]

- e Cells in plants and animals break down glucose to carbon dioxide and water.

glucose + oxygen → carbon dioxide + water

i State the name of this process.


[1]

ii In this process enzymes act as catalysts. What do you understand by the term catalyst?


[1]

[Cambridge IGCSE® Chemistry 0620/2, Question 5, June 2009]

- 4 Hydrogen peroxide decomposes slowly at room temperature to form water and oxygen. The reaction is catalysed by manganese(IV) oxide.




A student used the apparatus shown below to study how changing the concentration of hydrogen peroxide affects the speed of this reaction.



- a Apart from the volume of hydrogen peroxide, state two things that the student must keep the same in each experiment.

[2]

- b The student measured the volume of oxygen produced using three different concentrations of hydrogen peroxide. The results are shown on the graph below.



- Describe how the speed of the reaction varies with the concentration of hydrogen peroxide. [1]
 - Explain why the final volume of oxygen given off is less for graph B than for graph A. [1]
 - From the graph, determine:
 - ◆ the time taken for the reaction to be completed when 3 g/dm^3 hydrogen peroxide (line A) was used. [1]
 - ◆ the volume of oxygen produced by 2 g/dm^3 hydrogen peroxide (line B) in the first 15 seconds. [1]
- c The student then tested various compounds to see how well they catalysed the reaction. He used the same concentration of hydrogen peroxide in each experiment. The table shows the time taken to produce 20 cm^3 of oxygen using each compound as a catalyst.

Compound	Time taken to produce 20 cm^3 of oxygen / s
copper(II) oxide	130
lead(IV) oxide	15
magnesium oxide	did not produce any oxygen
manganese(IV) oxide	18

Put these compounds in order of their effectiveness as catalysts.

worst catalyst $\longrightarrow$ best catalyst


[1]

[Cambridge IGCSE® Chemistry 0620/22, Question 3, November 2011]

- 5 The equation for the reaction between sodium thiosulfate and hydrochloric acid is given below.



The speed of this reaction was investigated using the following experiment. A beaker containing 50 cm^3 of 0.2 mol/dm^3 sodium thiosulfate was placed on a black cross. 5.0 cm^3 of 2.0 mol/dm^3 hydrochloric acid was added and the clock was started.



Initially the cross was clearly visible. When the solution became cloudy and the cross could no longer be seen, the clock was stopped and the time recorded.

- a The experiment was repeated with 25 cm^3 of 0.2 mol/dm^3 sodium thiosulfate and 25 cm^3 of water. Typical results for this experiment and a further two experiments are given in the table.

Experiment	1	2	3	4
Volume of thiosulfate / cm^3	50	40	25	10
Volume of water / cm^3	0	10	25	40
Volume of acid / cm^3	5	5	5	5
Total volume / cm^3	55	55	55	55
Time / s	48	60	96	

- Explain why it is necessary to keep the total volume the same in all the experiments. [2]
- Copy and complete the table. [1]
- How and why does the speed of the reaction vary from experiment 1 to 4? [3]

S

- b The idea of collisions between reacting particles is used to explain changes in the speed of reactions. Use this idea to explain the following results.


Volume of sodium thiosulfate / cm ³	25	25
Volume of water / cm ³	25	25
Volume of acid / cm ³	5	5
Temperature / °C	20	42
Time / s	96	40

[4]


[Cambridge IGCSE® Chemistry 0620/32, Question 3, June 2011]

S

- 6 Ammonia is made by the Haber process.



- a State **one** major use of ammonia. [1]
- b Describe how hydrogen is obtained for the Haber process. [3]
- c This reaction is carried out at a high pressure, 200 atmospheres. State, with an explanation for each, **two** advantages of using a high pressure. [5]
- d i What is the difference between an endothermic and an exothermic reaction? [1]
- ii Bond breaking is an endothermic process. Bond energy is the amount of energy needed to break or form one mole of the bond. Complete the table and explain why the forward reaction is exothermic.



Bond	Bond energy / kJ/mol	Energy change / kJ	Exothermic or endothermic
N≡N	944	+ 944	endothermic
H—H	436	3 × 436 = + 1308	
N—H	388		

[3]

[Cambridge IGCSE® Chemistry 0620/33, Question 7, November 2012]

8 Patterns and properties of metals

In this chapter, you will find out about:

- ◆ the alkali metals – trends in properties
- S** ◆ aluminium and its protective oxide layer
- ◆ the transition elements – distinctive properties of these metals
- ◆ the reactivity series
- ◆ methods of extraction in relation to reactivity
- S** ◆ metal displacement reactions
- S** ◆ electrochemical cells – link to reactivity.

Smart wires remember that shape!

Metals have been in use for many thousands of years. The skills of the smiths and metalworkers stretch back through history. The ‘art’ of the folding and tempering of the blades of Samurai swords is truly astounding, for instance. Such technology grew out of practical understanding. It gave rise to a whole series of techniques and alloys which produced metals fit for a purpose.

This expertise has now been added to as the structure of metals has been increasingly understood. We have a wide range of steels and other alloys suited to demanding uses.

However, a new series of alloys with remarkable properties has appeared on the scene. Metals with great elasticity and a property not usually linked to a metal – memory! Shape memory metals such as ‘nitinol’ have introduced a new phenomenon into the use of metals. Nitinol (or nickel-titanium) has the ability to be deformed at one temperature but then recover its original, undeformed shape upon heating.

Figure 8.1 shows this phenomenon using a piece of shape memory wire bent to form the word ‘ice’.

There are now a range of these shape memory alloys. Some are based on the original nickel/titanium combination alloyed with either copper or aluminium. A number of significant uses are suggested for them. You may even have seen television adverts for wired frame spectacles that remember their shape after being sat on – or worse! They can be used to act as switches on control circuits, as part of a patented heat engine where the movement of the wire turns a pulley, and in dental braces. A significant medical use is as miniaturised stents to hold veins and arteries open and allow blood flow.

The chemistry of the metals involved is of importance in this last application because the metals must be unreactive. This ensures that the wires are biocompatible – with no adverse reactions in the body. Here we will see that there is a whole spectrum of reactivity linked to metals from different regions of the Periodic Table.



Figure 8.1 Restoring the shape of memory wire by heating: **a** the original shape of the wire, **b** the deformed wire, **c** the wire returning to its original shape in hot water.

8.1 The alkali metals

		H					0
I	II	III	IV	V	VI	VII	He
Li	Be	B	C	N	O	F	Ne
Na	Mg						
K	Ca						
Rb	Sr						
Cs	Ba						
Fr	Ra						

The distinctive metals of Group I are called the **alkali metals**. The most memorable thing about them is their spectacular reaction with cold water (Figure 8.2). These metals do not have many uses because they are so reactive and tarnish easily. They have to be stored under oil. The one familiar use of sodium is in sodium vapour lamps. These are the yellow street and motorway lights seen throughout towns and cities.

The melting points of the alkali metals decrease gradually as you go down the group. There is a similar trend in the hardness of the metals. They are all soft, low-density metals. Lithium is the hardest, but it can still be cut with a knife. The metals get easier to cut going down the group. The **density** of the metals tends to increase down the group, though potassium is an exception, being slightly less dense than sodium.

There are many ways in which the different elements of Group I show similar properties. Some of these common characteristics are given in the box that follows.



Figure 8.2 The reaction of sodium with water. Note that the hydrogen released burns with the metal's characteristic flame colour.

The common properties of the alkali metals

- ◆ They are all reactive metals. They have to be stored under oil to stop them reacting with the oxygen and water vapour in the air (Table 8.1).
- ◆ They are soft and can be cut with a knife.
- ◆ Like all metals, they form positive ions. The metals of Group I form ions with a single positive charge (for example, Li^+ , Na^+ , K^+).
- ◆ As a result, they form compounds that have similar formulae; for example, their carbonates are lithium carbonate (Li_2CO_3), sodium carbonate (Na_2CO_3) and potassium carbonate (K_2CO_3).
- ◆ They all react strongly and directly with non-metals to form salts. These salts are all white, crystalline, ionic solids that dissolve in water.

Study tip

Make sure of the wording of your comments when discussing these metals. The alkali metals have 'similar' properties to each other, they are not the same. There is a gradual change in properties as you go down the group.


Remember that you can be asked to 'predict' properties of these elements by comparison with others in the group, so practise that type of question.

The reaction of the alkali metals with water

All the alkali metals react spontaneously with water to produce hydrogen gas and the metal hydroxide (Table 8.1). The reactions are exothermic. The heat produced is sufficient to melt sodium and potassium as they skid over the surface of the water. Lithium does not melt as it reacts. This begins to show the gradual differences in reactivity between the metals as you go down the group. Lithium (at the top) is the least reactive and caesium (at the bottom) is the most reactive. The reaction with water is the same in each case:



For example:



Element	Reaction with water	Reaction with air	
lithium	reacts steadily $2\text{Li} + 2\text{H}_2\text{O} \rightarrow 2\text{LiOH} + \text{H}_2$	tarnishes slowly to give a layer of oxide	increasing reactivity 
sodium	reacts strongly $2\text{Na} + 2\text{H}_2\text{O} \rightarrow 2\text{NaOH} + \text{H}_2$	tarnishes quickly to give a layer of oxide	
potassium	reacts violently $2\text{K} + 2\text{H}_2\text{O} \rightarrow 2\text{KOH} + \text{H}_2$	tarnishes very quickly to give a layer of oxide	

Table 8.1 Reactions of lithium, sodium and potassium with air and water.

The reaction gets more vigorous as you move down the group. The reaction of lithium with water is quite steady: the metal does not melt and the hydrogen does not ignite. Sodium reacts more strongly: the metal melts but, if the sodium is free to move, the hydrogen does not usually ignite. Restricting the movement of the sodium, by placing it on a piece of filter paper on the water surface, results in the hydrogen gas igniting. The flame is coloured yellow by the sodium. Potassium reacts so strongly with water that the hydrogen gas ignites spontaneously. The potassium may even explode dangerously. The flame is coloured lilac. Rubidium and caesium explode as soon as they are put into water. The metal hydroxide produced in each case makes the water become alkaline.

Study tip

Remember to read any questions carefully. When asked, 'What would you observe?', make sure that you give your observations carefully – talk about what you see, hear and smell. If there is a gas given off then state its colour, for instance. Make sure you give detail.

Flame tests for the alkali metals

Compounds of the alkali metals can be detected by a **flame test**. All alkali-metal ions give characteristic colours in a Bunsen flame. Table 8.2 lists the colours obtained. The intensity (brightness) of the flame colour can be measured using a flame photometer. This instrument is used in hospitals to measure the levels of sodium ions and potassium ions in body fluids. Sodium and potassium are essential to good health. The cells

Metal ion	Formula	Flame colour
lithium	Li^+	red
sodium	Na^+	yellow
potassium	K^+	lilac

Table 8.2 Flame colours of Group I metal ions.

in our body are surrounded by a solution that usually contains more sodium ions, while the fluid inside the cells contains more potassium ions. The balance between the two ions is very important. The nerve impulses in our bodies are controlled by the movement of these two ions.

Our bodies can store excess sodium ions but not potassium ions. This means that the body levels of potassium ions, which come from fresh fruit and vegetables, may fall in some people. An imbalance between sodium and potassium is set up, which can lead to high blood pressure.

Compounds of the alkali metals

The alkali metals themselves do not have many general uses. But the compounds of the alkali metals are very important. Sodium chloride (common salt) has a very wide range of uses, both domestic and industrial. Its importance stretches back in history. Salt is a major food preservative, which was even more significant before the development of refrigeration. The word 'salary' derives from a time when workers were paid with salt. In 1930, when Britain still ruled over India, Mahatma Gandhi led a protest march to the sea to collect salt. This was to demonstrate the Indians' wish to be free of the British monopoly of salt and the taxes they imposed on it.

Group II metals

		H						0
I	II	III	IV	V	VI	VII	He	
Li	Be	B	C	N	O	F	Ne	
Na	Mg	Al						
K	Ca	Ga						
Rb	Sr	In						
Cs	Ba	Tl						
Fr	Ra							

Metal ion	Ion	Flame colour
magnesium	Mg ²⁺	no colour
calcium	Ca ²⁺	brick red
strontium	Sr ²⁺	scarlet
barium	Ba ²⁺	apple green

Table 8.3 Flame colours of Group II metal ions.

Magnesium ions do not give a characteristic flame colour. Magnesium metal burns fiercely with a brilliant (very bright) white light. For this reason it is used in distress flares, in flashbulbs and in fireworks that give a white light.

$$\begin{array}{ccccccc} \text{magnesium} & + & \text{oxygen} & \rightarrow & \text{magnesium oxide} \\ 2\text{Mg(s)} & + & \text{O}_2\text{(g)} & \rightarrow & 2\text{MgO(s)} \end{array}$$

Study tip

Burning magnesium can also reduce carbon dioxide to carbon if it is lowered into a gas jar of the gas.





Figure 8.3 Some Group II metals give characteristic colours in the flame test: **a** calcium, **b** strontium, and **c** barium.


Trends in reactivity

As in Group I, the reactivity of the alkaline earth metals increases going down the group. Beryllium (at the top) is the least reactive and barium (at the bottom) is the most reactive. Again the change in reactivity is best shown by using their reactions with water.

Magnesium reacts **very slowly** when placed in **cold** water. A much **more vigorous** reaction is obtained if **steam** is passed over heated magnesium. The magnesium glows brightly to form hydrogen and magnesium oxide:



Calcium, however, **reacts strongly** with **cold** water, giving off hydrogen rapidly:



Calcium hydroxide is more soluble than magnesium hydroxide, so an alkaline solution is produced (limewater). As the reaction proceeds, a white suspension is obtained because not all the calcium hydroxide dissolves.


Questions

- 8.1 State **two** physical characteristics of the alkali metals.
- 8.2 Give the colours of sodium and potassium if their salts are tested in the flame test.
- 8.3 What gas is given off when the alkali metals are reacted with water?
- 8.4 Name the product, other than hydrogen, when potassium is reacted with water.
- 8.5 Write a word equation for the reaction of sodium with water.
- 8.6 Write a balanced chemical equation for the reaction of potassium with water.
- 8.7 Which of the alkali metals does not melt when a piece of it is placed on the surface of water?

8.2 Aluminium

I	II	III	IV	V	VI	VII	0		
Li	Be	B	C	N	O	F	Ne		
	Mg	Al	Si						
	Ca	Ga	Ge						
	Sr	In	Sn						
	Ba	Tl	Pb						
	Ra								

Aluminium was, for a long time, an expensive and little-used metal. In France, around the 1860s, at the Court of Napoleon III (the nephew of Napoleon Bonaparte), honoured guests used cutlery made of aluminium rather than gold. At that time the metal was expensively extracted from aluminium chloride using sodium or potassium:



The breakthrough came in 1886 when Charles Hall and Paul Héroult independently found a way to obtain the metal by electrolysis.

Aluminium is the most common metal in the Earth's crust. The one major ore of aluminium is **bauxite**, and aluminium oxide is purified from this. Electrolysis of molten aluminium oxide produces aluminium at the cathode.

Aluminium's usefulness

Aluminium is a light, strong metal and has good electrical conductivity. Increasingly it is being used for construction purposes. The Lunar Rover 'moon-buggy' was built out of aluminium, and so too are some modern cars. For use in aeroplanes, it is usually alloyed with other metals such as copper (Figure 8.4). Its low density and good conductivity have led to its use in overhead power lines.

Aluminium is particularly useful because it is protected from corrosion by the stable layer of aluminium oxide that forms on its surface. This protective layer stops the aluminium (a reactive metal) from reacting. This makes aluminium foil containers ideal for food packaging because they resist corrosion by natural acids. Aluminium is also used for external structures such as window frames because they resist weathering. Figure 8.5 shows the uses made of aluminium produced in the USA.




Figure 8.4 The supersonic passenger jet *Concorde* was built out of an aluminium alloy.






Figure 8.5 The widespread and increasing uses of the aluminium produced in the USA.

The thermit reaction

The high reactivity of aluminium is used to extract some metals from their oxides in small quantities. Thus aluminium can be used to produce iron from iron(III) oxide:



The aluminium and iron(III) oxide are powdered and well mixed to help them react (Figure 8.6a). The reaction is powerful, exothermic and produces iron in the molten state. Because of this, the reaction is used to weld together damaged railway lines (Figure 8.6b). The reaction is an example of reduction–oxidation (**redox**) and is known as the **thermit reaction**. Other metals such as chromium can be prepared from their oxides by such redox reactions.



The analytical test for aluminium ions

Aluminium ions do not give a characteristic colour in the flame test. The presence of aluminium ions (Al^{3+}) in a compound must be detected by some other method. If an aluminium salt is dissolved in water and sodium hydroxide solution is added, a white precipitate is formed. For example:






Figure 8.6 **a** The thermit reaction. **b** Using the thermit reaction to weld fractured railway lines.

S



8.10 Why does aluminium not corrode like iron?

II										III											
Be											B										
Mg											Al										
Ca	Sc	Ti	V	Cr	Mn	Fe	Co	Ni	Cu	Zn	Ga										
Sr	Y	Zr	Nb	Mo	Tc	Ru	Rh	Pd	Ag	Cd	In										
Ba		Hf	Ta	W	Re	Os	Ir	Pt	Au	Hg	Tl										
Ra																					

212 Cambridge IGCSE Chemistry

The distinctive properties of the **transition elements**:

- ◆ Many of their compounds are coloured.
- ◆ These metals often show more than one **valency** – they form more than one type of ion.
- ◆ The metals or their compounds often make useful **catalysts**.
- ◆ A few of the metals are strongly magnetic (iron, cobalt and nickel).

Coloured compounds

The salts of the metals in Groups I, II and III are generally white solids. They give colourless solutions if they dissolve in water. In contrast, the salts of the transition elements are often coloured and produce coloured solutions when dissolved. For example, vanadium compounds in solution can be yellow, blue, green or purple. Some other examples of the colours produced by transition-element ions are given in Table 8.4. The presence of such metals in negative ions also gives rise to colour.

The transition elements are one of the major contributors to colour in our lives. The impressive colours of stained glass windows are produced by the presence of these metal ions in the glass (Figure 8.8). Similar trace amounts (very small amounts) of metals produce the colours of gemstones such as sapphire and ruby. These stones are corundum, the naturally occurring crystalline form of aluminium oxide (Al_2O_3). Pure corundum is colourless but trace




Figure 8.8 Meherangarh Fort stained glass windows, Jodhpur, India. The colours of the stained glass are due to the presence of transition metal ions in the glass.

amounts of titanium and iron ions together produce the blue colour of sapphires, while chromium ions (Cr^{3+}) produce the red colour of rubies.

The colours associated with transition elements also help in chemical analysis. When testing a salt solution by adding sodium hydroxide, the transition elements give hydroxide precipitates with a characteristic colour. For example, iron(II) hydroxide is grey-green whereas iron(III) hydroxide is red-brown.

Variable valency oxidation states (valency)

The metals in Group I always show a **valency** of 1.

When reacting to form ionic compounds, their atoms lose their one outer electron to form ions with a single positive charge (Na^+ , K^+ , etc.). The metals in Group II all show a valency of 2; they form ions with two positive charges (Mg^{2+} , Ca^{2+} , etc.). Aluminium in Group III has a valency of 3 and always forms the Al^{3+} ion.

Transition-element atoms, however, are not so straightforward. For example, iron atoms can lose either two electrons, to form the Fe^{2+} ion, or three electrons, to give Fe^{3+} . Compounds containing these ions have different colours and different properties. A distinction is made in their name: iron(II) oxide has the formula FeO , iron(III) oxide the formula Fe_2O_3 . Other transition elements also have more than one valency or **oxidation state**.

Catalytic properties

Catalysts are substances that speed up a chemical reaction without themselves being used up or changed

Metal ion in solution ^(a)	Formula	Colour
copper(II)	Cu^{2+}	blue
iron(II)	Fe^{2+}	green
iron(III)	Fe^{3+}	red-brown
chromium(III)	Cr^{3+}	green
cobalt(II)	Co^{2+}	pink
manganate(VII)	MnO_4^-	purple
chromate(VI)	CrO_4^{2-}	yellow
dichromate(VI)	$\text{Cr}_2\text{O}_7^{2-}$	orange

^(a) Including some negative ions that contain these metals.

Table 8.4 The colours of some transition-element ions in solution.

at the end of the reaction. Many of the important industrial catalysts are either transition elements or their compounds, for example iron in the Haber process.

Magnetic properties


Three of the first row of transition elements are strongly magnetic. They are iron, cobalt and nickel. The Earth's magnetic field is produced by the liquid and solid iron and nickel in the outer and inner core of the planet.

It is important to realise that most metals, aluminium for instance, are not magnetic.

The reactions of certain transition elements


Iron

Iron is only a moderately reactive metal, but it will still react with steam or acids to displace hydrogen gas. For example:




The fact that iron can form two different positive ions means that an analytical test is needed to distinguish between the two. The salt being tested is dissolved in water and then alkali is added.

With solutions of iron(II) salts, a grey-green gelatinous (jelly-like) precipitate of iron(II) hydroxide is formed on adding the alkali:




The precipitate is not affected by adding excess alkali. The same precipitate is formed if ammonia solution is used instead of sodium hydroxide. With solutions of iron(III) salts, a red-brown gelatinous precipitate of iron(III) hydroxide is formed when alkali is added:



Copper


Copper has a distinctive colour. It is one of the least reactive metals in common use. It does **not** react with dilute acids to produce hydrogen. If the metal is heated

in air, a black layer of copper(II) oxide is formed on the metal:



Copper statues and roofs become coated in a green layer of basic copper(II) carbonate (Figure 8.9) when exposed to the atmosphere for a long time.

Copper(II) carbonate is also found in the Earth's crust as the mineral malachite. Like most other carbonates, copper(II) carbonate will decompose on heating to release carbon dioxide:



The presence of copper ions in compounds can be detected using the flame test. Copper gives a characteristic blue-green colour. Solutions of copper salts also give a blue gelatinous precipitate of copper(II) hydroxide if sodium hydroxide is added:







Figure 8.9 The copper sheets of this roof have become coated in a layer of green copper(II) carbonate.

If the precipitate formed is heated carefully, it will turn black. Copper(II) hydroxide is unstable when heated and is converted to copper(II) oxide.



Ammonia solution will also produce the same blue precipitate of copper(II) hydroxide when added to copper(II) sulfate solution. However, if excess ammonia is added, the precipitate re-dissolves to give a deep-blue solution.

Zinc

Zinc is a moderately reactive metal that will displace hydrogen from steam or dilute acids:





Zinc carbonate decomposes on heating to give off carbon dioxide:





Interestingly, when hot, the zinc oxide produced is yellow. However, when it cools down it turns white again. This is simply a physical change that occurs on heating; it is not a chemical reaction.

Solutions of zinc salts produce a white precipitate of zinc hydroxide when sodium hydroxide solution is added:



Zinc hydroxide, like aluminium hydroxide, is an amphoteric hydroxide and it re-dissolves if excess sodium hydroxide is added. Zinc hydroxide reacts with excess sodium hydroxide to form sodium zincate:



These reactions with sodium hydroxide do not help us to distinguish between zinc salts and aluminium

salts. Both give white precipitates that re-dissolve in excess alkali. The two can be distinguished, however, if ammonia solution is used (not sodium hydroxide). In both cases, the hydroxide precipitate forms; but zinc hydroxide re-dissolves in excess ammonia solution, whereas aluminium hydroxide does not.

Questions

- 8.11 Give three distinctive properties of the transition metals.
- 8.12 What are the two oxidation states (valencies) of iron in its compounds?
- 8.13 What colour do you associate with copper compounds?
- 8.14 Iron corrodes to form rust. What is the chemical name and formula for 'rust'?
- 8.15 Name an important industrial process for which iron is the catalyst.

8.4 The reactivity of metals

Most of the elements in the Periodic Table are metals. Many of them are useful for a wide variety of purposes; some, such as iron, have an enormous number of uses. The early history of human life is marked by the metals used in making jewellery, ornaments and tools. Early civilisations used metals that could be found 'native' (for example, gold) for decorative items, and then alloys such as bronze. Later, iron was used for tools. Even after the Bronze and Iron Ages, only a few metals continued to be used widely. Other more reactive metals could not be obtained until the nineteenth century. Even among the metals that were available, there were obvious differences in resistance to corrosion. The Viking sword in Figure 8.10, overleaf emphasises the different reactivities of the gold and silver of the hilt and the iron of the blade.

We have seen how reactivity changes in a particular group. But the more important metals we use come from more than one group. Is there a broader picture in which we can compare these?

An overview of reactivity

We can get information on reactivity by investigating the following aspects of metal chemistry:

- ◆ ease of extraction
- ◆ reactions with air or oxygen



Figure 8.10 This Viking sword had a handle made from gold and silver and an iron blade. The blade has corroded badly but the handle is untouched.

- ◆ reactions with water
- ◆ reactions with dilute acids
- ◆ metal displacement reactions and redox reactions
- ◆ heat stability of metal compounds.

The overall picture that emerges is summarised in Figure 8.11. This is known as the **reactivity series** of metals.

The extraction of metals

A few metals are so **unreactive** that they occur in an uncombined state. These unreactive metals include copper (Figure 8.12), gold and silver. The metals that occur native form the first broad group of metals. They are found as metals in the Earth's crust.

However, most metals are **too reactive** to exist on their own in the ground. They exist combined with other elements as compounds called **ores** (Table 8.5). These are the raw materials for making metals. The metals that must be mined as ores can be subdivided into two other broad groups.

potassium	K
sodium	Na
calcium	Ca
magnesium	Mg
aluminium	Al
(carbon)	C
zinc	Zn
iron	Fe
tin	Sn
lead	Pb
(hydrogen)	H
copper	Cu
silver	Ag
gold	Au
platinum	Pt



Figure 8.11 The reactivity series of metals.



Figure 8.12 A piece of copper found 'native'.

Activity 8.1 Extracting metals with charcoal


Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates

In this activity, copper and lead are extracted from their oxides using powdered charcoal.

A worksheet is included on the CD-ROM.

The moderately reactive metals such as iron, zinc, tin and lead occur either as oxide or as sulfide ores (Figure 8.13). One sulfide ore that is quite noteworthy is iron pyrites which, because of its colour, became known as 'fool's gold' (Figure 8.14). The sulfide ores can easily be converted to the oxide by heating in air. For example:



The oxide must then be reduced to give the metal. Carbon, in the form of coke, is used for this. Coke can be made

Metal	Name of ore	Compound present
aluminium	bauxite	aluminium oxide, Al_2O_3
copper	copper pyrites	copper iron sulfide, CuFeS_2
iron	hematite	iron(III) oxide, Fe_2O_3
sodium	rock salt	sodium chloride, NaCl
tin	cassiterite	tin(IV) oxide, SnO_2
zinc	zinc-blende	zinc sulfide, ZnS
lead	galena	lead(II) sulfide, PbS

Table 8.5 Some metals and their ores.




Figure 8.13 The major ores of iron: limonite, hematite and magnetite.



Figure 8.14 'Fool's gold' – a notorious ore of iron called iron pyrites (FeS_2).

cheaply from coal. At high temperatures, carbon has a strong tendency to react with oxygen. It is a good **reducing agent** and will remove oxygen from these metal ores:



So this group of moderately reactive metals can be extracted by reduction with carbon using essentially the blast furnace method (page 227).

However, some metals are too reactive to be extracted by this method. The very reactive metals


such as aluminium, magnesium and sodium have to be extracted by **electrolysis** of their molten ores. The three broad groups are summarised in Table 8.6 (overleaf).

Activity 8.2 Reacting iron wool with steam

Skills

A03.3 Make and record observations, measurements and estimates

In this demonstration, steam is passed over red-hot iron wool. The gas produced in the reaction is collected and tested with a lighted splint.



A worksheet is included on the CD-ROM.

Questions

- A1 What colour is the surface of the iron after the reaction?
- A2 The form of iron oxide produced in this reaction has the formula Fe_3O_4 . Write a balanced symbol equation for the reaction taking place.

Reactions of metals with air, water and dilute acids

Considering the methods of extraction of the metals gives a broad pattern of reactivity. More detail can be found by looking at certain basic reactions of metals. The results are summarised in Table 8.7 (page 219).

Metal displacement reactions


A **displacement reaction** can help us to place particular metals more precisely in the **reactivity series**. We can

	Metal	Method of extraction
decreasing reactivity ↓	potassium	electrolysis of molten ores
	sodium	
	calcium	
	magnesium	
	aluminium	
	zinc	reduction of oxides with carbon (sulfide ores heated to give oxide)
	iron	
	tin	
	lead	
	copper	occur native in the ground
	silver	
	gold	

Table 8.6 Methods of extraction in relation to the reactivity series.

use it to compare directly the reactivity of two metals. In a displacement reaction, a more reactive metal displaces a less reactive metal from solutions of salts of the less reactive metal.

In this type of reaction, the two metals are in direct 'competition'. If a piece of zinc is left to stand in a solution of copper(II) sulfate, a reaction occurs:



The observed effect of the reaction is that the zinc metal becomes coated with a red-brown layer of copper. The blue colour of the solution fades. The solution will eventually become colourless zinc sulfate (Figure 8.15).

Zinc displaces copper from solution, so zinc is more reactive than copper.

Activity 8.3 Displacement reactions of metals

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

 **Wear eye protection.**

In this experiment, you will investigate the reactions between metals and solutions of their salts.

- Using a measuring cylinder, pour 10 cm³ of zinc sulfate solution into a boiling tube.
- Place the tube in a rack and, using a stirring thermometer, record the temperature of the solution.
- Add one spatula measure of magnesium powder to the tube, start a stopclock and stir.
- Record the temperature every 30 seconds for 5 minutes, stirring between each reading.

- Using a fresh tube, repeat the above experiment using copper sulfate solution and zinc powder.
- Again, record the temperature change over 5 minutes.
- Repeat the experiment again, this time using copper sulfate solution and iron powder.
- Plot three graphs on the same grid showing the temperature change over time for each metal.

A worksheet is included on the CD-ROM.

The Notes on Activities for teachers/technicians contain details of how this experiment can be used as an assessment of skill AO3.4. This activity could be used as a pilot for Activity 7.3.

Questions

- What would you expect to happen if the experiment was carried out using iron(II) sulfate solution and zinc powder? Explain your answer.
- How could you improve the accuracy of your experiment?

Reactivity series	Reaction with ...		
	Air	Water	Dilute HCl
sodium	burn very strongly in air to form oxide	react with cold water to give hydrogen	react very strongly to give hydrogen
calcium			
magnesium			
aluminium ^(a)	burn less strongly in air to form oxide	react with steam, when heated, to give hydrogen	react less strongly to give hydrogen
zinc			
iron			
lead	react slowly to form oxide layer when heated	do not react	do not react
copper			
silver	do not react	do not react	do not react
gold			

^(a)These reactions only occur if the protective oxide layer is removed from the aluminium.

Table 8.7 The reaction of metals with air, water and dilute hydrochloric acid.





Figure 8.15 Zinc is more reactive than copper and displaces copper from copper(II) sulfate solution. Note the brown deposit of copper, and the fact that the blue colour of the solution has faded.

The reverse reaction does not happen. A piece of copper does not react with zinc sulfate solution.

It is possible to confirm the reactivity series using displacement reactions of this type. For example, if copper metal is put into colourless silver nitrate solution, the copper will become coated with silver, and the solution becomes blue because of the formation of copper nitrate solution:



Copper displaces silver from solution, so copper is more reactive than silver.

Activity 8.4 The reactivity series

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data


This activity uses microscale Comboplates® or white spotting tiles to investigate the reactions between powdered metals and their solutions. This observational exercise allows the metals to be placed in series depending on their reactivity.

A worksheet is included on the CD-ROM.

Other redox competition reactions

Reactive metals are good **reducing agents**. The nature of the reaction taking place between zinc and copper

S sulfate can be explored in more detail by looking at the ionic equation:



This shows that the reaction is a redox reaction involving the transfer of two electrons from zinc atoms to copper(II) ions. Zinc atoms are oxidised to zinc ions, while copper(II) ions are reduced (Figure 8.16). In general, the atoms of the more reactive metal lose electrons to become positive ions.






Figure 8.16 The displacement reaction between zinc and copper(II) sulfate is a redox reaction. A summary of the redox change in terms of oxidation number and electron exchange is shown.

The thermit reaction discussed earlier is an example of a competition reaction in the solid state. Aluminium, the more reactive metal, removes oxygen from the less reactive iron in iron(III) oxide:



This is a redox reaction. Similar redox reactions can be used to extract metals other than iron. Other powdered metal oxides can be used, such as chromium(III) oxide (see page 210). A thermit reaction using copper oxide and aluminium can be used to create electrical joints.




Reactive metals such as magnesium can be used instead of aluminium in this type of reaction. Some thermit-like mixtures are used as initiators in fireworks. In general, a reactive metal will displace a less reactive metal from its oxide.

Like displacement reactions in solution, this type of reaction helps us to compare directly the reactivity of two metals and to establish the order of the reactivity series.



Thermal decomposition of metal compounds

The stability of certain metal compounds is related to the reactivity of the metal. For instance, most metal carbonates are decomposed on heating:





However, sodium carbonate is stable to heat. So also are the carbonates of metals below sodium in Group I, as they are more reactive than sodium.

Metal hydroxides and nitrates are also unstable to heat. Most decompose to give the metal oxide:



However, sodium and potassium hydroxides are stable to heat: they do not decompose. The nitrates of sodium and potassium do not decompose in the same way as those of less reactive metals. They lose oxygen to form sodium or potassium nitrite:



Questions

- 8.16** Write a word equation for the reaction of zinc and dilute hydrochloric acid.
- 8.17** Select from this list a metal that will not react with hydrochloric acid to produce hydrogen: magnesium, iron, copper.
- 8.18** Write a word equation for the reaction between magnesium and copper(II) sulfate solution.
- 8.19** State **two** observations you would see when a piece of magnesium ribbon is placed in copper(II) sulfate solution.
- 8.20** Write a balanced chemical equation and an ionic equation for the reaction between magnesium and copper(II) sulfate solution.

8.5 Electrical cells and energy

Electrochemical cells

An unusual way to power a simple digital clock is with an electrical cell made using a potato. The current is produced by pushing two different metals (for example, copper and zinc) into the potato. The metals make contact with the solution inside the potato. Connecting up these electrodes to the clock produces a small current in the circuit which powers the clock. You could even use the apple you were going to have for lunch, or a water melon, to power the clock!


This cell works because the two metals have different reactivities. Zinc is more reactive and so forms ions more easily. The zinc releases electrons as its atoms become ions, and these electrons give the zinc electrode a negative charge. The electrons move around the circuit to the copper electrode.

A simple **electrochemical cell** works best if the metals used as the electrodes are far apart in the reactivity series. The voltage of a cell made using zinc and copper electrodes is about 1.1 V. If a magnesium strip is used instead of zinc, then the voltage increases to about 2.7 V because magnesium is more reactive than zinc (Figure 8.17). The further apart the metals are in the reactivity series, the greater the cell voltage becomes.


This explains the use of lithium, the very reactive metal at the top of Group I, as one of the electrodes in modern lithium batteries. The aim is to make the difference in reactivity as large as is safely possible.

Oxidation and reduction in power cells

In electrical power cells, the electrode made from the more reactive metal is the one at which electrons are released. The first electrochemical cell, for example, consisted of zinc and copper electrodes in a copper(II) sulfate solution. Zinc is more reactive than copper. At this electrode, zinc atoms become zinc ions:



while at the other terminal, copper ions become copper atoms:



The zinc electrode becomes the negative terminal as electrons are released (**oxidation** takes place). The copper electrode becomes the positive terminal where electrons are removed, and gained by the copper(II) ions (**reduction** takes place). The overall reaction of the cell is the same as the ionic equation for the displacement reaction that can be done in a test tube:





Figure 8.17 Setting up a simple cell with strips of different metals. **a** Although the solution is an electrolyte, with two copper strips nothing happens. **b** With one zinc and one copper electrode, there is a voltage. **c** With magnesium and copper electrodes, the voltage is even bigger.

Activity 8.5 Investigating electrochemical cells

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

This activity investigates the voltage generated when strips of different metals are combined with copper to make an electrochemical cell (see Figure 8.17).

A novel addition to this activity is to make a cell using a fruit or potato. The voltage generated can be used to power a digital timer!

A worksheet is included on the CD-ROM.

Questions

- 8.21 Which of these metals will give the biggest voltage when combined with a copper electrode in an electrochemical cell: zinc, tin or magnesium?
- 8.22 Write the half-equation for the reaction at the magnesium electrode when it is combined with a copper electrode in a cell.

Summary

You should know:

- ◆ that the alkali metals (Group I) are soft metals with low densities – they are the most reactive group of metals, displacing hydrogen from cold water and having to be stored under oil
- ◆ how reactivity increases as you move down a group and that this is true for both Group I and Group II (the alkaline earth metals)
- ◆ that aluminium is a useful construction metal because it is strong but has a low density, and that it is resistant to corrosion because of its protective oxide coating
- ◆ that the transition metals are less reactive than the metals in Groups I and II and have certain distinctive properties
- ◆ how metals can be arranged into a series based on their reactivity, with the most reactive metals lying to the left of the Periodic Table
- S ◆ how a more reactive metal will displace a less reactive metal from its oxide
- S ◆ how a more reactive metal can displace a less reactive metal from a solution of one of its salts
- S ◆ that these displacement reactions are redox reactions involving the transfer of electrons
- S ◆ how these differences in reactivity between metals can be used to generate electricity in cells and batteries
- ◆ the tests and observations for iron, copper and zinc ions
- S ◆ that the salts of iron, copper and zinc have distinctive reactions with sodium hydroxide and ammonia solutions which help to distinguish them in analysis.

End-of-chapter questions

- 1
 - a Which properties of metals and their alloys are important when selecting the right metal for a particular job?
 - b Brass conducts electricity less well than copper. Explain why it is used in plugs and switches.
- 2 A student observed the reaction of various metals with both cold water and steam. Her results are shown below.

Metal	Reaction with cold water	Reaction with steam
calcium	reacts rapidly	reacts very rapidly
copper	no reaction	no reaction
magnesium	reacts very slowly	reacts rapidly
zinc	no reaction	reacts

- a
 - i Put these metals in order of their reactivity.
 least reactive $\longrightarrow$ most reactive [1]
 - ii Iron is a metal between zinc and copper in the reactivity series. Predict the reactivity of iron with cold water and with steam. [2]
- b The equation for the reaction of zinc with steam is:

$$\text{Zn} + \text{H}_2\text{O} \rightarrow \text{ZnO} + \text{H}_2$$

Write a word equation for this reaction. [1]
- c State **three** physical properties that are characteristic of **most** metals. [3]
- d Some properties of the Group I metals are shown in the table.


Metal	Melting point / °C	Hardness	Density / g/cm ³
lithium		fairly hard	0.53
sodium	98	fairly soft	
potassium	63	soft	
rubidium	39	very soft	1.53
caesium	29	extremely soft	1.88

- i Estimate the melting point of lithium. [1]
- ii How does the hardness of these metals change down the group? [1]
- iii Estimate the density of potassium. [1]

[Cambridge IGCSE® Chemistry 0620/21, Question 6, June 2011]

3 Lithium, sodium and potassium are in Group I of the Periodic Table.

a The equation for the reaction of lithium with water is



i Write a word equation for this reaction. [2]

ii Sodium reacts with water in a similar way to lithium.


Write a symbol equation for the reaction of sodium with water. [1]

b Describe the reactions of lithium, sodium and potassium with water. In your description, write about:

i the difference in the reactivity of the metals

ii the observations you would make when these metals react with water. [5]

c The diagram below shows an electrolysis cell used to manufacture sodium from molten sodium chloride.



i Which letter in the diagram above represents:

the anode?

the electrolyte? [2]

ii State the name of the product formed:

at the positive electrode

at the negative electrode. [2]

iii Which one of the following substances is most likely to be used for the anode?

graphite

iodine


magnesium

sodium [1]

d Lithium, sodium and potassium are metals with a low density. State **two** other physical properties of these metals. [2]

[Cambridge IGCSE® Chemistry 0620/21, Question 6, June 2012]

- S** 4 The diagram shows a simple cell.



- a Write an equation for the overall reaction occurring in the cell. [2]
- b Explain why all cell reactions are exothermic and redox. [3]
- c Which electrode, zinc or iron, is the negative electrode? Give a reason for your choice. [2]
- d Suggest **two** ways of increasing the voltage of this cell. [2]

[Cambridge IGCSE® Chemistry 0620/32, Question 5, June 2011]

- 5 Reactive metals tend to have unreactive compounds. The following is part of the reactivity series.


sodium	most reactive
calcium	
zinc	↓
copper	
silver	least reactive

- a Sodium hydroxide and sodium carbonate do not decompose when heated. The corresponding calcium compounds do decompose when heated. Complete the following equations.

calcium carbonate → +
.....
 $\text{Ca(OH)}_2 \rightarrow \dots\dots\dots + \dots\dots\dots$ [2]

- b All nitrates decompose when heated.

- i The equation for the thermal decomposition of silver(I) nitrate is given below.



What are the products formed when copper(II) nitrate is heated? [1]

- ii Complete the equation for the action of heat on sodium nitrate.

..... $\text{NaNO}_3 \rightarrow \dots\dots\dots + \dots\dots\dots$ [2]

- c Which of the metals listed have oxides that are not reduced by carbon? [1]
- d Choose from the list those metals whose ions would react with zinc. [2]

[Cambridge IGCSE® Chemistry 0620/31, Question 5, June 2012]

9

Industrial inorganic chemistry

In this chapter, you will find out about:

- ◆ the production of iron in the blast furnace
- ◆ steel making
- ◆ rusting of iron and its prevention
- S** ◆ the extraction of zinc and aluminium
- S** ◆ the Haber–Bosch process for the manufacture of ammonia
- ◆ the manufacture and use of fertilisers
- S** ◆ the manufacture of sulfuric acid
- ◆ the uses of sulfur compounds
- ◆ the commercial electrolysis of brine
- ◆ the uses of chlorine
- ◆ limestone and its uses
- ◆ the production of lime and its uses
- ◆ the economics of the chemical industry
- ◆ the siting of chemical plants
- ◆ the environmental cost of industry
- ◆ recycling.

A controversial life in science

Fritz Haber (Figure 9.1) is one of Germany's most famous chemists. He is also one of the most complex figures in the history of science whose life and career were intricately linked with the political struggles and turmoil in Europe that led to two world wars.

Working at the University of Karlsruhe in the 1890s, he devised a method for the direct synthesis of ammonia from nitrogen and hydrogen, using high pressure and temperature together with an osmium catalyst. In 1918, Haber received the Nobel Prize in Chemistry for his work on the process.



Figure 9.1 Fritz Haber (1868–1934) was responsible for one of the most influential discoveries in the history of science.

Continuing his research, Haber developed a process for converting ammonia into nitric acid, which was then used as the basis for producing nitrate high explosives. This significantly helped the German effort in the First World War (1914–18) and Haber became increasingly involved. His work on gases such as chlorine that could be used against enemy troops in the trenches had tragic personal consequences for him. His first wife was fiercely opposed to this work and she committed suicide at the height of his connection with the war effort.

After World War I, Haber continued to work in chemistry but in 1933 he was forced to leave Germany, and he died in Switzerland in 1934.

The Haber process is just one example of chemistry on a large scale. This chapter explores how industry converts raw materials into the chemical compounds that we use every day. We consider the raw materials that feed the industry, the chemistry involved, the costs of some of the processes used and the environmental challenges they present.

9.1 The extraction of metals by carbon reduction

Iron and steel

In our modern world, we have invented and shaped many machines and clever devices. These are often made of **steel**. It is the most widely used of all metals. The durability, tensile strength and low cost of steel make it the basis of countless industries, from ship-building to watch-making. Iron and steel making are at the centre of our heavy industries.

Steel is mainly iron with between 0.2 and 1.5% carbon. The carbon makes the iron harder and stronger. Small quantities of other **transition metals** can also be added to make special steels. Steels are **alloys** in which the main metal is iron. The magnetic properties of iron make it easy to separate steel products from other waste. This means that the metal can be easily recycled.

The production of iron in the blast furnace


The main ore of iron is hematite (Fe_2O_3). The iron is obtained by reduction with carbon in a **blast furnace** (Figures 9.2 and 9.3). The furnace is a steel tower about 30 metres high. It is lined with refractory (heat-resistant) bricks of magnesium oxide which are cooled by water. The furnace is loaded with the 'charge', which consists of iron ore, coke (a form of carbon made from coal) and limestone (calcium carbonate). The charge is **sintered** (the ore is heated with coke and limestone) to make sure the solids mix well, and it is mixed with more coke. Blasts of hot air are sent in through holes near the



Figure 9.2 A worker in protective clothing takes a sample from a blast furnace in a steel works.



bottom of the furnace. The carbon burns in the air blast and the furnace gets very hot.

A series of chemical reactions takes place to produce molten iron (Figure 9.4, overleaf). The most important reaction that occurs is the reduction of the ore by carbon monoxide:



The iron produced flows to the bottom of the furnace where it can be 'tapped off' because the temperature at the bottom of the furnace is higher than the melting point of iron.

One of the major impurities in iron ore is sand (silica, SiO_2). The limestone added to the furnace helps to remove this impurity. The limestone decomposes to lime in the furnace. This then reacts with the silica:



The calcium silicate formed is also molten. It flows down the furnace and forms a molten layer of **slag** on top of the iron. It does not mix with the iron, and it is less dense. The molten slag is 'tapped off' separately. When solidified, the slag is used by builders and road-makers. The hot waste




Figure 9.3 The blast furnace reduction of iron ore to iron.

gases escape from the top of the furnace. They are used in heat exchangers to heat the incoming air. This helps to reduce the energy costs of the process. The extraction of iron is a continuous process. It is much cheaper than the electrolytic processes used to extract other metals.

The **blast furnace** extraction of iron:

- ◆ uses iron ore, coke, limestone and hot air
- ◆ involves the reduction of iron(III) oxide by carbon monoxide
- ◆ uses limestone to remove the main impurity (sand) as slag (calcium silicate).

Study tip

For the blast furnace it is important that you are aware of the different aspects of how it works. You should be able to label a diagram of it and know what is fed into it.

Importantly, you should also know the key reactions of the furnace, including the formation of slag.




Figure 9.4 Iron is produced in the blast furnace by a series of reactions. Carbon monoxide is thought to be the main reducing agent.

Steel-making

The iron produced by the blast furnace is known as ‘pig iron’ or ‘cast iron’ and is not pure. It contains about 4% carbon, and other impurities. This amount of carbon makes the iron brittle. This limits the usefulness of the iron, though it can be cast (moulded) into large objects that are not likely to be subjected to deforming forces.

Most of the pig iron produced is taken to make steel. The carbon content is reduced by burning it off as carbon dioxide. Any sulfur contamination is oxidised to sulfur dioxide. This **basic oxygen process** is carried out in a tilting furnace (Figure 9.5). The method is fast: 350 tonnes of molten iron can be converted in 40 minutes. Scrap steel is added to the molten pig iron for recycling. A high-speed jet of oxygen is blown into the vessel through a water-cooled lance. Some impurities, for example silicon and phosphorus, do not produce gaseous oxides, so lime (CaO) is added to the furnace. The impurities form a ‘slag’, which floats on top of the molten iron. The molten iron is poured off by tilting the furnace. Controlled amounts of other elements such as chromium, manganese, tungsten or other transition metals are added to make different types of steel (see Tables 9.1 and 9.2).




Figure 9.5 The different stages of the steel-making process (the basic oxygen process). **a** The furnace is charged with scrap steel and molten iron. **b** Oxygen is blown in through an ‘oxygen lance’. **c** The molten steel, and then the slag, are poured from the furnace by tilting it in different directions.

Carbon steels and alloy steels

There is a wide variety of steels to suit particular applications. Some steels are alloys of iron and carbon only. The amount of carbon in steels can vary between 0.2% and 1.5%. These **carbon steels**, which include the mild steel used for car bodies, are listed in Table 9.1.

But carbon steels tend to rust unless protected. So other metals, for example chromium, are added to prevent corrosion and to make the steel harder. Some of these **alloy steels** are listed in Table 9.2.

Study tip

The syllabus very clearly states some examples of the major uses of mild and stainless steel. Make sure that you are aware of these.

The uses of other substances are also explicitly stated in the syllabus – so go through and make a list of these (for aluminium and various alloys, for example) and specifically learn them.

Activity 9.1 Preventing rusting

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

In this activity, iron nails are protected from rusting using a variety of methods, including painting, greasing and sacrificial protection. By using corrosion indicator solution, the effectiveness of the different types of protection can be assessed.

A worksheet, with a self-assessment checklist, is included on the CD-ROM.

Metal	Carbon content / %	Properties	Uses
cast iron	2.5–4.5	cheaper than steel; easily moulded	gear boxes, engine blocks, brake discs
mild steel	< 0.25	easily worked; not brittle	car bodies, chains, pylons
medium steel	0.25–0.45	tougher than mild steel	car springs, axles, bridges
high-carbon steel	0.45–1.5	hard and brittle	chisels, cutting tools, razor blades

Table 9.1 Cast iron and carbon steels.

Steel ^(a)	Typical composition		Properties	Uses
stainless steel	iron	74%	tough; does not corrode	cutlery, surgical instruments, kitchen sinks, chemical plant
	chromium	18%		
	nickel	8%		
tungsten steel	iron	95%	tough; hard, even at high temperatures	edges of high-speed cutting tools
	tungsten	5%		
manganese steel	iron	87%	tough; springy	drill bits, springs
	manganese	13%		

^(a) All these alloys have a low content of carbon (<0.45%).

Table 9.2 Some typical alloy steels.

The rusting of iron and its prevention

When a metal is attacked by air, water or other surrounding substances, it is said to **corrode**. In the case of iron and steel, the corrosion process is also known as **rusting**. Rusting is a serious economic problem. Large sums of money are spent each year replacing damaged iron and steel structures, or protecting structures from such damage. **Rust** is a red-brown powder consisting mainly of hydrated iron(III) oxide ($\text{Fe}_2\text{O}_3 \cdot x\text{H}_2\text{O}$). Water and oxygen are essential for iron to rust (Figure 9.6). The problem is made worse by the presence of salt; seawater increases the rate of corrosion. Pictures from the seabed of the wreck of the *Titanic* show that it has a huge amount of rust (Figure 9.7). Acid rain also increases the rate at which iron objects rust.

Aluminium is **more** reactive than iron, but it does not corrode in the damaging way that iron does. Both metals react with air. In the case of aluminium, a very thin single layer of aluminium oxide forms, which sticks strongly to the surface of the metal. This micro-layer seals the metal surface and protects it from

further attack. Aluminium is a useful construction material because it is protected by this layer. The protective layer can be made thicker by electrolysis (**anodising**, see page 235).

In contrast, when iron corrodes, the rust forms in flakes. It does not form a single layer. The attack on the metal can continue over time as the rust flakes come off. Indeed, a sheet of iron can be eaten right through by the rusting process.

Chromium is another metal, similar to aluminium, that is protected by an oxide layer. If chromium is alloyed with iron, a 'stainless' steel is produced. However, it would be too expensive to use stainless steel for all the objects built out of iron. Electroplating a layer of chromium on steel is used to protect some objects from rusting, for example car bumpers and bicycle handlebars.

Rust prevention

The need to protect iron and steel from rusting has led to many methods being devised. Some of these are outlined here.




Figure 9.6 The results of an experiment to investigate the factors that are involved in rusting. In tube 2, the air is dry, so the nails do not rust. In tube 3, there is no oxygen in the water, so the nails do not rust. In tube 4, pure oxygen and water are present, so the nails are very rusty.



Figure 9.7 Photograph of the highly rusted bow of the *Titanic* taken from a submersible.

- ◆ **Painting:** This method is widespread, and is used for objects ranging in size from ships and bridges to garden gates. Some paints react with the iron to form a stronger protective layer. However, generally, painting only protects the metal as long as the paint layer is unscratched. Regular re-painting is often necessary to keep this protection intact.
- ◆ **Oiling and greasing:** The oiling and/or greasing of the moving parts of machinery forms a protective film, preventing rusting. Again, the treatment must be repeated to continue the protection.
- ◆ **Plastic coatings:** These are used to form a protective layer on items such as refrigerators and garden chairs. The plastic poly(vinyl chloride), PVC, is often used for this purpose.
- ◆ **Electroplating:** An iron or steel object can be electroplated with a layer of chromium or tin to protect against rusting. A 'tin can' is made of steel coated on both sides with a fine layer of tin. Tin is used because it is unreactive and non-toxic. However, this does raise a problem. With both these metals, if the protective layer is broken, then the steel beneath will begin to rust.
- ◆ **Galvanising:** An object may be coated with a layer of the more reactive metal, zinc. This is called **galvanising**. It has the advantage over other plating methods in that the protection still works even if the zinc layer is badly scratched. The zinc layer can be applied by several different methods. These include electroplating or dipping the object into molten zinc. The bodies of cars are dipped into a bath of molten zinc to form a protective layer.
- ◆ **Sacrificial protection:** This is a method of rust prevention in which blocks of a reactive metal are attached to the iron surface. Zinc or magnesium blocks are attached to oil rigs and to the hulls of ships (Figure 9.8). These metals are more reactive than iron and will be corroded in preference to it. Underground gas and water pipes are connected by wire to blocks of magnesium to obtain the

same protection. In all cases, an electrochemical cell is set up. The metal blocks lose electrons in preference to the iron and so prevent the iron forming iron(III) oxide.

- ◆ **Electrolytic protection:** Large, static steel structures can be protected by this method. It involves setting up an electrolytic cell using the iron or steel object as the negative electrode of the cell. An inert electrode and a power supply are needed to complete this form of protection, which is used to protect oil rigs, for example (Figure 9.9).




Figure 9.8 Blocks of zinc (or magnesium) are used for the sacrificial protection of the hulls of ships.




Figure 9.9 The electrolytic protection of an oil rig's structure.


Activity 9.2

Investigating how air is involved in rusting

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

This activity involves setting up some iron wool to rust in a test tube inverted in a beaker of water. As the iron wool reacts and rusts, water is drawn up the tube. This tube is left for a prolonged period, until there is no



further observable change. Observation of what has taken place and measurement of the decreased volume of air in the tube suggest which part of the air has taken part in the rusting.

- 1 Put about 3 cm depth of iron wool into a test tube and wet it with water. Tip away any excess water.
- 2 Put about 20 cm³ of water into the beaker. Invert the test tube and place it in the beaker of water. Measure the length of the column of air with a ruler.
- 3 Leave for at least a week.
- 4 Measure the new length of the column of air, being sure not to lift the test tube out of the water.
- 5 From your initial and final measurements of the length of the column of air, calculate the percentage of the air which has been used up during rusting.



A worksheet is included on the CD-ROM.

Questions


- A1 How could you show that the reaction had gone to completion?
- A2 How could the experiment be adapted to show whether seawater or acid rain speeds up the rusting process?

S The extraction of zinc

The main ore of zinc is its sulfide: zinc blende (ZnS). The sulfide ore is heated very strongly in a current of air. This converts the sulfide to the metal oxide:



The sulfur dioxide produced can be used to make sulfuric acid. The metal oxide is heated in a blast furnace with coke (Figure 9.10). Carbon reduces the oxide to the metal:



Zinc vapour passes out of the furnace and is cooled and condensed (note particularly the condensing tray at the

top of the furnace in Figure 9.10). Zinc is used in alloys such as brass and for galvanising iron.

Study tip

As with the blast furnace for extracting iron, you should be able to recognise a diagram of the furnace for zinc extraction. You must be able to label a diagram, including the key feature of the condensing tray to collect the molten zinc. This is quite different from the blast furnace for iron.

The extraction of copper

Copper is less reactive than the other metals we have considered so far. It can be found native in the USA, but most copper is extracted from copper pyrites, CuFeS₂.

A The copper produced from this ore is suitable for piping, boilers and cooking utensils. When it is to be used for electrical wiring, it must be refined (purified) by electrolysis (see page 114).

Figure 9.11 summarises the overall approach to chemically extracting metals such as iron, zinc and copper that sit in the middle to lower range of the reactivity series from their ores.

Activity 9.3 The extraction of copper and the reactivity series

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity explores the reactivities of copper, hydrogen and carbon using microscale apparatus. The aim is to see whether copper(II) oxide can be reduced to copper by either hydrogen or carbon.

A worksheet is included on the CD-ROM. Details of a scaled-up version of this experiment are given in the Notes on Activities for teachers/technicians.




Figure 9.10 A blast furnace for extracting zinc.

Questions

- 9.1 Why is limestone added to the blast furnace?
- 9.2 Write an equation for the reduction of iron(III) oxide.
- 9.3 Which element is used to remove the carbon from cast iron?
- 9.4 Why is chromium sometimes added to steel?
- 9.5 Which **two** substances are essential for the rusting of iron?
- 9.6 Give **two** ways in which zinc can be used to stop the rusting of iron.
- 9.7 How is zinc separated from the rest of the substances in the blast furnace?
- 9.8 Why is it sometimes necessary to purify copper by electrolysis?




Figure 9.11 A summary of the metal extraction methods using reduction by carbon.

9.2 The extraction of metals by electrolysis

Reduction with carbon does not work for more reactive metals. The metals are held in their compounds (oxides or chlorides) by stronger bonds which need a lot of energy to break them. This energy is best supplied by electricity. Extracting metals in this way is a three-stage process:

- ♦ mining the ore
- ♦ purification of the ore
- ♦ electrolysis of the molten ore.

The extraction of a metal by electrolysis is expensive. Energy costs to keep the ore molten and to separate the ions can be very high. Because of this, many of these metals are extracted in regions where hydroelectric power is available. Aluminium plants are the most important examples. They produce sufficient aluminium to make it the second most widely used metal after iron.

The extraction of aluminium

Bauxite, the major ore of aluminium, takes its name from the mediaeval village of Les Baux in France, where it was first mined (Figure 9.12). Napoleon III saw its possibilities for military purposes and ordered studies on its commercial production. A method of extraction using sodium to displace aluminium from aluminium chloride existed at that time. However,



Figure 9.12 The major ore of aluminium is bauxite. It is usually mixed with iron(III) oxide, which gives the ore its brown colour.

in 1886, the Hall–Héroult electrolytic method for extracting aluminium was invented by Hall (an American) and Héroult (a Frenchman).

The Hall–Héroult process

Bauxite (Figure 9.12) is an impure form of aluminium oxide. Up to 25% of bauxite consists of the impurities iron(III) oxide and sand. The iron(III) oxide gives it a red-brown colour.

The Hall–Héroult process involves the following stages.

- 1 The bauxite is treated with sodium hydroxide to obtain pure aluminium oxide (alumina). The alumina produced is shipped to the electrolysis plant.
- 2 The purified aluminium oxide (Al_2O_3) is dissolved in molten cryolite (sodium aluminium fluoride, Na_3AlF_6). Cryolite is a mineral found naturally in Greenland. It is no longer mined commercially there, and all the cryolite now used is made synthetically. Cryolite is used to lower the working temperature of the electrolytic cell. The melting point of aluminium oxide is 2030°C . This is reduced to $900\text{--}1000^\circ\text{C}$ by dissolving it in cryolite. The cryolite thus provides a considerable saving in energy costs.
- 3 The molten mixture of aluminium oxide and cryolite is electrolysed in a cell fitted with graphite electrodes (Figure 9.13).






Figure 9.13 A cross-section of the electrolytic cell for extracting aluminium. At the cathode: $\text{Al}^{3+} + 3\text{e}^- \rightarrow \text{Al}$. At the anode: $2\text{O}^{2-} \rightarrow \text{O}_2 + 4\text{e}^-$.

Aluminium ions are attracted to the cathode where they are discharged to form liquid aluminium metal:



Oxide ions are attracted to the anode where they are discharged to form oxygen gas. At the high temperature of the cell this reacts with the carbon of the anode to form carbon dioxide:



The anodes burn away and have to be replaced regularly.

The Hall-Héroult process uses a great deal of energy. It is also costly to replace the anodes, which are burned away during the process. It is **much** cheaper to recycle the metal than to manufacture it. The energy requirement for recycling is about 5% of that needed to manufacture the same amount of 'new' metal (see page 247).

Other industrial electrolytic processes

Anodising aluminium

The protective layer of oxide that covers the surface of aluminium can be artificially thickened by anodising. The aluminium is used as the anode in an electrolytic cell which contains dilute sulfuric acid and has a carbon cathode. The oxygen produced at the anode reacts with the aluminium, thickening the oxide film. A coloured dye can be included during electrolysis; the oxide layer formed traps the dye to give a coloured surface to the metal.

Electroplating and copper refining

When electrolytic cells are set up with appropriate metal electrodes, metal can be effectively transferred from the anode to the cathode. Such methods can be used to plate objects with metals such as chromium or tin, or to refine copper to a very high degree of purity (see page 114).

Questions

- 9.9** Why is aluminium expensive to extract?
9.10 Why is cryolite added to the cell as well as alumina?
9.11 Why do the anodes need replacing regularly?
9.12 Write an equation for the reaction at the cathode.
9.13 Aluminium is a reactive metal. Why, then, is it useful for window frames and aircraft?

9.3 Ammonia and fertilisers

The Haber-Bosch process for the synthesis of ammonia was one of the most significant new ideas of the twentieth century. It was developed in 1913 following Haber's earlier experiment (Figure 9.14, overleaf), and it allowed industrial chemists to make ammonia cheaply and on a huge scale.

Ammonia has the following general properties as a gas:

- ◆ colourless
- ◆ distinctive smell
- ◆ less dense than air
- ◆ very soluble in water to give an alkaline solution.

As a raw material for both fertilisers and explosives, ammonia played a large part in human history. It helped to feed a growing population in peacetime, and it was used to manufacture explosives in wartime.

Nitrogen is an unreactive gas, and changing it into compounds useful for plant growth (**nitrogen fixation**) is important for agriculture. Most plants cannot directly use (or fix) nitrogen from the air. The main purpose of industrial manufacture of ammonia is to make agricultural fertilisers.





Figure 9.14 Haber's original experimental apparatus, designed for adjusting the pressure of the reacting mixture.

In the Haber process (Figure 9.15), nitrogen and hydrogen are directly combined to form ammonia:



Nitrogen is obtained from air, and hydrogen from natural gas by reaction with steam. The two gases are mixed in a 1 : 3 ratio and compressed to 200 atmospheres. They are then passed over a series of catalyst beds containing finely divided iron. The temperature of the converter is about 450 °C. The reaction is reversible and does not go to completion. A mixture of nitrogen, hydrogen and ammonia leaves the converter. The proportion of




Figure 9.15 A schematic drawing of the different stages of the Haber process. Nitrogen and hydrogen are mixed in a ratio of 1 : 3 at the start of the process.




Figure 9.16 The uses of ammonia produced by the Haber process.

ammonia in the mixture is about 15%. This is separated from the other gases by cooling the mixture. Ammonia has a much higher boiling point than nitrogen or hydrogen, so it condenses easily. The unchanged nitrogen and hydrogen gases are re-circulated over the catalyst. By re-circulating in this way, an eventual yield of 98% can be achieved. The ammonia produced is stored as a liquid under pressure.

Study tip


For the Haber process, and the Contact process for making sulfuric acid, it is important that you know the conditions used and how these are chosen. Remember these are both reversible reactions that reach an equilibrium under the conditions used (see Section 7.5).

Most of the ammonia produced is used to manufacture **fertilisers**. Liquid ammonia itself can in fact be used directly as a fertiliser, but it is an unpleasant liquid to handle and to transport. The majority is converted into a variety of **solid** fertilisers. A substantial amount of ammonia is converted into nitric acid by oxidation (Figure 9.16).

Ammonium nitrate and other fertilisers

Ammonium nitrate ('Nitram') is the most important of the **nitrogenous** fertilisers. It contains 35% by mass of

nitrogen. It is produced when ammonia solution reacts with nitric acid:



The ammonium nitrate can be crystallised into pellet form suitable for spreading on the land.

Study tip

Writing equations for neutralisation reactions involving ammonia solution is the one time when a neutralisation equation does not involve water as one of the products. The equation is simply: ammonia plus the acid gives the salt.

Ammonium nitrate is soluble in water, as are all other ammonium salts, for example ammonium sulfate, $(\text{NH}_4)_2\text{SO}_4$. This solubility is important because plants need soluble nitrogen compounds that they can take up through their roots. There are two types of nitrogen compounds that plants can use – ammonium compounds (which contain the NH_4^+ ion) and nitrates (which contain the NO_3^- ion). Ammonium nitrate provides both these ions.

Ammonium salts tend to make the soil slightly acidic. To overcome this, they can be mixed with chalk (calcium carbonate), which will neutralise this effect. 'Nitro-chalk' is an example of a **compound fertiliser**.

A modern fertiliser factory will produce two main types of product:

- ♦ **straight N fertilisers** are solid nitrogen-containing fertilisers sold in pellet form, for example ammonium nitrate (NH_4NO_3), ammonium sulfate ($(\text{NH}_4)_2\text{SO}_4$) and urea ($\text{CO}(\text{NH}_2)_2$)
- ♦ **NPK compound fertilisers** (Figure 9.17) are mixtures that supply the three most essential elements lost from the soil by extensive use, namely nitrogen (N), phosphorus (P) and potassium (K). They are usually a mixture of ammonium nitrate, ammonium phosphate and potassium chloride, in different proportions to suit different conditions.

The production process for an NPK fertiliser is complex. It involves the production not only of ammonia, but also of sulfuric acid and phosphoric



Figure 9.17 Some fertiliser products; note the three key numbers (N:P:K) on the fertiliser bags.


acid. A fertiliser factory is not just a single unit but six separate plants built close together on the same site (see the aerial view of the factory complex on Burrup Peninsula, Western Australia, Figure 9.32, page 246).

Activity 9.4 Making a fertiliser

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

The introduction of the Haber process revolutionised agriculture by making it possible to manufacture artificial fertilisers. An example is ammonium sulfate and it is made in this activity by neutralising sulfuric acid with ammonia solution:



The ammonium sulfate solution can be concentrated by heating. It is then cooled to allow crystals to form.

A worksheet is included on the accompanying CD-ROM.

Why fertilisers are important for plants

Plants make their own food by photosynthesis from carbon dioxide and water. They also need other

chemicals for producing healthy leaves, roots, flowers and fruit. They get these chemicals from minerals in the soil. When many crops are grown on the same piece of land, these minerals get used up and have to be replaced by **artificial fertilisers**. The three most important additional elements which plants need are:

- ♦ **nitrogen (N)**, which is specially important for healthy leaves
- ♦ **phosphorus (P)**, specially important for healthy roots
- ♦ **potassium (K)**, which is important for the production of flowers and fruit.

Different plants need different combinations of these elements, which is why NPK fertilisers are produced. The NPK value (Figure 9.17) informs the farmer how much of each element is present. Fruits like apples and tomatoes need a lot of potassium, whereas leafy vegetables like cabbage need a lot of nitrogen and root crops like carrots need a lot of phosphorus.

Questions

- 9.14 How is hydrogen obtained for use in the Haber process?
- 9.15 What conditions are needed to ensure the Haber process works efficiently?
- 9.16 Why are the unreacted gases re-circulated?
- 9.17 Why do many fertilisers contain N, P and K?
- 9.18 How can fertilisers cause pollution?

9.4 Sulfur and sulfuric acid

Sulfuric acid is a major product of the chemical industry. It is made from sulfur by the Contact process.

Sulfur is produced as a by-product of the petrochemical industry, as it is removed from fuels such as gasoline before they are sold for use. It can also be obtained from the craters of volcanoes (Figure 9.18) and is mined by pumping steam into sulfur beds underground. The sulfur is then forced to the surface by compressed air. This method of mining is called the **Frasch process** (Figure 9.19).

Sulfur is then burned in air to form sulfur dioxide. The main reaction in the Contact process (Figure 9.20, page 240) is the one in which sulfur dioxide and oxygen combine to form sulfur trioxide. This reaction is reversible. The conditions needed to give the best

S equilibrium position are carefully considered. A temperature of 450°C and 1–2 atmospheres pressure are used. The gases are passed over a catalyst of vanadium(v) oxide. A yield of 98% sulfur trioxide is achieved. The overall process is summarised in the flow chart shown in Figure 9.20b (overleaf).

The sulfur trioxide produced is dissolved in 98% sulfuric acid, and not water, in order to prevent environmental problems of an acid mist which is formed if sulfur trioxide is reacted directly with water. The reaction between sulfur trioxide and water is extremely exothermic. The solution formed means that the acid can be transported in concentrated form (98.5% acid, sometimes known as **oleum**) and then diluted on-site.

Sulfuric acid is important for the fertiliser industry because it is needed to make ammonium sulfate and phosphoric acid. Figure 9.21 (overleaf) summarises the various uses of sulfuric acid.

The uses of sulfur compounds

Sulfur dioxide is an important compound in its own right. It is used in the manufacture of paper. When made from wood pulp or from other materials, paper is usually pale yellow in colour. Sulfur dioxide is used to bleach it to the white colour which is needed. Sulfur




Figure 9.18 A man carrying baskets of sulfur deposits from around the crater lake in Ijen volcano, Java.

dioxide is used in preference to chlorine as it is less harmful to the environment.

Sulfur dioxide is also used in the food industry. It is used to kill bacteria in foods to prevent them from 'going bad'. Examples of foods where it is used include dried apricots and wine.

When concentrated, sulfuric acid is very dangerous. It is a powerful dehydrating agent and oxidising agent and can cause very severe burns.




Figure 9.19 Sulfur is mined from underground deposits using super-heated water and compressed air.





Figure 9.20 a The Contact process plant at Billingham, Teesside, in the UK. b A flow chart for making sulfuric acid by this process.




Figure 9.21 The uses of sulfuric acid.

Concentrated sulfuric acid is:

- ◆ a powerful dehydrating agent
- ◆ a powerful oxidising agent
- ◆ very corrosive.

Key definition



dehydration – the removal of water, or the elements of water, from a substance.

The dehydrating properties of the concentrated acid can be demonstrated in the laboratory by its reaction with sugar (sucrose) as shown in Figure 9.22. Sugar is a carbohydrate – it contains carbon, hydrogen and



Figure 9.22 Concentrated sulfuric acid will dehydrate sugar: **a** the start of the reaction, and **b** when it is completed.

oxygen. The concentrated acid removes the hydrogen and oxygen as water, leaving carbon behind:



The acid will dehydrate other carbohydrate materials, such as paper, clothing and wood, in a similar way.

When dilute, sulfuric acid is safer, but it is still a strong acid with normal acid properties (see page 131).

Questions

- 9.19** Write an equation for the burning of sulfur.
9.20 What conditions are needed to convert sulfur dioxide into sulfur trioxide?
9.21 Why is sulfur trioxide not reacted with water to make sulfuric acid?
9.22 Give **two** uses of sulfur dioxide and **two** uses of sulfuric acid.

9.5 The chlor-alkali industry

The chlor-alkali industry is a major branch of the chemical industry that has been built up around a single electrolysis reaction. The industry is centred around the electrolysis of concentrated sodium chloride solution (**brine**). Three different types of electrolytic cell have been used for this process.

- ◆ **Mercury cathode cell:** In this, sodium (Na) is produced at, and dissolves in, the flowing mercury (Hg) cathode. Sodium hydroxide is produced by treating the Na-Hg cathode material with water.
- ◆ **Diaphragm cell:** Here the products of electrolysis are kept separate by an asbestos diaphragm.
- ◆ **Membrane cell:** This is the most modern system, and it uses a selective ion-exchange membrane (see page 110) to keep the products apart.

All three systems are currently in use, but the membrane cell is likely to replace the others.

In all three processes, chlorine is produced at the anode (positive electrode) and hydrogen is produced at the cathode (negative electrode). Sodium ions from the sodium chloride and hydroxide ions from the water are left behind as sodium hydroxide. All three products are useful; their uses are summarised in Figure 9.23, overleaf.

In Britain, the industry has developed around the Cheshire salt deposits (see page 245). In this region, salt is brought to the surface by both underground mining and solution mining. One factory in Cheshire uses 1% of the entire UK electricity output just to electrolyse brine.

The uses of chlorine

One use of chlorine we tend to be aware of is its use in water treatment, both for the domestic water supply (see page 11) and for swimming pools (Figure 9.24). Chlorine is also used in the manufacture of bleach and to make the plastic PVC.

Taken together, the **halogens** are a very important group of elements. Because of their reactivity, they form a wide range of useful compounds, including polymers, solvents, bleaches and disinfectants. Their uses are summed up in Table 9.3 (overleaf).




Figure 9.23 The chlor-alkali industry.



Figure 9.24 The water of our swimming pools is chlorine-treated to kill harmful bacteria.

Halogen	Product and/or use
fluorine	fluoride in toothpaste and drinking water PTFE – non-stick coating for pans, etc.
chlorine	water treatment bleach PVC – plastic pipes, windows, clothing fabric, etc. solvents for dry-cleaning and degreasing disinfectants and antiseptics pesticides
bromine	flame retardants pesticides petrol additives photographic film
iodine	antiseptics photographic film and paper

Table 9.3 The halogens are involved in the making of a wide range of useful products.

? Questions

- 9.23** Give two important uses of chlorine.
- 9.24** What is brine?
- 9.25** Why is the electrolysis of brine such an important process?
- 9.26** What is the most efficient method of electrolysing brine?

9.6 Limestone

Limestone is quarried (Figure 9.25) in large amounts world-wide. It has a wide range of uses (see page 14). In some of these, the limestone is used directly; in others, it acts as a raw material for making other compounds.

Direct uses of limestone

Powdered limestone is often used to neutralise acid soils and lakes acidified by acid rain. It is cheaper than using lime (calcium oxide), which has to be produced by heating limestone. In the blast furnace for the extraction of iron, limestone is used to remove impurities found in the iron ore as slag (calcium silicate).

Cement is made by heating powdered limestone with clay in a rotary kiln (Figure 9.26). This material is then powdered and mixed with gypsum (calcium sulfate, $\text{CaSO}_4 \cdot 2\text{H}_2\text{O}$). When water is added to this mixture, complex chemical changes take place, giving a hard interlocked mass of crystals of

hydrated calcium aluminate ($\text{Ca}(\text{AlO}_2)_2$) and calcium silicate (CaSiO_3).

Concrete is a mixture of cement and aggregate (stone chippings and gravel), which give it body. The mixture is mixed with water and can be poured into wooden moulds. It is then allowed to harden. Reinforced concrete is made by allowing the concrete to set around steel rods or mesh (Figure 9.27).

Sodium carbonate (Na_2CO_3) is an important industrial chemical, which is manufactured from limestone. It is used in the manufacture of glass (Figure 9.28, overleaf), soaps, detergents, paper, dyes and other chemicals.

The manufacture of lime (calcium oxide)

Lime (quicklime) is calcium oxide and is produced by roasting limestone in a lime kiln (Figure 9.29, overleaf). The limestone is decomposed by heat:

calcium carbonate
 $\xrightarrow{\text{heat}}$ calcium oxide + carbon dioxide



Lime is used in agriculture to neutralise acid soils and to improve drainage in soils that contain a large amount of clay. It is used with sodium carbonate and sand in making glass. Large amounts of lime are converted into slaked lime (hydrated lime), which is calcium hydroxide ($\text{Ca}(\text{OH})_2$). Equal amounts of lime and water are mixed to produce this material. It is used to make bleaching powder, in making glass and

for water purification. It is mixed with sand to give mortar. When mixed with water and then allowed to dry, mortar sets into a strongly bonded material to hold bricks together: the calcium hydroxide reacts with carbon dioxide in the air to form calcium carbonate.




Figure 9.26 Limestone is used to make cement.



Figure 9.25 A limestone quarry in Maizeret, Belgium.



Figure 9.27 Construction workers using a pump to lay concrete around a mesh of metal rods. The rods will strengthen this reinforced concrete.




Figure 9.28 Making glass.




Figure 9.29 **a** A functioning rotary lime kiln in Belgium. Note the heated glow at the far end of the kiln. **b** A diagram of a rotary kiln.

Study tip

Remember that the reaction involved in the production of lime is an example of **thermal decomposition**. The calcium carbonate is not reacting with anything else. It is breaking up into simpler substances because of the high temperature. When you write the equation, do not try to include anything else on the left-hand side of the equation.

Questions

- 9.27** Why is limestone sometimes added to lakes?
- 9.28** How is limestone used in iron production?
- 9.29** Write an equation for the thermal decomposition of limestone.
- 9.30** Write the chemical formula of slaked lime.
- 9.31** Give two important uses of lime.

9.7 The economics of the chemical industry

Siting a chemical plant

When building a chemical processing plant, many things need to be taken into consideration. Some of the most important are:

- ◆ availability of the raw materials needed by the process
- ◆ transport links for importing raw materials and export of products
- ◆ availability of a workforce
- ◆ nearness of customers for the products
- ◆ environmental considerations.

The chlor-alkali industry in the UK

The map (Figure 9.30) shows the location of the industry.

- ◆ The only raw material is salt, which is obtained from the rock salt deposits in Cheshire. The major salt mine here is the Winsford mine.
- ◆ Transport links are plentiful, with motorways, railways and seaports all close at hand.
- ◆ Greater Manchester with its large population provides the workforce.
- ◆ There are many other chemical industries in the area which use the hydrogen, chlorine and sodium hydroxide produced in their own processes.
- ◆ The process itself causes few environmental problems. The salt is extracted by solution mining. Water is pumped down into the salt deposits, where it dissolves salt to become brine as it rises back to the surface.

The fertiliser industry in Burrup, Western Australia

This is the largest ammonia plant of its type in the world. It can produce 760 000 tonnes of liquid ammonia a year.

- ◆ The raw materials for the production of ammonium nitrate fertiliser are air and natural gas (Figure 9.31). This factory is situated next to the onshore base for an offshore gas field (Figure 9.32, overleaf).
- ◆ The products are transported to customers from the deep-water port by ship. They are transported directly to the port by pipeline.




Figure 9.30 The location of the chlor-alkali industry in Cheshire, England.




Figure 9.31 A summary of the steps involved in the Haber process.

A



Figure 9.32 An aerial view of the ammonia and fertiliser plants on the Burrup Peninsula, Western Australia.

- ◆ The process is largely automated and the workforce needed is not large.
- ◆ Australian and worldwide customers are supplied by sea.
- ◆ The Burrup peninsula is an area well known for its Aboriginal art. The companies involved in the development contribute to its preservation.

The environmental costs of industry

Any factory has an effect on its surroundings. In the case of a chemical plant, the effects can be serious. There have been a number of accidents in different parts of the world, where something has gone wrong with disastrous results. Most chemical plants, however, run successfully without causing any great harm. The ways in which the environment could be affected are as follows.

- ◆ **Air pollution:** Acidic or poisonous gases are often produced in chemical processes. At one time these gases were released into the atmosphere, causing health problems nearby and acid rain further afield. Nowadays, gases have to be treated before they are released into the atmosphere to make sure anything harmful is removed. For example, acidic gases are removed by 'scrubbing' – passing them over an alkaline material with which they react. This removes them from the waste gases before they are released.
- ◆ **Water pollution:** Liquid waste and cooling water from chemical plants were, at one time, released into rivers. Now this waste must be treated first. Water boards and river authorities test the water leaving



Figure 9.33 Orchids growing on a reclaimed quarry site.

chemical plants to ensure it is clean, and chemical companies receive large fines if they fail to stick to the rules. For example, poisonous metal compounds are removed by adding sodium hydroxide, which removes the metals as a precipitate that can be filtered out.

- ◆ **Land pollution:** Chemical processes often produce solid waste which used to be left in large 'spoil heaps'. These often contained poisonous substances. Most countries in the world still have areas of land where it is not safe to live because of poisons in the ground. Solid waste products now have to be treated to make them harmless, and then have to be disposed of safely.
- ◆ **Appearance of the surroundings:** Quarrying and mining can leave the land surrounding a chemical plant looking very much the worse for wear. Chemical companies now have a responsibility, when they have finished using land, to restore it to the sort of environment it used to be (Figure 9.33).

All of these responsibilities placed on chemical companies increase the cost of producing the chemicals which they make, but they decrease the cost to the environment and make the world a more pleasant place to live in.

Recycling

Recycling used substances is good for three reasons:

- ◆ it conserves the raw materials which the substances were made from
- ◆ often uses less energy to recycle something than would be needed to make it from raw materials

- ◆ avoids the need to bury the substances in landfill sites, possibly causing pollution.

Many substances can be recycled. Some of those most commonly recycled are aluminium, steel, glass, plastics and paper.

Aluminium

This metal is the ideal candidate for recycling because it costs so much to extract it from its ore. Using recycled aluminium saves 95% of the energy needed to make new aluminium. Recycling one aluminium can saves enough energy to run a television for 3 hours. Around 60% of the aluminium used in the UK and 50% worldwide is recycled.



(aluminium)

Steel

Steel, too, is cheaper to recycle than to make from scratch but the difference in cost is not as great as for aluminium. However, steel is easy to recycle because it is magnetic and so can easily be separated from other rubbish. For this reason, quite a lot of steel is recycled.



(steel)

Glass

If glass is left in landfill, it never decomposes. Recycling it saves energy. Recycling one glass bottle saves enough energy to run a light bulb for 4 hours. It is important to separate different colours of glass. In the UK, clear glass is needed most, whereas in Europe, green glass is in greater demand.



(glass)

Plastics

PET and HDPE are the commonest plastics used, and both can be recycled. A plastic bottle takes around 700 years to decompose in landfill, and recycling one bottle saves enough energy to keep a light bulb lit for 6 hours. When recycling plastic, the different types of plastic need to be kept separate.



(plastics)



(plastics)

Paper

Paper has been recycled for many years. Recycling uses more than 60% less energy than making new paper from trees. In Europe, around 54.6% of paper is recycled and in the USA, around 53.4%.



(paper)

Recycling not only saves energy and raw materials: it avoids the need for huge piles of rubbish in landfill sites. The highest point in the state of Ohio, USA, is Mount Rumpke at a height of 1000 ft. It is made of rubbish.

? Questions

- 9.32 Why is the recycling of aluminium the most profitable type of recycling?
- 9.33 Saving energy is one reason for recycling. What other reasons are there?
- 9.34 Why can recycling plastics be difficult?

Summary

You should know:

- ◆ the chemistry involved in the production of iron and steel
 - the reduction of iron ore (hematite) in the blast furnace
 - the production of mild steel by the basic oxygen process
- S ◆ the uses of different types of steel alloys
- the problem of the rusting of iron and steel structures
- barrier methods of preventing the rusting of iron and steel
- S ◆ the use of sacrificial protection to prevent rusting
- ◆ how the extraction of other metals is linked to their reactivity
- S ◆ the extraction of zinc
- S ◆ the extraction of aluminium from its ore (bauxite) by electrolysis
- S ◆ the protective oxide layer which prevents the corrosion of aluminium
- S ◆ the chemistry involved in the production of ammonia by the Haber process
 - the use of ammonia in the manufacture of fertilisers
 - the importance of NPK (nitrogen, phosphorus and potassium) fertilisers
- S ◆ the chemistry involved in the production of sulfuric acid
 - sources of the element sulfur
 - the uses of sulfur dioxide
 - S ◆ the uses of dilute and concentrated sulfuric acid
- ◆ how the electrolysis of brine forms useful products
 - the uses of chlorine, sodium hydroxide and hydrogen
- ◆ about the importance of limestone as a raw material
 - the production of lime in a lime kiln
 - the uses of lime and slaked lime
 - the use of limestone in iron production and to make cement
- ◆ the costs to the environment from pollution
- ◆ the advantages of recycling.

End-of-chapter questions


- 1 Apart from saving money, why is it important to recycle as many substances as possible?
- 2 A farmer uses slaked lime ($\text{Ca}(\text{OH})_2$) and ammonium sulfate to increase the fertility of his fields.
 - a What type of soil might the farmer use lime on? [1]
 - b Which essential element will ammonium sulfate add to the soil? [1]
 - c What reaction could take place between slaked lime and ammonium sulfate? [2]
Lime (CaO) is manufactured from limestone by heating it strongly.
 - d What is the chemical formula of limestone? [1]

- e Write a symbol equation for the reaction which occurs when limestone is changed to lime. [2]
 f How is lime changed into slaked lime? [1]

Ammonium sulfate is manufactured by reacting ammonia with sulfuric acid. Ammonia is manufactured by the Haber process and sulfuric acid by the Contact process.

- g Write an equation for the main reaction in the Haber process and give the conditions used. [4]
 h Write an equation for the main reaction in the Contact process and give the conditions used. [4]


- 3 The diagram shows an experiment to investigate the rusting of some iron nails.



- a For each tube, A, B and C, predict whether the nails will rust. In each case give a reason. [3]
 b Iron from the blast furnace contains impurities such as carbon, phosphorus, silicon and sulfur. Describe how the level of these impurities is decreased when steel is made from impure iron. [3]
 c State a use for stainless steel. [1]

[Cambridge IGCSE® Chemistry 0620/2, Question 7(a–c), November 2009]


- 4 Iron is extracted from its ore, hematite, in the blast furnace.




Describe the reactions involved in this extraction. Include in your description an equation for a redox reaction and one for an acid/base reaction. [5]

[Cambridge IGCSE® Chemistry 0620/32, Question 4, June 2011]

- 5 The diagram shows a basic oxygen converter. This is used to convert impure iron from the blast furnace into steel. During this process, some of the impurities in the iron are converted into a slag.



- a Label a copy of the diagram to show each of the following:
- i where the oxygen enters
 - ii the slag
 - iii the molten steel.
- b In the converter, the oxygen oxidises sulfur, carbon and phosphorus to their oxides.
- i Explain why sulfur dioxide and carbon dioxide are easily removed from the converter.
 - ii Explain how calcium oxide is used to remove phosphorus(v) oxide from the converter.
- c Stainless steel is an alloy.
- i Which **one** of the diagrams, A, B, C or D, best represents an alloy?




- ii State **one** use of stainless steel.

[Cambridge IGCSE® Chemistry 0620/21, Question 7, June 2011]

S 6


- a An important ore of zinc is zinc blende, ZnS .
- i How is zinc blende changed into zinc oxide?
 - ii Write a balanced equation for the reduction of zinc oxide to zinc by carbon.
- b A major use of zinc is galvanising; steel objects are coated with a thin layer of zinc. This protects the steel from rusting even when the layer of zinc is broken.



- Explain, by mentioning ions and electrons, why the exposed steel does not rust.

[Cambridge IGCSE® Chemistry 0620/31, Question 3a, b, November 2009]

- S** 7 Aluminium is extracted by the electrolysis of aluminium oxide.



- a Hydrated aluminium oxide is heated to produce pure aluminium oxide.



What type of reaction is this? Choose from these possibilities:

decomposition neutralisation oxidation reduction [1]

- b Explain why the electrolyte must be molten for electrolysis to occur. [1]
c What is the purpose of the cryolite? [1]
d Which letter in the diagram, A, B, C or D, represents the cathode? [1]
e State the name of the products formed at the anode and cathode during this electrolysis. [2]
f Why do the anodes have to be renewed periodically? [2]
g Complete the equation for the formation of aluminium from aluminium ions. [1]
 $\text{Al}^{3+} + \dots\dots\dots \text{e}^- \rightarrow \text{Al}$
h State **one** use of aluminium. [1]

[Cambridge IGCSE® Chemistry 0620/2, Question 6, November 2009]

10

Organic chemistry

In this chapter, you will find out about:

- ◆ the unique properties of carbon
- ◆ hydrocarbons as compounds of carbon and hydrogen only
- ◆ the alkanes and their properties
- S** ◆ isomerism
- ◆ the halogen compounds of the alkanes
- ◆ the alkenes
- ◆ the reactivity of the C=C double bond in alkenes
- S** ◆ addition reactions
- ◆ the alcohols as a homologous series
- ◆ fermentation as a source of ethanol
- S** ◆ comparing the methods of ethanol production
- ◆ the reactions of ethanol
- S** ◆ carboxylic acids as a homologous series
- ◆ ethanoic acid as a weak acid
- S** ◆ esterification.

Carbon's amazing versatility

Carbon is a non-metal in Group IV of the Periodic Table. It forms covalent compounds. The uniqueness of carbon lies in the different ways in which it can form bonds. This shows itself even in the element itself. Carbon exists in several different forms. Two of the forms we have met earlier: diamond and graphite (see page 83). A third form, the fullerenes (Figure 10.1) and carbon nanotubes, have been discovered relatively recently and their exploitation is one of the major features of the exciting new area of research referred to as **nanotechnology**.

The ring structures that carbon can form have been highlighted recently in the revolutionary images

of pentacene. The bonding in this hydrocarbon molecule has been observed electronically using an atomic force microscope. This microscope is able to probe structures at an atomic level. The images produced are the first to show the bonds in a molecule. It is even possible to see the bonds between the outer carbon atoms and the hydrogen atoms attached to them. This image joins the other iconic visualisations of the atomic world produced by this microscope technology, including the 'IBM logo' (see Chapter 2, Figure 2.22).

The remarkable versatility and complexity of the structures that carbon is able to form is the very basis of the different forms of life here on Earth.




Figure 10.1 **a** A computer image of the structure of carbon-60 (C_{60}) – the first fullerene to be discovered. The structure resembles the panelled structure of a modern soccer ball. **b** The revolutionary image of pentacene from the IBM research laboratory in Zurich (With kind permission of IBM Research - Zurich).

10.1 The unique properties of carbon

Amino acids, simple sugar molecules and even fats may be relatively simple molecules but the construction of complex molecules, such as long-chain carbohydrates and proteins, shows the versatility of carbon-containing compounds. The peak of this complexity must be DNA (deoxyribonucleic acid), the molecule that makes life possible (Figure 10.2).

Carbon is unique in the variety of molecules it can form. The chemistry of these molecules is a separate branch of the subject known as **organic chemistry**. Organic chemistry is the chemistry of carbon-containing compounds.

There are three special features of **covalent bonding** involving carbon:

- ♦ Carbon atoms can join to each other to form long chains. Atoms of other elements can then attach to the chain.
- ♦ The carbon atoms in a chain can be linked by single, double or triple covalent bonds.
- ♦ Carbon atoms can also arrange themselves in rings.

Only carbon can achieve all these different bonding arrangements to the extent that we see. Indeed, there are more compounds of carbon than of all the other elements put together. Figure 10.3 gives some idea of how these bonding arrangements can produce different types of molecules.





Figure 10.2 Two ways of showing a section of the complex molecule DNA.




Figure 10.3 Carbon is very versatile.

Questions

- 10.1 What type of bonding do carbon atoms normally participate in?
- 10.2 What is the valency of carbon?
- 10.3 What are the two different structural forms of carbon? What is the name of the new form of carbon, discovered relatively recently?
- 10.4 What are the names of two different carbon-containing molecules that are important for living organisms?

10.2 Alkanes

What is a hydrocarbon?

Around six million compounds of carbon are already known! Because there are so many, it is helpful to pick out those compounds which have similar structures. One of the simplest types of organic compound is the **hydrocarbons**.

Key definition

hydrocarbon – a compound that contains carbon and hydrogen only.

The hydrocarbons that we study at this level can be subdivided into two 'families'. Some hydrocarbons are **saturated**. These molecules contain **only** single covalent bonds between carbon atoms. Since carbon has a valency of 4, the bonds not used in making the chain are linked to hydrogen atoms (see Figure 10.3, overleaf). No further atoms can be added to molecules of these compounds. This family of saturated hydrocarbons is known as the **alkanes**.

Key definition

alkanes – saturated hydrocarbons.

Molecules of these compounds contain only **single bonds** between the carbon atoms in the chain and they have the general molecular formula C_nH_{2n+2} .

Table 10.1 gives the names and formulae of the first six members of the series of alkanes. The simplest alkane contains one carbon atom and is called methane. Note that the names of this series of hydrocarbons all end in *-ane*. The first part of the name (the **prefix**) tells you the number of carbon atoms in the chain. These prefixes are used consistently in naming organic compounds.

The formulae given in Table 10.1 are the **molecular formulae** of the compounds. Each molecule increases by a $\text{—CH}_2\text{—}$ group as the chain gets longer (see Figure 10.3). Indeed, the formulae of long-chain alkanes can be written showing the number of $\text{—CH}_2\text{—}$ groups in the chain. For example, octane (C_8H_{18}) can be written as $\text{CH}_3\text{—}(\text{CH}_2)_6\text{—CH}_3$. The formulae of these molecules all fit the general formula $\text{C}_n\text{H}_{2n+2}$ (where n is the number of carbon atoms present).

In organic chemistry, the **structure** of a molecule is also very important. Figure 10.4 shows the structural formulae of the first six alkanes in the series. A **structural formula** shows the bonds between the atoms. As the length of the hydrocarbon chain increases, the strength of the weak forces between the molecules (**intermolecular forces** or van der Waals' forces) is increased. This shows itself in the increasing boiling points of the members of the series (Table 10.1). The melting points and boiling points of the alkanes increase gradually. Under normal conditions, the first four members of the family are gases, and those between C_5H_{12} and $\text{C}_{16}\text{H}_{34}$ (which in short are called C_5 to C_{16} alkanes) are liquids. The compounds in the alkane family with 17 or more carbon atoms are waxy solids.

Every organic compound has three different formulae. The first of these is the **empirical formula** (see page 160). This formula is the simplest possible whole-number ratio of the atoms in a compound; thus for methane it is CH_4 , but for ethane it is CH_3 .

The second formula for any compound, and the most crucial, is the **molecular formula**. This represents the actual number of atoms present in the molecule; thus for methane it is CH_4 , for ethane it is C_2H_6 , and so on.

The final formula for any compound, and a highly important one, is the **structural formula** of the molecule of the compound. This formula shows all the atoms in the molecule and how they are bonded together. The structural formulae of the first six alkanes are shown in Figure 10.4 (overleaf).

Study tip

It is important to think carefully when you are asked to give the formula of a compound. Make sure you realise whether you are being asked for the molecular formula or the structural formula, and give the correct type.

When giving the structural formula of a compound, make sure you show all the atoms and all the bonds.

Remember, too, to count the bonds around each carbon atom you draw; there can only be four. It is worth practising drawing some of the regular molecules that are asked about.

Alkane	Molecular formula $\text{C}_n\text{H}_{2n+2}$	Number of carbon atoms	Boiling point / $^{\circ}\text{C}$		Physical state at room temperature
methane	CH_4	1	−164		gas
ethane	C_2H_6	2	−87		gas
propane	C_3H_8	3	−42		gas
butane	C_4H_{10}	4	0		gas
pentane	C_5H_{12}	5	+36		liquid
hexane	C_6H_{14}	6	+69		liquid

Table 10.1 Some details of the early members of the alkane series.






Figure 10.4 The structures of the first six alkanes.

Burning alkanes

One chemical property that all these alkanes have in common is that they burn very exothermically (Figure 10.5). They make good fuels. Controlling their availability and cost can have great political consequences. When they burn in a good supply of air, the products are carbon dioxide and water vapour:



Methane forms the major part of natural gas. Propane and butane burn with very hot flames and are sold as liquefied petroleum gas (LPG). They are kept as liquids under pressure, but they vaporise easily when that pressure is released. In areas where there is no mains supply of natural gas, you may have seen propane tanks in gardens, which supply the fuel for heating systems. Cylinders of butane gas are used in portable gas fires in the home. Butane is also used in



Figure 10.5 A spectacular demonstration of methane burning on the hand.

portable camping stoves, blowtorches and gas lighters (Figure 10.6).

A homologous series

The family of alkanes has similar chemical properties. Together they are an example of a **homologous series** of compounds.

Key definition

homologous series – a family of organic compounds that:

- ♦ have the same general formula
- ♦ have similar chemical properties
- ♦ show a gradual increase in physical properties such as melting point and boiling point.

Questions

- 10.5 Write down the names and formulae of the first six alkanes.
- 10.6 Draw the structural formulae of methane and butane.
- 10.7 Plot a graph of the boiling points of the first six alkanes against the number of carbon atoms in the molecule. Comment on the shape of the graph.
- 10.8 What is the formula of the first alkane that is:
a a liquid at room temperature and pressure?
b a solid at room temperature?
- 10.9 Write a word equation for the complete combustion of ethane.
- 10.10 What is the major natural source of methane?
- 10.11 Draw a diagram of the arrangement of the electrons in the bonding of methane, showing just the outer (valency) electrons.



Figure 10.6 A butane portable camping stove.

10.3 Alkenes

Unsaturated hydrocarbons

The ability of carbon atoms to form double bonds gives rise to the **alkenes**. The alkenes are another family of hydrocarbons or homologous series.

Key definition

alkenes – unsaturated hydrocarbons. Molecules of these compounds contain a **C=C double bond** somewhere in the chain and they have the general formula C_nH_{2n} .

Alkenes have the general formula C_nH_{2n} (where n is the number of carbon atoms). Such molecules are unsaturated because it is possible to break this double bond and add extra atoms to the molecule.

The simplest alkene must contain **two** carbon atoms (needed for one C=C double bond) and is called ethene (Figure 10.7). Table 10.2 shows the molecular





Figure 10.7 The structures of the first three alkenes, and the bonding in ethene.

Alkene	Molecular formula C_nH_{2n}	Number of carbon atoms	Boiling point / °C		Physical state at room temperature
ethene	C_2H_4	2	-104	 b.p. increasing	gas
propene	C_3H_6	3	-47		gas
butene	C_4H_8	4	-6		gas
pentene	C_5H_{10}	5	+30		liquid

Table 10.2 Details of the first four alkenes.

formulae of the first alkenes. The boiling points of these compounds again show a gradual increase as the molecules get larger. Figure 10.7 also shows the structures of the first three alkenes.

Alkenes are similar to other hydrocarbons when burnt. They give carbon dioxide and water vapour as long as the air supply is sufficient:




The presence of the $C=C$ double bond in an alkene molecule makes alkenes much more reactive than alkanes (alkanes contain only $C-C$ single bonds). Other atoms can add on to alkene molecules when the double bond breaks open. This difference produces a simple test for unsaturation.

It is the presence of the $C=C$ double bond in an alkene molecule that gives the homologous series its characteristic properties. For this reason the $C=C$ double bond is known as the **functional group** of the alkenes. We will meet other functional groups, such as that for the alcohols ($-OH$), later in the chapter. All the members of a particular homologous series contain the same functional group.

Chemical tests for unsaturation

If an alkene, such as ethene, is shaken with a solution of bromine in water, the bromine loses its colour. Bromine has reacted with ethene, producing a colourless compound:



type of reaction, where a double bond breaks and adds two new atoms, is known as an **addition reaction**. An alkane would give no reaction with bromine water; the solution would stay orange-brown (Figure 10.9). In an addition reaction, two substances add together to form a single product.

A similar colour reaction occurs between alkenes and an acidified dilute solution of potassium manganate(VII). This solution is purple, and it turns colourless when shaken with an unsaturated compound. Again, an alkane would produce no change.




Figure 10.8 The addition of bromine to ethene.




Figure 10.9 The test for unsaturation: bromine water with **a** an alkane and **b** an alkene added and then shaken. The bromine water is decolorised by the alkene. There is no reaction with the alkane.

S The double bond in ethene breaks open and forms new bonds to the bromine atoms (Figure 10.8). This

Activity 10.1

Testing alkanes and alkenes

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity compares the reaction with bromine water of several liquid alkanes and alkenes. The test for unsaturation is demonstrated. Small samples of the liquids are also ignited and the appearance of the flames compared.

A worksheet is included on the CD-ROM.



10.4 Hydrocarbon structure and isomerism



Naming organic compounds

The alkanes are a 'family' (or homologous series) of saturated hydrocarbons. Their names all end in *-ane*; Figure 10.10 shows a model of tetradecane ($C_{14}H_{30}$). The names of the first six alkanes were given in Figure 10.4 (page 256).

The prefixes to the names of the alkanes are standard and indicate the number of carbon atoms in the chain (see Table 10.1, page 255). So a compound in any homologous series with just one carbon atom will always have a name beginning with *meth-*, one with two carbon atoms *eth-*, and so on. Hence the names of the alcohols and carboxylic acids are as shown in Tables 10.4 and 10.6 (pages 265 and 270). When a halogen atom is introduced into a chain, the name of the compound contains a prefix indicating which halogen is present.

The different homologous series all have particular endings to their names (Table 10.3).

Many different organic compounds are formed when a hydrogen in the original alkane 'backbone' is replaced by another group. The product formed when ethene reacts with bromine in solution (Figure 10.8) illustrates the system of naming organic compounds.



- 10.12** Write down the names and molecular formulae of the first **four** alkenes.
- 10.13** Draw the structures of ethene and propene.
- 10.14** What is the common empirical formula of the first **four** alkenes?
- 10.15** What do you observe if ethene is bubbled through bromine water?
- 10.16** Write a word equation for the reaction between ethene and bromine water.
- 10.17** Draw a diagram showing the arrangement of electrons in the bonding of ethene. Show just the outer (valency) electrons.

- ◆ The product has **two** carbon atoms joined by a **single** bond. So it is named after **ethane**.
- ◆ The molecule contains **two bromine** atoms. It is called **dibromoethane**.




Figure 10.10 A model of a straight-chain alkane ($C_{14}H_{30}$).

Homologous series	Name ending	Example
alkane	-ane	propane
alkene	-ene	propene
alcohol	-ol	propanol
carboxylic acid	-oic acid	propanoic acid

Table 10.3 The naming of the different homologous series.


- The bromine atoms are not both attached to the same carbon atom. One bromine atom is bonded to each carbon atom. The carbon atoms are numbered 1 and 2. The full name of the compound is **1,2-dibromoethane**.

Branched-chain alkanes exist where a hydrocarbon side-chain has replaced a hydrogen to produce a more complex molecule. In order to show where this side-chain is attached, we number the carbon atoms in the chain. This means that we can indicate where the side-chain is, in the name. The numbering always starts at one end of the chain. The counting starts at the end which keeps the number of the side-chain position as low as possible. You will see some examples of this numbering in the next section.

S Isomerism


The system of naming compounds emphasises the importance of structure. Molecules with the same molecular formula can have different structures. The same number of atoms can be connected together in different ways. This is known as **isomerism**.

There are two **different** compounds with the molecular formula C_4H_{10} :



burns in air to form CO_2 and H_2O
liquefies at $0^\circ C$

2-methylpropane




colourless gas
burns in air to form CO_2 and H_2O
liquefies at $-12^\circ C$


In butane, all four carbon atoms are arranged in one 'straight' main chain. However, the atoms do not have to be arranged in this way. The fourth carbon atom can go off from the main chain to give the 'Y-shaped' or branched structure of 2-methylpropane. Compounds such as these are known as **isomers**. The properties of these particular isomers are quite similar; the difference shows itself mainly in their melting points and boiling points. Hydrocarbons containing branched chains have lower melting points and lower boiling points than straight-chain compounds with the same number of carbon atoms.

All the **alkane** molecules with four or more carbon atoms possess isomers. For example, there are three isomers with the formula C_5H_{12} . The **alkenes** with four or more carbon atoms can show a different kind of isomerism. In this, the **position** of the $C=C$ double bond is moved along the chain. There are two molecules with a 'straight' chain of four carbon atoms and the molecular formula C_4H_8 :

but-1-ene



but-2-ene



The structures are different. Again, the carbon atoms are numbered. The number added to the formula indicates the position of the double bond. In but-1-ene the double bond is between carbon atoms 1 and 2, whereas in but-2-ene it is between carbon atoms 2 and 3.

S

Key definition

isomers – compounds that have the same molecular formula but different structural formulae.

A

Alkynes are a third family of hydrocarbons. In alkynes, the molecules contain a $C\equiv C$ triple bond. The simplest member is ethyne (C_2H_2). This highly reactive gas used to be known as acetylene. It is used in oxy-acetylene welding torches. We do not study the alkynes any further at this level.

Activity 10.2 Modelling the structures of hydrocarbon isomers

Skills

- A03.3 Make and record observations, measurements and estimates
A03.4 Interpret and evaluate experimental observations and data

The purpose of this activity is to use molecular models to explore the differences in structure between isomers.

Models are built to answer questions as to how many isomers there are for certain given molecular formulae and to visualise the structural differences between certain isomers. The basis of different types of isomerism is modelled.

The approach can be extended by looking at computer-generated images of hydrocarbons at certain websites such as 'Molecule of the Month' (www.chm.bris.ac.uk/motm/motm.htm).

A worksheet is included on the CD-ROM.



S

Questions

10.18 Give the names of the first member of each of these homologous series:

- a** the alkenes **b** the alcohols
c the carboxylic acids.

10.19 Define the term **isomer**.

10.20 Draw the structures of but-1-ene and but-2-ene.

10.21 Draw the structures of the **two** isomers having the formula C_4H_{10} .

10.22 Draw **two** isomers of an alkane with five carbon atoms.









10.23 Draw the structure of 1,2-dibromoethane.

10.24 Structures A to H are the structural formulae of some organic compounds.

a Give the letters that represent:

- i** two alkanes
ii two compounds which are not hydrocarbons
iii the molecule that is ethene.

b What is the name of H?




10.5 Chemical reactions of the alkanes

The alkanes are rather unreactive compounds. They are saturated, so they cannot take part in addition reactions. They are unaffected by acids or alkalis. However, they can take part in substitution reactions, particularly with the halogens.


Combustion

We have seen earlier that, when a hydrocarbon burns in a good supply of air or oxygen, the two products are carbon dioxide and water. The word equation for the burning of butane, for instance, is:



The same products are obtained whichever alkane is burnt, so long as there is a sufficient oxygen supply.

However, if the air supply is limited, then the poisonous gas carbon monoxide can also be formed. Carbon monoxide is the product of incomplete combustion of a hydrocarbon. For example:



Carbon monoxide (CO) is toxic because it interferes with the transport of oxygen around our bodies by our red blood cells. Every year a number of people die accidentally from carbon monoxide poisoning because of poorly serviced gas fires in their homes. If the flues to the fire are blocked, insufficient air is supplied to the fire and carbon monoxide is produced. Simple carbon monoxide detectors can be bought in supermarkets, or electronic detectors fitted in homes (Figure 10.11).

Incomplete combustion can also produce fine particles of carbon itself. These have not even reacted to produce carbon monoxide. It is these fine carbon particles (or soot) which can glow yellow in the heat of a flame. They give a candle flame or the 'safety' flame of a Bunsen burner its characteristic yellow colour (Figure 10.12).

Study tip

Exam questions very frequently ask about the combustion products of organic fuels and hydrocarbons, in both the presence of sufficient and insufficient air. It is useful to make sure you know the word equations.

Questions on the combustion of hydrocarbons are also quite often asked in the form of equations that you have to complete by balancing them.




Figure 10.11 An electronic carbon monoxide detector.



Figure 10.12 The 'safety' flame of the Bunsen burner. The air supply to the flame is restricted.


S Substitution reactions with the halogens

The **substitution reaction** with chlorine is interesting because it is a **photochemical reaction**:



Methane and chlorine react in the presence of sunlight. Ultraviolet light splits chlorine molecules into separate energised atoms. These atoms then react with methane. So the overall result is that a chlorine atom replaces (substitutes for) a hydrogen atom in a methane molecule to give chloromethane (CH_3Cl). The reaction can continue further as more hydrogen atoms are substituted. Compounds such as dichloromethane (CH_2Cl_2), trichloromethane (CHCl_3) and tetrachloromethane (CCl_4) are formed in this way.

Trichloromethane (CHCl_3), or **chloroform**, was an early anaesthetic. However, the dose which can kill a patient is not much higher than the amount needed to anaesthetise a patient! So it was very easy to make mistakes. Something else was needed. Investigations were carried out on the anaesthetic effect of other substituted alkanes. In 1956, **halothane** was discovered. It is a more useful anaesthetic. Its formula is CF_3CHBrCl , and its structure is:




Substituted alkanes are also good organic solvents. 1,1,1-trichloroethane is one solvent that is used frequently, in dry-cleaning, for example.

? Questions

- 10.25 Write a word equation for the incomplete combustion of methane.
- 10.26 What is the formula of carbon monoxide?
- 10.27 What causes a candle flame to be yellow?
- 10.28 Why is carbon monoxide toxic?
- 10.29 What are the name and formula of the first substitution product of the reaction between methane and chlorine?
- 10.30 The hydrocarbon propane is an important constituent of the fuel liquid petroleum gas (LPG). For the burning of propane in an excess of air, give:
- a word equation
 - a balanced symbol equation.

- 10.31 What source of energy is required for the substitution reaction between methane and chlorine to take place?

- 10.32 Bromine reacts with alkanes in a similar way to chlorine. Hydrogen bromide is made in the substitution reaction between propane and bromine:



- Draw the structure of propane.
- Draw the structure of a form of bromopropane.
- The reaction between propane and bromine is a photochemical reaction. Suggest what is meant by **photochemical**.

S 10.6 Chemical reactions of the alkenes



Alkenes are much more reactive than alkanes. Under suitable conditions, molecules such as bromine, hydrogen and water (steam) will add across the $\text{C}=\text{C}$ double bond.

Bromination

This reaction is used as the chemical test for an unsaturated hydrocarbon (see Figure 10.9, page 258). Bromine water is decolorised when shaken with an alkene. The reaction will also work with the bromine dissolved in an organic solvent such as hexane.

S Hydrogenation

The addition of hydrogen across a C=C double bond is known as **hydrogenation**. Ethene reacts with hydrogen if the heated gases are passed together over a catalyst. The unsaturated ethane is the product:



Hydrogenation reactions similar to the reaction with ethene are used in the manufacture of margarine from vegetable oils.

The vegetable oils of interest include corn oil and sunflower oil. They are edible oils and contain long-chain organic acids (**fatty acids**). The hydrocarbon chains of these acids contain one or more C=C double bonds; they are unsaturated molecules (Figure 10.13). Oils such as sunflower oil are rich in **polyunsaturated** molecules. This means that the melting point is relatively low and the oil remains liquid at normal temperatures (and even with refrigeration). By hydrogenating some, but not all, of the C=C double bonds, the liquid vegetable oil can be made into a solid but spreadable fat (margarine).

Animal fats tend to be more saturated than vegetable oils and fats. The animal fats in cream can be made into butter. Many doctors now believe that unsaturated fats are healthier than saturated ones.





Figure 10.13 Sunflower oil and its products are rich in fats containing unsaturated molecules (note the C=C double bonds in the chain).

This is why margarine is left partially unsaturated: not all the C=C double bonds are hydrogenated. Olive oil is distinctive in having a high content of oleic acid, which is a **monounsaturated** fatty acid. Margarine can be made from olive oil without any hydrogenation.

Hydration

Another important addition reaction is the one used in the manufacture of ethanol. Ethanol is an important industrial chemical and solvent. It is formed when a mixture of steam and ethene is passed over a catalyst of immobilised phosphoric(v) acid (the acid is adsorbed on silica pellets) at a temperature of 300 °C and a pressure of 60 atmospheres:



This reaction produces the ethanol of high purity needed in industrial organic chemistry.

? Questions

- 10.33** What are the molecular and structural formulae of 1,2-dibromoethane?
- 10.34** Write the word and chemical equations for the hydrogenation of ethene.
- 10.35** What is the catalyst used in hydrogenation reactions?
- 10.36** Unsaturated hydrocarbons take part in addition reactions.
 - a** Write a word equation for the reaction between propene and hydrogen.
 - b** Write a symbol equation for the reaction between butene and steam.
- 10.37 a** Chloroethane is one of the chemicals manufactured from ethene.
 - i** Name the compound that reacts with ethene in an addition reaction to give chloroethane.
 - ii** Draw the structural formula of chloroethane.
- b** Chloroethane can also be made by a substitution reaction. What are the reagents and reaction conditions for this reaction?

10.7 Alcohols

Ethanol is one of the best-known organic compounds. It is just one of a whole family of compounds – the **alcohols**. The alcohols are a homologous series of compounds that contain —OH as the functional group (Figure 10.14). A functional group is a group of atoms in a structure that determines the characteristic reactions of a compound.

Table 10.4 shows the molecular formulae of the early members of the series. The simplest alcohol contains one carbon atom and is called methanol. Note that the names all have the same ending (*-ol*). The general formula of the alcohols is $\text{C}_n\text{H}_{2n+1}\text{OH}$, and they can be referred to as the alkanols. The structural formulae of the first four alcohols are as shown in Figure 10.15. The early alcohols are all neutral, colourless liquids that do not conduct electricity.

Key definition

alcohols – a series of organic compounds containing the functional group —OH and with the general formula $\text{C}_n\text{H}_{2n+1}\text{OH}$




Figure 10.14 The structure of ethanol.

Alcohol	Molecular formula $\text{C}_n\text{H}_{2n+1}\text{OH}$	Boiling point / $^{\circ}\text{C}$	
methanol	CH_3OH	65	
ethanol	$\text{C}_2\text{H}_5\text{OH}$	78	
propan-1-ol	$\text{C}_3\text{H}_7\text{OH}$	97	
butan-1-ol	$\text{C}_4\text{H}_9\text{OH}$	117	
pentan-1-ol	$\text{C}_5\text{H}_{11}\text{OH}$	137	

Table 10.4 Some alcohols.





Figure 10.15 Alcohols are a homologous series – these are the structures of the first four members. Two isomers of butanol are shown.

Making ethanol

Hydration of ethene

The industrial method of making ethanol involves the addition reaction that we saw at the end of Section 10.6. In this, ethene and steam are compressed to 60 atmospheres and passed over a catalyst (immobilised phosphoric(v) acid) at 300°C :



Ethanol is an important solvent and a raw material for making other organic chemicals. Many everyday items use ethanol as a solvent. These include paints, glues, perfumes, aftershave, etc.

Fermentation

Ethanol and carbon dioxide are the natural waste products of yeasts when they ferment sugar. Sugar is present in all fruit and grains, and in the sap and nectar of all plants. Yeasts are found everywhere. The ancient Babylonians and Egyptians found that, if they crushed grapes or germinated grain, the paste would bubble

Activity 10.3

The fermentation of glucose using yeast


Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates

Beer and wine are produced by fermenting glucose with yeast. Yeast contains enzymes that catalyse the breakdown of glucose to ethanol and carbon dioxide. In this experiment, a glucose solution is left to ferment. The products of fermentation are then tested. The solutions generated by the class may be retained for a demonstration of distillation (see Activity 2.3).

A worksheet is included on the CD-ROM.

and produce an intoxicating drink. Pasteur discovered that yeasts are single-cell, living fungi. They ferment sugar to gain energy – by **anaerobic respiration**. As ethanol is toxic to yeast, fermentation is self-limiting. Once the ethanol concentration has reached about 14%, or the sugar runs out, the multiplying yeast die and fermentation ends. The best temperature for carrying out the process is 37 °C. The reaction is catalysed by enzymes in the yeast:



Alcoholic drinks such as beer and wine are made on a large scale in vast quantities in copper or steel fermentation vats. Beer is made from barley, with hops and other ingredients added to produce distinctive flavours. Wine is made by fermenting grape juice. Beer contains about 4% by volume of ethanol, whereas wine contains between 8% and 14%. Stronger, more alcoholic, drinks are made in one of two ways. Fortified wines, such as sherry and port, have pure ethanol added to them. Spirits, such as whisky, brandy and vodka, are made by distillation (see page 30).

Fermentation can be carried out in the laboratory using the apparatus in Figure 10.16. The air-lock allows gas to escape from the vessel but prevents airborne bacteria entering.

Study tip

Fermentation is an anaerobic process. It takes place under conditions where there is no air or oxygen available.

Therefore, there is no oxygen (O₂) present in the equation for the reaction taking place.

Carbon dioxide is the gas produced in the reaction.

Comparing the methods of ethanol production

The two different methods of producing ethanol have their respective advantages and disadvantages. The method chosen will depend on the availability of resources and the main purpose for producing the ethanol. A comparison of the methods is summarised in Table 10.5.

The ethanol produced by fermentation comes from a renewable resource. When used as a fuel, the ethanol produced in this way is potentially 'carbon neutral'. The carbon dioxide released during fermentation and by burning the fuel is balanced by that absorbed from the atmosphere by the crop, usually sugar cane, as it grows.





Figure 10.16 A laboratory fermentation vessel.

Questions

- 10.38** Name the first three members of the alcohol homologous series.
- 10.39** Write the word and chemical equations for the hydration of ethene by steam.
- 10.40** What are the essentials needed for the production of ethanol by fermentation?
- 10.41** Ethanol can be made by the addition of water to ethene. Ethanol can also be made by the fermentation of sugars using the apparatus shown here.



- a** Name the gas produced during the fermentation shown above.
- b** This gas escapes through the piece of apparatus labelled A. What is the main purpose of this piece of apparatus?
- c** What must be added to a sugar solution to make it ferment?
- d** At about what temperature does fermentation take place at its fastest rate?
- e** Explain your choice of temperature given in **d**.
- 10.42** Methanol and ethanol are members of a homologous series.
- a** Draw the molecular structures of methanol and ethanol.
- b** Explain what the term **homologous series** means.
- 10.43** What are the names and structures of the two isomers of propanol?


Ethanol by the hydration of ethene	Ethanol by fermentation
originates from a non-renewable resource – petroleum	made from readily renewable resources
small-scale equipment capable of withstanding pressure	relatively simple, large vessels
a continuous process	a batch process – need to start process again each time
a fast reaction rate	a relatively slow process
yields highly pure ethanol	ethanol must be purified by subsequent distillation – though fermented product can be used as it is for some purposes
a sophisticated, complex method	a simple, straightforward method

Table 10.5 A comparison of the methods of ethanol production.

10.8 The reactions of ethanol

Ethanol as a fuel

Ethanol burns with a clear flame, giving out quite a lot of heat:



On a small scale, ethanol can be used as methylated spirit (ethanol mixed with methanol or other compounds) in spirit lamps and stoves. However, ethanol is such a useful fuel that some countries have developed it as a fuel for cars.

Brazil, whose climate is suitable for growing sugar cane, started producing ethanol fuel in 1973. It has one of the largest ethanol fuel programmes in the world (Figure 10.17). The ethanol is produced by fermenting crop residues, and as such is considered a **biofuel**. Ethanol and other biofuels are used in motor vehicles as an alternative to fuel obtained from oil deposits. Ethanol produced by fermentation of sugar from sugar cane has been used as an alternative fuel to gasoline (petrol), or mixed with gasoline to produce 'gasohol'. It



Figure 10.17 An ethanol and petrol station in Sao Paulo, Brazil.

is a renewable resource and has the potential to reduce petroleum imports. 'Gasohol' now accounts for 10% of the gasoline sales in the USA. 'Gasohol' and other 'oxygenated fuels' have the advantage of **reducing** the emissions of carbon monoxide from cars. It is thought that biofuels can reduce environmental damage if developed and controlled properly, but overuse of biofuels could be harmful if it leads to more deforestation to grow biofuel crops.



Study tip

Exam questions often ask you to balance the equations for the combustion reactions of either hydrocarbons or alcohols.

Make sure you balance the oxygen (O) atoms in the equation. Remember, with alcohols, that there is an oxygen atom in the alcohol molecule itself.

Oxidation

Vinegar is a weak solution of ethanoic acid (previously called acetic acid). It is produced commercially from wine by biochemical oxidation using bacteria (*Acetobacter*). Wine can also become 'vinegary' if it is left open to the air. The same oxidation can be achieved quickly by powerful oxidising agents such as warm acidified potassium manganate(VII):



The colour of the potassium manganate(VII) solution turns from purple to colourless.





Figure 10.18 The dehydration of ethanol in the laboratory.

Dehydration

Ethanol can be dehydrated to produce ethene. This is one way of preparing ethene in the laboratory. Ethanol vapour is passed over a heated catalyst. The catalyst can be aluminium oxide or broken pieces of porous pot. Ethene is not soluble in water, so it can be collected as shown in Figure 10.18.

Esterification

Alcohols react with organic acids (see Section 10.9) to form sweet-smelling oily liquids known as **esters**. For example:



Concentrated sulfuric acid is added as a catalyst for this esterification reaction.

Alcohol and health

Ethanol is the only alcohol that is safe to drink. It must only be drunk in moderation, if at all. Methanol is very toxic and even in small amounts can cause blindness and death.

Ethanol mixes totally with water, which takes it everywhere in the body that water goes. The amount of alcohol that a person may drink varies with age, sex, weight and drinking history.

Heavy drinking can cause a healthy liver to become fatty and enlarged. Eventually scarring (**cirrhosis**) can cause liver failure and death. Prolonged heavy drinking can eventually damage the muscle tissue of the heart. It may also lead to some long-term damage to the brain. Alcohol is a depressive drug and can be addictive. Drinking heavily on a particular occasion produces drunkenness, during which speech becomes slurred, vision is blurred and reaction times are slowed. Some cultures forbid its use.

Questions


10.44 Sugar cane grows quickly in tropical areas. Sugar can be fermented to make ethanol. Either ethanol or mixtures of petrol and ethanol (gasohol) can be used as the fuel for cars.

- a** Ethanol consists of organic molecules.
- What type of compound is ethanol?
 - Ethanol has the formula C_2H_5OH . Draw its structure.

b Gasohol boils over a temperature range of $40\text{--}150^\circ\text{C}$ in the laboratory. Ethanol has a boiling point of 78°C . Draw a labelled diagram to show how a sample of ethanol may be obtained from gasohol.

10.45 Ethanol is a fuel. In laboratories that do not have a gas supply, it may be used in a spirit burner.

- a** The diagram shows a spirit burner being used to heat a beaker of water. A black solid is formed on the bottom of the beaker.
- Name the black substance formed on the beaker.
 - Suggest why the black substance is formed when the ethanol is burnt.
- b** Both methanol and ethanol burn in an excess of air to form the same products.



- Name these products.
- Suggest why it is not possible to set fire to the contents of a bottle of wine.

10.46 Write the word and chemical equations for the oxidation of ethanol to ethanoic acid (use [O] for the oxidising agent).

10.47 What alkene is produced when propan-1-ol is dehydrated?

10.48 Name the ester produced when ethanol reacts with ethanoic acid. Write the word equation for the reaction. What is the catalyst for the reaction?

10.9 Organic acids and esters

Carboxylic acids

The **carboxylic acids** are another homologous series of organic compounds. All these acids have the functional group —COOH attached to a hydrocarbon chain. Table 10.6 (overleaf) shows the molecular formulae of the first two members of the series. The compounds have the general formula $C_nH_{2n+1}COOH$ (or $C_nH_{2n+1}CO_2H$). Figure 10.19 shows the structural formulae of the first four acids in the series.

The first two acids in the series are liquids at room temperature, although ethanoic acid will solidify if the temperature falls only slightly. The acids dissolve in water to produce solutions that are weakly acidic. Methanoic acid is present in nettle stings and ant stings, while ethanoic acid (once called acetic acid) is well known as the acid in vinegar.


Study tip

When naming a carboxylic acid, remember that the carbon atom of the acid group is part of the chain. It is counted as the first carbon in the chain.

That is why CH_3COOH is the formula of ethanoic acid: there are two carbon atoms in the molecule.

Ethanoic acid as a weak acid

Whereas a strong acid such as hydrochloric acid is completely split into ions, ethanoic acid only partially dissociates into ions in water. A **dynamic equilibrium** is set up in the solution. The solution does contain an excess of hydrogen ions (H^+) over hydroxide ions (OH^-), so the solution is weakly acidic (see page 143):



Carboxylic acid	Molecular formula $C_nH_{2n+1}COOH$	Melting point / °C	Boiling point / °C	
methanoic acid	HCOOH	9	101	 m.p. and b.p. increasing
ethanoic acid	CH ₃ COOH	17	118	

Table 10.6 The first two carboxylic acids.






Figure 10.19 The structures of methanoic, ethanoic, propanoic and butanoic acids.

A solution of the acid will show the characteristic reactions of an acid. For example, it will react with bases to form salts:



Vinegar can be used as a 'descaler' in hard water areas. The ethanoic acid in vinegar reacts with limescale (calcium carbonate), producing carbon dioxide and dissolving the scale:



Commercial descalers are often based on weak acids, methanoic acid for instance, or on moderately strong acids such as sulfamic acid.

Activity 10.4

The acidic reactions of ethanoic acid

Skills


- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

This activity tests ethanoic acid with Universal Indicator solution, magnesium, sodium hydroxide solution and sodium carbonate solution. These reactions are then compared with those of a hydrochloric acid solution of the same concentration. The comparison shows that ethanoic acid is a weak acid.


A worksheet is included on the CD-ROM.

Esterification

Ethanoic acid will react with ethanol, in the presence of a few drops of concentrated sulfuric acid, to produce ethyl ethanoate. The concentrated sulfuric acid is a catalyst for the reaction:



This type of reaction is known as **esterification**. The structure of ethyl ethanoate is shown below:



Ethyl ethanoate is just one example of an **ester**. This family of compounds have strong and pleasant smells. Many of these compounds occur naturally. They are responsible for the flavours in fruits and for the scents of flowers (Table 10.7). We use them as food flavourings and in perfumes. The ester group or

linkage is also found in complex molecules such as natural fats and oils, and in man-made fibres such as Terylene (see page 288).

Ester	Smell or flavour
ethyl 2-methylbutanoate	apple
3-methylbutyl ethanoate	pear
1-methylbutyl ethanoate	banana
butyl butanoate	pineapple
octyl ethanoate	orange
methylpropyl methanoate	raspberry
pentyl butanoate	strawberry

Table 10.7 The smells of esters.

Activity 10.5

Making esters from alcohols and acids

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

In this activity, the reactions between a range of alcohols and acids are carried out on a test-tube scale, to produce small quantities of a variety of esters quickly. The characteristic odours of the different esters are then tested.


A worksheet is included on the CD-ROM.



Questions


10.49 Ethanol is a product of many fermentation reactions. The molecular formula of ethanol is C_2H_5OH .

- Draw the structural formula for ethanol.
- When ethanol is heated with an excess of acidified potassium dichromate, it is converted to ethanoic acid:



What type of chemical reaction is this?

- Some synthetic flavourings are made by reacting an alcohol with a carboxylic acid: alcohol + carboxylic acid $\rightarrow$ ester + water
What other substance and conditions are needed to carry out this reaction?
- The structure of the ester propyl butanoate is shown here.




Draw the structural formula of the carboxylic acid from which this ester is made.

10.50 The flavour and smell of foods are partly due to esters. An ester can be made from ethanol and ethanoic acid.

- Name this ester.
- Write a word equation for the reaction between ethanol and ethanoic acid.

10.51 The diagram below shows a method used in France to change wine into vinegar. Living organisms (*Acetobacter*) bringing about a chemical change and producing a marketable product is an example of traditional biotechnology.



- What type of reaction has occurred in the vat?
- Name a chemical reagent, other than oxygen, that can change ethanol into ethanoic acid.
- Name a technique that could be used to separate ethanoic acid from the other liquids in vinegar.
- Describe a chemical test that would distinguish between wine and vinegar.

Summary

You should know:

- that carbon forms a vast range of compounds and that the study of their properties is known as organic chemistry
- that hydrocarbons are the simplest of the many types of organic compound
- about the different 'families' (or homologous series) of hydrocarbons: the alkanes are saturated hydrocarbons, while the alkenes are a second series of unsaturated hydrocarbons
- how the alkanes are important fuels and that the simplest, methane, is the main component of natural gas
- that the simple test for unsaturated hydrocarbons is the fact that they decolorise bromine water
- that there are many more different series of organic compounds, each with a different functional group attached to a hydrocarbon backbone

- ◆ that the alcohols are a separate series of compounds, the most important of which is ethanol
- ◆ how ethanol can be manufactured industrially by the hydration of ethene or by large-scale fermentation
- ◆ that ethanol has major uses as a fuel and as a solvent
- ◆ that hydrocarbons and alcohols burn in excess air to produce carbon dioxide and water vapour
- S** ◆ how different organic compounds can have the same molecular formula but different structural formulae – they can be isomers of each other
- S** ◆ how alkanes undergo substitution reactions with the halogens, but alkenes are more reactive and take part in addition reactions with hydrogen, the halogens and steam
- S** ◆ that oxidation of alcohols produces a further series of compounds, the carboxylic acids
- S** ◆ the fact that these acids are weak acids, only partly ionised in water
- S** ◆ how alcohols and carboxylic acids react to produce esters in reactions known as esterification.

End-of-chapter questions

1 There are very many more compounds of the element carbon than there are of any other element. Why are these compounds particularly important to us?

2 These three compounds, A, B and C, belong to three different homologous series.



A




B




C

- a What is meant by the term **homologous series**? [1]
- b To which homologous series does each compound belong? [3]
- c Give a chemical test which could distinguish between compound A and compound B. Describe the test and give the result for compounds A and B. [3]
- d How could compound A be chemically converted to compound C? [2]
- e What is the name of the process which forms compound C from sugar? [1]

S 3 But-1-ene is a typical alkene. It has the structural formula shown below.



The structural formula of cyclobutane is given below.




- a These two hydrocarbons are isomers.
 - i Define the term *isomer*. [2]
 - ii Draw the structural formula of another isomer of but-1-ene. [1]
 - iii Describe a test which would distinguish between but-1-ene and cyclobutane. Name the reagent used and give the result for both isomers. [3]

- S**
- b Describe how alkenes, such as but-1-ene, can be made from alkanes. [2]
- c Name the product formed when but-1-ene reacts with each of the following:
- i bromine [1]
 - ii hydrogen [1]
 - iii steam. [1]

[Cambridge IGCSE® Chemistry 0620/32, Question 4, June 2010]


- 4 Butane is an alkane. It has the following structural formula.



- a The equation for the complete combustion of butane is given below. Insert the two missing volumes.
- $$2\text{C}_4\text{H}_{10}(\text{g}) + 13\text{O}_2(\text{g}) \rightarrow 8\text{CO}_2(\text{g}) + 10\text{H}_2\text{O}(\text{g})$$
- | | | | | |
|-------|-------|----|---------------------------------|-----|
| | | 40 | volume of gas / cm ³ | [2] |
|-------|-------|----|---------------------------------|-----|
- b Butane reacts with chlorine to form two isomers of chlorobutane.
- i What type of reaction is this? [1]
 - ii Explain the term *isomer*. [2]
 - iii Draw the structural formulae of these two chlorobutanes. [2]
- c One of the chlorobutanes reacts with sodium hydroxide to form butan-1-ol. Butan-1-ol can be oxidised to a carboxylic acid.
- i State a reagent, other than oxygen, which will oxidise butan-1-ol to a carboxylic acid. [1]
 - ii Name the carboxylic acid formed. [1]
 - iii Butan-1-ol reacts with ethanoic acid to form an ester. Name this ester and give its structural formula, showing all the individual bonds. [3]

[Cambridge IGCSE® Chemistry 0620/31, Question 6, June 2012]

- 5 Propenoic acid is an unsaturated carboxylic acid. The structural formula of propenoic acid is given below.



- a i Describe how you could show that propenoic acid is an unsaturated compound. Give details of the test and the result. [2]
- ii Without using an indicator, describe how you could show that a compound is an acid. Give details of the test and the result. [2]
- b Propenoic acid reacts with ethanol to form an ester. Deduce the name of this ester. Draw its structural formula, showing all bonds. [3]
- c An organic compound has a molecular formula C₆H₈O₄. It is an unsaturated carboxylic acid. One mole of the compound reacts with two moles of sodium hydroxide.

 - i Explain the phrase *molecular formula*. [2]
 - ii One mole of this carboxylic acid reacts with two moles of sodium hydroxide. How many moles of -COOH groups are there in one mole of this compound? [1]
 - iii What is the formula of another functional group in this compound? [1]
 - iv Deduce a structural formula of this compound. [1]

[Cambridge IGCSE® Chemistry 0620/33, Question 5, November 2012]

11 Petrochemicals and polymers

In this chapter, you will find out about:

- ♦ fossil fuels
- ♦ the formation and fractional distillation of petroleum (crude oil)
- ♦ catalytic cracking
- ♦ alternative transport fuels
- ♦ biogas
- ♦ addition polymerisation
- ♦ condensation polymerisation
- ♦ the disposal and recycling of plastic waste
- ♦ biological condensation polymers
 - proteins
 - carbohydrates.

Sheets and tubes of carbon – new technology

Industry based on organic chemistry has given us a vast range of new fuels and materials that have revolutionised our lives. As we explore the virtuosity of carbon as an element, novel materials continue to be discovered. In 2010, the Nobel Prize was awarded to Andre Geim and Konstantin Novoselov for their work on graphene sheets (Figure 11.1a).

Graphene is a flat sheet of carbon atoms arranged in a hexagonal pattern – atomic-scale carbon ‘chicken wire’. Stacks of graphene sheets make up the graphite in the pencils you use every day. However, the individual sheets are providing many new ideas for their use. Graphene is very strong and flexible.

It allows electrons to flow very efficiently across its surfaces. Its electrical conductivity is high and it may eventually replace silicon in computer chips.

Graphene sheets are also the starting point for making carbon nanotubes (Figure 11.1b). The discovery of nanotubes has suggested, among other things, new methods of medical drug delivery and conducting materials. Chemical polymerisation reactions have been carried out in miniature within nanotubes, with the carbon tubes being used as linear reaction vessels.

This chapter will focus on some of the ways we exploit the rich chemistry of carbon. The future holds the prospect of even more incredible adaptations and technological developments.




Figure 11.1 Computer graphics of the structures of: **a** a honeycombed sheet of graphene; **b** a stack of carbon nanotubes.

11.1 Petroleum

Fossil fuels were formed in the Earth's crust from material that was once living. **Coal** comes from fossil plant material. **Petroleum** (or **crude oil**) and **natural gas** are formed from the bodies of marine microorganisms. The formation of these fuels took place over **geological periods of time** (many millions of years). These fuels are therefore a **non-renewable** and **finite resource**.

There are three major **fossil fuels**:

- ◆ **coal**
- ◆ **petroleum (crude oil)**
- ◆ **natural gas.**

The formation of petroleum

Petroleum (or **crude oil**) is one of the Earth's major natural resources, the result of a process that began up to 400 million years ago. When prehistoric marine creatures died, they sank to the seabed and were covered by mud. The change into petroleum and natural gas was brought about by high pressure, high temperature and bacteria acting over millions of years. The original organic material broke down into hydrocarbons. Compression of the mud above the hydrocarbon mixture transformed it into shale. Then geological movements and pressure changed this shale into harder rocks, squeezing out the oil and gas. The oil and gas moved upwards through the porous rocks, moving from high-pressure to low-pressure conditions. Sometimes they reached the surface, but often they became trapped by a layer of non-porous rock.

Reservoirs of oil and gas were created. These reservoirs are **not** lakes of oil or pockets of gas. Instead, the oil or gas is spread throughout the pores in coarse rocks such as sandstone or limestone, in much the same way as water is held in a sponge.

Oilfields and gasfields are detected by a series of geological and seismic surveys. Promising areas are then drilled to gain more geological information or, if oil or gas is found, to see how extensive the oilfield or gasfield is. Once a field is established, production oil rigs can be set up, on land or at sea (Figure 11.2).



Figure 11.2 An oil rig in the Caspian Sea.

Recently, novel approaches for the exploitation of shale gas- and oilfields have added new and abundant availability of fossil fuel resources. The 'fracking' techniques involved in shale gas extraction are proving controversial, however, particularly in countries with large population density.

Fractional distillation

Petroleum is a mixture of many different hydrocarbon molecules. Most of the petroleum that is extracted from the ground is used to make fuel, but around 10% is used as a **feedstock**, or raw material, in the chemical industry. Before it can be used, the various hydrocarbon molecules are separated by refining. This is done by fractional distillation at an **oil refinery**.

At a refinery, petroleum is separated into different fractions – groups of hydrocarbons that have different boiling points. These different boiling points are roughly related to the number of carbon atoms in the hydrocarbons (Table 11.1).

Separation of the hydrocarbons takes place by **fractional distillation** using a **fractionating column** (or tower). At the start of the refining process, petroleum is preheated to a temperature of 350–400 °C and pumped in at the base of the tower. As it boils, the vapour passes up the tower. It passes through a series of bubble caps, and cools as it rises further up the column. The different fractions cool and condense at different temperatures, and therefore at different heights in the column. The fractions condensing at the different levels are collected on trays. Fractions from the top of the tower are called

'light' and those from the bottom 'heavy'. Each fraction contains a number of different hydrocarbons. The individual single hydrocarbons can then be

obtained by further distillation. Figure 11.3 shows the separation into different fractions and some of their uses.

Fraction	Approximate number of carbon atoms in hydrocarbons		Approximate boiling range / °C	 b.p. and viscosity increasing
refinery gas	1–4	C_1-C_4	below 25	
gasoline/petrol ^(a)	4–12	C_4-C_{12}	40–100	
naphtha	7–14	C_7-C_{14}	90–150	
kerosene/paraffin ^(a)	12–16	C_9-C_{16}	150–240	
diesel oil/gas oil	14–18	$C_{14}-C_{18}$	220–300	
fuel oil	19–25	$C_{19}-C_{25}$	250–320	
lubricating oil	20–40	$C_{20}-C_{40}$	300–350	
bitumen	over 70	$> C_{70}$	above 350	

(a) Different terms are used in the UK and the USA. Note that 'crude oil' (UK) is the same as 'petroleum' (USA), 'petrol' (UK) is the same as 'gasoline' (USA), and 'paraffin' (UK) is the same as 'kerosene' (USA).

Table 11.1 Various petroleum^(a) fractions.




Figure 11.3 Fractional distillation of petroleum in a refinery.

Study tip

Take care over names for the different fractions in different parts of the world. Note that the syllabus uses 'petroleum' as the name of the crude oil drilled from the ground.

Study tip

Make sure you know the order of the fractions as they are produced from the fractionating tower, and a use for each of the fractions.

Activity 11.1


Fractional distillation of petroleum

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

 Wear eye protection. The petroleum is highly flammable and harmful.

This experiment simulates the industrial fractional distillation of petroleum (crude oil) in the laboratory.



- 1 Place about a 2 cm³ depth of ceramic fibre in the bottom of a side-arm test tube. Add about 2 cm³ of petroleum substitute to this, using a teat pipette.
- 2 Set up the apparatus as shown in the diagram. The beaker of cold water around the collecting tube helps

to condense the low boiling point fraction. The bulb of the thermometer should be level with, or just below, the side arm. Heat the bottom of the side-arm test tube gently, with the lowest Bunsen flame. Watch the thermometer carefully.

- 3 When the temperature reaches 100°C, replace the collection tube with another empty one. The beaker of water is no longer necessary and can be removed.
- 4 Collect three further fractions, to give the fractions as follows:
A Room temperature to 100°C B 100–150°C
C 150–200°C D 200–250°C
- 5 A black residue remains in the side-arm test tube. Test the four fractions for viscosity (see how easily they pour), colour, smell and flammability.
 - ◆ To test the smell, gently waft the smell towards you with your hand.
 - ◆ To test for flammability, pour a small quantity on to a hard-glass watch glass and light the fraction with a burning splint.
- 6 Keep one set of fractions and see that they combine to form a mixture very like the original sample.

A worksheet is included on the CD-ROM.

Questions

- A1 What differences did you observe in the viscosity of the fractions? What molecular property would you suggest causes this difference?
- A2 What differences were there in flammability between the fractions?


Catalytic cracking

The demand for the various fractions from the refinery does not necessarily match with their supply from the oil (Figure 11.4). For lighter fractions such as gasoline (petrol), the demand is greater than the supply. The

opposite is true for heavier fractions such as kerosene (paraffin) and diesel. Larger molecules from these heavier fractions can be broken into smaller, more valuable, molecules. This process is called **catalytic cracking** ('cat cracking').

Cracking takes place in a huge reactor (Figure 11.5). In this reactor, particles of catalyst (made of powdered minerals such as silica, alumina and zeolites) are mixed with the hydrocarbon fraction at a temperature around 500 °C. The cracked vapours containing smaller molecules are separated by distillation.

The shortened hydrocarbon molecules are produced by the following type of reaction:



This is just one of the possible reactions when decane is cracked. The molecules may not all break in the same place. The alkene fragment is not always ethene: propene and but-1-ene may also be produced.

All cracking reactions give:

- ♦ an **alkane** with a shorter chain than the original, and a short-chain **alkene**
- ♦ or two or more **alkenes** and **hydrogen**.

Both products are useful. The shortened alkanes can be blended with the gasoline fraction to enrich the petrol. The alkenes are useful as raw materials for making several important products. Figure 11.6 shows the various uses for the ethene produced.

Propene polymerises to poly(propene) (trade name 'polypropylene'), while butene polymerises to produce synthetic rubber. The cracking reaction can be carried out in the laboratory using paraffin oil (Figure 11.7).



Figure 11.5 A cracking plant in an oil refinery.



Figure 11.4 There is not the same economic demand for all the fractions from petroleum.

Activity 11.2 Cracking hydrocarbons

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data

The exact composition of petroleum varies depending on where it comes from, but most oil contains more of the larger molecules than the smaller ones. The smaller ones, however, are more useful and therefore more economically important. To increase the profit that can be made from a barrel of oil, the larger hydrocarbons are broken down into smaller ones. This activity involves a small-scale version of this conversion, which is performed in industry every day.

A worksheet is included on the CD-ROM.

Details of a scaled-up version of this experiment are given in the Notes on Activities for teachers/technicians.




Figure 11.7 The cracking of a long-chain alkane in the laboratory.



Figure 11.8 Computer image of an internal combustion engine cylinder. The piston (lower right) is moved up and down by the combustion (burning) of fuel. This image shows the fuel/air mixture being ignited by the spark plug.




Figure 11.6 Important products can be made from the ethene produced by catalytic cracking.

Blending gasoline

Some of the products from cracking are added to the gasoline fraction to improve the quality of the petrol. As many as 12 different components (containing over 300 different hydrocarbons and additives) may be used in a blend of petrol for the motorist. Different blends are made for winter and summer use. An important consideration is how easily the fuel vapour ignites. If the fuel ignites too easily, then the engine will not run smoothly – ‘knocking’ will occur. However, if the fuel is too difficult to ignite, then the engine will be difficult to start, especially on cold mornings. High-quality petrol contains many branched-chain hydrocarbons, made in a process known as re-forming, so that the fuel does not ignite too soon (Figure 11.8). The ignition temperature of a petrol/[solidus] air mixture is around 550 °C.

‘Lead’ (actually tetraethyl-lead) was added to gasoline to prevent ‘knocking’. But this caused high

levels of lead in the air, particularly in large cities. This led to concern over the link with brain damage in young children. Unleaded fuel is now almost universally available and has to be used in modern cars fitted with catalytic converters (the lead would poison the catalyst and so prevent it working).

The removal of sulfur from gasoline fractions is now very efficient. Car exhaust emissions contain very little

sulfur dioxide. The carbon monoxide (CO), unburnt hydrocarbons (HC) and oxides of nitrogen (NO_x) in exhaust fumes do continue to cause concern. The levels of emission of these compounds are reduced by fitting a catalytic converter to the exhaust.

Gasoline vapour also escapes into the air at petrol stations. Modern pumps now have hoods on the nozzles to cut down the escape of fumes.

Activity 11.3 Comparing fuels


Skills

- AO3.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- AO3.2 Plan experiments and investigations
- AO3.3 Make and record observations, measurements and estimates
- AO3.4 Interpret and evaluate experimental observations and data
- AO3.5 Evaluate methods and suggest possible improvements

! Wear eye protection.

There is concern that fossil fuels will run out. There is also concern that burning fossil fuels is causing global warming because of all the carbon dioxide which is released into the atmosphere.

You are asked to design an experiment to compare two fuels: one a fossil fuel and the other a renewable fuel.



The apparatus shown could be used to discover how much heat a fuel produces. A small quantity of the fuel is placed on the 'ceramic wool' and ignited. The temperature change of the water in the boiling tube is then recorded.

- 1 You are asked to compare paraffin, a fossil fuel obtained from petroleum (crude oil), and ethanol, a renewable fuel which can be made by fermenting sugar from plants. You will need to use a relatively small amount of fuel (around 1 cm^3).
- 2 When you have planned your investigation, you should carry it out and record all your observations and measurements.
- 3 You should then write a reasoned conclusion that states which fuel you think is better, together with your reasons.

A worksheet is included on the CD-ROM.

The Notes on Activities for teachers/technicians contain details of how the experiment can be used as an assessment of skills AO3.2 and AO3.5.

Questions

- 11.1 Put the following fractions in order of increasing boiling point: kerosene, diesel, petrol, refinery gas, bitumen, naphtha.
- 11.2 Name **three** fossil fuels.
- 11.3 Explain what is meant by 'cracking', and write word and balanced symbol equations to show how ethene can be formed from decane by this method.
- 11.4 State a use for the following fractions from the distillation of petroleum (crude oil): bitumen, fuel oil, diesel, kerosene.

11.2 Alternative fuels and energy sources

Alternative transport fuels

There is growing interest and a great deal of development work taking place on alternative transport fuels in order to reduce dependence on fossil fuels and find 'greener' forms of transport.


Diesel

High-speed diesel engines in cars, buses and trucks use a fuel (DERV – diesel engine road vehicle) that contains hydrocarbon molecules consisting of between 6 and 20 carbon atoms (in short this is written as C_6 – C_{20} molecules). Slower-speed diesel engines for ships, etc., use a slightly heavier fuel. Diesel engines are compression ignition engines (the fuel ignites spontaneously **without** a spark). Diesel engines are more efficient than petrol engines and produce much less carbon monoxide. However, because their working temperature is higher, they produce more oxides of nitrogen. The major problems are smoke, and the particles it contains, and odour.

A Gasoline from methanol

New Zealand has large reserves of natural gas (mainly methane) but very little petroleum. The problem of producing petrol has been transformed by a catalyst known as zeolite ZSM-5. (A zeolite is one of a large

group of aluminosilicates of sodium, potassium, calcium and barium.) Methane is first converted into methanol. The methanol produced is then turned into hydrocarbons using the ZSM-5 catalyst:



ZSM-5 is an artificial zeolite composed of aluminium, silicon and oxygen. It was first made by two chemists working for the US Mobil Oil company.

LPG and CNG

Liquid petroleum gas (LPG or 'autogas') is composed of propane and butane. Compressed natural gas (CNG) is 90% methane. These products already have a significant market in some countries. For example, all the taxis in Japan use LPG. In India, many of the motorised rickshaws in the major cities run on CNG (Figure 11.9).

Biofuels

There have been significant developments in the use of fuels based on ethanol (see page 267) and vegetable oils such as rapeseed or sunflower oil. The potential for adding plant oils to diesel fuel is being investigated worldwide. The future use of these fuels will depend on economic factors. Some countries grow oil-producing crops but do not have their own reserves of petroleum. Recently there has been controversy about the use of land to grow crops for these fuels and the



Figure 11.9 In India, many of the motorised rickshaws ('tuk-tuks') run on CNG.

A fact that this diverts farmland from food production. The consequent decrease in food availability and increase in prices have been sources of concern. These have led to other sources of ethanol being explored, including, for instance, using sawdust from sawmills as a starting point for production (Figure 11.10).

Vegetable oils from crops such as rape and sunflowers are also being developed as fuels. Recycled cooking oil is being used as a component of biodiesel. Biodiesel contains esters, which are made from vegetable oils such as rapeseed or animal fats. The continual growth of new oil-producing plants, which absorb carbon dioxide from the air through photosynthesis, means that biodiesel contributes less to global warming than fossil fuels do. Motor manufacturers have all developed cars with engines adapted to run on these new fuels.

Others

We discussed the use of ethanol- and hydrogen-powered cars on pages 89 and 267. Electric and solar-powered cars are also being investigated as alternatives to gasoline, and many manufacturers now have hybrid cars that run on a combination of power systems (Figure 11.11).

Alternative energy sources

Alternative energy sources are very much under discussion. Nuclear energy, wind farms and solar energy are some of the areas being explored. In terms of chemical systems, those based around our use of waste offer an opportunity for development, particularly at local level.

Biogas

Methane gas is formed naturally in a number of different circumstances. Anaerobic bacteria helped to decompose

organic matter under geological conditions to produce natural gas. Methane accumulates in coalmines, where it can cause explosions. Marsh gas, which bubbles up through the stagnant water of marshes, swamps and rice paddy fields, is also methane. Methane produced in this way contributes to the **greenhouse effect**.

Methane is produced from organic waste (biomass) when it decays in the absence of air. This can be exploited as a source of energy. In countries such as India and China, biomass digesters are important sources of fuel for rural villages (Figure 11.12). The methane is useful for heating and cooking, and the solid residue is used as a fertiliser.

Industrialised countries produce large amounts of waste, much of which is deposited in landfill sites. Biogas forms as the rubbish decays (Figure 11.13). This gas can be used as a fuel for local industry. On Merseyside in the UK, biogas is used to heat the ovens in a Cadbury's biscuit factory.



Figure 11.11 The Toyota Prius is a hybrid gas/electric car with low emissions. The battery charges while running on petrol and an on-board computer switches when petrol is low.



Figure 11.10 The sawdust from sawmills can be used as a starting point in making ethanol for biofuels.



Figure 11.12 A small-scale biogas generator uses animal waste to produce methane for a village's needs.

A



Figure 11.13 a Deep in the waste of landfill sites, methane gas accumulates and must be burnt off or it could become dangerous – a landfill flare-off. b Alternatively, a power-generating plant can be set up at a landfill site to generate power for the local area.

S 11.3 Addition polymerisation

All living things contain **polymers**. Proteins, carbohydrates, wood and natural rubber are all polymers. What nature first invented, chemists have learned to copy, alter and use successfully. Synthetic polymers, often called **plastics**, are to be found everywhere in modern technological societies, made into bulky objects, films and fibres. They have properties to suit particular needs, ranging from car and aircraft components to packaging and clothing.

Polymers are large organic **macromolecules**. They are made up of small repeating units known as **monomers** (Figure 11.14) joined together by **polymerisation**. These units are repeated any number of times from about a hundred to more than a million. Some are **homopolymers**, containing just one monomer. Poly(ethene), poly(propene) and poly(chloroethene) are three examples of homopolymers. Other





Figure 11.14 Making a chain of beads is similar to joining the monomers together to make a polymer.

macromolecules are **copolymers**, made of two or more different types of monomer. For example, nylon is made from two monomers, and biological proteins are made from 20 different monomers, the **amino acids**.

The alkene fragments from the catalytic cracking of petroleum fractions produced the starting monomers for the first plastics. Alkenes such as ethene contain a C=C double bond. These molecules can take part in **addition reactions** (see page 258) where the double bond is broken and other atoms attach to the carbons. The double bond in ethene enables many molecules of ethene to join to each other to form a large molecule, poly(ethene) (Figure 11.15). This is an **addition polymer**. When first made by ICI, it was a revolutionary new material called 'Alkathene'. It is now commonly called by the trade name 'polythene'.

Various conditions can be used to produce different types of poly(ethene). Generally a high pressure, a temperature at or above room temperature and a catalyst are needed. The reaction can be summarised by the equation:



where n is a very large number.

Study tip

When drawing the structure of poly(ethene) and other polymers, do not forget to put the n outside the bracket.





Figure 11.15 The polymerisation of ethene produces poly(ethene), whose structure is shown.

Poly(ethene) was found to be a chemically resistant material that was very tough and durable, and a very good electrical insulator.

Other alkene molecules can also produce addition polymers. Propene will polymerise to produce poly(propene):





This long-chain molecule is similar in structure to poly(ethene) but with a methyl ($-\text{CH}_3$) group attached to every other carbon atom in the chain (Figure 11.16a). It is commonly referred to by its trade name 'polypropylene'.

Study tip

The diagram of the structure of poly(propene) is quite easy to get wrong. It is important to realise that the $-\text{CH}_3$ group is a side-group here – it does not become part of the chain. The chain is formed by the carbon atoms that are joined by the $\text{C}=\text{C}$ bond in the monomer.

Chemists also experimented with other substituted alkenes to produce plastics with particular properties in mind. Poly(chloroethene) (known by the trade name of polyvinyl chloride or PVC) and poly(tetrafluoroethene) (known by the trade name of polytetrafluoroethylene, 'Teflon' or PTFE) are two such polymers:



Their structures are shown in Figures 11.16b and c.

Poly(chloroethene) (PVC) was found to be stronger and harder than poly(ethene) and therefore good for




Figure 11.16 The structures of **a** poly(propene), PP, **b** poly(chloroethene), PVC, and **c** poly(tetrafluoroethene), PTFE.

making pipes for plumbing. PTFE proved to have some unusual properties: it was very stable at high temperatures and formed a very slippery surface. The properties of some addition polymers are given in Table 11.2. Such synthetic polymers have proved to be very versatile. Many, for example poly(propene), are easy to shape by melting and moulding. Poly(propene) is therefore used to make sturdy plastic objects such as crates. However, it can also be drawn out into long fibres for making ropes.

Some of the properties of **addition polymers**:

- ◆ All polymers are long-chain molecules made by joining together a large number of monomer molecules.
- ◆ Addition polymerisation involves monomer molecules that contain a $C=C$ double bond.
- ◆ Addition polymers are homopolymers, made from a single monomer.
- ◆ During addition, the double bonds open up and the molecules join to themselves to make a molecule with a very long chain.

Polymer (and trade name(s))	Monomer	Properties	Examples of use
poly(ethene) (polyethylene, polythene, PE)	ethene $CH_2=CH_2$	tough, durable	plastic bags, bowls, bottles, packaging
poly(propene) (polypropylene, PP)	propene $CH_3CH=CH_2$	tough, durable	crates and boxes, plastic rope
poly(chloroethene) (polyvinyl chloride, PVC)	chloroethene $CH_2=CHCl$	strong, hard (not as flexible as polythene)	insulation, pipes and guttering
poly(tetrafluoroethene) (polytetrafluoroethylene, Teflon, PTFE)	tetrafluoroethene $CF_2=CF_2$	non-stick surface, withstands high temperatures	non-stick frying pans, non-stick taps and joints
poly(phenylethene) (polystyrene, PS)	phenylethene (styrene) $C_6H_5CH=CH_2$	light, poor conductor of heat	insulation, packaging (foam)

Table 11.2 Examples of some widely used addition polymers.

Activity 11.4

Comparing different plastics

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- ICT skills

Different plastics have been devised for different purposes. This activity explores both the physical property of density and the chemical properties of acid/alkali and solvent resistance of a range of different materials. The results of the investigation can be linked with the uses to which the plastics are put and to a PowerPoint or poster presentation on the impact of plastics on the environment.


A worksheet, with a self-assessment checklist, is included on the CD-ROM.

11.4 Condensation polymerisation

Nylon

In the early 1930s, DuPont were conducting research into artificial fibres. Knowledge of silk and wool gave clues as to how protein molecules are built. Wallace Carothers imitated the linkage in proteins and produced the first **synthetic fibre**, 'nylon'. Nylon is a solid when first formed, but it can then be melted and forced through small holes. The long filaments cool, and the fibres produced are stretched to align the polymer molecules and then dried. The fibres can be woven into fabric to make shirts, ties, sheets, etc., or turned into ropes or racquet strings. However, nylon is not just made into fibres. It has proved to be a very versatile material and can be moulded into strong plastic items such as gearwheels.

Nylon is a copolymer of two different monomers, a diamine and a dicarboxylic acid. Each monomer consists of a chain of carbon atoms (which are shown in the following diagrams simplified as blocks). At both ends of the monomers are functional groups. An amine group (—NH_2) on the first monomer reacts with a carboxylic acid group (—COOH) on the second monomer to make a link between the two molecules. Each time a link is made, a water molecule is lost:



Questions

- 11.5 Give the molecular and structural formulae of ethene.
- 11.6 State what is meant by addition polymerisation and give an equation for the formation of poly(ethene) from ethene.
- 11.7 Draw the structure of the repeating unit in the following polymers:
 - a poly(propene) b poly(chloroethene) (PVC).
- 11.8 What is the monomer used for making Teflon?
- 11.9 Give a use for the following polymers:
 - a poly(propene) b poly(vinyl chloride)
 - c poly(tetrafluoroethene).

As a result, this type of polymer is known as a **condensation polymer**. Because an **amide link** (or peptide link) is formed during polymerisation, nylon is known as a **polyamide**. A version of nylon polymerisation can be carried out in the laboratory (Figure 11.17, overleaf).

Study tip

Questions on the structure of nylon, and other condensation polymers, are difficult. You will not be asked the detailed structure of the monomers. You can represent the central structure of each monomer as a block, as shown in the diagrams here.

You should know the structure (and name) of the links between the monomers in the chain, though – in this case the peptide link.

It is worth practising these diagrams to make sure you are very familiar with them and can recall them readily.





Figure 11.17 Nylon is a polyamide and can be made in the laboratory.

Activity 11.5 The nylon rope trick

Skills


A03.3 Make and record observations, measurements and estimates

This demonstration shows the production of nylon at the interface between two reactant layers. A solution of decanedioyl dichloride in cyclohexane is carefully floated on an aqueous solution of 1,6-diaminohexane. Nylon forms at the interface and can be pulled out as fast as it is produced, forming a long thread – the ‘nylon rope’ (see Figure 11.17).

A worksheet is included on the CD-ROM.

Polyesters

Condensation polymerisation can also be used to make other polymers with properties different from those of nylon. **Polyesters** are condensation copolymers made from two monomers. One monomer has an alcohol group (—OH) at each end. The other monomer has a carboxylic acid group (—COOH) at each end. When the monomers react, an **ester link** is formed, with water being lost each time:



One such polyester has the trade name ‘Terylene’. Like nylon, Terylene can be turned into fibres and woven into clothing. Terylene clothing is generally softer than that made from nylon (Figure 11.18).

The ester linkage that joins the monomer units in the man-made fibre Terylene can be broken down by acid or alkaline **hydrolysis**. So it is not good news if spots of alkali fall on your shirts or sweaters!



Figure 11.18 Shirts are often made out of a fabric made of Terylene and cotton.

Comparing synthetic addition and condensation polymers

Some immensely useful synthetic polymers have been made by the two types of polymerisation. Both methods take small molecules and make long repeating chains from them. However, there are differences between the two methods. These are summarised in Table 11.3.

The re-use, recycling and disposal of plastic waste

Plastic rubbish is a common but unwelcome sight around the world. Over the past 30 years, plastics have taken over as replacement materials in many applications. This is not surprising because they are light, cheap and corrosion-resistant, and they can be easily

moulded and dyed bright colours. The problem arises because most plastics are not **biodegradable** – there are no natural microorganisms that can break them down.

Some modern plastics are suitable for re-use. Soft-drinks bottles can be made from a plastic with the trade name ‘polyethylene terephthalate’ (PET) (Figure 11.19). These bottles are sturdy and have



Figure 11.19 Soft-drinks bottles are often made from polyethylene terephthalate, PET.

	Addition polymerisation	Condensation polymerisation
monomers used	usually many molecules of a single monomer	molecules of two monomers usually used
	monomer is unsaturated, usually contains a C=C bond	monomers contain reactive functional groups at ends of molecule
reaction taking place	an addition reaction – monomers join together by opening the C=C double bond	condensation reaction with loss of a small molecule (usually water) each time a monomer joins the chain
nature of product	only a single product – the polymer	two products – the polymer plus water (or some other small molecule)
	non-biodegradable	biodegradable
	resistant to acids	hydrolysed by acids

Table 11.3 A comparison of the processes of making synthetic polymers.

several advantages for this particular use. In some countries, schemes for the re-use of these bottles are operated. However, such a re-use policy is not suitable for most plastics. So what **do** we do with our waste plastic? We must either recycle it or dispose of it. Recycling is more economical and satisfactory than the alternative, of depositing plastic waste in landfill sites. But there are problems with recycling because most plastic waste is a mixture of different types.

Identification numbers and symbols (Figure 11.20) are in use to identify different plastics for recycling. Methods of sorting plastic waste by optical scanners, or manually, are being introduced. Once sorted, alternative treatments are available for recycling the different types of plastic waste.

Incineration can be used to burn plastic waste, though care must be taken not to release toxic fumes into the air. Incineration of PVC, for instance, can release acidic fumes of hydrogen chloride. **Pyrolysis** – the burning of the plastic waste at around 600 °C in the absence of air – is an alternative to incineration. Most of the products from pyrolysis can be used as fuels or separated by fractional distillation. They can then be made into monomers for making more plastics. Research is also being carried out to produce plastics that are biodegradable or **photodegradable** (can be broken down by the action of light). A poly(ethenol) plastic has been developed that is soluble in hot water.

Biological polymers


All living organisms rely on polymers for their existence. These polymers range from the very

complex DNA that makes life itself possible to the more straightforward proteins and carbohydrates that keep living things 'running'.

Proteins

Proteins are what cells are made of. All the tissues and organs of our bodies are made up of protein. In addition, enzymes, which are responsible for controlling the body's chemical reactions, are proteins. DNA makes life possible and allows living things to reproduce, but without proteins there would be no structure or chemistry to keep the living things going.

Proteins are built from **amino acid** monomers. There are 20 different amino acids used, and they each contain two functional groups —NH₂ and —COOH. Glycine and alanine are two of the simplest amino acids. When they react together, an amide linkage (or peptide linkage) is formed to produce a **dipeptide** (two amino acids joined together):



When this is repeated many times using the different amino acids, a polymer is formed. Short polymers (up to 15 amino acids) are known as **peptides**. Chains with between 15 and 100 amino acids are known as **polypeptides**. Chains involving more than 100 amino acids are called **proteins**.

Protein analysis

Proteins can be hydrolysed (broken down) to amino acids by heating in concentrated hydrochloric acid.





Figure 11.20 Different identification symbols help with the sorting of plastics for recycling. The symbols stand for the following plastics: 1 = poly(ethylene terephthalate) (PET); 2 = high-density poly(ethylene); 3 = vinyl polymers such as PVC; 4 = low-density poly(ethylene); 5 = poly(propene); 6 = poly(styrene); 7 = others, such as multi-layer plastics.

S (6 mol/dm^3). This is the reverse of the condensation process that formed them:



The mixture of amino acids can then be separated by chromatography (see page 31). Amino acids are colourless substances, so a locating agent is used. The locating agent reacts with the amino acids to produce coloured spots.

Activity 11.6

Chromatography of amino acids

Skills

- A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)
- A03.2 Plan experiments and investigations
- A03.3 Make and record observations, measurements and estimates
- A03.4 Interpret and evaluate experimental observations and data
- A03.5 Evaluate methods and suggest possible improvements

The artificial sweetener aspartame contains two amino acids: aspartic acid and phenylalanine. In this activity, aspartame is hydrolysed by heating with hydrochloric acid and the hydrolysed product is then analysed by paper chromatography using amino acid standards to demonstrate their identity. The amino acids are located using a UV lamp or ninhydrin spray.


A worksheet, with a self-assessment checklist, is included on the CD-ROM.

Carbohydrates

The sugar we use to sweeten our tea or coffee is sucrose ($\text{C}_{12}\text{H}_{22}\text{O}_{11}$). This is just one example of a carbohydrate; glucose ($\text{C}_6\text{H}_{12}\text{O}_6$) is another.

Carbohydrates are an important source of energy in our bodies, and in all living organisms. A carbohydrate is a compound containing carbon, hydrogen and oxygen only. The ratio of hydrogen to oxygen is always 2 : 1 (as in water).

All long-chain carbohydrates (**polysaccharides**) are long-chain condensation polymers of sugar molecules (monosaccharides). **Starch**, for example, is a polysaccharide found in plants. Condensation polymerisation of sugar monomers produces such long-chain carbohydrates.



Starch and glycogen are two different polysaccharides of glucose, a monosaccharide. They store the glucose in an insoluble form in plants and animals, respectively. When energy is needed, cells break down the starch or glycogen back to glucose. The glucose is then oxidised by respiration. Cellulose is a third polymer of glucose. It forms the fibrous structure of plant cell walls. These three polymers differ in the way in which the glucose monomer units are linked together.

Polysaccharides can be broken down in the laboratory by warming with hydrochloric acid (acid **hydrolysis**). The sugars present in the hydrolysis mixture can then be analysed by chromatography (see page 31). A locating agent must be used to detect the spots, because sugars are colourless. An interesting comparison is to analyse the products of the acid and enzyme digestions of starch. Acid hydrolysis breaks down starch to give glucose. However, the enzyme amylase present in human saliva only breaks starch down to give maltose. This is a molecule made of two glucose units joined together. The difference can be seen on chromatography of the products.

S The presence of starch can be detected by testing with iodine solution: the solution turns a deep blue colour.

Food

Proteins and carbohydrates are two of the main constituents of food. They, together with fats, are all digested by cells and organisms and are converted back to their monomers. These monomers are then used as the building blocks for new molecular structures or as sources of energy. Our bodies can make a whole range of molecules necessary for our cells to function properly. However, some of these building blocks must come from our diet. For instance, there are some amino acids that we must obtain from our food. These are known as the **essential amino acids**.

Fats and oils are mixtures of large molecules that are the esters of long-chain carboxylic acid molecules and glycerol. Fats that contain unsaturated acids are called unsaturated or polyunsaturated fats, depending on the number of C=C double bonds in the chain. Fats that contain saturated acids, with only C—C single bonds in their chains, are known as saturated fats. There is evidence that eating a lot of animal fat, which is higher in saturated fats, may increase the risk of heart disease.

It is important for us to maintain a balanced diet of all the necessary components of our food, without over-indulgence in any aspect.

Questions

- 11.10** Name two natural condensation polymers.
- 11.11** What are the essential features of condensation polymerisation?
- 11.12** Name two artificial condensation polymers, and specify the type of linkage present in each.
- 11.13** Draw schematic diagrams representing the formation of:
- a** Terylene
 - b** starch
- showing the linkage between the monomers (the structure of the monomer is not required and can be represented as a block).
- 11.14** Nylon is a synthetic macromolecule which is held together by the same linkage as protein molecules.
- a** What is the name of this linkage?
 - b** Draw a diagram of the structure of nylon (again, the structure of the monomer is not required and can be represented as a block).
 - c** Give a major difference between the structure of nylon and of a protein.
 - d** How can proteins be chemically broken back down to amino acids?

Summary

You should know:

- ◆ that the three major fossil fuels are coal, petroleum (crude oil) and natural gas
- ◆ how these resources provide energy and also a wide variety of chemicals
- ◆ that fractional distillation of petroleum provides a series of different hydrocarbon fractions, each with its own uses
- ◆ how these hydrocarbon fractions can be further changed by processes such as catalytic cracking, producing shorter-chain alkane molecules and alkenes from the original longer chains
- ◆ how alkene and other unsaturated molecules can be polymerised to form a range of useful addition polymers
- S** ◆ that plastics made by addition polymerisation are generally non-biodegradable and pose problems for waste disposal
- S** ◆ that condensation polymerisation is another means by which monomers can join together to make polymeric molecules
- S** ◆ how there are both significant natural (e.g. proteins and carbohydrates) and synthetic (e.g. nylon and polyesters) condensation polymers
- S** ◆ that condensation polymers can be hydrolysed both by enzymes and by concentrated acid
- S** ◆ that proteins and carbohydrates are two of the main constituents of our food.


End-of-chapter questions

- 1 Methane, gasoline (petrol) and ethanol are all commonly used as fuels. Why are both methane and ethanol more environmentally friendly than gasoline?
- 2 Petroleum is a mixture of hydrocarbons.
Two of the processes carried out in an oil refinery are fractional distillation of petroleum and cracking of hydrocarbon fractions.

- a Which of the following properties of hydrocarbons is used to separate petroleum into fractions?

boiling point chemical reactivity electrical conductivity melting point [1]

- b Copy and match the fractions on the left with their uses on the right. The first one has been done for you.



- c Cracking is used to break down long-chained alkanes into shorter-chained alkanes and alkenes. [4]

- i State two conditions needed for cracking. [2]

- ii The hydrocarbon, $C_{14}H_{30}$, can be cracked to make ethene and one other hydrocarbon.
Complete the equation for this reaction.



- iii Draw the full structure of ethene showing all atoms and bonds. [1]

- d State the name of the polymer formed from ethene. [1]

- e Ethene is used to make ethanol.

- i Which substance is needed for this reaction?

ammonia hydrogen oxygen steam [1]

- ii Phosphoric acid is a catalyst in this reaction. What do you understand by the term *catalyst*? [1]

[Cambridge IGCSE® Chemistry 0620/21, Question 7, June 2010]

- 3 Ethene, C_2H_4 , is manufactured by cracking petroleum fractions.

- a i What do you understand by the term *petroleum fraction*? [1]

- ii Complete the equation for the manufacture of ethene from dodecane, $C_{12}H_{26}$.



- b Two fractions obtained from the distillation of petroleum are refinery gas and gasoline.
State **one** use of each of these fractions. [2]

- c Ethene is an unsaturated hydrocarbon.
What do you understand by the terms **unsaturated** and **hydrocarbon**? [2]

- d Ethene is used to make ethanol.

- i Which of these reactions is used to make ethanol from ethene?

catalytic addition of steam	fermentation	
oxidation using oxygen	reduction using hydrogen	[1]

- ii Draw the structure of ethanol showing all atoms and bonds. [2]

- e Ethene is used to make poly(ethene).

Copy and complete the following sentences about this reaction. Use words from the list below.

additions carbohydrates catalysts monomers polymers

The ethene molecules which join to form poly(ethene) are the

The poly(ethene) molecules formed are [2]


[Cambridge IGCSE® Chemistry 0620/21, Question 7, November 2010]

- S** 4 Monomers polymerise to form polymers or macromolecules.

- a i Explain the term *polymerise*. [1]

- ii There are two types of polymerisation – addition and condensation. What is the difference between them? [2]

- b An important monomer is chloroethene which has the structural formula shown below.



It is made by the following method.




This is then heated to make chloroethene.



- i Ethene is made by cracking alkanes. Complete the equation for cracking dodecane.



Another method of making dichloroethane is from ethane.



- ii Suggest a reason why the method using ethene is preferred. [1]

- iii Describe an industrial method of making chlorine. [2]

- iv Draw the structural formula of poly(chloroethene). Include three monomer units. [2]

[Cambridge IGCSE® Chemistry 0620/31, Question 5, November 2010]

- 5 Structural formulae are an essential part of organic chemistry.


- a Draw the structural formula of each of the following. Show all the bonds in the structure.

- i Ethanoic acid [1]


- ii Ethanol [1]

S

- b i Ethanoic acid and ethanol react to form an ester. What is the name of this ester? [1]
- ii The same linkage is found in polyesters. Draw the structure of the polyester which can be formed from the monomers shown below. [3]
- $\text{HOOC}-\text{C}_6\text{H}_4-\text{COOH}$ and $\text{HO}-\text{CH}_2-\text{CH}_2-\text{OH}$
- iii Describe the pollution problems caused by non-biodegradable polymers. [2]
- c Two macromolecules have the same amide linkage. Nylon, a synthetic polymer, has the following structure.



Protein, a natural macromolecule, has the following structure.



How are they different?

[2]

[Cambridge IGCSE® Chemistry 0620/31, Question 6, November 2011]

12

Chemical analysis and investigation

In this chapter, you will find out about:

- ♦ testing for anions and cations
- ♦ testing for gases and water
- ♦ collecting and drying gases
- ♦ testing pH
- ♦ how to test for unsaturated hydrocarbons
- ♦ how to distinguish between ethanol and ethanoic acid
- ♦ the use of chromatography as a test for purity and to analyse a mixture
- ♦ aspects of experimental work and the scientific method.

Curiosity rewarded!

Our most distant laboratory for chemical analysis sits on the surface of the planet Mars. *Curiosity*, NASA's US\$2.5bn six-wheeled, nuclear-powered roving research lab, has been exploring the floor of Gale Crater just south of the equator on Mars since it landed there in August 2012. The mission seems to have gone stunningly well and the scientists involved are suggesting that analysis of the Martian soil will produce results 'for the history books'!

Curiosity has found evidence for past running water in Gale Crater, and that is significant in evaluating whether some form of life was ever possible on the planet. However, it is the more detailed experiments on the chemistry of the soil and rocks that would extend our understanding impressively, and *Curiosity* has scooped soil and drilled out rock samples from the surface of the crater for analysis.

The Mars rover is remarkable, not just for the technology that enables it to move at such a distant location from Earth, but also for the laboratory systems on board which enable it to collect and analyse samples. Two 'laboratories', CheMin and Sam, are currently playing a key role. CheMin (Chemistry & Mineralogy X-ray diffraction) analyses the material first, then its findings help determine




Figure 12.1 A self-portrait of the Mars rover *Curiosity*, created from images it has taken of itself.

the most productive settings for the analysis by Sam (Sample Analysis at Mars).

One of the most significant possible outcomes of the analysis would be the finding of organic compounds in the soil or rock samples. Controversial results from NASA dating from the *Viking* landings in the 1970s suggested evidence of microbial life on Mars, but these were subsequently dismissed. The vindication of these earlier results by *Curiosity* would be strong circumstantial evidence that the planet is, or has been, the home of life.

12.1 Inorganic analysis

There are certain important tests that we can use to identify gases and substances in solution. Testing for inorganic compounds is important in itself, but also because it introduces some of the methods behind this type of analysis. In the first instance, we simply want to know **which** compound is present. This type of analysis is known as **qualitative analysis**. We need to find a reaction that clearly indicates that a particular ion is present. It must be a reaction that only works for that ion. The most useful reactions are **precipitation reactions** – where two solutions are mixed and an insoluble product is formed. The alternative to forming a characteristic precipitate is to produce a gas that can be tested.

Testing for anions

The tests for the common **anions** (negative ions) are listed in Table 12.1. For example, silver nitrate solution can be used to identify halide ions in solution. All chlorides will react with silver nitrate solution to give a white precipitate of silver chloride, AgCl, all bromides give a cream

precipitate of silver bromide, AgBr, and all iodides give a yellow precipitate of silver iodide, AgI (Figure 12.2).

Testing for cations

Once we have identified the anion present, the remaining part of the puzzle is to see which **cation**




Figure 12.2 The precipitates produced in the tests for halide ions using silver nitrate. The precipitates are silver chloride (white), silver bromide (cream) and silver iodide (yellow).

Negative ion	Test	Test result ^(a)
carbonate (CO_3^{2-})	add dilute hydrochloric acid to solid	effervescence (fizzing), carbon dioxide produced (test with limewater)
chloride (Cl^-) (in solution)	acidify solution with dilute nitric acid, then add aqueous silver nitrate	white ppt. of silver chloride formed; ppt. soluble in ammonia solution
bromide (Br^-) (in solution)	acidify solution with dilute nitric acid, then add aqueous silver nitrate	cream ppt. of silver bromide formed; only slightly soluble in ammonia solution
iodide (I^-) (in solution)	acidify solution with dilute nitric acid, then add aqueous silver nitrate	yellow ppt. of silver iodide formed; insoluble in ammonia solution
sulfate (SO_4^{2-}) (in solution)	acidify solution with dilute hydrochloric acid, then add barium chloride solution OR acidify solution with dilute nitric acid, then add barium nitrate solution	white ppt. of barium sulfate formed
sulfite (SO_3^{2-}) (in solution)	add dilute hydrochloric acid to solid, then add aqueous potassium manganate(VII) solution	decolorises the purple potassium manganate(VII) solution
nitrate (NO_3^-) (in solution)	make solution alkaline with sodium hydroxide solution, then add aluminium foil (or Devarda's alloy) and warm carefully	ammonia gas given off (test with moist red litmus)

^(a)Note: ppt. = precipitate.

Table 12.1 Tests for negative ions (anions).

(positive ion) is present in the compound. The situation is more complicated, because there are more common alternatives, but the basic approach is the same.

We are helped in testing for positive ions by the fact that certain metal ions will give a characteristic colour in the flame test. If a clean nichrome wire is dipped in a metal compound and then held in the hot part of a Bunsen flame, the flame may become coloured (see Chapter 8, Figure 8.3, and Table 12.2).

The precipitation tests for metal ions are based on the fact that most metal hydroxides are insoluble. Some are also coloured and are therefore easily identified. Together, these precipitation tests form the basis of a strategy for identifying the common metal ions in solutions of various salts (Figure 12.3). Table 12.3 lists the different tests used to identify positive ions using sodium hydroxide (a strong alkali) and ammonia solution (a weak alkali).

When adding the alkali, add it slowly at first (one drop at a time). If it is added too quickly, it is easy to miss a precipitate that re-dissolves in excess.

When carrying out an analysis using these tests, try not to forget the background chemistry involved.

Metal ion	Formula	Colour of flame
sodium	Na^+	yellow
potassium	K^+	lilac
calcium	Ca^{2+}	brick red (orange-red)
lithium	Li^+	crimson
copper	Cu^{2+}	blue-green
barium	Ba^{2+}	apple green

Table 12.2 Some flame test colours.

The hydroxides of aluminium and zinc are both white. They both re-dissolve in excess sodium hydroxide because they are **amphoteric hydroxides** – they react with both acids and bases (see page 126). Chromium hydroxide is also amphoteric but it is grey-green in colour. The hydroxides of the other metals in the table do not re-dissolve in excess sodium hydroxide because they are basic hydroxides – reacting only with acids in neutralisation reactions.




Figure 12.3 The strategy behind testing for metal ions in salts.

Positive ion (in solution)	Effect of adding sodium hydroxide ^(a)	Effect of adding ammonia solution ^(a)
ammonium (NH_4^+)	ammonia produced on warming (test with damp red litmus paper)	–
copper(II) (Cu^{2+})	light blue gelatinous ppt. of copper hydroxide; insoluble in excess sodium hydroxide	light blue gelatinous ppt.; dissolves in excess ammonia, giving a deep blue solution
iron(II) (Fe^{2+})	green gelatinous ppt. of iron(II) hydroxide; insoluble in excess	green gelatinous ppt.; insoluble in excess
iron(III) (Fe^{3+})	rust-brown gelatinous ppt. of iron(III) hydroxide; insoluble in excess	rust-brown gelatinous ppt.; insoluble in excess
chromium(III) (Cr^{3+})	grey-green precipitate of chromium(III) hydroxide; soluble in excess to give a green solution	grey-green precipitate; insoluble in excess
calcium (Ca^{2+})	white ppt. of calcium hydroxide; insoluble in excess	no ppt. (or only a very slight ppt.)
magnesium (Mg^{2+})	white ppt. of magnesium hydroxide; insoluble in excess	white ppt.; insoluble in excess
zinc (Zn^{2+})	white ppt. of zinc hydroxide; soluble in excess, giving a colourless solution	white ppt.; soluble in excess
aluminium (Al^{3+})	white ppt. of aluminium hydroxide; soluble in excess, giving a colourless solution	white ppt.; insoluble in excess

^(a)Note: ppt. = precipitate.

Table 12.3 Tests for positive ions (cations).

Study tip

It is important to learn the tests in Tables 12.1 and 12.3 because you will not have a copy of them in the written examinations, where questions often need knowledge of these tests.

Indeed these tests, and those for gases, are regularly asked for as part of any of the exam papers you will take.

Study tip

When describing when a precipitate re-dissolves to give a colourless solution, you must be careful to use precisely that word – ‘colourless’. Many students use the word ‘clear’ here and this is wrong; the word ‘clear’ does not mean the same thing as colourless, and you will not gain the mark for it in an exam.

The tests for gases

Several of the tests for anions and cations involve detecting gases produced by the test reactions. The gas tests are another important set of general analytical tests (Table 12.4, overleaf). The test for carbon dioxide is shown in Figure 12.4.

To study gases further, samples can be collected in a variety of ways, depending on their density and solubility in water.




Figure 12.4 The limewater test for carbon dioxide.

Gas	Colour and smell	Test	Test result
ammonia (NH ₃)	colourless, pungent smell	hold damp red litmus paper (or Universal Indicator paper) in gas	indicator paper turns blue
carbon dioxide (CO ₂)	colourless, odourless	bubble gas through limewater (calcium hydroxide solution)	white ppt. of calcium carbonate formed (solution turns milky) (Figure 12.4)
chlorine (Cl ₂) ^(a)	pale green, choking smell	hold damp litmus paper (or Universal Indicator paper) in gas	indicator paper is bleached white (blue litmus will turn red first)
sulfur dioxide (SO ₂) ^(b)	colourless, pungent acidic smell	add to a solution of, or filter paper soaked in, potassium manganate(VII)	potassium manganate(VII) changes from purple to colourless
hydrogen (H ₂)	colourless, odourless	hold a lighted splint in gas	hydrogen burns with a squeaky 'pop'
oxygen (O ₂)	colourless, odourless	hold a 'glowing' wooden splint in gas	the splint re-lights

^(a)This gas is poisonous, so test with care and use a fume cupboard.

^(b)This gas is harmful and can cause breathing difficulties.

Table 12.4 Tests for gases.

Activity 12.1

Analysing the make-up of a compound

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

A03.3 Make and record observations, measurements and estimates

Ammonium carbonate is a white solid sometimes known as 'smelling salts'. It is an ionic solid made from ammonium (NH₄⁺) ions and carbonate (CO₃²⁻) ions with the chemical formula (NH₄)₂CO₃. This activity introduces you to some of the chemical tests for ions and gases.

A worksheet is included on the CD-ROM.

Methods of collecting gases:

- ◆ **Downward delivery** is used to collect gases that are denser than air (Figure 12.5a).
- ◆ **Upward delivery** is used for gases that are less dense than air (Figure 12.5b).
- ◆ **Collection over water** is used for gases that are not very soluble in water (Figure 12.5c).
- ◆ **Collection in a gas syringe** is useful when the volume of gas needs to be measured (Figure 12.5d).

Sometimes it is necessary to produce a gas by a reaction that requires heating. In such cases, there is a danger of 'sucking back' if the gas is collected over water. The problem arises if heating is stopped before the delivery tube is removed from the water. The reduced pressure in the reaction tube as it cools results in water rising up the delivery tube. In the worst case, the cold water can be sucked back into the hot boiling tube. The tube will crack and an explosion may occur. 'Sucking back' can be prevented by making sure that the delivery tube is removed first, before heating is stopped.

Methods of collecting gases

There are four general methods of collecting gases – the apparatus used in each case is shown in Figure 12.5.




Figure 12.5 The different methods of collecting gases: **a** downward delivery, **b** upward delivery, **c** collection over water, and **d** collection in a gas syringe.

Alternatively, a **Bunsen valve** (Figure 12.6) can be fitted to the end of the tube.

One other useful adaptation for the delivery of gases is used for making a solution of a gas that is very soluble in water, for example ammonia or hydrogen chloride. The adaptation is shown in Figure 12.7. The filter funnel increases the area over which the gas can dissolve, and prevents water rising up the delivery tube into the reaction vessel.

Methods of drying gases

Quite often we need to produce a dry sample of gas. This is done by passing the gas through a **drying agent**. Figure 12.8 (overleaf) gives the appropriate method for the three commonest drying agents. The different drying agents are suitable for particular gases.




Figure 12.6 Using a Bunsen valve to prevent 'sucking back'.




Figure 12.7 Making a solution of a very soluble gas.

The commonest drying agents

- ◆ Concentrated sulfuric acid is used to dry all gases except ammonia.
- ◆ Anhydrous calcium chloride is used for all gases except ammonia, which forms a complex with calcium chloride.
- ◆ Calcium oxide is used to dry ammonia and neutral gases.

Other tests

There are the two other useful general tests that we need to consider. Then our discussion of qualitative inorganic analysis is complete.

Activity 12.2

Identifying an unknown mixture

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

A03.3 Make and record observations, measurements and estimates



Wear eye protection.

- 1 Take a sample of unknown substance **Z** in a test tube and, using a dropper, add dilute sulfuric acid.
- 2 Continue adding acid, a little at a time, until no further reaction takes place.
- 3 Test any gas given off.
- 4 Filter the mixture and keep both the filtrate and the residue.

5 Tests on filtrate

Split the filtrate into two equal parts.

To the first part:

- a Add, one drop at a time, aqueous sodium hydroxide. Note observations.
- b Add excess sodium hydroxide. Note observations.

To the second part:

- c Add, one drop at a time, aqueous ammonia. Note observations.
- d Add excess aqueous ammonia. Note observations.

6 Tests on residue

- a Add aqueous hydrogen peroxide, a little at a time.
 - b Test and identify any gas given off.
- 7 Identify, with reasons, the compound present in the filtrate.
 - 8 Give as much information as possible about the compound which is the residue.

The Notes on Activities for teachers/technicians contain details of how this experiment can be used as an assessment of skill AO3.1




Figure 12.8 The different methods of drying gases with **a** sulfuric acid, **b** anhydrous calcium chloride, and **c** calcium oxide.

pH testing

The acidity or alkalinity of a solution can be tested using indicator papers (usually litmus or Universal Indicator, see page 121). It is not good chemical practice to dip the paper directly into the solution. Instead, a glass rod should be used to place a drop of the solution on the paper. Measurements of pH and other analyses are often carried out on soil samples. Soil is stirred with distilled water. The insoluble material settles out and the remaining solution can be tested with Universal Indicator paper. The pH of soil can be important, as different plants 'prefer' to grow at different pH.

Testing for the presence of water

Not all neutral colourless liquids are water. The presence of water can be detected using anhydrous copper(II) sulfate or cobalt(II) chloride. Water will




Figure 12.9 The test for the presence of water using cobalt chloride paper. The paper turns from blue to pink.

turn anhydrous copper(II) sulfate from white to blue, and anhydrous cobalt(II) chloride from blue to pink (Figure 12.9). Cobalt chloride paper contains blue anhydrous cobalt chloride. It turns pink if water is present. To decide whether a liquid is **pure** water, you would need to test to show that its boiling point is exactly 100 °C.

The purity of a solid substance can be checked by finding its melting point. A pure substance has a sharp melting point which agrees with known values.

Study tip

If you are asked for a chemical test for the presence of water, you must name a test in which a chemical change takes place. Testing the boiling point will not do. The cobalt chloride test is a correct answer.

However, the cobalt chloride test will only tell you that the water is there, not that it is pure. To see if water is pure, you must test the boiling point.

Activity 12.3

An observation exercise

Skills

A03.1 Demonstrate knowledge of how to safely use techniques, apparatus and materials (including following a sequence of instructions where appropriate)

A03.3 Make and record observations, measurements and estimates

 **Wear eye protection.**

In this activity, you will be observing what happens to a number of substances in various reactions. You should note their appearance before, during and after the process.

- 1 Using a pair of tongs, heat each of metals A and B in a Bunsen burner flame.
- 2 In a test tube, heat a sample of substances C, D and E in a Bunsen flame.

- 3 Add water, drop by drop, to samples of substances F and G in test tubes.
- 4 Record your results in a clear and appropriate manner.
- 5 Which of the substances changed permanently (chemical change)?
- 6 Explain how you know that this was a chemical change.
- 7 Which of the substances changed temporarily (physical change)?
- 8 Explain how you know that this was not a chemical change.
- 9 Which of the substances did not change at all?
- 10 Suggest why they did not change.

The Notes on Activities for teachers/technicians contain details of how this experiment can be used as an assessment of skill A03.3.

Questions

- 12.1** Why can many metal ions be identified by using sodium hydroxide solution?
- 12.2** Which metal hydroxides will dissolve in excess sodium hydroxide solution?
- 12.3** Why can iron ions give two different coloured precipitates with sodium hydroxide?
- 12.4** What gas is produced when acid is added to a solution of carbonate ions?
- 12.5** What solution will give a precipitate with halide ions?
- 12.6** What must be added before barium chloride when testing for sulfate ions?
- 12.7** Which gas is tested with a glowing splint?
- 12.8** Name a cation which is not a metal ion.
- 12.9** The table below shows the results of practical tests on substances A to E. Choose, from A to E, the substance that is likely to be:
- a** distilled water
 - b** sodium chloride solution
 - c** chlorine gas
 - d** hydrochloric acid.

Substance	Action on Universal Indicator solution	Action on hydrochloric acid	Action on silver nitrate solution
A	goes red then bleaches	no reaction	no reaction
B	goes blue	fizzes	white precipitate
C	goes red	no reaction	white precipitate
D	stays green	no reaction	no reaction
E	stays green	no reaction	white precipitate

12.2 Organic analysis

There are also tests to characterise certain organic compounds. You should be familiar with a few simple ones at this stage.

The test for unsaturated hydrocarbons

The simplest test for an unsaturated compound such as an alkene (for example, ethene) is to use bromine water (see page 258). If the unknown compound is a liquid, then a small amount is mixed with bromine water and shaken. If the unknown compound is a gas, the gas should be bubbled through bromine water. The bromine water is initially an orange-brown colour. If the gas or liquid being tested turns it colourless, then that compound is unsaturated – it contains at least one double bond. Alkanes are saturated and would not react.

Study tip

When describing a test, always give the colour before and after the change. For example, 'Ethene changes bromine water from brown to colourless.'

The test for ethanol and ethanoic acid

These two substances provide a simple test reaction for each other. They react with each other, with the addition of a few drops of concentrated sulfuric acid, to produce a sweet-smelling ester. The mixture is warmed gently, and the fruity smell of the ester can best be detected by pouring the reaction mixture into a beaker of water or sodium carbonate solution. This spreads the ester and disperses the distinctive 'pear-drop' smell (Figure 12.10).




Figure 12.10 The making of an ester.

Chromatography

Chromatography was originally used as a method of separating coloured substances (Figure 12.11). However, the usefulness of the technique has been extended by the use of locating agents to detect the presence of colourless compounds once the **chromatogram** has been produced.

The individual monomers from proteins and carbohydrates (amino acids and sugars) can be separated by chromatography. In both cases, the spots must be detected using locating agents because the compounds themselves are colourless. If a sample gives only a single spot, then this is an indication that it might be pure. It would be better to check, using different solvents, for confirmation.

The identity of the compound can be confirmed by measuring its R_f value in the solvent being used. For more detail of this technique see page 31.




Figure 12.11 Chromatography can be used to separate coloured inks. The solvent front can be seen rising up the paper.

The analyses described in this section are concerned with **which** compounds are present. That is, they are focused on detection and identification. They are **qualitative** tests. However, precipitation reactions can also be carried out to answer questions of **how much** of a substance is present. Titrations can also be carried out to answer such questions in solutions. This type of analysis is known as **quantitative** analysis. More detail of these techniques can be found in Section 6.5.

Questions

- 12.10 Outline the test for an alkene, giving the reagent used and the colour change observed.
- 12.11 How would you test to distinguish between ethanol and a solution of ethanoic acid?
- 12.12 Why is a locating agent needed to identify sugars and amino acids on a chromatogram?

12.3 Experimental design and investigation

The scientific method

Science is concerned with providing evidence to explain the world we experience and how it works. Ideas of how it may work are a good start, but it is the job of the scientist to provide **evidence** to support those ideas or to prove them wrong. Over many hundreds of years, the ways in which scientists fulfil

this role have developed into what we now call 'the scientific method'. Below is a simplified version of what it involves.

- 1 We start with an **idea** about how something works or how something may be accomplished.
- 2 We do some **research** to discover if anyone has already done any useful work on this topic. This may be done using books or the internet, or may involve some initial practical investigation.
- 3 We then develop a **hypothesis**. This is a statement based on our idea and the results of our research which can be tested by means of an experiment.
- 4 We plan and carry out our **experiment**, or series of experiments, which we design to test whether our hypothesis was correct.
- 5 We then **analyse** our results and conclude whether or not our hypothesis was correct.

- 6 Next, a **report** is written, giving the results and the conclusion reached. If the hypothesis was not confirmed, we have still learned something and must start again with a new hypothesis.

Planning investigations and controlling variables

Figure 12.12 outlines a basic strategy for planning an investigation in chemistry and making sure you have thought of the issues involved.

The hypothesis

The hypothesis is a statement of the 'If...then...' type; for example, 'If I heat this reaction then it will get faster'. The statement should be one which can be tested with an experiment. Some statements are difficult or impossible to test: 'If the Earth is hit by an asteroid then most living things will die' for instance.




Figure 12.12 The stages involved in an experimental investigation.

The variables

When marble chips react with hydrochloric acid, a number of factors affect the speed of the reaction (the temperature, the concentration of the acid, the size of the marble chips and the pressure of the air). These are referred to as **variables**. If we wish to investigate the effect of temperature on the speed, the other variables must all be kept constant. Then we can be sure that the effect which we observe is due to the change in temperature.

When we plan our investigation, we must decide which variable we are going to vary/control (the **controlled** variable) and which one will change as a result (the **dependent** variable). These will be the two variables in our hypothesis. All the other variables must be kept constant.

Selecting the apparatus

When selecting suitable apparatus for an experiment, it is important to consider scale and accuracy. Containers should be of a suitable size and shape. Apparatus for measuring should be capable of giving sufficiently accurate results. In particular, the apparatus used for measuring the controlled and dependent variables should be able to produce precise results.

Measuring time, mass and temperature: A stopclock or stopwatch is often a useful piece of apparatus, particularly when studying rates of reaction. Many are now digital and capable of giving readings in seconds to two decimal places. Be careful of a false sense of accuracy and consider how to report your results. It is unlikely that other parts of your experiment will be set up to this degree of precision.

Digital balances are now available which routinely give readings to two decimal places. Such balances are convenient and straightforward to use provided you remember to set the balance to zero with the empty container in place (called 'taring' the balance).

Temperatures in practical work are measured in 'degrees Celsius' ($^{\circ}\text{C}$) and thermometers are usually straightforward to read to the nearest degree. This is usually accurate enough, although it is possible with some thermometers to measure to the nearest half degree. Digital thermometers are becoming more readily available for practical work.

Measuring volumes: When measuring volumes of liquids, it is important to be aware of the level of accuracy needed for a particular experiment. Often a measuring cylinder is sufficiently accurate for routine use and for making up large volumes of solutions. However, do remember that they are not as accurate as either a pipette or a burette for measuring the volume of a liquid really accurately. Pipettes are the most accurate way of measuring out a fixed volume (usually 10 or 25 cm^3). Burettes are the most accurate way of measuring a variable volume (usually between 0 and 50 cm^3). Burettes and pipettes are the apparatus used in titrations. If we need to make up a solution accurately to a known concentration then a volumetric flask is the container to make it in.

In some rate of reaction experiments, for instance, it is necessary to measure the volume of a gas. In this case a gas syringe is the apparatus of choice. It is possible, however, to use an inverted measuring cylinder for this, and collect the gas over water. Be careful not to use this method for a gas that dissolves in water, though.

You should be aware of the purpose and accuracy of the common pieces of experimental equipment (Figure 12.13, overleaf), and make sure you use their correct names when answering questions.

Safety

Safety is of great importance in experiments, and you should be aware of those chemicals that can pose a risk. The meaning of the safety symbols and some chemical examples are shown in Figure 12.14 (overleaf).

When you plan your investigation, it is important to carry out a **risk assessment** for each part of the experiment. At the end of an experiment, be sure to clean up carefully and wash your hands.

Sources of error and the display of observations

Almost every measurement has some degree of **error** or **uncertainty** in it. Some pieces of apparatus are more accurate than others. An awareness of **accuracy** and sources of error is important in evaluating the results of an experiment. Tables and graphs of results should be checked for results that do not fit the pattern. A typical graph is shown in Figure 12.15, page 309. When plotting graphs, the line through the points should be a 'best-fit' line. Do not try to include points that are obviously out of place. The line you draw,




Figure 12.13 Common experimental apparatus.



Figure 12.14 Chemical safety symbols.

after carefully plotting the points, should show up the general pattern of the results. Very often this will be a straight line or a gentle curve. Try to draw the line so

that the points are evenly scattered on either side. If a curve seems best, then make it as smooth as possible, avoiding sharp angles.

Plotting graphs

- ◆ Plot the controlled variable ('Temperature' in Figure 12.15) on the horizontal axis (x -axis), with the scale as large as possible.
- ◆ Plot the dependent variable ('Time' in Figure 12.15) on the vertical axis (y -axis), again with the scale as large as possible.
- ◆ Remember that the scales do **not** have to start at zero.
- ◆ Label each axis clearly with the name of the variable and its units.
- ◆ Give your graph a title.
- ◆ Plot the points with a cross (or a dot in a small circle) using a **sharp** pencil.
- ◆ Draw the best-fit line, which does not have to pass through **all** the points and which may be a straight line or a curve.




Figure 12.15 Plotting a graph is important to get the most from experimental data. This sample graph is from an experiment like the one in Chapter 7, Figure 7.20.

A point that does not fit the pattern is probably due to a **random error** in a particular reading. Measurements like this should be repeated where possible.

Other errors can be introduced in a different way. For instance, always reading a burette as shown in Figure 12.16 would mean that the values given were always too high. This is an example of a **systematic error**. The presence of such an error can show itself when a graph is drawn. For example, a line that should pass through the origin does not do so.




Figure 12.16 Poor experimental technique can result in systematic errors.

Reducing errors

- ◆ **Random errors** can be reduced by using apparatus that gives greater accuracy, by making measurements more carefully, or by making multiple measurements and taking an average.
- ◆ **Systematic errors** can be eliminated by using accurate apparatus and improved technique.

Interpreting observations and data

An experiment can produce either observations made directly (usually visually) or numerical data, which is usually obtained via some measuring device. In both cases it is usual to put the results of the experiment into a table with suitably headed columns.

In the case of visual observations, this would normally include the appearance before and after any change, described in as much detail as possible. These observations would be interpreted by linking them with the expected outcomes (from the hypothesis) and by writing an appropriate equation where possible.

Numerical data should be recorded in a table with units and with values shown as accurately as possible. Numerical data are often used to plot a graph, which again should be interpreted by reference to the hypothesis – does it confirm or contradict the hypothesis? Remember that a straight line often indicates some form of proportional relationship between the variables.

Questions

- 12.13** If you were investigating which of three fuels will heat water fastest, what variables would you have to keep constant?
- 12.14** If you were investigating the effect of heat on a number of different compounds, what headings would be needed for the columns in the results table?

12.4 Practical examinations

For the Cambridge IGCSE examination there are two possible routes for the assessing of practical skills.

Practical examination (Paper 5)

This is a timed practical test carried out at the end of the course.

The alternative to practical examination paper (Paper 6)

This is a written paper drawing on experience of practical work gained during the course

It is important to consult the syllabus for the year of entry to find details of the structure and timing of the individual papers for that year.

Example practical paper

An example of a completed practical examination paper follows to give an idea of the tasks a student may face.

It includes an example of student answers and feedback from their teacher.

Some example practical-style questions are included, with example answers and comments written by the authors.

- 1 You are going to investigate what happens when two different solids, C and D, dissolve in water.

Read all the instructions below carefully before starting the experiments.

Instructions

You are going to carry out two experiments.

(a) Experiment 1

Place the polystyrene cup in the 250 cm³ of beaker for support.

Use a measuring cylinder to pour 25 cm³ of distilled water into the polystyrene cup. Measure the temperature of the water and record it in the table below.

Add all of solid C to the water, start the timer and stir the mixture with the thermometer.

Measure the temperature of the solution every 30 seconds for three minutes. Record your results in the table.

time/s	0	30	60	90	120	150	180
temperature of solution / °C	21	26	28	29	29	28	27

[2]

(b) Experiment 2

Empty the polystyrene cup and rinse it with water.

Use a measuring cylinder to pour 25 cm³ of distilled water into the polystyrene cup. Measure the temperature of the water and record it in the table below.


Add all of solid D to the water, start the timer and stir the mixture with the thermometer.

Measure the temperature of the solution every 30 seconds for three minutes. Record your results in the table.

time/s	0	30	60	90	120	150	180
temperature of solution / °C	20	18	17	16	16	17	17

[2]

(c) Plot the results for Experiments 1 and 2 on the grid and draw two smooth line graphs. Clearly label your graphs.



[6]

- (d) (i) From your graph, deduce the temperature of the solution in Experiment 1 after 45 seconds. Show clearly on the graph how you worked out your answer.

.....27..... °C

[2]

- (ii) From your graph, deduce how long it takes for the initial temperature of the solution in Experiment 2 to change by 1 °C. Show clearly on the graph how you worked out your answer.

.....15..... s

[2]

The deletion to cross out a mistake is fine. Do not use correcting fluid to correct errors.

- (e) What type of change occurs when substance D dissolves in water?

~~exo~~ endothermic [1]

- (f) Suggest and explain the effect on the results if Experiment 1 was repeated using 50 cm³ of distilled water.

temperature ^{change} would be lower because
there is more water to heat [2]

- (g) Predict the temperature of the solution in Experiment 2 after 1 hour. Explain your answer.

20°C because Room Temperature and the
substance is all dissolved. [2]

- (h) When carrying out the experiments, what would be the advantage of taking the temperature readings every 15 seconds?

more points on graph makes it more
accurate [2]

This method of inserting a missing word is fine.
Without it, this would be a very common error.

[Total: 21]

In examination, similar questions may be worth different marks to those shown here.

- 2 You are provided with solid E and liquid F.
Carry out the following tests on E and F, recording all of your observations in the table.
Conclusions must **not** be written in the table.

tests	observations
<u>tests on solid E</u>	
(a) Describe the appearance of solid E.	green powder [1]
(b) Place half of solid E in a test-tube. Heat the test-tube gently. Test any gas given off.	turns black condensation on tube limewater, milky. [3]
(c) (i) Add half of the remaining solid E to about 5 cm ³ of dilute sulfuric acid in a test-tube. Allow the mixture to settle. Decant off the liquid into a test-tube. Divide the solution into two equal portions in test-tubes. Add 1cm depth of distilled water to each test-tube and shake. Carry out the following tests. (ii) Add several drops of aqueous sodium hydroxide to the first portion of the solution and shake the test-tube. Now add excess sodium hydroxide to the test-tube. (iii) Add several drops of aqueous ammonia to the second portion of the solution and shake the test-tube. Now add excess aqueous ammonia to the test-tube.	gas given off solution turns blue [2] blue precipitate no effect [2] blue precipitate royal blue solution formed [3]

This student has made four points.

'Gas given off' is not enough. Need to say how this is observed – refer to 'bubbling' or 'effervescence'.

'Clear' is wrong here; it should say 'colourless'. Clear does not mean the same thing. This is a very common error.

tests	observations
tests on liquid F	
(d) Describe the appearance and smell of liquid F.	appearance <i>clear liquid.</i> [1] smell <i>like vinegar</i> [1]
(e) Use pH indicator paper to measure the pH of liquid F.	pH <i>orange</i> [1]
(f) Add about 3 cm ³ of liquid F to the rest of solid E in a test-tube. Leave to stand for five minutes.	 <i>green solution formed,</i> <i>and bubbles</i> [2]

(g) identify solid E.

..... *copper carbonate* [2]

(h) Draw **one** conclusion about liquid F.

..... *weak acid organic vinegar?* [1]

Colour of indicator given
not the pH.

[Total: 19]

Four conclusions given here – but this is fine because all are correct. If one correct and one incorrect conclusion had been given, the student would have contradicted themselves. If one answer is asked for, you should only give one.

Alternative to practical examinations

An alternative to practical paper will test the experimental skills you have gained during your course through experience of practical work. It is important to know about common apparatus and experimental procedures. Examples of the sorts of things you might be asked follow:

- ◆ labelling diagrams of common apparatus
- ◆ taking readings from diagrams of apparatus
- ◆ plotting graphs
- ◆ interpreting the results of simple experiments
- ◆ planning simple investigations.



Summary

You should know:

- ◆ how to identify inorganic compounds:
 - test for cations
 - test anions using flame tests
 - test anions using sodium hydroxide and aqueous ammonia
 - test gases
 - test pH
 - test for the presence of water
- ◆ how to identify organic compounds:
 - test for unsaturated hydrocarbons
 - test alcohols and carboxylic acids
 - use chromatography for identification
- ◆ how to plan and conduct experiments:
 - plan investigations
 - control variables
 - record data and observations
 - interpret observations and data.

End-of-chapter questions


- 1 Why is it important for chemists to be able to do tests to discover what elements and compounds substances contain?
- 2 A student reacted dry ammonia gas with hot copper(II) oxide. The apparatus used is shown below. The equation for the reaction is



- a On a copy of the diagram, indicate with an arrow where the heat is applied. [1]
- b The colour of the copper(II) oxide would change from to [2]
- c Draw a labelled diagram to show how liquid water could be obtained from the water vapour produced. [2]
- d Suggest the effect of nitrogen on a lighted splint. [1]

[Cambridge IGCSE® Chemistry 0620/61, Question 1, November 2012]

- 3 Electricity was passed through aqueous copper(II) sulfate using inert electrodes as shown in the diagram below. Copper was deposited at one of the electrodes.




- a Name a suitable material for the electrodes. [1]
- b At which electrode was copper deposited? [1]
- c Give **one** other observation seen during the electrolysis. [1]
- The electrode at which copper was deposited was removed at intervals, washed, dried and weighed. The results are shown in the following results table.
- d i Suggest how the electrode was washed? [1]
- ii How could the electrode be dried quickly? [1]

Table of results

Time / min	Mass of electrode / g	Total increase in mass / g
0	3.75	0.00
10	4.00	0.25
20	4.25	0.50
30	4.50	
40	4.75	
50	4.90	
60	4.90	
70	4.90	

- e Complete the table by calculating the total increase in mass for the remaining time intervals. [1]


- f Plot the points on a copy of the grid below. Draw a graph with two intersecting straight lines. [3]











- g Suggest why the last three readings were the same. [1]

[Cambridge IGCSE® Chemistry 0620/61, Question 2, November 2012]

- 4 Heat is given out when alcohols are burned.
A student used the apparatus below to find the amount of heat produced when four different alcohols, methanol, ethanol, propanol and butanol, were burned.




- a Some methanol was put into the burner. The initial temperature of the water was measured. The burner was lit and allowed to burn for one minute. The flame was extinguished and the final temperature of the water was measured. The experiment was repeated with ethanol, propanol and butanol. Use the thermometer diagrams to record the temperatures in the table. Complete the table by recording the temperature rise for each alcohol.

Alcohol	Formula	Initial		Final		Temperature rise / °C
		Thermometer diagram	Temperature / °C	Thermometer diagram	Temperature / °C	
methanol	CH ₃ OH					
ethanol	C ₂ H ₅ OH					
propanol	C ₃ H ₇ OH					
butanol	C ₄ H ₉ OH					

[4]

- b Plot the results obtained on the grid and draw a straight-line graph.




[4]

- c From your graph, work out the temperature rise expected if the experiment was repeated using pentanol, C₅H₁₁OH. Show clearly on the grid how you obtained your answer. [3]
- d Suggest the effect of using a copper can to contain the water instead of a boiling tube. Explain your answer. [2]

[Cambridge IGCSE® Chemistry 0620/61, Question 2, June 2012]

- 5 The diagram shows the results of an experiment to separate and identify the colours present in two coloured mixtures, A and B. Substances C, D, E and F are single colours.



- Name this method of separation. [1]
- Draw a line **on the diagram** to show the level of the solvent at the beginning of the experiment. [1]
- Why should a pencil be used instead of a pen to draw the origin line? [1]
- State **one** difference and **one** similarity between the coloured mixtures, A and B. [2]
- Which substances are present in mixture A? [1]

[Cambridge IGCSE® Chemistry 0620/61, Question 3, November 2011]










- 6 A student investigated the reaction between aqueous copper(II) sulfate and two different metals, zinc and iron. Two experiments were carried out.

Experiment 1

Using a measuring cylinder, 25 cm³ of aqueous copper(II) sulfate was poured into a polystyrene cup. The temperature of the solution was measured. The timer was started and the temperature was measured every half a minute for one minute.

At one minute, 5 g of zinc powder was added to the cup and the mixture stirred with the thermometer. The temperature of the mixture was measured every half minute for an additional three minutes.

- a Use the thermometer diagrams in the table to record the temperatures.










Time/min	Thermometer diagrams	Temperature / °C
0.0		
0.5		
1.0		
1.5		
2.0		
2.5		
3.0		
3.5		
4.0		

[3]

Experiment 2


Experiment 1 was repeated using 5 g of iron powder instead of the zinc powder.

b Use the thermometer diagrams in the table to record the temperatures.

Time/min	Thermometer diagrams	Temperature / °C
0.0		
0.5		
1.0		
1.5		
2.0		
2.5		
3.0		
3.5		
4.0		

[3]

- c Plot the results of both experiments on the grid below. Draw two smooth line graphs. Clearly label your graphs.



[5]

- d From your graph, work out the temperature of the reaction mixture in Experiment 1 after 1 minute 15 seconds. Show clearly on the graph how you worked out your answer. [3]
- e What type of chemical process occurs when zinc and iron react with aqueous copper(II) sulfate? [1]
- f i Compare the temperature changes in Experiments 1 and 2. [1]
- ii Suggest an explanation for the difference in temperature changes. [1]
- g Explain how the temperature changes would differ in the experiments if 12.5 cm^3 of copper(II) sulfate solution were used. [2]
- h Predict the effect of using lumps of zinc in Experiment 1. Explain your answer. [2]

[Cambridge IGCSE® Chemistry 0620/61, Question 4, November 2011]

- 7 The reaction between aqueous barium chloride and aqueous sodium sulfate produces a white precipitate. Six experiments were carried out to find the mass of precipitate produced using solution P and solution Q. Solution P was aqueous barium chloride. Solution Q was aqueous sodium sulfate. Both solutions were of the same concentration.

5 cm^3 of solution P was put into each of six test-tubes. Increasing volumes of solution Q were added to each test-tube. The mixtures were filtered to obtain the precipitates, which were washed, dried and then weighed in a suitable container.


- a Draw a labelled diagram to show how the mixture was filtered. [2]
- The results are shown in the table below.

- b Complete the table.

Volume of P / cm^3	Volume of Q / cm^3	Mass of container / g	Mass of container and precipitate / g	Mass of precipitate / g
5	1	4.50	4.95	
5	2	4.50	5.45	
5	3	4.50	5.90	
5	4	4.50	6.40	
5	5	4.50	6.85	
5	6	4.50	6.85	

[2]

- c Plot the points on the grid below. Join the points with two intersecting straight lines.




[3]

- d What is the minimum volume of Q required to completely react with 5 cm³ of P?

[1]

[Cambridge IGCSE® Chemistry 0620/61, Question 6, June 2011]

- 8 The label shows some information on a bottle of liquid sink and drain cleaner.



- a Give a chemical test for the presence of sodium hydroxide. Give the test and the result. [2]
 b Suggest why it could be dangerous to pour fizzy drinks into a sink containing this liquid cleaner. [2]
 c Why should the container be rinsed with water before throwing out? [1]
 d Give a chemical test for chlorine. Give the test and the result. [2]

[Cambridge IGCSE® Chemistry 0620/61, Question 7, June 2011]

- 9 Malachite is a naturally occurring form of copper carbonate. Outline how a sample of copper metal could be obtained from large lumps of malachite in the laboratory.

Copper is one of the least reactive metals.

Your answer should include any chemicals used and conditions.

[6]

[Cambridge IGCSE® Chemistry 0620/61, Question 7, June, 2010]

10 Solid E was analysed. E was an aluminium salt.

The tests on the solid and some of the observations are in the following table.

Complete the observations in the table.

Tests	Observations
<u>Tests on solid E</u>	
a Appearance of solid E.	white crystalline solid
b A little of solid E was heated in a test tube.	colourless drops of liquid formed at the top of the tube
c A little of solid E was dissolved in distilled water. The solution was divided into four test tubes and the following tests were carried out.	
i To the first test tube of solution, drops of aqueous sodium hydroxide were added. Excess sodium hydroxide was then added to the test tube.	 [3]
ii Test i was repeated using aqueous ammonia solution instead of aqueous sodium hydroxide.	 [2]
iii To the third test tube of solution, dilute hydrochloric acid was added, followed by barium chloride solution.	no reaction
iv To the fourth test tube of solution, aqueous sodium hydroxide and aluminium powder were added. The mixture was heated.	effervescence pungent gas given off turned damp litmus paper blue

d What does test b tell you about solid E.

[1]

e Identify the gas given off in test c iv.

[1]

f What conclusions can you draw about solid E?

[2]

[Cambridge IGCSE® Chemistry 0620/61, Question 5, June 2010]

Answers to questions


Chapter 1

- 1.1** Petroleum and natural gas are formed from the bodies of dead marine creatures subjected to heat and pressure over very long geological periods of time.
- 1.2** It provides the energy needed for photosynthesis, which removes carbon dioxide from the atmosphere.
- 1.3** They are regarded as non-renewable because they were formed over very long periods of time and are being used up at a rate far faster than they can be formed.
- 1.4** **a** carbon dioxide + water $\rightarrow$ glucose + oxygen
(chemical equation) $6\text{CO}_2 + 6\text{H}_2\text{O} \rightarrow \text{C}_6\text{H}_{12}\text{O}_6 + 6\text{O}_2$
- b** carbon + oxygen $\rightarrow$ carbon dioxide
(chemical equation) $\text{C} + \text{O}_2 \rightarrow \text{CO}_2$
- c** glucose + oxygen $\rightarrow$ carbon dioxide + water
(chemical equation) $\text{C}_6\text{H}_{12}\text{O}_6 + 6\text{O}_2 \rightarrow 6\text{CO}_2 + 6\text{H}_2\text{O}$
- 1.5** sulfur dioxide and nitrogen dioxide
- 1.6** the burning of fossil fuels (mainly coal for sulfur dioxide)
- 1.7** damage to limestone buildings, death of trees, acidification of lakes leading to death of fish
- 1.8** a combination of nitrogen oxides and low-level ozone that causes breathing problems, especially for people with asthma
- 1.9** It combines with the haemoglobin in red blood cells, stopping them from carrying oxygen.
- 1.10** because it does not react with the filament, which would burn in air when it became hot
- 1.11** from rotting vegetable matter and from the intestines of animals such as cows
- 1.12** Heat which would normally escape into space is reflected back to the Earth's surface by gases such as carbon dioxide and methane in the atmosphere.
- 1.13** It changes nitrogen oxides and carbon monoxide to nitrogen and carbon dioxide.
- 1.14** because they have different boiling points
- 1.15** because solid matter is easiest to remove and would interfere with subsequent processes
- 1.16** to kill bacteria present in the water
- 1.17** because the energy needed to boil the water is costly
- 1.18** The sewage reacts with oxygen in the water, leaving less for water creatures to breathe.
- 1.19** They can cause too many algae to grow and they are not removed by water treatment.
- 1.20** It contains a high concentration of a particular metal compound.
- 1.21** Lime is calcium oxide which is reacted with water to make calcium hydroxide (slaked lime).
- 1.22** plastics, drugs, paints, detergents, etc.
- 1.23** It reflects heat back to Earth when present in the atmosphere. Heat is kept in the atmospheric layer.
- 1.24** The electrolysis of water. It is an expensive process.
- 1.25** It produces only water when burned.
- 1.26** hydrogen + oxygen $\rightarrow$ water
 $2\text{H}_2 + \text{O}_2 \rightarrow 2\text{H}_2\text{O}$

Chapter 2

- 2.1** **a** freezing (solidification)
b boiling
c condensation
d sublimation
- 2.2** The impurity lowers the freezing point of the liquid.

2.3



- 2.4** A volatile liquid is one that evaporates easily; it has a low boiling point.





- 2.5** ethanol > water > ethanoic acid. Ethanol is the most volatile, ethanoic acid the least.
- 2.6** **a** distillation **b** fractional distillation
c crystallisation (evaporation to concentrate the solution, cooling, crystallisation, filtration and drying)
- 2.7** Sublimation is when a solid changes to a gas without passing through the liquid phase (and the reverse).
- 2.8** coloured substances (e.g. dyes)
- 2.9** by the use of locating agents that react with colourless 'spots' to produce a colour that can be seen
- 2.10** R_f gives a standard measure of how far a sample moves in a chromatography system, as it relates the movement of the sample compound to how far the solvent front has moved. It is equal to the distance moved by the sample divided by the distance moved by the solvent front.
- 2.11** An element is a substance that cannot be broken down into anything simpler by chemical means.
- 2.12** A compound is a substance formed from two or more elements chemically bonded together.
- 2.13** Solid: particles packed close together in a regular arrangement; each particle only vibrating about a fixed point
Liquid: particles close together but less regularly arranged; particles able to move about
Gas: particles far apart and irregularly arranged; particles moving independently
- 2.14** Ammonia, because it has a lower molecular mass. Place cotton wool plugs soaked in ammonia solution and hydrochloric acid at opposite ends of a tube. Seal the tube at both ends. Allow the gases to diffuse towards each other. A white smoke disc of ammonium chloride will form where the two gases meet. This disc is closer to the hydrochloric acid end of the tube, as ammonia diffuses faster.
- 2.15** hydrogen
- 2.16** proton = 1, neutron = 1, electron = 0 (or $\frac{1}{1840}$)
- 2.17** 15 protons, 16 neutrons, 15 electrons
- 2.18** Chlorine-37 has two more neutrons in the nucleus.
- 2.19** Medical: radiotherapy treatment of cancer, sterilisation of surgical instruments


Industrial: detection of leaks in gas pipelines, controlling the thickness of aluminium foil sheets

- 2.20** first shell, maximum 2: second shell, maximum 8
- 2.21** 2,8,8,2
- 2.22** 8 in both cases
- 2.23** 6 in both cases


Chapter 3

- 3.1** fluorine
- 3.2** Helium has a full first shell. The others all have eight electrons in the outer energy level (shell/orbit).
- 3.3** 2
- 3.4** the bottom of Group I
- 3.5** Metal: can be beaten into sheets, gives a ringing sound when hit, conducts heat, conducts electricity
Non-metal: is an insulator, has a dull surface
- 3.6** potassium hydroxide
- 3.7** lithium + water $\rightarrow$ lithium hydroxide + hydrogen
- 3.8** chlorine and fluorine
- 3.9** It is used in the treatment of drinking water; it will bleach moist litmus paper.
- 3.10** metal to non-metal
- 3.11** aluminium
- 3.12** sodium
- 3.13** Cl_2
- 3.14** silicon
- 3.15** because copper is a transition metal
- 3.16** **a** covalent **b** covalent **c** ionic **d** metallic
- 3.17** because in hydrogen gas two atoms are covalently bonded together
- 3.18** an electrostatic force (attraction between two oppositely charged ions)
- 3.19** **a**





3.21 The calcium ion is ionically bonded to the carbonate ion but the carbonate ion is held together by covalent bonds.



3.23 a sodium iodide b magnesium sulfide
c potassium oxide d lithium nitride
e calcium hydroxide f nitrogen monoxide
g nitrogen dioxide h sulfur trioxide

3.24 a SiCl_4 b CS_2 c PCl_3 (or PCl_5) d SiO_2

3.25 a i Na = 1, O = 1, H = 1 ii C = 2, H = 6
iii H = 2, S = 1, O = 4 iv Cu = 1, N = 2, O = 6
v C = 12, H = 22, O = 11

b i potassium bromide ii aluminium hydroxide
iii copper carbonate iv magnesium nitride
v phosphorus trichloride vi nitric acid
vii silicon tetrachloride viii iron(II) sulfate
ix methane x sulfuric acid

c i K_2SO_4 ii AlF_3 iii Fe_2O_3 iv $\text{Ca}(\text{NO}_3)_2$
v ZnCl_2 vi NH_3 vii HCl viii CuSO_4
ix SO_3

3.26 a carbon, hydrogen and oxygen

b 8

c carbon and oxygen

d 4

e A liquid: it is a small covalent molecule.

f No, it is covalently bonded.

3.27 The ions are free to move and they carry the charge.

3.28 because the ions are fixed in position and cannot move

3.29 a because there are electrons between the flat planes of atoms which are free to move

b There are only weak forces between the layers in graphite and therefore they can slide over each other.

3.30 because, in diamond, each carbon atom is attached to four other carbon atoms, making a strong lattice

3.31 because there are no charged particles to move around

3.32 because there are electrons which are free to move in solid metals

3.33 Both substances have a three-dimensional structure in which the atoms are arranged tetrahedrally and all the atoms are joined by covalent bonds.

Chapter 4

4.1 a physical b chemical

c physical d physical

4.2 a exothermic b exothermic

c exothermic d endothermic

4.3 A new substance(s) has been formed.

4.4 a iron + oxygen $\rightarrow$ iron(III) oxide

b sodium hydroxide + sulfuric acid
 $\rightarrow$ sodium sulfate + water

c sodium + water

$\rightarrow$ sodium hydroxide + hydrogen

4.5 a $2\text{Cu} + \text{O}_2 \rightarrow 2\text{CuO}$

b $\text{N}_2 + 3\text{H}_2 \rightleftharpoons 2\text{NH}_3$

c $4\text{Na} + \text{O}_2 \rightarrow 2\text{Na}_2\text{O}$

d $2\text{NaOH} + \text{H}_2\text{SO}_4 \rightarrow \text{Na}_2\text{SO}_4 + 2\text{H}_2\text{O}$

e $2\text{Al} + 3\text{Cl}_2 \rightarrow 2\text{AlCl}_3$

f $3\text{Fe} + 4\text{H}_2\text{O} \rightarrow \text{Fe}_3\text{O}_4 + 4\text{H}_2$

4.6 a chlorine + potassium bromide


$\rightarrow$ potassium chloride + bromine

b Iodine is less reactive than chlorine so it will not displace chlorine from its salts.

4.7 a combustion b decomposition


c redox d neutralisation

4.8 a sodium + water $\rightarrow$ sodium hydroxide + hydrogen




b magnesium + steam

$\rightarrow$ magnesium oxide + hydrogen



c calcium + oxygen $\rightarrow$ calcium oxide



d bromine + potassium iodide

$\rightarrow$ potassium bromide + iodine



e zinc + copper sulfate $\rightarrow$ zinc sulfate + copper



- 4.9 a** Solid sodium carbonate reacts with hydrochloric acid **solution** to give sodium chloride **solution** and carbon dioxide **gas**. Water, a **liquid**, is also produced.
- b i** $\text{Ag}^+(\text{aq}) + \text{Cl}^-(\text{aq}) \rightarrow \text{AgCl}(\text{s})$
ii $\text{Ba}^{2+}(\text{aq}) + \text{SO}_4^{2-}(\text{aq}) \rightarrow \text{BaSO}_4(\text{s})$
iii $\text{H}^+(\text{aq}) + \text{OH}^-(\text{aq}) \rightarrow \text{H}_2\text{O}(\text{l})$
iv $2\text{H}^+(\text{aq}) + \text{CO}_3^{2-}(\text{s}) \rightarrow \text{H}_2\text{O}(\text{l}) + \text{CO}_2(\text{g})$
- 4.10** Reduction is the gain of electrons; oxidation is the loss of electrons. During a redox reaction the oxidising agent **gains** electrons; the oxidising agent is itself **reduced** during the reaction.
- 4.11 a** The compound is split into its elements.
b The ions are not free to move in the solid, so they cannot move to the electrodes to be discharged.
c The vapour is brown.
d because bromine vapour is toxic
e the cathode
- 4.12 a** the cathode
b copper sulfate solution
- 4.13 a** $2\text{Br}^- \rightarrow \text{Br}_2 + 2\text{e}^-$
b because electrons are gained by the lead ions.
- 4.14**


Solution (electrolyte)	Gas given off at the anode	Gas given off or metal deposited at the cathode	Substance left in solution at the end of electrolysis
silver sulfate	oxygen	silver	sulfuric acid
sodium nitrate	oxygen	hydrogen	sodium nitrate

- 4.15 a i** electrode Y **ii** a cathode
b The solution would become acidic.
c To make the electrode conduct electricity.
- 4.16 a** the anode **b** the cathode
c Oxidation is defined as loss of electrons, which happens at the anode; reduction is defined as gain of electrons, which happens at the cathode.

Chapter 5

- 5.1** A corrosive substance 'eats' things away.
5.2 citric acid

- 5.3 a** alkaline **b** neutral **c** alkaline **d** acidic
5.4 It changes its colour depending on whether it is in an acidic or alkaline solution.
5.5 pH 1 is more acidic.
5.6 green
5.7 ethanoic acid
5.8 hydrogen
5.9 hydroxide ion, OH^-
5.10 a hydrogen ions and nitrate ions
b calcium ions and hydroxide ions
c ammonium ions and hydroxide ions
5.11 a H_2SO_4 **b** HCl
5.12 They are equal.
5.13 blue
5.14 white
5.15 sulfur + oxygen $\rightarrow$ sulfur dioxide
5.16 $\text{S} + \text{O}_2 \rightarrow \text{SO}_2$
5.17 magnesium + oxygen $\rightarrow$ magnesium oxide
5.18 carbon monoxide
5.19 zinc hydroxide *or* aluminium hydroxide




- 5.20** baking soda
5.21 hydrochloric acid, to help digest our food
5.22 calcium carbonate, magnesium hydroxide
5.23 insoluble bases: copper oxide, zinc oxide
 alkalis: sodium hydroxide, potassium hydroxide
5.24 a sodium hydroxide + hydrochloric acid
 $\rightarrow$ sodium chloride + water
 $\text{NaOH} + \text{HCl} \rightarrow \text{NaCl} + \text{H}_2\text{O}$
b potassium hydroxide + sulfuric acid
 $\rightarrow$ potassium sulfate + water
 $2\text{KOH} + \text{H}_2\text{SO}_4 \rightarrow \text{K}_2\text{SO}_4 + 2\text{H}_2\text{O}$
c copper oxide + nitric acid
 $\rightarrow$ copper nitrate + water
 $\text{CuO} + 2\text{HNO}_3 \rightarrow \text{Cu(NO}_3)_2 + \text{H}_2\text{O}$
5.25 sodium hydroxide, potassium hydroxide, calcium hydroxide (limewater), ammonia solution
5.26 ammonia
5.27 hydrochloric acid (HCl), nitric acid (HNO_3), sulfuric acid (H_2SO_4)

- 5.28 a** potassium hydroxide + hydrochloric acid
→ potassium chloride + water
b copper oxide + hydrochloric acid
→ copper chloride + water
c zinc + hydrochloric acid
→ zinc chloride + hydrogen
d sodium carbonate + hydrochloric acid
→ sodium chloride + water + carbon dioxide
- 5.29 a** $\text{KOH} + \text{HCl} \rightarrow \text{KCl} + \text{H}_2\text{O}$
b $\text{CuO} + 2\text{HCl} \rightarrow \text{CuCl}_2 + \text{H}_2\text{O}$
c $\text{Zn} + 2\text{HCl} \rightarrow \text{ZnCl}_2 + \text{H}_2$
d $\text{Na}_2\text{CO}_3 + 2\text{HCl} \rightarrow 2\text{NaCl} + \text{H}_2\text{O} + \text{CO}_2$
- 5.30 a** carbonate + hydrochloric acid
→ salt + water + carbon dioxide
- 5.31** blue precipitate, copper(II) hydroxide
- 5.32** ammonia solution
You get a white precipitate in both cases but the zinc hydroxide precipitate re-dissolves in excess ammonia and the aluminium hydroxide precipitate does not.
- 5.33 a** hydrogen **b** copper(II) sulfate
c carbon dioxide **d** litmus
e potassium hydroxide
- 5.34** pink (purple)
- 5.35** to make sure all the acid is used up/reacted
- 5.36** filtration
- 5.37** pipette, burette
- 5.38** If heated too strongly, the salt could dehydrate (lose water of crystallisation) or even decompose.
- 5.39 a i** method C **ii** sulfuric acid
iii zinc oxide + sulfuric acid
→ zinc sulfate + water
b i method A **ii** hydrochloric acid
iii $\text{KOH} + \text{HCl} \rightarrow \text{KCl} + \text{H}_2\text{O}$
c i method B **ii** potassium iodide
iii $\text{Pb}^{2+}(\text{aq}) + 2\text{I}^- \rightarrow \text{PbI}_2$
- 5.40** $\text{HCl}(\text{g}) + \text{aq} \rightarrow \text{H}^+(\text{aq}) + \text{Cl}^-(\text{aq})$
- 5.41** $\text{NH}_3(\text{g}) + \text{aq} \rightleftharpoons \text{NH}_4^+(\text{aq}) + \text{OH}^-(\text{aq})$
- 5.42** Ethanoic acid is a weak acid and so is only partly ionised in solution; hydrochloric acid is a strong acid, so it is fully ionised: there are more ions to carry the electric current.
- 5.43** The hydrogen atom is just 1 proton and 1 electron; when the electron is lost, it is just left with the proton of the nucleus.
- 5.44** An acid is a proton donor; a base is a proton acceptor.

- 5.45 a** An ionic equation includes just those ions and molecules that actually take part in the reaction.
b A spectator ion is present in the reaction mixture but does not actually take part in the reaction.
- 5.46 a** $2\text{H}^+(\text{aq}) + \text{O}^{2-}(\text{s}) \rightarrow \text{H}_2\text{O}(\text{l})$
b $2\text{H}^+(\text{aq}) + \text{CO}_3^{2-}(\text{s}) \rightarrow \text{H}_2\text{O}(\text{l}) + \text{CO}_2(\text{g})$
c $\text{H}^+(\text{aq}) + \text{OH}^-(\text{aq}) \rightarrow \text{H}_2\text{O}(\text{l})$


Chapter 6

- 6.1 a** covalent **b** ionic
c CH_4 , NaI, C_3H_6 , ICl_3 , BrF_5 , HBr
- 6.2 a** 32 **b** 17 **c** 64 **d** 114 **e** 98 **f** 119
g 188 **h** 133.5
- 6.3 a** 21.2% **b** 28.2% **c** 46.7% **d** 35.0%
e 18.7%
- 6.4 a** 0.20 g; 0.18 g; 0.08 g; 0.12 g



- c** The graph is a straight line, showing a fixed ratio of oxygen to magnesium; this indicates a fixed formula.
- 6.5** molar ratio of Cu:Fe:S is 1:1:2
empirical formula = CuFeS_2
- 6.6 a** molar ratio of C:H:O is 1:3:1
empirical formula = CH_3O
b molar mass of CH_3O = 31
so actual formula is $\text{C}_2\text{H}_6\text{O}_2$
c $\text{CH}_2(\text{OH})\text{CH}_2(\text{OH})$
- 6.7 a i** near the neck of the test tube
ii to flush out all of the air from the tube
iii to make sure the reaction was complete
b i C = 1.60 g, E = 1.28 g, F = 0.32 g
ii 0.02 moles
iii 0.02 moles


- iv 1 mole
v CuO
vi copper(II) oxide + hydrogen → copper + water



- 6.8 a 0.02 moles b 2 moles c 0.07 moles
6.9 a 36 000 cm³ b 1440 cm³ c 12 000 cm³
6.10 a 2 mol/dm³ b 0.2 mol/dm³ c 1 mol/dm³
d 0.8 g of NaOH = 0.2 moles; 0.2 mol/dm³

Chapter 7

- 7.1 endothermic
7.2 endothermic
7.3 Polystyrene is a good insulator (and absorbs very little heat itself).
7.4 -210 kJ/mol; exothermic
7.5




- 7.6 a rate increases b rate increases
c rate increases
7.7 The reactions which would spoil the food are slowed down at the lower temperature.
7.8 at the beginning
7.9 because the reactants are being used up
7.10 A catalyst is a substance that speeds up a chemical reaction but is not itself used up in the course of the reaction.
7.11 a biological catalyst
7.12 manganese(IV) oxide
7.13 a iron b vanadium(V) oxide
7.14 changes in temperature and pH
7.15 The presence of a catalyst decreases the activation energy of reaction.
7.16 a An increased temperature means that the particles are moving faster and will therefore collide more frequently; when they collide, more particles will have energy greater than the activation energy so there will be more collisions that result in a reaction.
b There will be more surface area of the solid exposed to the reactant and therefore more frequent collisions.

- c Greater concentration means there are more reactant molecules present and so there will be a greater frequency of collision.

7.17 sunlight (ultraviolet radiation) and the presence of chlorophyll

7.18 carbon dioxide + water → glucose + oxygen




- 7.19 photochemical reactions
7.20 glucose + oxygen → carbon dioxide + water
7.21 Where most light falls on the film the most silver is deposited, causing the film to be blackened – so the film is dark where most light hits it.

7.22 white to blue


7.23 the presence of water

7.24 Haber process: nitrogen + hydrogen ⇌ ammonia



Contact process: sulfur dioxide + oxygen

⇌ sulfur trioxide



- 7.25 450 °C, 200 atmospheres pressure, iron catalyst
7.26 Increased pressure will produce more ammonia at equilibrium.
7.27 Increasing the temperature will produce less ammonia at equilibrium.

Chapter 8

- 8.1 They are soft and have a low density.
8.2 Sodium gives a yellow flame, potassium a lilac flame.
8.3 hydrogen
8.4 potassium hydroxide
8.5 sodium + water → sodium hydroxide + hydrogen
8.6 $2\text{K} + 2\text{H}_2\text{O} \rightarrow 2\text{KOH} + \text{H}_2$
8.7 lithium
8.8 It is strong but light and it does not corrode.
8.9 It is more reactive than carbon (so its oxide cannot be reduced by carbon).
8.10 iron(III) oxide + aluminium
→ iron + aluminium oxide
8.11 A thin layer of aluminium oxide forms on the surface of the metal and sticks to it, giving it a protective coating; with iron, the oxide forms but flakes off and so does not protect the metal.

- 8.12** They are strong and dense, have high melting points, their compounds are often coloured, they can show more than one valency, they or their compounds often act as catalysts (*any three*).
- 8.13** 2 and 3
- 8.14** blue
- 8.15** (hydrated) iron(III) oxide, Fe_2O_3
- 8.16** the Haber process
- 8.17** zinc + hydrochloric acid $\rightarrow$ zinc chloride + hydrogen
- 8.18** copper
- 8.19** magnesium + copper(II) sulfate
 $\rightarrow$ magnesium sulfate + copper
- 8.20** A brown deposit is formed and the blue colour of the solution fades to colourless.
- 8.21** $\text{Mg} + \text{CuSO}_4 \rightarrow \text{MgSO}_4 + \text{Cu}$
 $\text{Mg(s)} + \text{Cu}^{2+}(\text{aq}) \rightarrow \text{Mg}^{2+}(\text{aq}) + \text{Cu(s)}$
- 8.22** magnesium
- 8.23** $\text{Mg(s)} \rightarrow \text{Mg}^{2+}(\text{aq}) + 2\text{e}^-$

Chapter 9

- 9.1** to combine with the silicon dioxide (sand) and remove it as slag
- 9.2** $\text{Fe}_2\text{O}_3 + 3\text{CO} \rightarrow 2\text{Fe} + 3\text{CO}_2$
- 9.3** oxygen
- 9.4** to make an alloy which doesn't corrode (stainless steel)
- 9.5** water and oxygen (air)
- 9.6** It can be used to coat iron (galvanisation) or can be attached to iron as blocks (cathodic protection).
- 9.7** It distils off as a gas and is condensed back to a liquid.
- 9.8** because very pure copper is needed for electrical conductors
- 9.9** because of the high cost of electricity, which is needed in large quantities
- 9.10** because this makes the temperature needed to melt the aluminium oxide much lower
- 9.11** because the oxygen produced at the anode causes them to burn away
- 9.12** $\text{Al}^{3+} + 3\text{e}^- \rightarrow \text{Al}$
- 9.13** because it forms an oxide layer which prevents any further reaction with oxygen (corrosion)
- 9.14** by reacting methane gas with steam
- 9.15** an iron catalyst, a moderately high temperature (450°C) and a high pressure (200 atmospheres)
- 9.16** so that they react the second time around (saves producing more raw materials)
- 9.17** because these are the three elements needed by plants which can become used up in soil
- 9.18** They are washed off fields by rain and end up in streams and rivers.
- 9.19** $\text{S} + \text{O}_2 \rightarrow \text{SO}_2$
- 9.20** a catalyst (vanadium(V) oxide) and a temperature of around 450°C
- 9.21** because the reaction is too violent: a mist of sulfuric acid is formed which is very dangerous
- 9.22** SO_2 : bleaching paper and sterilising food
 H_2SO_4 : making detergents, cleaning metals such as steel, making fertilisers
- 9.23** sterilisation of drinking water, making PVC, use as a bleach (*any two*)
- 9.24** a concentrated solution of sodium chloride in water
- 9.25** because it converts a cheap raw material (common salt) into three important chemicals: chlorine, hydrogen and sodium hydroxide. There are no waste products.
- 9.26** the membrane cell, followed by the diaphragm cell
- 9.27** to neutralise acidity in the water
- 9.28** to remove silicon dioxide (sand) from the iron ore
- 9.29** $\text{CaCO}_3 \rightarrow \text{CaO} + \text{CO}_2$
- 9.30** Ca(OH)_2
- 9.31** treating soil to remove excess acidity; removing impurities from iron during the basic oxygen steel making process
- 9.32** because it is quick to recycle, and 'new' aluminium is very expensive to produce
- 9.33** conserving non-renewable resources such as metal ores; avoiding dumping waste in landfill
- 9.34** It can be difficult to separate the different types of plastic, which ideally need to be recycled separately.


Chapter 10

- 10.1** covalent
- 10.2** 4
- 10.3** diamond and graphite; the fullerenes
- 10.4** proteins, carbohydrates, nucleic acids (*any two*)
- 10.5** methane, ethane, propane, butane, pentane, hexane
 CH_4 , C_2H_6 , C_3H_8 , C_4H_{10} , C_5H_{12} , C_6H_{14}

10.6




methane



butane

10.7




The graph shows a smooth curve with a steady, but decreasing, change in boiling point as the hydrocarbon chain gets longer.

10.8 a C_5H_{12} , pentane b $\text{C}_{17}\text{H}_{36}$ 10.9 ethane + oxygen $\rightarrow$ carbon dioxide + water

10.10 natural gas


10.11




10.12 ethene, propene, butene, pentene



10.13



ethene




propene

10.14 CH_2

10.15 The bromine water is decolorised from brown to colourless.

10.16 bromine + ethene $\rightarrow$ 1,2-dibromoethane


10.17




10.18 a ethene b methanol c methanoic acid

10.19 Isomers are compounds with the same molecular formula but different structural formulae.

10.20




but-1-ene




but-2-ene

10.21




butane




2-methylpropane

10.22




pentane




2-methylbutane

or



2,2-dimethylpropane

10.23



10.24 a i A, G or H (any two) ii E and F iii C

b (2-)methylpropane

10.25 methane + oxygen $\rightarrow$

carbon monoxide + water



10.26 CO

10.27 particles of carbon (soot) glowing in the heat


10.28 It binds to red blood cells (to the haemoglobin) and interferes with the transport of oxygen in the body.

10.29 chloromethane, CH_3Cl 10.30 propane + oxygen $\rightarrow$ carbon dioxide + water


10.31 sunlight (ultraviolet light)



c The reaction requires light for it to take place.




10.34 ethene + hydrogen $\rightarrow$ ethane




10.35 finely divided nickel

10.36 a propene + hydrogen $\rightarrow$ propane



10.37 a i hydrogen chloride



b ethane and chlorine in sunlight (ultraviolet light)

10.38 methanol, ethanol, propanol

10.39 ethene + steam $\rightarrow$ ethanol



10.40 yeast, carbohydrate source, water


10.41 a carbon dioxide

b It is an air-lock – allowing the carbon dioxide to escape but not allowing air/bacteria in.

c yeast

d at around 37°C

e This is the temperature favoured by the yeast, which are living organisms.




methanol


ethanol

b A homologous series of compounds is a family of organic compounds that have the same general formula, similar chemical properties and a gradual trend in their physical properties.


10.43 propan-1-ol



propan-2-ol



10.44 a i It is an alcohol.



b a diagram showing fractional distillation (see page 30)


10.45 a i carbon (soot)

ii incomplete combustion

b i carbon dioxide and water

ii The alcohol content is not high enough – there is too much water.

10.46 ethanol + $[O] \rightarrow$ ethanoic acid + water




10.47 propene

10.48 ethyl ethanoate

ethanol + ethanoic acid


$\rightarrow$ ethyl ethanoate + water

catalyst: H^+ ions



b oxidation

c hydrogen ions as a catalyst (a few drops of concentrated sulfuric acid is added), heat (reflux)



10.50 a ethyl ethanoate

b ethanol + ethanoic acid

$\rightarrow$ ethyl ethanoate + water


10.51 a oxidation


b acidified potassium dichromate



c fractional distillation



d Measure the pH of the two using a pH meter.

Chapter 11

- 11.1** refinery gas, petrol (gasoline), naphtha, kerosene (paraffin), diesel, bitumen
- 11.2** coal, natural gas, petroleum (crude oil)
- 11.3** Cracking is the thermal decomposition of a long-chain alkane to a shorter-chain alkane and an alkene (or hydrogen).
decane $\rightarrow$ octane + ethene
 $C_{10}H_{22} \rightarrow C_8H_{18} + C_2H_4$
- 11.4** road surfacing, ships' engines, car engines, aircraft fuel (domestic heating)
- 11.5** C_2H_4 
- 11.6** Addition polymerisation takes place when many molecules of an unsaturated monomer join together to form a long-chain polymer.




- 11.7** **a** 
- b** 
- 11.8** tetrafluoroethene
- 11.9** **a** crates/plastic rope
b insulation/pipes
c non-stick pans/gear wheels
- 11.10** starch, protein, nucleic acids (*any two*)
- 11.11** The monomers join together by a reaction in which a small molecule (usually water) is eliminated each time a link is made.
- 11.12** nylon – the amide link (or peptide link)
Terylene (a polyester) – the ester link
- 11.13** **a**



$\downarrow$



- 11.14** **a** the amide link (or peptide link)
- b** 
- c** Proteins are made from 20 different amino acid monomers; nylon is made from just two monomers.
- d** Proteins can be hydrolysed (broken down) by heating with concentrated hydrochloric acid.

Chapter 12

- 12.1** because their hydroxides are insoluble and form as precipitates
- 12.2** aluminium and zinc hydroxides
- 12.3** because iron has two different oxidation states (iron(II) and iron(III))
- 12.4** carbon dioxide
- 12.5** silver nitrate
- 12.6** hydrochloric acid
- 12.7** oxygen
- 12.8** the ammonium ion
- 12.9** **a** D **b** E **c** A **d** C
- 12.10** Add bromine water: it turns from brown to colourless.
- 12.11** Add indicator (turns red/orange in the acid), or add sodium carbonate solution (fizzes with the acid).
- 12.12** because they are colourless
- 12.13** the amount of water, the amount of fuel used, or the time it was used for
- 12.14** substance, appearance before heating, appearance during heating, appearance after cooling

Glossary

- acid** a substance that dissolves in water, producing $\text{H}^+(\text{aq})$ ions – a solution of an acid turns litmus red and has a pH below 7; in their reactions acids act as proton donors
- acid rain** rain which has been made more acidic than normal by the presence of dissolved pollutants such as sulfur dioxide (SO_2) and nitrogen oxides (NO_x)
- acidic oxides** oxides of non-metals which will react with bases and dissolve in water to produce acid solutions
- activation energy (E_A)** the energy required to start a chemical reaction – for a reaction to take place the colliding particles must possess at least this amount of energy
- addition polymer** a polymer formed by an addition reaction – the monomer molecules must contain a $\text{C}=\text{C}$ double bond
- addition reaction** a reaction in which a simple molecule adds across the carbon–carbon double bond of an alkene
- alcohols** a series of organic compounds containing the functional group $-\text{OH}$ and with the general formula $\text{C}_n\text{H}_{2n+1}\text{OH}$
- alkali metals** elements in Group I of the Periodic Table; they are the most reactive group of metals
- alkaline earth metals** elements in Group II of the Periodic Table
- alkalis** soluble bases which produce $\text{OH}^-(\text{aq})$ ions in water – a solution of an alkali turns litmus blue and has a pH above 7
- alkanes** a series of hydrocarbons with the general formula $\text{C}_n\text{H}_{2n+2}$; they are saturated compounds as they have only single bonds between carbon atoms in their structure
- alkenes** a series of hydrocarbons with the general formula C_nH_{2n} ; they are unsaturated molecules as they have a $\text{C}=\text{C}$ double bond somewhere in the chain
- alloy steels** steels in which iron is mixed with other transition metals (and a small amount of carbon)
- alloys** mixtures of elements (usually metals) designed to have the properties useful for a particular purpose; for example, solder (an alloy of tin and lead) has a low melting point
- amide link (or peptide link)** the link between monomers in a protein or nylon, formed by a condensation reaction between a carboxylic acid group on one monomer and an amine group on the next monomer
- amino acids** naturally occurring organic compounds which possess both an amino ($-\text{NH}_2$) group and an acid ($-\text{COOH}$) group in the molecule; there are 20 naturally occurring amino acids and they are polymerised in cells to make proteins
- amount** physical quantity of substance relating to the number of constituent particles present in a sample; measured in moles
- amphoteric hydroxides** hydroxides which can react with both acids and alkalis to produce salts; for example, zinc hydroxide; certain metal oxides can also be amphoteric
- anaerobic decay** decay of organic matter which takes place in the absence of air
- anion** a negative ion which would be attracted to the anode in electrolysis
- anode** the electrode in any type of cell at which oxidation (the loss of electrons) takes place – in electrolysis it is the positive electrode
- antacids** compounds used medically to treat indigestion by neutralising excess stomach acid
- artificial fertiliser** a substance added to soil to increase the amount of elements such as nitrogen, potassium and phosphorus (NPK fertilisers): this enables crops to grow more healthily and produce higher yields
- atmospheric pressure** the pressure exerted by the atmosphere on the surface of the Earth due to the weight of the atmosphere
- atom** the smallest particle of an element that can take part in a chemical reaction
- atomic number (or proton number) (Z)** the number of protons in the nucleus of an atom; it is also the number

of electrons present in an atom and determines the position of the element in the Periodic Table

Avogadro constant *see* **mole**

balanced chemical (symbol) equation a summary of a chemical reaction using chemical formulae – the total number of any of the atoms involved is the same on both the reactant and product sides of the equation

base a substance that neutralises an acid, producing a salt and water as the only products; in their reactions bases act as proton acceptors

basic oxide oxide of a metal that will react with acids to neutralise the acid

basic oxygen process the process used to make steel from iron from the blast furnace: oxygen is blown into the molten iron using an 'oxygen lance' and lime is added to remove non-metallic impurities

biodegradable plastics plastics which are designed to be degraded (decomposed) by bacteria

blast furnace a furnace for smelting iron ores such as hematite (Fe_2O_3) with carbon to produce pig (or cast) iron (in a modified form the furnace can be used to extract metals such as zinc)

boiling a condition under which gas bubbles are able to form within a liquid – gas molecules escape from the body of a liquid, not just from its surface

boiling point the temperature at which a liquid boils, when the pressure of the gas created above the liquid equals atmospheric pressure

bond energy the energy required to break a particular type of covalent bond

brine a concentrated solution of sodium chloride in water

Brownian motion the observed jerky and erratic motion of smoke particles in a smoke cell as they are hit by the unseen molecules in the air

burning combustion in which a flame is produced

carbohydrates a group of naturally occurring organic compounds containing carbon, hydrogen and oxygen; the ratio of hydrogen to oxygen atoms in the molecules is always 2:1 and they have the general formula $\text{C}_x(\text{H}_2\text{O})_y$

carbon cycle the system by which carbon and its compounds in the air, oceans and rocks are interchanged

carbon steel alloys of iron and carbon only; the amount of carbon in steels can vary between 0.2% and 1.5%

carboxylic acids (alkanoic acids) a family of organic compounds containing the functional group $-\text{COOH}$ ($-\text{CO}_2\text{H}$), with the general formula $\text{C}_n\text{H}_{2n+1}\text{COOH}$

catalyst a substance which increases the rate of a chemical reaction but itself remains unchanged at the end of the reaction

catalytic converter a device for converting polluting exhaust gases from cars into less dangerous emissions

catalytic cracking the decomposition of long-chain alkanes into alkenes and alkanes of lower relative molecular mass; involves passing the larger alkane molecules over a catalyst heated to 500°C

cathode the electrode in any type of cell at which reduction (the gain of electrons) takes place; in electrolysis it is the negative electrode

cation a positive ion which would be attracted to the cathode in electrolysis

centrifugation the separation of an insoluble solid from a liquid by rapid spinning during which the solid collects at the bottom of the sample tubes – the liquid can then be decanted off carefully

ceramic material such as pottery made from inorganic chemicals by high-temperature processing

chemical bonding the strong forces that hold atoms (or ions) together in the various structures that chemical substances can form – metallic bonding, covalent bonding and ionic (electrovalent bonding)

chemical reaction (change) a change in which a new substance is formed

chemiluminescence light given out by certain chemical reactions

chromatogram the result of a paper chromatography run, showing where the spots of the samples have moved to

chromatography a technique employed for the separation of mixtures of dissolved substances, which was originally used to separate coloured dyes

coal a black, solid fossil fuel formed underground over geological periods of time by conditions of high pressure and temperature acting on decayed vegetation

collision theory a theory which states that a chemical reaction takes place when particles of the reactants collide with sufficient energy to initiate the reaction

- combustion** a chemical reaction in which a substance reacts with oxygen – the reaction is exothermic; **burning** is a combustion reaction which produces a flame
- compound** a substance formed by the chemical combination of two or more elements in fixed proportions
- concentration** a measure of how much solute is dissolved in a solvent. Solutions can be **dilute** (with a high proportion of the solvent), or **concentrated** (with a high proportion of the solute)
- condensation** the change of a vapour or a gas into a liquid; during this process heat is given out to the surroundings
- condensation polymer** a polymer formed by a **condensation reaction**; for example, nylon is produced by the condensation reaction between 1,6-diaminohexane and hexanedioic acid – this is the type of polymerisation used in biological systems to produce proteins, nucleic acids and polysaccharides
- Contact process** the industrial manufacture of sulfuric acid using the raw materials sulfur and air
- core (of Earth)** the central, densest part of the Earth, composed mainly of iron and nickel; the outer core is molten and surrounds the solid, inner core which exists at very high temperature and pressure
- corrosion** the name given to the process that takes place when metals and alloys are chemically attacked by oxygen, water or any other substances found in their immediate environment
- corrosive** a corrosive substance (an acid, for example) is one that can dissolve or ‘eat away’ at other materials (wood, metals, or human skin, for instance)
- covalent bonding** chemical bonding formed by the sharing of one or more pairs of electrons between two atoms
- crude oil** *see* **petroleum**
- crust (of Earth)** the solid, outermost, layer of the Earth; it is not continuous, but subdivided into plates of continental or oceanic crust
- crystallisation** the process of forming crystals from a saturated solution
- decanting** the process of removing a liquid from a solid which has settled or from an immiscible heavier liquid by careful pouring
- decomposition** (*see also* **thermal decomposition**) a type of chemical reaction where a compound breaks down into simpler substances
- dehydration** a chemical reaction in which water is removed from a compound
- density** expresses the relationship between the mass of a substance and the volume it occupies:
density = mass / volume
- diatomic molecules** molecules containing two atoms; for example hydrogen, H_2
- dibasic acid (diprotic acid)** an acid that contains two replaceable hydrogen atoms per molecule of the acid; for example, sulfuric acid, H_2SO_4
- diffusion** the process by which different fluids mix as a result of the random motions of their particles
- displacement reaction** a reaction in which a more reactive element displaces a less reactive element from a solution of its salt
- distillate** the liquid distilling over during distillation
- distillation** the process of boiling a liquid and then condensing the vapour produced back into a liquid: used to purify liquids and to separate liquids from solutions
- downward delivery** a method of collecting a gas which is denser than air by passing it downwards into a gas jar
- drug** any substance, natural or synthetic, that alters the way in which the body works
- drying agent** a chemical substance that absorbs water; anhydrous calcium chloride and concentrated sulfuric acid are two examples
- ductile** a word used to describe the property that metals can be drawn out and stretched into wires
- dynamic (chemical) equilibrium** two chemical reactions, one the reverse of the other, taking place at the same time, where the concentrations of the reactants and products remain constant because the rate at which the forward reaction occurs is the same as that of the back reaction
- electrical conductor** a substance that conducts electricity but is not chemically changed in the process
- electrochemical cell** a system for converting chemical energy to electrical energy, made by connecting two metals of different reactivity via an electrolyte; **fuel cells** are electrolytic cells capable of providing a continuous supply of electricity without recharging
- electrodes** the points where the electric current enters or leaves a battery or **electrolytic cell**

electrolysis the breakdown of an ionic compound, molten or in aqueous solution, by the use of electricity

electrolyte an ionic compound that will conduct electricity when it is molten or dissolved in water; electrolytes will not conduct electricity when solid

electrolytic cell a cell consisting of an electrolyte and two electrodes (anode and cathode) connected to an external DC power source where positive and negative ions in the electrolyte are separated and discharged

electron a subatomic particle with negligible mass and a charge of -1 ; electrons are present in all atoms, located in energy levels outside the nucleus

electron (arrangement) configuration a shorthand method of describing the arrangement of electrons within the energy levels of an atom; also referred to as **electronic structure**

electronic structure *see* **electron configuration**

electroplating a process of electrolysis in which a metal object is coated (plated) with a layer of another metal

electrostatic forces strong forces of attraction between particles with opposite charges – such forces are involved in **ionic bonding**

element a substance which cannot be further divided into simpler substances by chemical methods; all the atoms of an element contain the same number of protons

empirical formula a formula for a compound which shows the simplest ratio of atoms present

endothermic change a process or chemical reaction which takes in heat from the surroundings; ΔH has a positive value

energy levels (of electrons) the allowed energies of electrons in atoms – electrons fill these levels (or shells) starting with the one closest to the nucleus

enzymes protein molecules that act as biological catalysts

equilibrium *see* **dynamic equilibrium**

ester link the link produced when an ester is formed from a carboxylic acid and an alcohol; also found in polyesters and in the esters present in fats and vegetable oils

esterification the chemical reaction between an alcohol and a carboxylic acid that produces an ester; the other product is water

esters a family of organic compounds formed by esterification, characterised by strong and pleasant tastes and smells

evaporation a process occurring at the surface of a liquid, involving the change of state from a liquid into a vapour at a temperature below the boiling point

exothermic change a process or chemical reaction in which heat energy is produced and released to the surroundings; ΔH has a negative value

filtrate the liquid that passes through the filter paper during filtration

filtration the separation of a solid from a liquid, using a fine filter paper which does not allow the solid to pass through

flue-gas desulfuriser (or 'scrubber') a tower in which the waste gases from a coal- or oil-fired power station are treated to remove acidic gases such as sulfur dioxide

fluid a gas or a liquid; they are able to flow

formula (chemical) a shorthand method of representing chemical elements and compounds using the symbols of the elements

fossil fuels fuels, such as coal, oil and natural gas, formed underground over geological periods of time from the remains of plants and animals

fractional distillation a method of distillation using a fractionating column, used to separate liquids with different boiling points

fractionating column the vertical column which is used to bring about the separation of liquids in fractional distillation

fractions (from distillation) the different mixtures that distil over at different temperatures during fractional distillation

Frasch process the process of obtaining sulfur from sulfur beds below the Earth's surface; superheated water is pumped down a shaft to liquefy the sulfur, which is then brought to the surface

fuel a substance that can be used as a source of energy, usually by burning (combustion)

fuel cell a device for continuously converting chemical energy into electrical energy using a combustion reaction; a hydrogen fuel cell uses the reaction between hydrogen and oxygen

functional group the atom or group of atoms responsible for the characteristic reactions of a compound

- galvanising** the protection of iron and steel objects by coating with a layer of zinc
- geological periods of time** very long, extended periods of time (over millions of years) during which the Earth was shaped
- giant ionic lattice (structure)** a lattice held together by the electrostatic forces of attraction between positive and negative ions
- giant metallic lattice** a regular arrangement of positive metal ions held together by the mobile 'sea' of electrons moving between the ions
- giant molecular lattice (structure)** substance where large numbers of atoms are joined by covalent bonds forming a strong lattice structure
- global warming** a long-term increase in the average temperature of the Earth's surface, which may be caused in part by human activities
- grain boundaries** the boundaries between the grains in a metal, along which a piece of metal may fracture
- grains** the small crystal areas in a metal: controlling the grain size affects the properties of a piece of metal
- greenhouse effect** the natural phenomenon in which heat from the Sun is 'trapped' at the Earth's surface by certain gases in the atmosphere (greenhouse gases)
- groups** vertical columns of the Periodic Table containing elements with similar properties; atoms of elements in the same group have the same number of electrons in their outer energy levels
- Haber process** the industrial manufacture of ammonia by the reaction of nitrogen with hydrogen in the presence of an iron catalyst
- half-life** the time taken for half of the radioactive atoms in a sample of a radioisotope to decay
- halides** compounds formed between an element and a halogen; for example, sodium iodide
- halogens** elements in Group VII of the Periodic Table – generally the most reactive group of non-metals
- heat of combustion** the heat change which takes place when one mole of a substance is completely burnt in oxygen
- heat of neutralisation** the heat change which takes place when one mole of hydrogen ions is completely neutralised
- heat of reaction** the heat change during the course of a reaction; can be either **exothermic** or **endothermic**
- homologous series** a 'family' of organic compounds with the same functional group and similar properties
- hydrated salts** salts containing water of crystallisation
- hydrocarbons** compounds which contain carbon and hydrogen only
- hydrogenation** an addition reaction in which hydrogen is added across the double bond in an alkene
- hydrolysis** a chemical reaction between a covalent compound and water; covalent bonds are broken during the reaction and the elements of water are added to the fragments; can be carried out with acids or alkalis, or by using enzymes
- immiscible** if two liquids form two layers when they are mixed together, they are said to be immiscible
- indicator** a substance which changes colour when added to acidic or alkaline solutions; for example, litmus or phenolphthalein
- insoluble** term that describes a substance that does not dissolve in a particular solvent
- insulator** substance that does not conduct electricity
- intermolecular forces** the weak attractive forces which act between molecules
- ionic (electrovalent) bonding** a strong electrostatic force of attraction between oppositely charged ions
- ionic equation** the simplified equation for a reaction involving ionic substances: only those ions which actually take part in the reaction are shown
- ions** charged particles made from an atom, or groups of atoms (polyatomic ions), by the loss or gain of electrons
- isomerism** the property shown by molecules which have the same molecular formula but different structures
- isomers** compounds which have the same molecular formula but different structural arrangements of the atoms – they have different **structural formulae**
- isotopes** atoms of the same element which have the same proton number but a different nucleon number; they have different numbers of neutrons in their nuclei; some isotopes are radioactive because their nuclei are unstable (**radioisotopes**)
- kinetic (particle) model** a model which accounts for the bulk properties of the different states of matter in terms of the movement of particles (atoms or molecules) – the model explains what happens during changes in physical state
- lattice** a regular three-dimensional arrangement of atoms, molecules or ions in a crystalline solid

law of conservation of mass matter cannot be lost or gained in a chemical reaction – the total mass of the reactants equals the total mass of the products

lime a white solid known chemically as calcium oxide (CaO), produced by heating limestone; it can be used to counteract soil acidity, to manufacture calcium hydroxide (slaked lime) and also as a drying agent

limestone a form of calcium carbonate (CaCO₃)

limewater a solution of calcium hydroxide in water; it is an alkali and is used in the test for carbon dioxide gas

litmus the most common indicator; turns red in acid and blue in alkali

locating agent a compound that reacts with invisible, colourless spots separated by chromatography to produce a coloured product which can be seen

main-group elements the elements in the outer groups of the Periodic Table (Groups I to VII and VIII / 0)

malleable a word used to describe the property that metals can be bent and beaten into sheets

mass practical measure of quantity of a sample found by weighing on a balance

mass concentration the measure of the concentration of a solution in terms of the mass of the solute, in grams, dissolved per cubic decimetre of solution (g/dm³)

mass number (or nucleon number) (A) the total number of protons and neutrons in the nucleus of an atom

mass spectrometer an instrument in which atoms or molecules are ionised and then accelerated; the ions are then separated according to their mass

matter anything which occupies space and has mass

melting point the temperature at which a solid turns into a liquid – it has the same value as the freezing point; a pure substance has a sharp melting point

metallic bonding an electrostatic force of attraction between the mobile 'sea' of electrons and the regular array of positive metal ions within a solid metal

metalloid (semi-metal) element which shows some of the properties of metals and some of non-metals; for example, boron and silicon

metals a class of chemical elements (and alloys) which have a characteristic shiny appearance and are good conductors of heat and electricity

methyl orange an acid–base indicator that is red in acidic and yellow in alkaline solutions

miscible if two liquids form a completely uniform mixture when added together, they are said to be miscible

mixture a system of two or more substances that can be separated by physical means

molar concentration the measure of the concentration of a solution in terms of the number of moles of the solute dissolved per cubic decimetre of solution (mol/dm³)

molar mass the mass, in grams, of one mole of a substance

molar volume of a gas one mole of any gas has the same volume under the same conditions of temperature and pressure (24 dm³ at one atmosphere and room temperature)

mole the measure of amount of substance in chemistry; one mole of a substance has a mass equal to its relative formula mass in grams – that amount of substance contains 6.02×10^{23} (the **Avogadro constant**) atoms, molecules or formula units depending on the substance considered

molecular formula a formula that shows the actual number of atoms of each element present in a molecule of the compound

molecular mass see **relative molecular mass**

molecule a group of atoms held together by covalent bonds

monomer a small molecule, such as ethene, which can be polymerised to make a **polymer**

nanotechnology the study and control of matter on an atomic and molecular scale; it is aimed at engineering working systems at this microscopic level

natural gas a fossil fuel formed underground over geological periods of time by conditions of high pressure and temperature acting on the remains of dead sea creatures; natural gas is more than 90% methane

neutralisation a chemical reaction between an acid and a base to produce a salt and water only; summarised by the ionic equation
$$\text{H}^+(\text{aq}) + \text{OH}^-(\text{aq}) \rightarrow \text{H}_2\text{O}(\text{l})$$

neutron an uncharged subatomic particle present in the nuclei of atoms – a neutron has a mass of 1 relative to a proton

nitrogen cycle the system by which nitrogen and its compounds, both in the air and in the soil, are interchanged

nitrogen fixation the direct use of atmospheric nitrogen in the formation of important

compounds of nitrogen; most plants cannot fix nitrogen directly, but bacteria present in the root nodules of certain plants are able to take nitrogen from the atmosphere to form essential protein molecules

noble gases elements in Group VIII / 0 – a group of stable, very unreactive gases

non-electrolytes liquids or solutions that do not take part in electrolysis: they do not contain ions

non-metals a class of chemical elements that are typically poor conductors of heat and electricity

non-renewable (finite) resources sources of energy, such as fossil fuels, and other resources formed in the Earth over millions of years, which we are now using up at a rapid rate and cannot replace

nucleon number (or mass number) (A) the total number of protons and neutrons in the nucleus of an atom

nucleus (of an atom) the central region of an atom that is made up of the protons and neutrons of the atom; the electrons orbit around the nucleus in different 'shells' or 'energy levels'

oil refinery the industrial plant where the processes of converting petroleum (crude oil) into useful fractions and products are carried out

ore a naturally occurring mineral from which a metal can be extracted

organic chemistry the branch of chemistry concerned with compounds of carbon found originally in living organisms

oxidation there are three definitions of oxidation:
(i) a reaction in which oxygen is added to an element or compound; (ii) a reaction involving the loss of electrons from an atom, molecule or ion;
(iii) a reaction in which the oxidation state of an element is increased

oxidation state a number given to show whether an element has been oxidised or reduced; the oxidation state of an ion is simply the charge on the ion

oxidising agent a substance which oxidises another substance during a redox reaction

percentage purity a measure of the purity of the product from a reaction carried out experimentally:

$$\text{percentage purity} = \frac{\text{mass of pure product}}{\text{mass of impure product}} \times 100$$

percentage yield a measure of the actual yield of a reaction when carried out experimentally compared to the theoretical yield calculated from the equation:

$$\text{percentage yield} = \frac{\text{actual yield}}{\text{predicted yield}} \times 100$$

period a horizontal row of the Periodic Table

Periodic Table a table of elements arranged in order of increasing proton number (atomic number) to show the similarities of the chemical elements with related electron configurations

petroleum (or crude oil) a fossil fuel formed underground over geological periods of time by conditions of high pressure and temperature acting on the remains of dead sea creatures

pH scale a scale running from below 0 to 14, used for expressing the acidity or alkalinity of a solution; a neutral solution has a pH of 7

photochemical reaction a chemical reaction that occurs when light, usually of a particular wavelength, falls on the reactants

photochemical smog a form of local atmospheric pollution found in large cities in which several gases react with each other to produce harmful products

photodegradable plastics plastics designed to degrade under the influence of sunlight

photosynthesis the chemical process by which plants synthesise glucose from atmospheric carbon dioxide and water: the energy required for the process is captured from sunlight by chlorophyll molecules in the green leaves of the plants

physical change a change in the physical state of a substance or the physical nature of a situation that does not involve a change in the chemical substance(s) present

pollution the harmful effects on the air, water and soil of human activity and waste

polyamide a polymer where the monomer units are joined together by amide (peptide) links; for example, nylon and proteins

polyester a polymer where the monomer units are joined together by ester links; for example, Terylene

polymer a substance consisting of very large molecules made by polymerising a large number of repeating units or **monomers**

polymerisation the chemical reaction in which molecules (monomers) join together to form a long-chain polymer

potentially renewable resources resources that can be renewed, but will run out if we use them more quickly than they can be renewed

precipitation the sudden formation of a solid when either two solutions are mixed or a gas is bubbled into a solution

precipitation reactions reactions in which an insoluble salt is prepared from solutions of two suitable soluble salts

products (in a chemical reaction) the substance(s) produced by a chemical reaction

proteins polymers of amino acids formed by a condensation reaction; they have a wide variety of biological functions

proton a subatomic particle with a relative mass of 1 and a charge +1 found in the nucleus of all atoms

proton number (or atomic number) (Z) the number of protons in the nucleus of an atom (*see also* **atomic number**)

pure substance a single chemical element or compound – it melts and boils at definite temperatures

radioactivity the spontaneous decay of unstable radioisotopes

radioisotopes (or radioactive isotopes) isotopes that give out radioactive emissions (α -, β - or γ -rays) because they have unstable nuclei

rancid a term used to describe oxidised organic material (food) – usually involving a bad smell

reactants (in a chemical reaction) the chemical substances that react together in a chemical reaction

reaction rate a measure of how fast a reaction takes place

reactivity series of metals an order of reactivity, giving the most reactive metal first, based on results from a range of experiments involving metals reacting with oxygen, water, dilute hydrochloric acid and metal salt solutions

redox reaction a reaction involving both reduction and oxidation

reducing agent a substance which reduces another substance during a redox reaction

reduction there are three definitions of reduction:

- (i) a reaction in which oxygen is removed from a compound; (ii) a reaction involving the gain of electrons by an atom, molecule or ion; (iii) a reaction in which the oxidation state of an element is decreased

relative atomic mass (A_r) the average mass of naturally occurring atoms of an element on a scale

where the carbon-12 atom has a mass of exactly 12 units

relative formula mass (M_r) the sum of all the relative atomic masses of the atoms present in a 'formula unit' of a substance (*see also* **relative molecular mass**)

relative molecular mass (M_r) the sum of all the relative atomic masses of the atoms present in a molecule (*see also* **relative formula mass**)

renewable resources sources of energy and other resources which cannot run out or which can be made at a rate faster than our current rate of use

residue the solid left behind in the filter paper after filtration has taken place

resources materials we get from the environment to meet our needs (*see also* **renewable resources** and **non-renewable resources**)

respiration the chemical reaction (a combustion reaction) by which biological cells release the energy stored in glucose for use by the cell or the body; the reaction is exothermic and produces carbon dioxide and water as the chemical by-products

reversible reaction a chemical reaction that can go either forwards or backwards, depending on the conditions

R_f value (retention factor) in chromatography, the ratio of the distance travelled by the solute to the distance travelled by the solvent front

risk assessment an evaluation of the methods and chemical substances used in a particular experiment to see what safety issues may be involved

rock cycle the natural cycle by which rocks are pushed upwards, then eroded, transported, deposited, and possibly changed into another type of rock by conditions of temperature and pressure – these rocks may then be uplifted to enter a new cycle

rust a loose, orange-brown, flaky layer of hydrated iron(III) oxide, $\text{Fe}_2\text{O}_3 \cdot x\text{H}_2\text{O}$, found on the surface of iron or steel

salts ionic compounds made by the neutralisation of an acid with a base (or alkali); for example, copper(II) sulfate and potassium nitrate

saturated solution a solution that contains as much dissolved solute as possible at a particular temperature

sewage water released after its use in the home or from factories; contains waste materials that must

- be removed before the water can be used again domestically or industrially
- simple molecular substances** substances made up of individual molecules held together by covalent bonds: there are only weak forces between the molecules
- solubility** a measure of how much of a solute dissolves in a solvent at a particular temperature
- solubility curve** a graph showing how the solubility of a substance in a solvent changes with temperature
- soluble** term that describes a solute that dissolves in a particular solvent
- solute** the solid substance that has dissolved in a liquid (the solvent) to form a solution
- solution** formed when a substance (solute) dissolves into another substance (solvent)
- solvent** the liquid that dissolves the solid solute to form a solution; water is the most common solvent but liquids in organic chemistry that can act as solvents are called **organic solvents**
- solvent front** the moving boundary of the liquid solvent that moves up the paper during chromatography
- spectator ions** ions that are present in a chemical reaction but take no part in it
- speed of reaction** *see* **reaction rate**
- spontaneous (reaction)** a reaction that takes place immediately simply by mixing the reactants
- standard atom** the atom against which the relative atomic masses of all other atoms are measured using the mass spectrometer; one atom of the carbon-12 isotope is given a mass of exactly 12
- standard solution** a solution whose concentration is known precisely – this solution is then used to find the concentration of another solution by titration
- state symbols** symbols used to show the physical state of the reactants and products in a chemical reaction: they are s (solid), l (liquid), g (gas) and aq (in solution in water)
- states of matter** solid, liquid and gas are the three states of matter in which any substance can exist, depending on the conditions of temperature and pressure
- strong acid** an acid that is completely ionised when dissolved in water – this produces the highest possible concentration of $\text{H}^+(\text{aq})$ ions in solution; for example, hydrochloric acid
- strong alkali** an alkali that is completely ionised when dissolved in water – this produces the highest possible concentration of $\text{OH}^-(\text{aq})$ ions in solution; for example, sodium hydroxide
- structural formula** the structural formula of an organic molecule shows how the atoms and bonds in a molecule are arranged in space: all the atoms and covalent bonds must be shown
- subatomic particles** very small particles – **protons**, **neutrons** and **electrons** – from which all atoms are built
- sublimation** the direct change of state from solid to gas or gas to solid: the liquid phase is bypassed
- substitution reaction** a reaction in which an atom (or atoms) of a molecule is (are) replaced by different atom(s), without changing the molecule's general structure
- suspension** a mixture containing small particles of an insoluble solid, or droplets of an insoluble liquid, spread (suspended) throughout a liquid
- symbol (chemical)** a simple letter, or group of letters, that represents an element in a chemical formula
- synthesis** (*see also* **photosynthesis**) a chemical reaction in which a compound is made from its elements
- thermal decomposition** the breakdown of a compound due to heating
- titration** a method of quantitative analysis using solutions: one solution is slowly added to a known volume of another solution using a burette until an end-point is reached
- transition elements (or transition metals)** elements from the central region of the Periodic Table – they are hard, strong, dense metals that form compounds that are often coloured
- Universal Indicator** a mixture of indicators that has different colours in solutions of different pH
- upward delivery** a method of collecting a gas that is lighter than air by passing it upwards into an inverted gas jar
- valency** the combining power of an atom or group of atoms: in ionic compounds the valency of each ion is equal to its charge; in a covalent molecule the valency of an atom is the number of bonds that atom makes
- volatile** term that describes a liquid that evaporates easily; it is a liquid with a low boiling point because there are only weak intermolecular forces between the molecules in the liquid

volatility the property of how easily a liquid evaporates

water cycle the system by which water circulates around the Earth, involving various changes of state in the process; the driving force behind the water cycle is energy from the Sun

water of crystallisation water included in the structure of certain salts as they crystallise; for example, copper(II) sulfate pentahydrate ($\text{CuSO}_4 \cdot 5\text{H}_2\text{O}$) contains five molecules of water of crystallisation per molecule of copper(II) sulfate

weak acid an acid that is only partially dissociated into ions in water – usually this produces a low concentration of $\text{H}^+(\text{aq})$ in the solution; for example, ethanoic acid

weak alkali an alkali that is only partially dissociated into ions in water – usually this produces a low concentration of $\text{OH}^-(\text{aq})$ in the solution; for example, ammonia solution

word equation a summary of a chemical reaction using the chemical names of the reactants and products

Appendix: The Periodic Table

Group																	
I	II											III	IV	V	VI	VII	VIII / 0
3 Li Lithium 7	4 Be Beryllium 9											5 B Boron 11	6 C Carbon 12	7 N Nitrogen 14	8 O Oxygen 16	9 F Fluorine 19	2 He Helium 4
11 Na Sodium 23	12 Mg Magnesium 24											13 Al Aluminium 27	14 Si Silicon 28	15 P Phosphorus 31	16 S Sulfur 32	17 Cl Chlorine 35.5	18 Ar Argon 40
19 K Potassium 39	20 Ca Calcium 40	21 Sc Scandium 45	22 Ti Titanium 48	23 V Vanadium 51	24 Cr Chromium 52	25 Mn Manganese 55	26 Fe Iron 56	27 Co Cobalt 59	28 Ni Nickel 59	29 Cu Copper 64	30 Zn Zinc 65	31 Ga Gallium 70	32 Ge Germanium 73	33 As Arsenic 75	34 Se Selenium 79	35 Br Bromine 80	36 Kr Krypton 84
37 Rb Rubidium 85	38 Sr Strontium 88	39 Y Yttrium 89	40 Zr Zirconium 91	41 Nb Niobium 93	42 Mo Molybdenum 96	43 Tc Technetium —	44 Ru Ruthenium 101	45 Rh Rhodium 103	46 Pd Palladium 106	47 Ag Silver 108	48 Cd Cadmium 112	49 In Indium 115	50 Sn Tin 119	51 Sb Antimony 122	52 Te Tellurium 128	53 I Iodine 127	54 Xe Xenon 131
55 Cs Caesium 133	56 Ba Barium 137	57 La Lanthanum 139	72 Hf Hafnium 179	73 Ta Tantalum 181	74 W Tungsten 184	75 Re Rhenium 186	76 Os Osmium 190	77 Ir Iridium 192	78 Pt Platinum 195	79 Au Gold 197	80 Hg Mercury 201	81 Tl Thallium 204	82 Pb Lead 207	83 Bi Bismuth 209	84 Po Polonium 210	85 At Astatine 210	86 Rn Radon 222
87 Fr Francium 223	88 Ra Radium 226	89 Ac Actinium 227	104 Rf Rutherfordium 261	105 Db Dubnium 262	106 Sg Seaborgium 263	107 Bh Bohrium 264	108 Hs Hassium 265	109 Mt Meitnerium 268	110 Ds Darmstadtium 281	111 Rg Roentgenium 273	112 Cn Copernicium —	113 Uut Ununtrium —	114 Fl Flerovium —	115 Uup Ununpentium —	116 Lv Livermorium —	117 Uus Ununseptium —	118 Uuo Ununoctium —
1 H Hydrogen 1 3 X a b a = atomic number X = atomic symbol b = relative atomic mass Key 4 Be Beryllium 9 12 Mg Magnesium 24																	
58 Ce Cerium 140 59 Pr Praseodymium 141 60 Nd Neodymium 144 61 Pm Promethium 145 62 Sm Samarium 150 63 Eu Europium 152 64 Gd Gadolinium 157 65 Tb Terbium 159 66 Dy Dysprosium 163 67 Ho Holmium 165 68 Er Erbium 167 69 Tm Thulium 169 70 Yb Ytterbium 173 71 Lu Lutetium 175 90 Th Thorium 232 91 Pa Protactinium 231 92 U Uranium 238 93 Np Neptunium 237 94 Pu Plutonium 244 95 Am Americium 243 96 Cm Curium 247 97 Bk Berkelium 247 98 Cf Californium 251 99 Es Einsteinium 252 100 Fm Fermium 257 101 Md Mendelevium 258 102 No Nobelium 259 103 Lr Lawrencium 262																	

*58–71 Lanthanoid series

†90–103 Actinoid series

Index

- accuracy, 307
Acetobacter, 268
acid hydrolysis, 291
acid rain, 7, 230, 242, 246
acid reactions, 127–9, 131–3
acid soils, 243
acid–base titrations, 168–9
acidic gases, 246
acidic oxides, 124, 125–6
acids, 120–3
acids, basicity of, 146
acids, chemical analysis using, 134–5
acids, neutralisation of, 127–8
acids, reactions with bases and alkalis, 132
acids, reactions with carbonates, 132–3
acids, reactions with metals, 132
activation energy, 181, 191–2
addition polymerisation, 284–6
addition polymers, 284, 285, 286, 289
addition reactions, 258, 284
adsorption, 190
air pollution, 7–9, 246
alanine, 290
alcohol and health, 268
alcoholic drinks, 266
alcohols, 259, 260, 265–6
alcohols, reactions of 267–8
alkali metal compounds, 208–9
alkali metals 60, 63–4, 93, 207–10
alkali metals, flame tests, 208
alkali metals, reaction with water, 207–8
alkaline earth metals, 209–10
alkalis, 120, 129–30, 131
alkalis, chemical analysis using, 134–5
alkanes, 254–6, 259, 279
alkanes, burning, 256
alkanes, chemical reactions, 262–3
alkanes, combustion, 262
alkanes, structures, 256
alkanes, substitution reactions with halogens, 263
alkanols, 265
Alkathene (polythene), 284
alkenes, 257–8, 259, 279
alkenes, bromination, 263
alkenes, chemical reactions, 263–4
alkenes, hydration, 264
alkenes, hydrogenation, 264
alkynes, 261
alloy steels, 229
alloys, 57, 80–1
alternative energy sources, 283
alternative fuels, 282–3
alternative transport fuels, 282–3
aluminium, 210–12, 217, 219, 247
aluminium, anodising, 235
aluminium, extraction, 234–5
aluminium hydroxide, 211–12
aluminium ions, analytical test for, 211–12
aluminium oxide, 210
aluminium electrolysis plants, 234
amide link, 287
amino acids, 253, 284, 291
ammonia, 196–8, 235–8
ammonium chloride, 29, 39
ammonium dichromate, 91
ammonium nitrate, 153, 237–8
ammonium salts using alkali, 135
amphoteric hydroxides, 298
amphoteric materials, 212
amphoteric oxides, 126–7
anaerobic decay, 18
anaerobic respiration, 266
anaesthetic material, 263
animal fats, 264
anions, 106
anions, testing for, 297
anodes, 105, 106, 107, 108, 109, 110
anodising, 230
ant sting, 119
antacids, 127–8
argon, 5, 6
artificial fertilisers, 238
atmosphere, 2, 5–10
atmospheric pressure, 24
‘atomic logo’ (IBM), 36
atomic number, 42
atomic structure, 41
atomic theory, 35–6
atoms, 40
aurora borealis, 47
autogas, 282
Avogadro constant, 159
Avogadro’s law, 166
balanced equations, writing 93–4
balanced symbol equations, 92
barium, 209, 210
bases, 129–30, 131
basic oxides, 125–6
basic oxygen process, 228
‘basicity’ of acids, 146
bauxite, 210, 217, 234
beryllium, 210
biochemical oxidation, 268
biodegradable plastics, 289
biodiesel, 283
biofuels, 267, 282–3
biogas, 283
biological catalysts, 189–90
biological polymers, 290–2
biomass, 283
biomass energy, 193
bitumen residue, 277
blast furnace, 99, 217, 227–8, 232
bleaching powder, 243
Bohr’s theory of arrangement of electrons, 47
boiling, 23–4
boiling point, 24
bond energy, 176, 179
brine, 136, 241
bromination, 263
bromine, 38, 60, 242, 259
Brownian motion 40
Bunsen valve, 301
burning, 97
burning alkanes, 256
butane portable camping stove, 257
butane, 255, 256, 260
butanoic acid, 270
butene, 257
butyl butanoate, 271
calcium chloride, 301
calcium oxide (lime), 301
calcium, 209, 210, 219
calorimeters, 180

- car exhaust, 8
- carbohydrates, 193, 291–2
- carbon cycle, 2–3
- carbon, forms of, 252, 275
- carbon, properties, 253–4
- carbon dioxide, 2–3, 4, 5, 9, 10, 96
- carbon dioxide limewater test, 299
- carbon monoxide, 8, 227, 262
- carbon nanotubes, 275
- carbon reduction process, extraction of
 - metals by, 227–33
- carbon steels, 229
- carbon-12, 41, 45, 47, 152
- carbon-60, 252
- carbonates, reactions of acids with, 132–3
- carboxylic acids, 259, 260, 269
- cassiterite, 217
- cast iron, 5, 212, 228, 229
- catalysts, 8, 187–92
- catalytic converters, 8, 188–9
- catalytic cracking, 278–80
- catalytic properties of transition
 - elements, 213–14
- cathodes, 105, 106, 107, 108, 109
- cations, 106
- cations, testing for, 297–9
- cellulose, 291
- cement, 242
- centrifugation, 28
- ceramic materials, 103
- chemical ‘accountancy’, 151
- chemical bonding, 65–74
- chemical bonds, 175–6
- chemical changes, 90
- chemical ‘footbridge’, 163
- chemical formulae, 75–7, 155–6
- chemical industry, economics 245–8
- chemical plants, 245–6
- chemical products, purity, 163–4
- chemical reactions and equations,
 - 90–1, 91–4
- chemical reactions, between methane
 - and oxygen, 175–6
- chemical reactions, between nitrogen
 - and oxygen, 176–7
- chemical reactions, energy changes in,
 - 174, 175–81
- chemical reactions, types of, 94–9
- chemical safety symbols, 307, 308
- chemical symbols, 36
- chemiluminescence, 90
- chlor-alkali industry, 241–2, 245–6
- chlorine water, 61
- chlorine, 61–2, 241
- chlorine, uses of, 241–2
- chloroform, 263
- chloromethane, 263
- chlorophyll, 95, 193
- chromatograms, 31, 32, 305
- chromatography, 31–2, 305
- chromium, 230
- cirrhosis, 268
- citrus fruits, 120
- closed system, 194
- coal, 15
- coal dust, 182
- collision theory, 190–1
- coloured compounds, 213
- combustion reactions, 3, 97–9, 262
- compound formation and chemical
 - formulae, 155–6
- compounds, 34, 40, 93
- compressed natural gas (CNG), 282
- concentrated solution, 33
- concentration of solutions, 167
- concrete, 243
- condensation polymerisation, 287–92
- condensation polymers, 287, 289
- condensation, 23–4
- conservation of mass, law of, 92
- Contact process plants, 238, 240
- Contact process, 190, 198–9
- controlling variables, 306–7
- copolymers, 284
- copper, 214–15, 216, 217, 219
- copper carbonate, 34
- copper, extraction, 232–3
- copper pyrites, 217, 232
- copper refining, 113–14, 235
- core, Earth’s, 14
- corn oil, 264
- corrosion, 99, 229
- corrosion resistance, 64, 210, 212
- corrosive acids, 120
- covalent bonding, 66, 67
- covalent compounds, 68–71, 73–4
- covalent compounds, formulae of, 76–7
- cracking, 279–80
- cracking plant, in oil refinery, 279
- crude oil (petroleum), 15, 282
- crust, Earth’s, 1, 2, 3, 5, 14–18
- cryogenics, 5
- cryolite, 234
- crystal lattices, 89, 144
- crystallisation, 29
- data, interpretation of, 309
- decanting, 28
- decomposition, 34–5, 95
- deep-sea divers, 182
- dehydrating agents, 239
- dehydration, 239–40, 268
- density of metals, 207
- dependent variable, 307
- desalination, 11
- diamond, 83, 252
- diaphragm cells, 241
- diatomic molecules, 66
- dibasic (diprotic) acids, 146, 147
- dibromoethane, 259
- dichloromethane, 263
- diesel engine road vehicle (DERV), 282
- diesel fuel, 282
- diesel oil, 277
- diffusion in fluids, 38–40
- diffusion of gases, 38–40
- digestion, 97
- dilute solution, 33
- dipeptides, 290
- diprotic acids, 146
- displacement reactions, 61, 97, 220
- distillates, 30
- distillation, 30
- DNA (deoxyribonucleic acid), 253
- domestic water supply, 13
- downward delivery method, for
 - collection of gases, 300, 301
- drugs (pharmaceuticals), 33
- dry cleaning, 263
- drying agents, 301
- ductile metals, 57, 79
- ductility, 58, 79
- dynamic equilibrium, 196, 269
- Earth, 1–18
- Earth, core, 14
- Earth, crust, 1, 2, 3, 5, 14–18
- Earth’s magnetic field, 214
- edible oils, 264
- effluent, 129
- electrical conductivity of liquids, 104–6
- electrical conductivity of metals, 58
- electrical conductivity of solids, 103
- electrical conductors, 103
- electrical melting-point apparatus, 25
- electricity supply, 103
- electrochemical cells, 221
- electrodes, 105
- electrolysis, 102–12, 210
- electrolysis of acid solutions, 110–11
- electrolysis of ionic solutions, 108–9
- electrolysis of molten compounds, 106–8

- electrolysis of sodium chloride
 solution, 109–10
 electrolysis, oxidation and reduction
 during, 113
 electrolytes, 104
 electrolytic cells, 106, 234, 241
 electrolytic conductivity, 105
 electrolytic protection, 231
 electron arrangement and Periodic
 Table, 59–60
 electron arrangements in atoms, 47–8
 electron pump, 103
 electron structure, 48
 electronic carbon monoxide
 detectors, 262
 electrons, 41
 electroplated nickel silver (EPNS), 112
 electroplating, 111–12, 231, 235
 electrostatic forces, 68, 71
 elements, 34, 93
 elements, formulae of, 75
 empirical formula, 160–1, 255
 emulsion, 194
 endothermic reactions, 90, 95, 175
 end-point, 140
 energy changes in chemical reactions,
 174, 175–81
 energy level diagram, 175
 energy levels, 47
 energy sources, 15
 environmental costs of chemical
 industry, 246
 enzymes, 189–90
 error, 307–8
 essential amino acids, 292
 ester link, 288
 esterification, 268, 270–1
 esters, 268, 269–72, 304, 305
 ethane, 255, 259
 ethanoic acid, 269–70
 ethanoic acid, testing for, 304
 ethanol, 265, 280
 ethanol, as fuel, 267–8
 ethanol, dehydration, 268
 ethanol, esterification, 268
 ethanol, oxidation, 268
 ethanol, production of, 266–7
 ethanol, reactions, 267–8
 ethanol, structure, 266
 ethanol, testing for, 304
 ethene, 257
 ethene, hydration, 265
 ethyl 2-methylbutanoate, 271
 evaporation, 23–4
 exothermic reactions, 14, 90, 94
 experimental apparatus, 307, 308
 experimental design and
 investigation, 305–9
 explosive combustion, 182
 extraction of metals, 216–17
 fats, 253, 283, 292
 fatty acids, 264
 feedstock, 276
 fermentation, 265–6
 fertiliser industry, 245–6
 fertilisers, importance of, 238
 fertilisers, production of, 237–8
 filtrates, 28
 filtration, 28
 finite resources, 276
 flame tests, colours, 298
 flame tests, for alkali metals, 207–8
 flue-gas desulfuriser, 129
 fluids, 22
 fluorine, 242
 foods, 292
 'fool's gold', 216
 forest fire, 175
 formula, 153
 formulae, writing, 77
 forward reaction, 196
 fossil fuels, 3, 5, 10, 15–16, 174, 176,
 193, 276, 281
 fracking, 276
 fraction, 31
 fractional distillation, 7, 30, 31, 276–8
 fractional distillation of petroleum in
 refinery, 277
 fractionating column, 30, 276–7
 Frasch process, 238
 free electrons, 103
 freezing, 22
 freezing point, 22
 fuel cells, 16
 fuel oil, 277
 fuels, 97
 fullerenes, 252
 functional groups, 258
 galena, 217
 galvanising process, 231, 232
 gas oil, 277
 gas reservoirs, 276
 gases, calculations involving, 166–7
 gases, collection methods, 300–1
 gases, diffusion of, 38–40
 gases, drying methods, 301
 gases, in air, 5–6
 gases, testing for, 299, 300
 gasfields, 276
 gasohol, 267–8
 gasoline, 267, 277
 gasoline, blending of, 280–1
 gasoline, from methanol, 282
 giant ionic lattice, 78
 giant ionic structure, 72
 giant metallic lattice, 78
 giant molecular crystals
 (macromolecules), 83–4
 giant molecular lattice, 68, 78
 glass making, 243
 glass, 247
 global warming, 9–10
 glow-in-the-dark bracelets, 90
 glycerol, 292
 glycine, 290
 gold, 216, 219
 grain boundaries, 79, 80
 grains, 79
 graphene, 275
 graphite, 83, 113, 252
 graphs, plotting, 308–9
 greenhouse effect, 9–10, 283
 Group II metals, 209–10
 Groups in Periodic Table, 56, 58, 60–3
 Haber process, 4, 5, 190, 195, 196–8,
 214, 226, 236, 237
 haemoglobin, 8, 194
 half-life, 45
 halides, 61
 Hall–Héroult electrolytic method,
 234–5
 halogens, 60–2
 halothane, 263
 heat of combustion, 179
 heat of neutralisation, 180
 heat of reaction, 177–8
 heating and cooling curves, 25–6
 hematite, 217
 hexane, 255, 256
 high-carbon steel, 229
 high-speed diesel engines, 282
 Hofmann voltmeters, 110, 111
 homologous series of organic
 compounds, 256
 homopolymers, 284
 hybrid cars, 283
 hydrated salts, 137–8, 161, 194, 195
 hydration, 264
 hydrocarbons, 175, 252, 254–8

- hydrocarbons, structure and isomerism, 259–61
- hydrogen, 16, 65, 153
- hydrogen as fuel, 16–17, 89
- hydrogen fuel cells, 17–18
- hydrogen ions, 124
- hydrogen peroxide, 187–8
- hydrogenation, 264
- hydrolysis, 288
- hydroxide precipitates, 135
- hypothesis, 306

- ignition temperature, 280
- immiscible liquids, 28
- impurities, effect of, 25–6
- incineration, 290
- indicators, 120–1
- industrial electrolysis of molten compounds, 107–8
- industrial electroplating of metal objects, 111
- industrial water supply, 13
- inorganic analysis, 297–303
- insoluble salts, preparation of, 141–3
- insoluble substances, 33
- insulators, 103
- intermolecular forces, 255
- intermolecular space (IMS), 37
- internal combustion engine
 - cylinder, 280
- iodine, 24, 242
- ion-exchange membranes, 241
- ionic bonding, 68
- ionic compounds, 71–2, 73–4
- ionic compounds, formulae of, 75–6
- ionic conductivity, 104
- ionic crystals, 82
- ionic equations, 100–1, 142
- iron, 212, 214, 217, 219
- iron, production in blast furnace, 227–8
- iron, rusting, 230–2
- isomerism, 260
- isomers, 261
- isotopes, 43–5

- kerosene, 277
- kinetic model of matter, 36–8, 40
- knocking, 280

- laboratory fermentation vessel, 266
- land pollution, 18, 246
- landfill, 247
- law of conservation of mass, 162
- Le Chatelier's principle, 196, 197

- lead in petrol (gasoline), 280–1
- lead, 8, 217, 219
- light bulbs, 6
- lime (calcium oxide), 14, 96, 128, 242
- lime (calcium oxide), manufacture of, 243
- lime kiln, 243, 244
- limescale, 128
- limestone cycle, 14–15
- limestone, 3, 14, 96, 242–4
- limewater test for carbon dioxide, 96, 299
- limiting reactants, 163
- limonite, 217
- liquid electrolytes, 106
- liquid petroleum gas (LPG), 256, 282
- lithium, 208
- litmus paper, 121
- litmus, 120–1
- locating agents, 32
- lubricating oil, 277
- Lunar Rover 'moon-buggy', 210
- Lusitania*, 181–2

- macromolecules, 83–4, 284
- magnesium, 35, 209, 210, 219
- magnetic properties of transition elements, 214
- magnetite, 217
- main-group elements, 58
- malachite, 214
- malleability, 58, 79
- malleable metals, 57, 79
- manganese steel, 229
- margarine, 264
- Mars rover (*Curiosity*), 296
- marsh gas, 283
- mass concentration, 167
- mass number, 42
- mass spectrometer, 41, 152
- matter, states of, 22–7
- medium steel, 229
- melting point, 22
- membrane cells, 110, 241
- mercury cathode cells, 241
- metal compounds, thermal decomposition of, 220
- metal crystals, 79–80
- metal lattices, 78
- metal oxides, 125–7
- metallic bonding, 66, 67
- metallic conductivity, 104
- metallic crystals, 80, 82
- metalloids, 57

- metals, 56–8
- metals, density, 207
- metals, displacement reactions, 218–19
- metals, extraction, 216–17
- metals, extraction, by carbon reduction process, 227–33
- metals, extraction, by electrolysis, 234–5
- metals, reaction with air, water and dilute acids, 217
- metals, reactions of acids with, 132
- metals, reactivity, 215–20
- metals, structures 78–84
- methane, 10, 18, 255, 256
- methane gas, 283
- methanoic acid, 119, 269, 270
- methanol, 265, 282
- 1-methylbutyl ethanoate, 271
- 3-methylbutyl ethanoate, 271
- 2-methylpropane, 260
- methylpropyl methanoate, 271
- mild steel, 229
- mineral acids, 120
- miscible solutions, 27
- mixtures, 26–7
- molar concentration, 167
- molar mass, 159
- molar volume, 166
- molecular crystals, 84
- molecular formula, 160–2, 255, 257–8, 260, 265, 269, 270
- molecules, 40
- moles, 158–61
- moles, and chemical equations, 162–4
- moles, and solution chemistry, 167–70
- monobasic (monoprotic) acids, 146, 147
- monomers, 284
- mono-unsaturated fatty acids, 264

- naming chemical compounds, 77
- nanotechnology, 252
- naphtha, 277
- naphthalene, 25–6
- natural gas, 15, 97, 256
- 'neon' lights, 63
- neutral oxide, 126–7
- neutralisation point, 140
- neutralisation reactions, 96, 131, 145–6
- neutrons, 41
- Nitram (ammonium nitrate), 237–8
- nitric acid, 237
- Nitro-chalk, 237
- nitrogen, 5, 235–6
- nitrogen cycle, 3–4
- nitrogen dioxide, 8

- nitrogen fixation, 235
- nitrogenous fertilisers, 237
- noble gases, 5, 6, 58, 59, 62–3
- non-electrolytes, 104
- non-metal oxides, 125–7
- non-metals, 56–8
- non-renewable fuels, 276
- non-renewable resources, 5
- NPK fertilisers, 151, 237–8
- nuclear energy, 16, 283
- nucleon number, 42–3
- nucleus, 41
- nylon, 284, 287–8

- observations, interpretation of, 309
- octane, 255, 279
- octyl ethanoate, 271
- offshore gas fields, 245
- oil refinery, 276
- oil reservoirs, 276
- oil-rig, 276
- oilfields, 276
- oiling and greasing, 231
- oleic acid, 264
- oleum, 239
- olive oil, 264
- ores, 14
- organic acids, 120, 269–71
- organic analysis, 304–5
- organic chemistry, 252–72
- organic compounds, naming of, 259–60
- organic solvents, 263
- overhead power lines, 103, 104
- oxidation reactions, 97–9, 113, 268
- oxidation state, 101
- oxidising agents, 61, 99, 101, 239
- oxygen, 3, 4
- oxygenated fuels, 268

- painting, 231
- paper, 247
- paraffin, 277
- pentane, 255, 256
- pentene, 257
- pentyl butanoate, 271
- peptides, 290
- percentage by mass of a particular element, 153
- percentage by mass of water of crystallisation, 154
- percentage yield, 163–4
- Periodic Table, 47, 55, 56–60, 63–5
- Periods in Periodic Table, 56, 58

- petroleum (crude oil), 15, 276–81
- petroleum, formation, 276
- pH meters, 122
- pH scale, 121, 122
- pH testing, 302
- phosphorus oxide, 160
- photochemical reactions, 95, 193–4, 263
- photochemical smog, 8
- photodegradable, 290
- photographic films, 193–4
- photography, 193–4
- photosynthesis, 1, 2, 95, 193–4, 238
- photosynthetic cycle, 193
- physical changes, 35, 90
- pig iron, 228
- planning investigations, 306–7
- plant growth, 128–9
- plastic coatings, 231
- plastics, 247, 284
- plastics, recycling, 5, 247, 289–90
- plastics, re-use, 289–90
- plastics, waste disposal, 289–90
- poisonous gases, 246
- pollution, 7–9
- poly(chloroethene) (PVC), 285
- polyamides, 287
- polyatomic (compound) ions, 72–3
- polyesters, 288
- polyethylene terephthalate (PET), 289
- polymers, 284
- polypeptides, 290
- polypropylene (PP), 279, 285, 286
- polysaccharides, 291
- polystyrene (PS), 180
- polytetrafluoroethylene (PTFE), 285–6
- polythene (PE), 284
- polyunsaturated compounds, 264
- polyvinyl chloride (PVC), 231, 285
- potassium, 208
- potassium manganate, 258
- potentially renewable resources, 5
- power cells, oxidation and reduction in, 221
- practical examination, 310–15
- practical examination, alternatives to, 316
- precipitation, 141–3
- precipitation reactions, 96, 141–3
- propane, 255
- propanoic acid, 270
- propene, 257, 279
- proteins, 290
- proteins, analysis, 290–1
- proton number, 42–3

- protons, 41, 146
- pure substances, 24–6
- pyrolysis, 290

- quarrying, 246
- quicklime, 14, 15

- radioactive dating, 45
- radioactivity, 44, 45–6
- radioisotopes, 44, 45–6
- rancidity, 99
- random error, 309
- rates of reaction, 181–7
- re-forming, 280
- reactants, concentration of, 183–4
- reactants, solid, surface area of, 182–3
- reacting amounts, calculation of, 156–8
- reactive metals, 219
- reactivity series of metals, 216, 219
- recycling, 246–7
- recycling, of metals, 5
- recycling, of plastics, 5, 247, 288–9
- redox reactions, 99, 101–2, 193, 211, 219–20
- reducing agents, 99, 102, 219
- reduction reaction, 97–9, 113
- refinery gas, 277
- refining (purification) of copper by electrolysis, 113–14
- relative atomic mass, 41, 45, 152
- relative formula mass, 152–3
- renewable energy resources, 5, 16
- residue, 28
- respiration, 3, 98, 193
- reverse reaction, 196
- reversible dissociation, 145
- reversible reactions and chemical equilibria, 194–9
- R_f value, 32
- rice fields, 10
- risk assessment, 307
- rivers, 11
- rock cycle, 4, 14
- rock salt, 136, 217, 245
- rotary kiln, 242
- rust, 99, 229, 230–2
- rust prevention, 230–1

- sacrificial protection, 231
- 'safety' flame, of Bunsen burner, 262
- safety, importance in experiments, 307
- salts, 96, 131, 136–8, 208–9
- salts, reversible hydration of, 195–6
- salts, solubility, 137

- sand, 227
- saturated hydrocarbons, 254, 259
- saturated solution, 33
- Saturn, 21
- sawdust, 283
- scientific method, 305–6
- scrubbing, 246
- sea salt, 136
- seas, 11
- seawater, 230
- semi-metals, 57
- separating funnels, 29
- separation methods, for immiscible liquids, 28
- separation methods, for insoluble solids in liquids, 27–8
- separation methods, for mixtures of solids, 28–9
- separation methods, for solutions, 29–32
- sewage treatment, 13
- silver, 216, 219
- simple molecular substances, 78
- sintering, 227
- slaked lime (hydrated lime), 14, 15, 243
- snowflake crystal, 78, 79
- soaps, 130, 131, 243
- sodium carbonate, 243
- sodium chloride, 136–7, 153
- sodium hydroxide, 211–12
- sodium, 208, 217, 219
- soil pH, 128–9
- solar energy, 283
- solid catalysts, 190
- solid fertilisers, 237
- solubility curves, 170
- solubility of gases in liquids, 33–4
- solubility of solute, 33
- soluble salts, preparation of, 138–41
- soluble substances, 33
- solute, 27
- solutions, 26, 27
- solvent front, 32
- solvents, 27
- sonorous metals, 57
- spectator ions, 100, 142
- 'spoil heaps', 246
- spontaneous synthesis, 94
- stained glass windows, 213
- stainless steel, 229, 230
- standard atom, 152
- standard solution, 168
- starch, 291
- state symbols, 100–1
- steel, 212, 247
- steel-making, 228–9
- stoichiometry, 163
- strong acids, 143–4
- strong alkalis, 144–5
- strong electrolytes, 144
- strontium, 209
- structural formulae of organic compounds, 255
- subatomic particles, 41
- sublimation, 22–3, 29
- substances, purity and identity of, 32–3
- substitution reaction, 263
- sugar, 240–1, 253, 265, 291
- sulfur, 238–41
- sulfur, compounds, 239–41
- sulfur dioxide, 153
- sulfuric acid, 198–9, 238–41, 301
- sunflower oil, 264, 282
- sunflowers, 282
- surface catalysts, 190–2
- suspension, 27
- synthesis, 35, 94–6
- synthetic fibre, 287
- synthetic polymers, 284
- systematic error, 309
- Teflon, 285
- temperature, 185–7
- termite mounds, 10
- Terylene, 288, 289
- tetrachloromethane, 263
- thermal decomposition, 96, 244
- thermal decomposition, of metal compounds, 220
- thermit reaction, 211, 220
- tin, 217
- titration, 140–1, 168
- transition element ions, colours of, 213
- transition elements, 58, 64–5, 212–15, 227
- transition elements, reactions, 214–15
- transition metals *see* transition elements
- tribasic (triprotic) acids, 146, 147
- 1,1,1-trichloroethane, 263
- trichloromethane, 263
- tungsten steel, 229
- uncertainty, 307
- Universal Indicator, 61, 121–2
- unsaturated hydrocarbons, 257–8
- unsaturated hydrocarbons, testing for, 258, 304
- upward delivery method, for collection of gases, 300, 301
- valency, 61
- van der Waals' forces, 255
- variable valency, of transition-element atoms, 213
- variables, controlling, 306–7
- vegetable oils, 264, 282–3
- Viking sword, 215, 216
- vinegar, 122, 128, 134, 143, 268, 270
- vitamin C (ascorbic acid), 128
- volatile materials, 24
- volatility, 24
- waste water treatment, 129
- water, 124, 153
- water cycle, 2
- water of crystallisation, 137–8, 154
- water, pollution, 13, 246
- water, testing for presence of, 302–3
- water, treatment, 11
- weak acids, 143–4, 199
- weak alkalis, 144–5, 199
- weak electrolytes, 145
- 'weighing' atoms, 152
- wind farms, 283
- word equations, 91–2
- yeasts, 265–6
- zeolite, 189, 279, 282
- zinc, 215, 217, 219
- zinc carbonate, 119, 215
- zinc extraction, 232
- zinc hydroxide, 215
- zinc nitrate, 139
- zinc-blende, 217, 232
- ZSM-5 catalyst, 282

Acknowledgements

All end-of-chapter questions from past examination papers are reproduced by permission of Cambridge International Examinations.

Cover image / David Taylor / SPL; 1.1, ESA / Kevin A Horgan / SPL; 1.7, @ Leslie Garland Picture Library / Alamy; 1.9, Docstock / www.photolibary.com; 1.13a, Andy Clarke / SPL; 1.13b, Peter Menzel / SPL; 1.22b, Martin Bond / SPL; 2.1, NASA; 2.4, Charles D. Winters / SPL; 2.5, Andrew Lambert / SPL; 2.6, R. Harwood; 2.12b, Jerry Mason / SPL; 2.16b, 2.17b, Andrew Lambert / SPL; 2.20, 2.21, Andrew Lambert / SPL; 2.22, IBM; 2.25, Andrew Lambert / SPL; 2.26, Andrew Lambert / SPL; 2.32, Pekka Parivianen / SPL; 3.1, Heidas; 3.4, M.C Talbot; 3.7, 3.9, Andrew Lambert; 3.10, Day Williams / SPL; 3.11 Richard Harwood 3.13, 3.14a, Martyn F. Chillmaid / SPL; 3.14b, Andrew Lambert / SPL; 3.32, Kenneth Libbrecht / SPL; 3.35, M.C. Talbot; 3.37, Lisa Moore / Alamy; 4.1, SPL; 4.3, Andrew Lambert; 4.4, Martyn F. Chillmaid / SPL; 4.5, Charles D. Winters / SPL; 4.6, Trevor Clifford Photography / SPL; 4.8, 4.10, 4.11, 4.12, 4.13, Andrew Lambert; 4.17, Cordelia Molloy / SPL; 4.23, Trevor Clifford Photography / SPL; 4.27, Sam Ogden / SPL; 4.29, Chris R. Sharp; 5.1a, Thierry Berrod, Mona Lisa Productions / SPL; 5.1b, Dr Jeremy Burgess / SPL; 5.2, David Munns / SPL; 5.3, 5.4a, Andrew Lambert / SPL; 5.4b, Trevor Clifford Photography / SPL; 5.6, European Space Agency / SPL; 5.7b, Andrew Lambert Photography / LGPL; 5.9, Gustoimages / SPL; 5.10, Andrew Lambert / SPL; 5.11, @ Jeremy Pardoe / Alamy; 5.12, Martin Bond / SPL; 5.14a, Martyn F. Chillmaid / SPL; 5.14b, Charles D. Winters / SPL; Fig. on p. 132, Arnold Fisher; 5.15, David Taylor / SPL; 5.17b, Andrew Lambert; 5.18, SPL; 5.19, 5.20, R. Harwood; 5.22, 5.23, Martyn F. Chillmaid / SPL; 5.25b SPL; 6.1, Christian Darkin / SPL; 6.13, Martyn F. Chillmaid / SPL; 6.14, Andrew Lambert; 7.1, SPL; 7.2, Scott Camazine /

K. Visscher / SPL; 7.3, Tek Image / SPL; 7.6, Charles D. Winters / SPL; 7.9, David Talbot; 7.11, Interfoto / Alamy; 7.12, Martyn F. Chillmaid / SPL; 7.13, Charles D. Winters / SPL; 7.14a, Andrew Lambert / SPL; 7.19a, Martyn F. Chillmaid / SPL; 7.23, Astrid & Hanns-Frieder Michler / SPL; 7.24, J.C. Revy, Ism / SPL; 7.29, Christian Darkin / SPL; 7.30, Professors P.M. Motta & S. Correr / SPL; 7.32, Martyn F. Chillmaid / SPL; 7.33, Andrew Lambert / SPL; 8.1, SPL; 8.2, Charles D. Winters / SPL; 8.3, Andrew Lambert; 8.4, James King-Holmes / SPL; 8.6b, photograph courtesy of NT Government; 8.7, David Talbot; 8.8, @ Art Directors & TRIP / Alamy; 8.9, J.C. Hurni, Publiphoto Diffusion / SPL; 8.10, @ Werner Forman / Corbis; 8.12, R. Harwood; 8.13, M. C. Talbot; 8.14, R. Harwood; 8.15, Charles D. Winters / SPL; 9.2, Rosenfeld Images Ltd / SPL; 9.7, National Oceanic and Atmospheric Administration; 9.12, Ben Johnson; 9.14, courtesy of Deutsches Museum von Meisterwerken der Naturwissenschaft und Technik; 9.17, Martyn F. Chillmaid / SPL; 9.18, Bernhard Edmaier; 9.20a, Martin Bond / SPL; 9.22, Andrew Lambert / SPL; 9.24, M. C. Talbot; 9.25, Dirk Wiersma / SPL; 9.27, Maximillian Stock Ltd / SPL; 9.29a, Dirk Wiersma / SPL; 9.32, Burrups International; 9.33, Bob Gibbons / SPL; 10.1a, Laguna Design / SPL; 10.1b, IBM; 10.5, R. Harwood; 10.6, Martyn F. Chillmaid / SPL; 10.9, Andrew Lambert / SPL; 10.10, R Harwood; 10.11, Martyn F. Chillmaid / SPL; 10.12, David Taylor / SPL; 10.17, David R. Frazier / SPL; 11.1a, 11.1b, SPL; 11.2, Ria Novosti / SPL; 11.4, 11.5, Paul Rapson / SPL; 11.8, Roger Harris / SPL; 11.9, @ Realimage / Alamy; 11.10, Alan Sirulnikoff / SPL; 11.11, Leonard Lesson / SPL; 11.12, Professor David Hall / SPL; 11.13a, 13b, Robert Brook / SPL; 11.14, David Talbot; 11.17b, Charles D. Winters / SPL; 11.18, 11.19, R. Harwood; 12.1, NASA; 12.2, 12.4, 12.9, 12.11, Andrew Lambert / SPL.

Terms and conditions of use for the CD-ROM

This is a legal agreement between 'You' (which means the individual customer or the Educational Institution and its authorised users) and Cambridge University Press ('the Licensor') for *Cambridge IGCSE Chemistry Coursebook CD-ROM*. By placing this CD in the CD-ROM drive of your computer, You agree to the terms of this licence.

1 Limited licence

- a You are purchasing only the right to use the CD-ROM and are acquiring no rights, express or implied, to it, other than those rights granted in this limited licence for not-for-profit educational use only.
- b The Licensor grants You the licence to use one copy of this CD-ROM.
- c You shall not: (i) copy or authorise copying of the CD-ROM, (ii) translate the CD-ROM, (iii) reverse-engineer, alter, adapt, disassemble or decompile the CD-ROM, (iv) transfer, sell, lease, lend, profit from, assign or otherwise convey all or any portion of the CD-ROM or (v) operate the CD-ROM from a mainframe system, except as provided in these terms and conditions.
- d Permission is explicitly granted for use of the CD-ROM on a data projector, interactive whiteboard or other public display in the context of classroom teaching at a purchasing institution.
- e If You are an Educational Institution, once a teacher ceases to be a member of the Educational Institution, all copies of the material on the CD-ROM stored on his/her personal computer must be destroyed and the CD-ROM returned to the Educational Institution.
- f You are permitted to print reasonable copies of the printable resources on the CD-ROM. These must be used solely for use within the context of classroom teaching at a purchasing institution.

2 Copyright

- a All original content is provided as part of the CD-ROM (including text, images and ancillary material) and is the copyright of the Licensor or has been licensed to the Licensor for use in the CD-ROM, protected by copyright and all other applicable intellectual-property laws and international treaties.
- b You may not copy the CD-ROM except for making one copy of the CD-ROM solely for backup or archival purposes. You may not alter, remove or destroy any copyright notice or other material placed on or with this CD-ROM.

3 Liability and Indemnification

- a The CD-ROM is supplied 'as is' with no express guarantee as to its suitability. To the extent permitted by applicable law, the Licensor is not liable for costs of procurement of substitute products, damages or losses of any kind whatsoever resulting from the use of this product, or errors or faults in the CD-ROM, and in every case the Licensor's liability shall be limited to the suggested list price or the amount actually paid by You for the product, whichever is lower.
- b You accept that the Licensor is not responsible for the availability of any links within or outside the CD-ROM and that the Licensor is not responsible or liable for any content available from sources outside the CD-ROM to which such links are made.
- c Where, through use of the original material, You infringe the copyright of the Licensor, You undertake to indemnify and keep indemnified the Licensor from and against any loss, cost, damage or expense (including without limitation damages paid to a third party and any reasonable legal costs) incurred by the Licensor as a result of such infringement.

4 Termination

Without prejudice to any other rights, the Licensor may terminate this licence if You fail to comply with the terms and conditions of the licence. In such an event, You must destroy all copies of the CD-ROM.

5 Governing law

This agreement is governed by the laws of England, without regard to its 'conflict of laws' provision, and each party irrevocably submits to the exclusive jurisdiction of the English courts. The parties disclaim the application of the United Nations Convention on the International Sale of Goods.

Cambridge IGCSE Chemistry

Coursebook with CD-ROM

Fourth edition

Richard Harwood and Ian Lodge

Cambridge IGCSE Chemistry, Fourth edition is tailored to the latest Cambridge IGCSE Chemistry syllabus (0620) and is endorsed by Cambridge International Examinations.

Coursebook features:

- Full coverage of the syllabus.
- Written in accessible language with the international learner in mind.
- Activities to help students develop practical and investigative skills.
- Study tips throughout to aid with understanding.
- Key definitions are highlighted throughout the chapters and a comprehensive glossary is provided at the back of the book.
- A specific chapter relating to the development of practical and investigative skills.
- Check your progress using the questions throughout and assess yourself with exam-style questions at the end of each chapter.



The accompanying CD-ROM contains:

- self-assessment checklists for making drawings, constructing and completing results tables, drawing graphs, and designing experiments
- answers to the end-of-chapter questions.
- advice on study and revision skills
- revision checklists for each chapter
- multiple-choice self tests and answers
- practice exam-style papers and mark schemes
- a series of animations to help students to visualise key concepts
- expanded notes on the activities for teachers and technicians.

Other components of *IGCSE Chemistry, Fourth edition*:

Workbook ISBN 978-1-107-61499-4

Teacher's resource ISBN 978-1-107-61501-4



**Completely Cambridge – Cambridge resources
for Cambridge qualifications**

Cambridge International Examinations is the world's largest provider of programmes and qualifications for 5–19 year olds. Cambridge University Press is the oldest publishing house in the world, having been operating continuously since 1584, and is one of the largest academic publishers globally.

Cambridge University Press works with Cambridge International Examinations, and experienced authors, to produce high-quality endorsed textbooks and software that support Cambridge Teachers and encourage Cambridge Learners.

To find out more about Cambridge International Examinations visit www.cie.org.uk

Visit cambridge.org/cie for information on our full range of Cambridge IGCSE titles.

ENDORSED BY



CAMBRIDGE
International Examinations



CAMBRIDGE
UNIVERSITY PRESS

Achieve
through
excellence

ISBN 978-1-107-61503-8



9 781107 615038 >